


The Poetry of Science

Robert Hunt

Or, Studies of the Physical Phenomena of Nature

The Project Gutenberg eBook of The Poetry of Science; or, Studies of the Physical Phenomena of Nature

This eBook is for the use of anyone anywhere in the United States and most other parts of the world at no cost and with almost no restrictions whatsoever. You may copy it, give it away or re-use it under the terms of the Project Gutenberg License included with this eBook or online at www.gutenberg.org. If you are not located in the United States, you will have to check the laws of the country where you are located before using this eBook.

Title: The Poetry of Science; or, Studies of the Physical Phenomena of Nature

Author: Robert Hunt

Release date: April 30, 2016 [eBook #51897]
Most recently updated: October 23, 2024

Language: English

Other information and formats: www.gutenberg.org/ebooks/51897

Credits: Produced by Emmanuel Ackerman and the Online Distributed Proofreading Team at http://www.pgdp.net (This file was

produced from images generously made
available by The
Internet Archive/Canadian Libraries)

*** START OF THE PROJECT GUTENBERG EBOOK
THE POETRY OF SCIENCE; OR, STUDIES OF THE
PHYSICAL PHENOMENA OF NATURE ***

THE

POETRY OF SCIENCE;

OR,

STUDIES

OF THE

PHYSICAL PHENOMENA OF NATURE.

BY

ROBERT HUNT,

AUTHOR OF

“RESEARCHES ON LIGHT;” “ELEMENTARY PHYSICS;”
“PANTHEA, OR THE SPIRIT OF NATURE,” ETC.

PROFESSOR OF PHYSICS, METROPOLITAN SCHOOL OF
SCIENCE, ETC., ETC.

THIRD EDITION, REVISED AND ENLARGED.

LONDON:

HENRY G. BOHN, YORK STREET, COVENT GARDEN.

MDCCCLIV.

From Shakespeare to Plato—from the philosophic poet to the poetic philosopher—the transition is easy, and the road is crowded with illustrations of our present subject.

Hast thou ever raised thy mind to the consideration of EXISTENCE, in and by itself, as the mere act of existing?

Hast thou ever said to thyself, thoughtfully, IT IS!—heedless, in that moment, whether it were a man before thee, or a flower, or a grain of sand,—without reference, in short, to this or that particular mode or form of existence? If thou hast, indeed, attained to this, thou wilt have felt the presence of a mystery, which must have fixed thy spirit in awe and wonder.

Coleridge.

LONDON:
WILSON and OGILVY,
57, Skinner Street.

PREFACE.

Since 1848, when the “Poetry of Science” was first submitted to the public, two editions have been exhausted. This, were proofs required, would of itself show that there is a large circle of readers to whom the deductions of science have an unfailing interest. Beyond this, it conveys an assurance that every truth, however abstract it may appear, has a large popular value if studied in its relations to those generalities which embrace great natural phenomena. With this persuasion the third edition of the “Poetry of Science” has been extended so as to include all the important discoveries which have been made in Natural Philosophy to the end of the year 1853. It is now presented to the world in a new and cheaper form, in the hope, that, with the extension of its circulation, there may be awakened, in still larger circles, a deep and healthful interest in the sciences of which the volume treats.

R. H.

Edinburgh, March 7, 1854.

CONTENTS.

Page

PREFACE. iii

CONTENTS. v

INTRODUCTION. ix

CHAPTER I.
GENERAL CONDITIONS
OF MATTER.

Its varied Characters, and constant change of external Form—The Grain of Dust, its Properties and Powers —Combinations in inorganic Masses and in organized Creations —Our knowledge of Matter—Theory of Ultimate Atoms—The Physical Forces acting on the Composition of Masses—The certainty of the exercise of subtile principles, which are beyond the reach of experimental Science 1

CHAPTER II.

MOTION.

Are the Physical Forces modes of Motion?—Motion defined—Philosophical Views of Motion, and the Principles to which it has been referred—Motions of the Earth and of the Solar System—Visible Proofs of the Earth's Motion on its Axis—Influence of the proper Motions of the Earth on the Conditions of Matter—Theory of the Conversion of Motion into Heat, &c.—The Physical Forces regarded as principles independent of Motion, although the Cause and often apparently the Effects of it 7

CHAPTER III.

GRAVITATION.

The Forms of Matter—Shape of the Earth—Probability of the Mass forming this Planet having existed in a Nebulous State—Zodiacal Lights—Comets—Volatilization of Solid Matter by Artificial means—The principle of Gravitation—Its Influence through Space and within the smallest Limits—Gravitating powers of the Planets—Density of the Earth—Certainty of Newton's Law of the Inverse Square—Discovery of Neptune—State of a Body relieved from Gravitation—Experiment explaining Saturn's Ring, &c.—General inference 21

CHAPTER IV.

MOLECULAR FORCES.

Conditions of Matter—Variety of organized Forms—Inorganic Forms—All matter reducible to the most simple conditions—Transmutation, a natural operation—Chemical Elementary Principles—Divisibility of Matter—Atom—Molecules—Particles—Molecular Force includes several Agencies—Instanced in the Action of Heat on Bodies—All Bodies porous—Solution—Mixture—Combination—Centres of Force—Different States of Matter (Allotropic Conditions)—Theories of Franklin, Æpinus, and Coulomb—Electrical and Magnetic Agencies—Ancient Notions—Cohesive Attraction, &c. 35

CHAPTER V.

CRYSTALLOGENIC FORCES.

Crystallisation and Molecular Force distinguished—Experimental Proof—Polarity of Particles forming a Crystal—Difference between Organic and Inorganic Forms—Decomposition of Crystals in Nature—Substitution of Particles in Crystals—Pseudomorphism—Crystalline Form not dependent on Chemical Nature—Isomorphism—Dimorphism—Theories of Crystallogenic Attraction—Influence of Electricity and Magnetism—Phenomena during Crystallisation—Can a change of Form take place in Primitive Atoms?—Illustrative Example of Crystallisation 50

CHAPTER VI.

HEAT—SOLAR AND TERRESTRIAL.

Solar and Terrestrial Heat —Position of the Earth in the Solar System—Heat and Light associated in the Sunbeam—Transparency of Bodies to Heat—Heating Powers of the Coloured Rays of the Spectrum—Undulatory Theory—Conducting Property of the Earth's Crust—Convection—Radiation—Action of the Atmosphere on Heat Rays—Peculiar Heat Rays—Absorption and Radiation of Heat by dissimilar Bodies—Changes in the Constitution of Solar Beam—Differences between Transmitted and Reflected Solar Heat—Phenomena of Dew—Action of Solar Heat of the Ocean—Circulation of Heat by the Atmosphere and the Ocean—Heat of the Earth—Mean Temperature—Central Heat—Constant Radiation of Heat Rays

from all Bodies—Thermography—Action of Heat on Molecular Arrangements—Sources of Terrestrial Heat—Latent Heat of Bodies—Animal Heat—Eremacausis—Spheroidal State Cold—Condensation—Freezing—Theories of Heat—Natural Phenomena—and Philosophical Conclusion 62

CHAPTER VII.

LIGHT.

Theories of the Nature of Light—Hypotheses of Newton and Huygens —Sources of Light— The Sun—Velocity of Light—Transparency— Dark Lines of the Spectrum—Absorption of Light—Colour— Prismatic Analysis— Rays of the Spectrum —Rainbow— Diffraction— Interference—Goethe's Theory—Polarisation —Magnetisation of Light—Vision—The Eye—Analogy—Sound and Light—Influence of Light on Animals and Vegetables— Phosphorescence arising from several Causes—Artificial Light—Its Colour dependent on Matter 118

CHAPTER VIII.

ACTINISM—CHEMICAL RADIATIONS.

The Sun-ray and its Powers —Darkening of Horn Silver—Niepce's Discovery—Prismatic Spectrum—Refrangibility of Light, Heat, and Actinism—Daguerre's Discovery —Photography—Chemical Effects produced by Solar Radiations—Absorption of Actinism —Phenomena of the Daguerreotype—Chemical Change produced upon all Bodies—Power of Matter to restore its Condition—Light protects from Chemical Change—Photographs taken in Darkness—Chemical Effects of Light on organized Forms—Chemical Effects of Solar Heat—Influence of Actinism on Electricity—Radiations in Darkness—Moser's Discoveries, &c. 166

CHAPTER IX.

ELECTRICITY.

Discovery of Electrical Force—Diffused through all Matter—What is Electricity?—Theories—Frictional Electricity—Conducting Power of Bodies—Hypothesis of two Fluids—Electrical Images—Galvanic Electricity—Effects on Animals—Chemistry of Galvanic Battery—Electricity of a Drop of Water—Electro-chemical Action—Electrical Currents—Thermo-Electricity—Animal Electricity—Gymnotus—Torpedo—Atmospheric Electricity—Lightning Conductors—Earth's Magnetism due to Electrical Currents—Influence on Vitality—Animal and Vegetable Development—Terrestrial Currents—Electricity of Mineral Veins—Electrotype—Influence of Heat, Light, and Actinism on Electrical Phenomena 193

CHAPTER X.

MAGNETISM.

Magnetic Iron—Knowledge of, by the Ancients—Artificial Magnets—Electro-Magnets—Electro-Magnetism—Magneto-Electricity—Theories of Magnetism—The Magnetic Power of soft Iron and Steel—Influence of Heat on Magnetism—Terrestrial Magnetism—Declination of the Compass-needle—Variation of the Earth's Magnetism—Magnetic Poles—Hansteen's Speculations—Monthly and Diurnal Variation—Dip and Intensity—Thermo-Magnetism—Aurora Borealis—Magnetic Storms—Magnetic conditions of Matter—Diamagnetism, &c. 235

CHAPTER XI.

CHEMICAL FORCES.

Nature’s Chemistry—
Changes produced by Chemical Combination —Atomic Constitution of Bodies—Laws of Combination— Combining Equivalents —Elective Affinity— Chemical Decomposition— Compound Character of Chemical Phenomena—Catalysis or action of Presence— Transformation of Organic Bodies— Organic Chemistry— Constancy of Combining Proportions —The Law of Volumes, the Law of Substitutions, Isomeric States, &c. 270

CHAPTER XII.

CHEMICAL PHENOMENA.

Water—Its Constituents—Oxygen—Hydrogen—Peroxide of Hydrogen—Physical Property of Water—Ice—Sea Water—Chlorine—Muriatic Acid—Iodine—Bromine—Compounds of Hydrogen with Carbon—Combustion—Flame—Safety Lamp—Respiration—Animal Heat—The Atmosphere—Carbonic Acid—Influence of Plants on the Air—Chemical Phenomena of Vegetation—Compounds of Nitrogen—Mineral Kingdom, &c. &c. 295

CHAPTER XIII.

TIME.—GEOLOGICAL PHENOMENA.

Time, an element in Nature's Operations—Geological Science—Its Facts and Inferences—Nebular Hypothesis applied—Primary Formations—Plutonic and Metamorphic Rocks—Transition Series—Palæozoic Rocks—Commencement of Organic Arrangements—Existence of Phosphoric Acid in Plutonic Rocks—Fossil Remains—Coal Formation—Sandstones—Tertiary Formations—Eocene, Miocene, and Pliocene Formations—Progressive changes now apparent—General Conclusions—Physics applied in explanation 332

CHAPTER XIV.

PHENOMENA OF VEGETABLE LIFE.

Psychology of Flowers—Progress of Matter towards Organization—Vital Force—Spontaneous Generation—The Vegetable Cell—Simplest Development of Organization—The Crystal and the Cell—Primitive Germ—Progress of Vegetation—Influence of Light—Morphology—Germination—Production of Woody Fibre—Leaves—Chlorophylle—Decomposition of Carbonic Acid—Influence of Light, Heat, and Actinism on the Phenomena of Vegetable Life—Flowers and Fruits—Etiolation—Changes in the Sun's Rays with the Seasons—Distribution of Plants—Electrical and Combined Physical Powers 357

CHAPTER XV.

PHENOMENA OF ANIMAL LIFE.

Distinction between the Kingdoms of Nature—Progress of Animal Life—Sponges—Polypes—Infusoria—Animalcula—Phosphorescent Animals—Annelidans—Myriapoda—Animal Metamorphoses—Fishes—Birds—Mammalia—Nervous System—Animal Electricity—Chemical Influences—Influence of Light on Animal Life—Animal Heat—Mechanical Action—Nervous Excitement—Man and the Animal Races, &c. 383

CHAPTER XVI.

GENERAL CONCLUSIONS.

The Changes produced on Physical Phenomena by the Movement of the Solar System considered—Exertion of the Physical Forces through the Celestial Spaces—The Balance of Powers—Varieties of Matter—Extension of Matter—Theory of Nonentity—A Material Creation an indisputable fact—Advantages of the Study of Science—Conclusion 403

INDEX. 413

BOHN'S BOOKS.

TRANSCRIBER'S NOTE.

INTRODUCTION.

The True is the Beautiful. Whenever this becomes evident to our senses, its influences are of a soul-elevating character. The beautiful, whether it is perceived in the external forms of matter, associated in the harmonies of light and colour, appreciated in the modulations of sweet sounds, or mingled with those influences which are, as the inner life of creation, ever appealing to the soul through the vesture which covers all things, is the natural theme of the poet, and the chosen study of the philosopher.

But, it will be asked, where is the relation between the stern labours of science and the ethereal system which constitutes poetry? The fumes of the laboratory, its alkalies and acids, the mechanical appliances of the observatory, its specula and its lenses, do not appear fitted for a place in the painted bowers of the Muses. But, from the labours of the chemist in his cell,—from the multitudinous observations of the astronomer on his tower,—spring truths which the philosopher employs to interpret nature's mysteries, and which give to the soul of the poet those realities to which he aspires in his high imaginings.

Science solicits from the material world, by the persuasion of inductive search, a development of its elementary principles, and of the laws which these obey. Philosophy strives to apply the discovered facts to the great phenomena of being,—to deduce large generalities from the fragmentary discoveries of severe induction,—and thus to ascend from matter and its properties up to those impulses which stir the whole, floating, as it were, on the confines of sense, and indicating, though dimly, those superior powers

which, more nearly related to infinity, mysteriously manifest themselves in the phenomena of mind. Poetry seizes the facts of the one and the theories of the other; unites them by a pleasing thought, which appeals for truth to the most unthinking soul, and leads the reflective intellect to higher and higher exercises; it connects common phenomena with exalted ideas; and, applying its holiest powers, it invests the human mind with the sovereign strength of the True.

Truth is the soul of the poet's thought;—truth is the reward of the philosopher's toil; and their works, bearing this stamp, live among men through all time. Science at present rejoices in her ministry to the requirements of advancing civilization, and is content to receive the reward given to applications which increase the comforts of life, or add to its luxuries. Every improvement in the arts or manufactures, beyond encreasing utilities for society, has a tendency to elevate the race. Science is ever useful in the working days of our week, but it is not to be neglected on our Sabbath,—when, resting from our labours, it becomes agreeable to contemplate the few truths permitted to our knowledge, and thus enter into communion as closely as is allowed to finite beings, with those influences which involve and interpenetrate the earth, giving to all things Life, Beauty, and Divinity.

The human mind naturally delights in the discovery of truth; and even when perverted by the constant operations of prevailing errors, a glimpse of the Real comes upon it like the smile of daylight to the sorrowing captive of some dark prison. The Psychean labours to try man's soul, and exalt it, are the search for truth beneath the mysteries which surround

creation,—to gather amaranths, shining with the hues of heaven, from plains upon which hang, dark and heavy, the mists of earth. The poet may pay the debt of nature,—the philosopher may return to the bosom of our common mother,—even their names fade in the passage of time, like planets blotted out of heaven but the truths they have revealed to man burn on for ever with unextinguishable brightness. Truth cannot die; it passes from mind to mind, imparting light in its progress, and constantly renewing its own brightness during its diffusion. The True is the Beautiful; and the truths revealed to the mind render us capable of perceiving new beauties on the earth. The gladness of truth is like the ringing voice of a joyous child, and the most remote recesses echo with the cheerful sound. To be for ever true is the Science of Poetry,—the revelation of truth is the Poetry of Science.

Man, a creation endued with mighty faculties, but a mystery to himself, stands in the midst of a wonderful world, and an infinite variety of phenomena arise around him in strange form and magical disposition, like the phantasma of a restless night.

The solid rock obeys a power which brings its congeries of atoms into a thousand shapes, each one geometrically perfect. Its vegetable covering, in obedience to some external excitation, developes itself in a curious diversity of forms, from the exquisitely graceful to the singularly grotesque, and exhibits properties still more varied and opposed. The animal organism quickened by higher impulses, —powers working within, and modifying the influence of the external forces,—presents, from the Monad to the Mammoth, and through every phase of

being up to Man, a yet more wonderful series of combinations, and features still more strangely contrasted.

Lifting our searching gaze into the measureless space beyond our earth, we find planet bound to planet, and system chained to system, all impelled by a universal force to roll in regularity and order around a common centre. The pendulations of the remotest star are communicated through the unseen bond; and our rocking world obeys the mysterious impulse throughout all those forces which regulate the inorganic combinations of this earth, and unto which its organic creation is irresistibly compelled to bow.

The glorious sun by day, and the moon and stars in the silence and the mystery of night, are felt to influence all material nature, holding the great Earth bound in a many-stranded cord which cannot be broken. The tidal flow of the vast ocean, with its variety of animal and vegetable life, the atmosphere, bright with light, obscured by the storm-cloud, spanned by the rainbow, or rent with the explosions of electric fire,—attest to the might of these elementary bonds.

These are but a few of the great phenomena which play their part around this globe of ours, exciting men to wonder, or shaking them with terror.

The mind of man, in its progress towards its higher destiny, is tasked with the physical earth as a problem, which, within the limits of a life, it must struggle to solve. The intellectual spirit is capable of embracing all finite things. Man is gifted with powers for studying the entire circle of visible creation; and he is equal, under proper training, to the task of examining much of the secret machinery

which stirs the whole.

In dim outshadowing, earth's first poets, from the loveliness of external nature, evoked beautiful spiritualizations. To them the shady forests teemed with aërial beings,—the gushing springs rejoiced in fantastic sprites,—the leaping cataracts gleamed with translucent shades,—the cavernous hills were the abodes of genii,—and the earth-girdling ocean was guarded by mysterious forms. Such were the creations of the far-searching mind in its early consciousness of the existence of unseen powers. The philosopher picked out his way through the dark and labyrinthine path, between effects and causes, and slowly approaching towards the light, he gathered semblances of the great Reality, like a mirage, beautiful and truthful, although still but a cloud-reflection of the vast Unseen.

It is thus that the human mind advances from the Ideal to the Real, and that the poet becomes the philosopher, and the philosopher rises into the poet; but at the same time as we progress from fable to fact, much of the soul-sentiment which made the romantic holy, and gave a noble tone to every aspiration, is too frequently merged in a cheerless philosophy which clings to the earth, and reduces the mind to a mechanical condition, delighting in the accumulation of facts, regardless of the great laws by which these are regulated, and the harmony of all Telluric combinations secured. In science we find the elements of the most exalted poetry; and in the mysterious workings of the physical forces we discover connections with the illimitable world of thought,—in which mighty minds delight to try their powers,—as strangely complicated, and as marvellously ordered, as in the psychological

phenomena which have, almost exclusively, been the objects of their studies.

In the aspect of visible nature, with its wonderful diversity of form and its charm of colour, we find the Beautiful; and in the operations of these principles, which are ever active in producing and maintaining the existing conditions of matter, we discover the Sublime.

The form and colour of a flower may excite our admiration; but when we come to examine all the phenomena which combine to produce that piece of symmetry and that lovely hue,—to learn the physiological arrangement of its structural parts,—the chemical actions by which its woody fibre and its juices are produced,—and to investigate those laws by which is regulated the power to throw back the white sunbeam from its surface in coloured rays,—our admiration passes to the higher feeling of deep astonishment at the perfection of the processes, and of reverence for their great Designer. There are, indeed, “tongues in trees;” but science alone can interpret their mysterious whispers, and in this consists its poetry.

To rest content with the bare enunciation of a truth, is to perform but one half of a task. As each atom of matter is involved in an atmosphere of properties and powers, which unites it to every mass of the universe, so each truth, however common it may be, is surrounded by impulses which, being awakened, pass from soul to soul like musical undulations, and which will be repeated through the echoes of space, and prolonged for all eternity.

The poetry which springs from the contemplation of the agencies which are actively employed in producing the transformation of matter, and which is

founded upon the truths developed by the aids of science, should be in no respect inferior to that which has been inspired by the beauty of the individual forms of matter, and the pleasing character of their combinations.

The imaginative view of man and his world—the creations of the romantic mind—have been, and ever will be, dwelt on with a soul-absorbing passion. The mystery of our being, and the mystery of our ceasing to be, acting upon intelligences which are for ever striving to comprehend the enigma of themselves, leads by a natural process to a love for the Ideal. The discovery of those truths which advance the human mind towards that point of knowledge to which all its secret longings tend, should excite a higher feeling than any mere creation of the fancy, how beautiful soever it may be. The phenomena of Reality are more startling than the phantoms of the Ideal. Truth is stranger than fiction. Surely many of the discoveries of science which relate to the combinations of matter, and exhibit results which we could not by any previous efforts of reasoning dare to reckon on, results which show the admirable balance of the forces of nature, and the might of their uncontrolled power, exhibit to our senses subjects for contemplation truly poetic in their character.

We tremble when the thunder-cloud bursts in fury above our heads. The poet seizes on the terrors of the storm to add to the interest of his verse. Fancy paints a storm-king, and the genius of romance clothes his demons in lightnings, and they are heralded by thunders. These wild imaginings have been the delight of mankind; there is subject for wonder in them: but is there anything less wonderful in the

well-authenticated fact, the dew-drop which glistens on the flower, that the tear which trembles on the eye-lid, holds locked in its transparent cells an amount of electric fire equal to that which is discharged during a storm from a thunder-cloud?

In these studies of the effects which are continually presenting themselves to the observing eye, and of the phenomena of causes, as far as they are revealed by Science in its search of the physical earth, it will be shown that beneath the beautiful vesture of the external world there exists, like its quickening soul, a pervading power, assuming the most varied aspects, giving to the whole its life and loveliness, and linking every portion of this material mass in a common bond with some great universal principle beyond our knowledge. Whether by the improvement of the powers of the human mind, man will ever be enabled to embrace within his knowledge the laws which regulate these remote principles, we are not sufficiently advanced in intelligence to determine. But if admitted even to a clear perception of the theoretical Power which we regard as regulating the known forces, we must still see an unknown agency beyond us, which can only be referred to the Creator's will.

THE

POETRY OF SCIENCE.

CHAPTER I.

GENERAL CONDITIONS OF MATTER.

Its varied Characters, and constant change of external Form—The Grain of Dust, its Properties and Powers—Combinations in inorganic Masses and in organized Creations—Our knowledge of Matter—Theory of Ultimate Atoms—The Physical Forces acting on the Composition of Masses—The certainty of the exercise of subtile principles, which are beyond the reach of experimental Science.

The Physical Earth presents to us, in every form of organic and inorganic matter, an infinite variety of phenomena. If we select specimens of rocks, either crystalline or stratified,—of metals in any of their various combinations with oxygen, sulphur, and other bodies,—of gems glistening with light and glowing with colour,—if we examine the varied

forms and hues of the vegetable world, or the more mysterious animal creations, we must inevitably come to the conclusion, long since proclaimed, and admit that dust they are, and to dust must they return. Whatever permanency may be given to matter, it is certain that its form is ever in a state of change. The surface of the "Eternal Hills" is worn away by the soft rains which fall to fertilize, and from their wrecks, borne by the waters to the ocean, new continents are forming. The mutations of the old earth may be read upon her rocks and mountains, and these records of former changes tell us the infallible truth, that as the present passes into the future, so will the form of Earth undergo an important alteration. The same forces which lifted the Andes and the Himalayas are still at work, and from the particles of matter carried from the present lands by the rivers into the sea, where they subside in stratified masses, there will, in the great future, be raised new worlds, upon which the work of life will go forward, and over which will be spread a vast Intelligence.

If we regard the conditions of the beautiful and varied organic covering of the Earth, the certainty, the constancy, of change is ever before us. Vegetable life passes into the animal form, and both perish to feed the future plant. Man, moving to-day the monarch of a mighty people, in a few years passes back to his primitive clod, and that combination of elementary atoms, which is dignified with the circle of sovereignty and the robe of purple, after a period may be sought for in the herbage of the fields, or in the humble flowers of the valley.

We have, then, this certain truth,—all things visible around us are but aggregations of atoms. From

particles of dust, which under the microscope could scarcely be distinguished one from the other, are all the varied forms of nature created. This grain of dust, this particle of sand, has strange properties and powers. Science has discovered some truths, but still more are hidden within this irregular molecule of matter which we now survey, than have yet been shadowed in the dreams of our philosophy. How strangely it obeys the impulses of heat—mysterious are the influences of light upon it—electricity wonderfully excites it—and still more curious is the manner in which it obeys the magic of chemical force. These are phenomena which we have seen; we know them, and we can reproduce them at our pleasure. We have advanced a little way into the secrets of nature, and from the spot we have gained, we look forward with a vision somewhat brightened by our task; but we discover so much to be yet unknown, that we learn another truth,—our vast ignorance of many things relating to this grain of dust.

It gathers around it other particles; they cling together, and each acting upon every other one, and all of them arranging themselves around the little centre according to some law, a beautiful crystal results, the geometric perfection of its form being a source of admiration.

It exerts some other powers, and atom cohering to atom, obeying the influences of many external radiant forces, undergoes inexplicable changes, and the same dust which we find forming the diamond, aggregates into the lordly tree,—blends to produce the graceful, scented, and richly painted flower,—and combines to yield the luxury of fruit.

It quickens with yet undiscovered energies; it moves

with life: dust is stirred by the mysterious excitement of vital force; and blood and bone, nerve and muscle, are the results. Forces, which we cannot by the utmost refinements of our philosophy detect, direct the whole, and from the same dust which formed the rock and grew in the tree, is produced a living and a breathing thing, capable of receiving a Divine illumination, of bearing in its new state the gladness and the glory of a Soul.

These considerations lead us to reflect on the amount of our knowledge. We are led to ask ourselves, what do we know? We know that the world with all its variety is composed of certain material atoms, which, although presented to us in a great variety of forms, do not in all probability differ very essentially from each other.

We know that those atoms obey certain conditions which appear to be dependent upon the influences of motion, gravitation, heat, light, electricity, and chemical force. These powers are only known to us by their effects; we only detect their action by their operations upon matter; and although we regard the several phenomena which we have discovered, as the manifestations of different principles, it is possible they may be but modifications of some one universal power, of which these are but a few of its modes of action.

In examining, therefore, the truths which science has revealed to us, it is advantageous, for the purpose of fixing the mind to the subject, that we assume certain conditions as true. These may be stated in a few sentences, and then, without wasting a thought upon those metaphysical subtleties which have from time to time perplexed science, and served to impede the progress of truth, we shall proceed to examine

our knowledge of the phenomena which constantly occur around us.

Every form, whether inorganic or organic, which we can discover within the limits of human search, is composed of atoms, which are capable of assuming, under the influence of certain physical forces, conditions essential to the physical state of that body of which they constitute a part.[1] The known forces, active in producing these conditions, are modes of motion; gravitation and aggregation, heat, light; and associated with these, actinism or chemical radiation; electricity, under all its conditions, whether static or dynamic; and chemical affinity, regarded as the result of a separate elementary principle.

These forces must be considered as powers capable of acting in perfect independence of each other. They are possibly modifications of one principle; but this view being an hypothesis, which, as yet, is only supported by loose analogies, cannot, without danger, be received in any explanation which attempts to deal only with the truths of science.

We cannot examine the varied phenomena of nature, without feeling that there must be other and most active principles of a higher order than any detected by science, to which belong the important operations of vitality, whether manifested in the plant or the animal. In treating of these, although speculation cannot be entirely avoided, it will be employed only so far as it gives any assistance in linking phenomena together.

We have to deal with the active agencies which give form and feature to nature—which regulate the harmony and beauty and vigour of life—and upon which depend those grand changes in the conditions

of matter, which must convince us that death is but the commencement of a new state of being.

FOOTNOTES:

[1] Sir Isaac Newton supposed matter to consist of hard, impenetrable, perfectly inelastic atoms.

Boscovich regarded the constitution of matter differently. The ultimate atom was with him a point surrounded by powers of infinite elasticity. (See *Dr. Robisons Mechanical Philosophy*, for a full explanation of the theory of Boscovich.)

The view entertained by Dr. Faraday, which will be comprehended from one or two short extracts from his valuable and suggestive paper, claims attention:—

"If the view of the constitution of matter already referred to be assumed to be correct—and I may be allowed to speak of the particles of matter, and the space between them (in water, or in the vapour of water, for instance), as two different things—the space must be taken as the only continuous part, for the particles are considered as separated by space from each other. Space will permeate all masses of matter in every direction like a net, except that in the place of meshes it will form cells, isolating each atom from its neighbours, and itself only being continuous."

Examining the question of the conducting power of different bodies, and observing that as space is the only continuous part, so space, according to the received view of matter, must be at one time a conductor, at others a non-

conductor, it is remarked:

"It would seem, therefore, that, in accepting the ordinary atomic theory, space may be proved to be a non-conductor in non-conducting bodies, and a conductor in conducting bodies; but the reasoning ends in this—a subversion of that theory altogether; for, if space be an insulator, it cannot exist in conducting bodies; and if it be a conductor, it cannot exist in insulating bodies."—*A Speculation touching Electric Conduction, and the Nature of Matter*: by Michael Faraday, D.C.L., F.R.S., &c.: Philosophical Magazine, vol. xxiv. Third Series.

See also Wollaston, *On the Finite Extent of the Atmosphere*.—Phil. Trans. 1822. Young, *On the Essential Properties of Matter*.—Lectures on Natural Philosophy. Mossotti, *On Molecular Action*.—Scientific Memoirs, vol. i. p. 448.

CHAPTER II.

MOTION.

Are the Physical Forces modes of Motion?—Motion defined—Philosophical Views of Motion, and the Principles to which it has been referred—Motions of the Earth and of the Solar System—Visible Proofs of the Earth's Motion on its Axis—Influence of the proper Motions of the Earth on the Conditions of Matter—Theory of the Conversion of Motion into Heat, &c.—The Physical Forces regarded as principles independent of Motion, although the Cause and often apparently the Effects of it.

Many of the most eminent thinkers of the present time are disposed to regard all the active principles of nature as "modes of motion,"—to look upon light, heat, electricity, and even vital force, as phenomena resulting from "change of place" among the particles of matter; this change, disturbance, or motion, being dependent upon some undefined mover.[2]

The habit of leaving purely inductive examination for the delusive charms of hypothesis—of viewing the material world as a metaphysical bundle of

essential properties, and nothing more—has led some eminent philosophers to struggle with the task of proving that all the wonderful manifestations of the great physical powers of the universe are but modifications of motion, without the evidence of any antecedent force.[3]

The views of metaphysicians regarding motion involve many subtle considerations which need not at present detain us. We can only consider motion as a change of place in a given mass of matter. Now matter cannot effect this of itself, no change of place being possible without a mover; and, consequently, motion cannot be a *property* of matter, in the strict sense in which that term should be accepted.[4]

Motion depends upon certain external disturbing and directing forces acting upon all matter; and, consequently, as every mode of action is determined by some excitement external to the body moved, motion cannot, philosophically, be regarded otherwise than as a peculiar affection of matter under determinable conditions. “We find,” says Sir Isaac Newton, “but little motion in the world, except what plainly flows from either the active principles of nature, or from the command of the willer.”[5]

Plato, Aristotle, and the Pythagoreans, supposed that throughout all nature an active principle was diffused, upon which depended all the properties exhibited by matter. This is the same as the “plastic nature” of Cudworth,[6] the “intellectual and artificial fire” of Bishop Berkeley;[7] and to these all modes of motion were referred. Sir Isaac Newton also regards the material universe and its phenomena as dependent upon “*active principles*”—for instance, the cause of gravity—whereby the planets and

comets preserve their motions in their orbits, and all bodies acquire a degree of motion in falling; and the cause of fomentation—whereby the heart and blood of animals preserve a perpetual warmth and motion—the inner parts of the earth are kept constantly warmed—many bodies burn and shine—and the sun himself burns and shines, and with his light warms and cheers all things.

The earth turns on its axis at the rate of more than 1,000 miles an hour, and passes around the sun with the speed of upwards of 68,000 miles in the same time.[8] The earth and the other planets of our system move in ellipses around a common centre: therefore their motion cannot have been originally communicated merely by the impressed force of projection. Two forces, at least, must have operated, one making the planets tend directly to the centre, and the other impelling them to fly off at a tangent to the curve described. Here we have a system of spheres, held by some power to a great central mass, around which they revolve with a fearful velocity. Nor is this all; the Solar System itself, bound by the same mystic chain to an undiscovered centre, moves towards a point in space at the rate of 33,550,000 geographical miles, whilst our earth performs one revolution around the sun.[9]

The evidence of the motion of the Earth around its axis, as afforded by the swinging of a pendulum or the rotation of a sphere, is too interesting to be omitted. In mechanical philosophy, we have two terms of the same general meaning—the conservation of the plane of vibration—and the conservation of the axis of rotation. For the non-scientific reader, these terms require explanation, and in endeavouring to simplify this as much as

possible, we must ask the indulgence of the Mechanical Philosopher. Let us fix in the centre of a small round table an upright rod, having an arm extending from its top, to which we can suspend a tolerably heavy weight attached to a string. This is our piece of apparatus: upon the table draw a chalk line, along which line we intend our pendulum to swing, and continuing this line upon the floor, or by a mark on the wall, our arrangements are complete. Raise steadily the bob of our pendulum, and set it free, so that its plane of vibration is along the line which has been marked. As the pendulum is swinging firmly along this line, slowly and steadily turn the table round. It will then be seen that the pendulum will still vibrate in the direction of the line we have continued onward to the wall, but that the line on the table is gradually withdrawn from it. If we had no upright, we might turn the table entirely round, without in the slightest degree altering the line along which the pendulum performs its oscillations. Now, if from some elevated spot, say, from the centre of the dome of St. Paul's, a long and heavy pendulum is suspended, and if on the floor we mark the line along which we set the pendulum free to vibrate, it will be seen, as in the experiment with the table, that the marked line moves away from under the pendulum. It continues to vibrate in the plane it first described, although the line on the earth's surface continues to move forward by the diurnal rotation around the axis. Similar to this is the law of the conservation of the axis of rotation. If a common humming-top, the spindle of which is its axis of rotation, is set spinning obliquely, it will be seen that the axis will continue to point along the line it took at the commencement of motion. By placing a heavy sphere in a lathe, resting its

projecting axial points on some moveable bearings, and then getting the sphere into extremely rapid motion, one of the bearings may be removed without the mass falling to the ground. The rapidity of motion changes so constantly and quickly the position of the particles which have a tendency to fall, that we have motion balanced against the force of gravitation in a striking manner; and we learn, from this experiment, the explanation of the planetary and stellar masses revolving on their axis at a speed sufficient to maintain them without support in space. A mass of matter, a sphere or a disc, carefully balanced, is fixed in gymbals such as we employ for fixing our compass needles, and it is set by some mechanical contrivance in rapid rotation. The position of the axis of rotation remains unaltered, although the earth is moving; and thus, by this instrument,—called the gyroscope,—we can determine, as with the pendulum, the motion of the earth around its axis; and we learn why, during its movement around the sun, its axis is undeviatingly pointed towards one point in space, marked in our Heavens as the Polar Star.

In addition to these great rotations, the earth is subjected to other motions, as the precession of the equinoxes and the nutation of its axis. Rocking regularly upon a point round which it rapidly revolves, whilst it progresses onward in its orbit, like some huge top in tremulous gyration upon the deck of a vast aërial ship gliding rapidly through space, is the earth performing its part in the great law of motion.

The rapidity of these impulses, supposing the powers of the physical forces were for a moment suspended, would be sufficient to scatter the mass of our planet

over space as a mere star-dust.

Limiting, as much as possible, the view which opens upon the mind as we contemplate the adjustments by which this great machine, our system, is preserved in all its order and beauty, let us forget the great movement of the whole through space, and endeavour to consider the effect of those motions which are directly related to the earth, as a member of one small group of worlds.

We cannot for a moment doubt, although we have not any experimental proof of the fact, that the proper motions of the earth materially influence the conditions of the matter of which it is formed. Every pair of atoms is, like a balance, delicately suspended, under the constant struggle which arises from the tendency to fly asunder, induced by one order of forces—centrifugal force—and the efforts of others, gravitation and cohesion, to chain them together. The spring is brought to the highest state of tension —one tremor more, and it would be destroyed.

We cannot, by any comparison with the labours of the most skilful human artisan, convey an idea of the exquisite perfection of planetary mechanics, even so far as they have been discovered by the labours of science; and we must admit that our insight into the vast machinery has been very limited.

All we know is the fact that this planet moves in a certain order, and at a fixed rate, and that the speed is of itself sufficient to rend the hardest rocks; yet the delicate down which rests so lightly upon the flower is undisturbed. It is, therefore, evident that matter is endued with powers, by which mass is bound to mass, and atom to atom; these powers are not the results of any of the motions which we have examined, but, acting in antagonism to them, they

sustain our globe in its present form.

Are there other motions to which these powers can be referred? We know of none. That absolute rest may not exist among the particles of matter is probable. Electrical action, chemical power, crystalline aggregation, the expansive force of heat, and many other known agencies, are in constant operation to prevent it. It must, however, be remembered, that each and every atom constituting a mass may be so suspended between the balanced forces, that it may be regarded as relatively at rest.

Theory imagines Motion as producing Force—a body is moved, and its mere mechanical change of place is regarded as generating heat; and hence the refinements of modern science have advanced to the conclusion that motion and heat are convertible. Admitting that the material atoms of which this world is formed are never in a state of quiescence, yet we cannot suppose any gross ponderable particle as capable of moving itself; but once set in motion, it may become the secondary cause of motion in other particles.[10] The difficulties of the case would appear to have been as follows:—Are heat, light, electricity, &c., material bodies? If they are material bodies—and heat, for example, is the cause of motion—must not the calorific matter move itself—or if it be not self-moving, by what is it moved? If heat is material, and the primary cause of motion, then matter must have an innate power of moving; it can convert itself into active force, or be at once a cause and an effect, which can scarcely be regarded as a logical deduction.

We move a particle of matter, and heat is manifested; the force being continued, light, electricity, and chemical action result; all, as appears from a limited

view of the phenomena, arising out of the mechanical force applied to the particle first moved. [11] This mechanical force, it must be remembered, is external to the body moved, and is, in all probability, set up by the movement of a muscle, acted upon by nerves, under the influence of a will.

The series of phenomena we have supposed to arise admit of an explanation free of the hypothesis of motion, and we avoid the dangerous ground of metaphysical speculation, and the subtleties of that logic which rests upon the immateriality of all creation. This explanation, it is freely admitted, is incomplete: we cannot distinctly correlate each feature of the phenomena, combine link to link, and thus form a perfect chain; but it is sufficiently clear to exhibit what we do know, and leave the unknown free for unbiassed investigation.

Each particle, each atom of that which conveys to our senses the only ideas we have of natural objects —ponderable matter—is involved in, or interpenetrated by, those principles which we call heat and electricity, with probably many others which are unknown to us; and although these principles or powers are, according to some law, bound in statical equilibrium to inert matter, they are freely developed by an external excitement, and the disturbance of any one of them, upsetting the equilibrium, leaves the other power equally free to be brought under the cognizance of human sense by their effects.

When we come to an examination of the influences exerted by these powers upon the physical earth, the position, that they must be regarded as the causes of motion rather than the effects of it, will be further considered. At present it is only necessary to state

thus generally the views we entertain of the conditions of matter in connection with the imponderable forces and mechanical powers. The conversion, as it has been called, of motion into heat, in the experiments of Count Rumford and Mr. Joule, [12] are only evidences that a certain uniformity exists between the mechanical force applied, and the amount of heat liberated. It does not appear that we have any proof of the conversion of motion into physical power.

It is necessary, to a satisfactory contemplation of the wonderful properties of matter, and of the forces regulating the forms of the entire creation, that we should be content with regarding the elementary bodies which chemistry instructs us form our globe, as tangible, ponderable atoms, having specific and distinguishing properties. That we should, as far as it is possible for finite minds to do so, endeavour to conceive the powers or forces—gravitation, molecular attraction, electricity, heat, light, and the principle which determines all chemical phenomena —as manifestations of agencies which hold a place between the most subtile form of matter and the hidden principles of vitality, which is still vastly inferior to the spiritual state, which reveals itself dimly in psychological phenomena, and arrives at its sublimity in the God of the universe.

FOOTNOTES:

[2] “Motion, therefore, is a change of rectilinear distance between two points. Allowing the accuracy of this definition, it appears that two points are necessary to

constitute motion; that in all cases, when we are inquiring whether or no any body or point is in motion, we must recur to some other point which we can compare with it; and that if a single atom existed alone in the universe, it could neither be said to be in motion nor at rest.

"The space which we call quiescent is in general the earth's surface; yet we well know, from astronomical considerations, that every point of the earth's surface is perpetually in motion, and that in very various directions: nor are any material objects accessible to our senses which we can consider as absolutely motionless, or even as motionless with regard to each other; since the continual variation of temperature to which all bodies are liable, and the minute agitations arising from the motion of other bodies with which they are connected, will always tend to produce some imperceptible changes in their distances."—*Lectures on Natural Philosophy, &c.*, by Thomas Young, M.D. Edited by the Rev. P. Kelland. 1845.

[3] "The position which I seek to establish in this essay is, that the various imponderable agencies, or the affections of matter which constitute the main objects of experimental physics, viz., heat, light, electricity, magnetism, chemical affinity, and motion, are all correlative, or have a reciprocal dependence;—that neither, taken abstractedly, can be said to be the essential or proximate cause of the others; but that either may, as a force, produce, or be convertible into, the other:—thus heat may mediately or immediately produce electricity, electricity may produce heat, and so of the rest.... Although strongly inclined to believe that the

five other affections of matter, which I have above named, are, and will ultimately be, resolved into modes of motion, it would be going too far at present to assume their identity with it: I, therefore, use the term force, in reference to them, as meaning that active force inseparable from matter, which induces its various changes."—*On the Correlation of Physical Forces*, by W. R. GROVE, Esq., M.A., F.R.S.

[4] When discussing the hypothesis of Hobbes —*that no body can possibly be moved but by a body contiguous and moved*—Boyle asks:—

"I demand how there comes to be local motion in the world? For either all the portions of matter that compose the universe have motion belonging to their natures, which the Epicureans affirmed for their atoms, or some parts of matter have this motive power, and some have not, or else none of them have it; but all of them are naturally devoid of motion. If it be granted that motion does naturally belong to all parts of matter, the dispute is at an end, the concession quite overthrowing the hypothesis.

"If Mr. Hobbes should reply that the motion is impressed upon any of the parts of matter by God, he will say that which I most readily grant to be true, but will not serve his turn, if he would speak congruously with his own hypothesis. For I demand whether this Supreme Being that the assertion has recourse to, be a corporeal or an incorporeal substance? If it be the latter, and yet the efficient cause of motion in bodies, then it will not be universally true that whatever body is moved is so by a body contiguous and moved. For, in our supposition, the bodies that God moves, either immediately or by the intervention of

any other immaterial being, are not moved by a body contiguous, but by an incorporeal spirit."—*Some Considerations about the Reconcileableness of Reason and Religion*: Boyle, vol. iii. p. 520.

[5] Boyle has some ingenious speculations on this point:—

"That there is local motion in many parts of matter is manifest to sense, but how matter came by this motion was of old, and is still, hotly disputed of: for the ancient Corpuscularian philosophers (whose doctrine in most other points, though not in all, we are the most inclinable to), not acknowledging an author of the universe, were thereby reduced to make motion congenite to matter, and consequently coeval with it. But since local motion, or an endeavour at it, is not included in the nature of matter, which is as much matter when it rests as when it moves; and since we see that the same portion of matter may from motion be reduced to rest, and after it hath continued at rest, so long as other bodies do not put it out of that state, may by external agents be set a moving again; I, who am not wont to think a man the worse naturalist for not being an atheist, shall not scruple to say with an eminent philosopher of old, whom I find to have proposed among the Greeks that opinion (for the main) that the excellent Des Cartes has revived amongst us, that the origin of motion in matter is from God; and not only so, but that thinking it very unfit to be believed, that matter barely put into motion, and then left to itself, should casually constitute this beautiful and orderly world; I think also further, that the wise Author of things did, by establishing the laws of motion among bodies, and by guiding the

first motions of the small parts of matter, bring them to convene after the manner requisite to compose the world; and especially did contrive those curious and elaborate engines, the bodies of living creatures, endowing most of them with the power of propagating their species."—*Considerations and Experiments touching the Origin of Forms and Qualities*: Boyle's Works, vol. ii. p. 460. Edinburgh. 1744.

[6] Cudworth's *Intellectual System*.

[7] "According to the Pythagoreans and Platonists, there is a life infused throughout all things ... an intellectual and artificial fire—an inward principle, animal spirit, or natural life, producing or forming within, as art doth without—regulating, moderating, and reconciling the various motions, qualities, and parts of the mundane system. By virtue of this life, the great masses are held together in their ordinary courses, as well as the minutest particles governed in their natural motions, according to the several laws of attraction, gravity, electricity, magnetism, and the rest. It is this gives instincts, teaches the spider her web, and the bee her honey;—this it is that directs the roots of plants to draw forth juice from the earth, and the leaves and the cortical vessels to separate and attract such particles of air and elementary fire as suit their respective natures."—Bishop Berkeley, *Siris*, No. 277.

[8] "The revolution of the earth is performed in a natural day, or, more strictly speaking, once in 23h. 56' 4", and as its mean circumference is 24,871 miles, it follows that any point in its equatorial surface has a rotatory motion of more than 1,000 miles per hour. This velocity must gradually diminish to nothing at either pole. Whilst the earth is thus

revolving on its axis, it has a progressive motion in its orbit. If we take the length of the earth's orbit at 630,000,000, its motion through space must exceed 68,490 miles in the hour."—Enc. Brit. art. *Physical Geography*.

[9] "Here then we have the splendid result of the united studies of MM. Argelander, O. Struve, and Peters, grounded on observations made at the three observatories of Dorpat, Abo, Pulkova, and which is expressed in the following thesis:—The motion of the solar system in space is directed to a point of the celestial vault situated on the right line which joins the two stars π and μ *Herculis*, at a quarter of the apparent distance of these stars, reckoning from π *Herculis*. The velocity of this motion is such, that the sun, with all the bodies which depend upon it, advances annually in the above direction 1·623 times the radius of the earth's orbit, or 33,550,000 geographical miles. The possible error of this last number amounts to 1,733,000 geographical miles, or to a *seventh* of the whole value. We may then wager 400,000 to 1 that the sun has a proper progressive motion, and 1 to 1 that it is comprised between the limits of thirty-eight and twenty-nine millions of geographical miles."—*Etudes d'Astronomie Stellaire: Sur la Voie Lactée et sur les Distances des Etoiles Fixes*: M. F. W. G. Struve. [A report addressed to his Excellency M. Le Comte Ouvaroff; Minister of Public Instruction and President of the Imperial Academy of Sciences at St. Petersburg.]

[10] "The first great agent which the analysis of natural phenomena offers to our consideration, more frequently and prominently than any other, is force. Its effects are either, 1st, to counteract the exertion of

opposing force, and thereby to maintain *equilibrium*; or, 2ndly, to produce *motion* in matter,

"Matter, or that whatever it be of which all the objects in nature which manifest themselves directly to our senses consist, presents us with two general qualities, which at first sight appear to stand in contradiction to each other —activity and inertness. Its activity is proved by its power of spontaneously setting other matter in motion, and of itself obeying their mutual impulse, and moving under the influence of its own and other force; inertness, in refusing to move unless obliged to do so by a force impressed externally, or mutually exerted between itself and other matter, and by persisting in its state of motion or rest unless disturbed by some external cause. Yet, in reality, this contradiction is only apparent. Force being the cause, and motion the effect produced by it on matter, to say that matter is inert, or has *inertia*, as it is termed, is only to say that the cause is expended in producing its effect, and that the same cause cannot (without renewal) produce double or triple its own proper effect. In this point of view, equilibrium may be conceived as a continual production of two opposite effects, each, undoing at every instant what the other has done,"?—See continuation of the argument in *Herschel's Discourse on the Study of Natural Philosophy*, page 223.

In the Edinburgh New Philosophical Journal, vol. xlv., will be found a paper by Dr Robert Brown—"*Of the sources of motions upon the Earth, and of the means by which they are sustained*," which will well repay an attentive perusal, as pointing to a class of investigation of the highest order, and containing

deductions of the most philosophic description.

[11] Friction, it is well known, generates heat; by rapidly rubbing two sticks together, the Indian produces their ignition; heat and light being both manifested. Under every mechanical disturbance electrical changes can be detected, and the action of heat in the combustion of the wood is a chemical phenomenon.

[12] Count Rumford's experiment consisted in placing a mass of metal in a box of water at a known temperature, and, by employing a boring apparatus, ascertaining carefully the increase of heat after a given number of revolutions. He thus describes his most satisfactory experiment:—

"Everything being ready, I proceeded to make the experiment I had projected, in the following manner. The hollow cylinder having been previously cleaned out, and the inside of its bore wiped with a clean towel till it was quite dry, the square iron bar, with the blunt steel borer fixed to the end of it, was put into its place; the mouth of the bore of the cylinder being closed at the same time by means of the circular piston through the centre of which the iron bar passed.

"This being done, the box was put in its place; and the joinings of the iron rod, and of the neck of the cylinder with the two ends of the box, having been made water-tight, by means of collars of oiled leather, the box was filled with cold water (viz., at the temperature of 60°) and the machine was put in motion. The result of this beautiful experiment was very striking, and the pleasure it afforded me amply repaid me for all the trouble I had had, in contriving and arranging the complicated

machinery used in making it. The cylinder, revolving at the rate of about thirty-two times in a minute, had been in motion but a short time, when I perceived, by putting my hand into the water and touching the outside of the cylinder, that heat was generated, and it was not long before the water which surrounded the cylinder began to be sensibly warm. At the end of one hour, I found, by plunging a thermometer into the water in the box (the quantity of which fluid amounted to 18·77 lbs. avoirdupois, or 2–1/4 wine gallons), that its temperature had been raised no less than 47°; being now 107° of Fahrenheit's scale. When thirty minutes more had elapsed, or one hour and thirty minutes after the machinery had been put in motion, the heat of the water in the box was 142°. At the end of two hours, reckoning from the beginning of the experiment, the temperature of the water was found to be raised to 178°. At two hours twenty minutes it was at 200°; and at two hours thirty minutes it *actually boiled*."—*Inquiry concerning the Source of the Heat excited by Friction*: Philosophical Transactions, vol. lxxxviii. A.D. 1798.

"Mr. Joule brought a communication on the same subject before the British Association at Cambridge, which was afterwards published in the Philosophical Magazine, and from that journal the following notices are extracted:—

"The apparatus exhibited before the Association consisted of a brass paddle-wheel, working horizontally in a can of water. Motion could be communicated to this paddle by means of weights, pulleys, &c. The paddle moved with great resistance in the can of water, so that the weights (each of four pounds) descended at the slow rate of about

one foot per second. The height of the pulleys from the ground was twelve yards, and consequently when the weights had descended through that distance they had to be wound up again in order to renew the motion of the paddle. After this operation had been repeated sixteen times, the increase of the temperature of the water was ascertained by means of a very sensible and accurate thermometer.

"A series of nine experiments was performed in the above manner, and nine experiments were made in order to eliminate the cooling or heating effects of the atmosphere. After reducing the result to the capacity for heat of a pound of water, it appeared that for each degree of heat evolved by the friction of water, a mechanical power equal to that which can raise a weight of 890 lbs. to the height of one foot, had been expended.

"Any of your readers who are so fortunate as to reside amid the romantic scenery of Wales or Scotland could, I doubt not, confirm my experiments by trying the temperature of the water at the top and at the bottom of a cascade. If my views be correct, a fall of 817 feet will of course generate one degree of heat, and the temperature of the river Niagara will be raised about one fifth of a degree by its fall of 160 feet."—*Relation between Heat and Mechanical Power*: Philosoph. Mag. vol. xxvii. 1845.

CHAPTER III.

GRAVITATION.

The Forms of Matter—Shape of the Earth—Probability of the Mass forming this Planet having existed in a Nebulous State—Zodiacal Lights—Comets—Volatilization of Solid Matter by Artificial means—The principle of Gravitation—Its Influence through Space and within the smallest Limits—Gravitating powers of the Planets—Density of the Earth—Certainty of Newton's Law of the Inverse Square—Discovery of Neptune—State of a Body relieved from Gravitation—Experiment explaining Saturn's Ring, &c.—General inference.

Let us suppose the earth—consisting of three conditions of matter; the solid, the fluid, and the aëriform—to be set free from that power by which it is retained in its present form of a spheroid flattened at the poles, but still subject to the influences of its diurnal and annual rotations. Agreeably to the law which regulates the conditions of all bodies moving at high velocities, the consequence of such a state of things would be, that our planet would instantly spread itself over an enormous area. The waters and even the solid masses of this globe would, in all

probability, present themselves amidst the other phenomena of space in a highly attenuated state, revolving in an orbit around the sun, as a band of nebulous matter, which might sometimes be rendered sensible to sight by still reflecting solar light, or by condensation in the form of flights of shooting stars.[13]

This may be illustrated by experiment. If upon a rapidly revolving disc we place a ball of dust, it will be almost immediately spread out, and its particles will arrange themselves in a series of regular curves, varying with the velocity of the motion. In addition to the disintegration which would arise from the tendency of the atoms to fly from the centre, the motion, in space, of the planetary mass would naturally occasion a trailing out, and the only degree of uniformity which this orb could, under these imaginary conditions, possibly present, would be derived from the combined effects of motions in different directions.

Amid the remoter stars, some remarkable cloud-like appearances are discovered. These nebulæ, presenting to the eye of the observer only a gleaming light, as from some phosphorescent vapour, were long regarded as indications of such a condition as that which we have just been considering. Astronomers saw, in those mysterious nebulæ, a confirmation of their views, which regarded all the orbs of the firmament as having once been thin sheets of vapour, which had gradually, from irregular bodies traversing space, been slowly condensed about a centre, and brought within the limits of aggregating agencies, until, after the lapse of ages, they become sphered stars, moving in harmony amid the bright host of heaven.[14]

Geologists seized on those views with eagerness, as confirming theoretical conclusions deduced from an examination of the structure of the earth itself, and explained by them the gradual accretion of atoms into crystalline rocks from a cooling mass.

The researches of modern astronomers, aided by the magnificent instruments of Lord Rosse,[15] have, however, shown that many of the most remarkable nebulæ are only clusters of stars; so remote from us, that the light from them appears blended into one diffused sheet or luminous film. There are, however, the Magellanic clouds, and other singular patches of light, exhibiting changes which can only be explained on the theory of their slow condensation. There is no evidence to disprove the position that world-formation may still be going on; that a slow and gradual aggregation of particles, under the influence of laws with which we are acquainted, may be constantly in progress, to end, eventually, in the formation of a sphere.

May we not regard the zodiacal light as the remains of a solar luminiferous atmosphere, which once embraced the entire system of which it is the centre? [16] Will not the strange changes which have been *seen to take place* in cometary bodies, even whilst they were passing near the earth,—as the division of Biela's comet and the ultimate formation of a second nucleus from the detached portion,—strongly tend to support the probability of the idea that attenuated matter has, in the progress of time, been condensed into solid masses, and that nebulous clouds must still exist in every state of tenuity in the regions of infinite space,[17] which, in the mysterious processes of world-formation, will, eventually, become stars, and reflect across the blue immensity of heaven, in

brightness, that light which is the necessary agent of organisation and all manifestations of beauty?

The inferences drawn from a careful study of the condition of our own globe are in favour of the assumption of the existence of nebulous matter. By the processes of art and manufacture, by the operation of those powers on which organisation and life depend, solid matter is constantly poured off in such a state that it cannot be detected, *as matter*, by any of the human senses. Yet a thousand results, daily and hourly accumulating as truths around us, prove that the solid metals, the gross earths, and the constituents of animal and vegetable life, all pass away invisible to us, and become "thin air." We know that, floating around us, these volatilized bodies exist in some material form, and numerous experiments in chemistry are calculated to convince us, that the most attenuated air is capable, with a slight change of circumstances, of being converted into the condition of solid masses. Hydrogen gas, the lightest, the most ethereal of the chemical elements, dissolves iron and zinc, arsenic, sulphur, and carbon; and from the transparent combinations thus formed, we can with facility separate those ponderous bodies. Such substances must exist in our own atmosphere; why not in the regions of space? Whether this planet ever floated a mass of nebulous matter, only known by its dim and filmy light, or comet-like rushed through space with widely eccentric orbit, are questions which can only receive the reply of speculative minds. Whether the earth and the other members of the Solar System were ever parts of a Central Sun,[18] and thrown from it by some mighty convulsion, though now revolving with all the other masses around that orb, chained in their circuits by some infinite power, is beyond the utmost

refinements of science to discover. This hypothesis is, however, in its sublime conception, worthy of the master-mind that gave it birth.

All we know is, that our earth is an oblate sphere, which, by the effects of its rotation around an axis, is somewhat enlarged at the equator and flattened at the poles;—that it maintains its regular course around the sun, in virtue of the operation of two forces, one of which, acting constantly, would eventually draw it into the body of the sun itself; but that it is opposed by the other, centrifugal force, and the varying momentum of the revolving mass;—that the same force acting from the centre of the earth itself, and from the centre of every particle of its substance, resolves the whole into a globular form.

The principle of Gravitation[19] is that force which resides in every form of matter, by which particle is attracted by particle, and mass by mass, the less towards the greater. What this may be, we scarcely dare to speculate. In the vast area of its action, which opens before the eye of the mind, we see a power spanning all space, and linking together every one of those myriads of worlds which spangle the robe of the Infinite, and we are compelled to pause. Is this principle of gravitation a property of matter, or is it a power higher than the more tangible forces, is the question which presses on the mind. If we regard it as a subtile principle pervading all space, we compel ourselves to look beyond it for another power yet more refined; and we cannot halt until, ascending from the limitable to the illimitable, we resolve gravitation and its governing influences to the centre of all power—the will of the eternal Creator.

Science has developed the grand truth, that it is by the exercise of this all-pervading influence that the

earth is retained in its orbit—that the pellucid globe of dew which glistens on the leaf is bound together—that the débris which float upon the lake accumulate into one mass—that the sea exhibits the phenomena of the tides—and the aërial ocean its barometric changes. In all things this force is active, and throughout nature it is ever present. Our knowledge of the laws which it obeys, enables us to conclude that the sun and distant planets are consolidated masses like this earth. We find that they have gravitating power, and by comparing this influence with that exerted by the earth, we are enabled to weigh the mass of one planet against another. In the balance of the astronomer, it is as easy to poise the remote star, as it is for the engineer to calculate the weight of the iron tunnel of the Menai Straits, or any other mechanical structure. Thus throughout the universe the balance of gravitating force is unerringly sustained. If one of the most remote of those gems of light, which flicker at midnight in the dark distance of the starry vault, was, by any power, removed from its place, the disturbance of these delicately balanced mysteries would be felt through all the created systems of worlds.

From the peculiarity of the laws which this power called gravity obeys, it has been inferred that it acts from centres of force; it is proved that its power diminishes in the inverse ratio of the square of the distance, and that the gravitating power of every material body is in the direct proportion of its mass. In astronomical calculations we have first to learn the mass of our earth. Experiment informs us that the density of our hardest rock is not above 2·8; but from the enormous pressure to which matter must be subjected, at great depths from the surface, the weight of the superincumbent mass constantly

increasing, it is quite certain that the earth's density must be far more than this. Maskelyne determined the attraction of large masses by a plummet and line on the mountain Schehallion.[20] Cavendish, with exceedingly delicate apparatus, observed the attraction of masses of known weight and size upon each other. Applying the powers of arithmetical calculation, and the data obtained from the small experiments to the larger phenomena, Maskelyne determined the earth's mean density to be 4·71, whilst Cavendish made it 5·48, but the more recent refined investigations of Baily have determined it to be 5·67.[21]

From data thus obtained by severe inductive experiments and mathematical analyses, the astronomer, by observing the deviations of a distant star, is enabled to determine the influence of those stellar bodies near which it passes, and, hence, to calculate the relative magnitudes of each. The accuracy of the law is in this way put to the severest test, and the precision of astronomical prediction is the strongest proof of its universality and truth.

Rolling onward its lonely way, in the far immensity of our system, the planet Uranus was discovered by the elder Herschel,—so great its distance that its diminished light could scarcely be detected by the most powerful telescopes; but since its discovery its path has been carefully watched, and some irregularities noticed. Most of these disturbances were referable to known causes; but a little alteration in its rate of motion observed when the planet was in one portion of its vast orbit was unexplained. Convinced of the certainty of Newton's law, and having determined that the attraction of known masses was insufficient to produce the disturbance

observed, these deviations were referred to the gravitating influence of a mass beyond the known limits of our Solar System. By the investigations of Adams in England,[22] and Le Verrier in France,[23] the place of the hypothetical mass was determined, and its size computed. As a grand confirmation of the great law, and to the glory of those two far-searching minds, who do honour to their respective countries and their age, the hypothesis became a fact, in the discovery of the planet Neptune in the place determined by rigorous calculation. Astronomy affords other examples of the sublime truth of the law of gravitation, than which science can afford no more elevated poetry.

So completely is all nature locked in the bonds of this infinite power, that it is no poetic exaggeration to declare, that the blow which rends any earthly mass is conveyed by successive impulses to every one of the myriads of orbs, which are even too remote for the reach of telescopic vision.

An illustrative experiment must close our consideration of relative operations of rotation and gravitation. We well know that a body in a fluid state would, if suspended above the earth, it being at the same time free to take any form, naturally assume that of a flattened spheroid, from the action of the mass of the earth upon it: whereas the force of cohesive attraction acting equally from all sides of a centre, would, if uninfluenced, necessarily produce a perfect sphere. The best method of showing that this would be the case, is as follows:—

Alcohol and water are to be mixed together until the fluid is of the same specific gravity as olive oil. If, when this is effected, we drop globules of the oil into the mixed fluid, it will be seen that they take an

orbicular form;—and, of course, in this experiment the power of the earth's gravitating influence is neutralized. The same drops of oil under any other conditions would be flattened. Simple as this illustration is, it tells much of the wondrous secret of those beautifully balanced forces of cohesion and of gravitation; and from the prosaic fact we rise to a great philosophical truth. Our experiment may lead us yet farther in exemplification of known phenomena. If we pass a steel wire through one of those floating spheres of oil, and make it revolve rapidly and steadily, thus imitating the motion of a planet on its axis, the oil spreads out, and we have the spheroidal form of our earth. Increase the rapidity of this rotation, and when a certain rate is obtained the oil widens into a disc, a ring separates itself from a central globe, and at a distance from it still revolves around it.[24] Here we have a miniature representation of the ring of Saturn. This is a suggestive experiment, the repetition of which, by reflective minds, cannot fail to lead to important deductions. The phenomena of cohesion, of motion, and gravitation, are all involved; and we produce results resembling, in a striking manner, the conditions which prevail in the planetary spaces, under the influence of the same powers. If we take a glass globe, and having filled it with a fluid of the proper density, drop into it large and small globules of oil, we may produce an instructive representation of the stellar vault, with its beautiful spheres of light revolving in their respective orbits; and though crossing each other's paths, still moving in obedience to attracting and repelling forces—onward in perfect harmony.

From the centre of our earth to the utmost extremity of the universe—from the infinitely small to the

immensely vast—gravitation exerts its force. It is met on all sides by physical powers acting in antagonism to it, but, like a ruling spirit, it restrains them in their wildest moods.

The smallest dust which floats upon the wind
Bears this strong impress of the Eternal Mind.
In mystery round it, subtile forces roll;
And gravitation binds and guides the whole.
In every sand, before the tempest hurl'd,
Lie locked the powers which regulate a world,
And from each atom human thought may rise
With might to pierce the mysteries of the skies,—
To try each force which rules the mighty plan,
Of moving planets, or of breathing man;
And from the secret wonders of each sod,
Evoke the truths, and learn the power of God.

FOOTNOTES:

[13] Three hypotheses may be used to account for this most curious phenomenon.

1st. The body shines by its own light, and then explodes like a sky-rocket, breaking into minute fragments too small to be any longer visible to the naked eye.

2nd. Such a body, having shone by its own light, suddenly ceases to be luminous. "The falling stars and other fiery meteors which are frequently seen at a considerable height in the atmosphere, and which have received different names according to the variety of their figure and size, arise from the fermentation of the effluvia of acid and alkaline bodies which float in the atmosphere. When the more subtile

parts of the effluvia are burned away, the viscous and earthy parts become too heavy for the air to support, and by their gravity fall to the earth."—Keith's *Use of the Globes*. According to Sir Humphry Davy, in the Philosophical Transactions for 1847, "the luminous appearances of shooting stars and meteors cannot be owing to any inflammation of elastic fluids, but must depend upon the ignition of solid bodies."

3. The body shines by the reflected light of the sun, and ceases to be visible by its passing into the earth's shadow, or, in other words, is eclipsed. Upon the two former suppositions the fact of the star's disappearance conveys to us no knowledge of its position, or of its distance from the earth; and all that can be said is, that if it be a satellite of the earth, the great rapidity of its motion involves the necessity of its being at no great distance from the earth's surface—much nearer than the moon; while the resistance it would encounter in traversing the air would be so great that it is probably without the limits of our atmosphere. *Sir J. W. Lubbock leans to the third hypothesis.*—Sir J. W. Lubbock, *On Shooting Stars*: Phil. Mag. No. 213, p. 81.

Sir J. Lubbock also published a supplementary paper on the same subject, in No. 214, p. 170.

Mr. J. P. Joule entertains an hypothesis with respect to Shooting Stars similar to that advocated by Chladni to account for meteoric stones, and he reckons the ignition of these miniature planetary bodies by their violent collision with our atmosphere, to be a remarkable illustration of the doctrine of the equivalency of heat to mechanical power, or *vis viva*.

If we suppose a meteoric stone of the size of a

six-inch cube to enter our atmosphere at the rate of eighteen miles per second of time, the atmosphere being 1/100 of its density at the earth's surface, the resistance offered to the motion of the stone will in this case be at least 51,600 lbs.; and if the stone traverse twenty miles with this amount of resistance, sufficient heat will thereby be developed to give 1° Fahrenheit to 6,967,980 lbs. of water. Of course by far the largest portion of this heat will be given to the displaced air, every particle of which will sustain the shock, whilst only the surface of the stone will be in violent collision with the atmosphere. Hence the stone may be considered as placed in a blast of intensely heated air, the heat being communicated from the surface to the centre by conduction. Only a small portion of the heat evolved will therefore be received by the stone; but if we estimate it at only 1/100 it will still be equal to 1° Fahrenheit per 69,679 lbs. of water, a quantity quite equal to the melting and dissipation of any materials of which it may be composed.—Mr. J. P. Joule, *On Shooting Stars*: Phil. Mag. No. 216, p. 348.

[14] "Laplace conjectures that in the original condition of the solar system, the sun revolved upon his axis, surrounded by an atmosphere which, in virtue of an excessive heat, extended far beyond the orbits of all the planets, the planets as yet having no existence. The heat gradually diminished, and as the solar atmosphere contracted by cooling, the rapidity of its rotation increased by the laws of rotatory motion; and an exterior zone of vapour was detached from the rest, the central attraction being no longer able to overcome the increased centrifugal force. This zone of vapour might in some cases retain its form, as we see it in Saturn's ring; but more usually the

ring of vapour would break into several masses, and these would generally coalesce into one mass, which would revolve about the sun,"—Whewell's *Bridgewater Treatise*.

The following passage is translated by the same author from Laplace:—

"The anterior state (a state of cloudy brightness) was itself preceded by other states, in which the nebulous matter was more and more diffuse, the nucleus being less and less luminous. We arrive in this manner at a nebulosity so diffuse, that its existence could scarce be suspected. Such is in fact the first state of the nebula which Herschel carefully observed by means of his telescope."

Sir William Herschel has the following observations on these remarkable masses:—

"The nature of planetary nebulæ, which has hitherto been involved in much darkness, may now be explained with some degree of satisfaction, since the uniform and very considerable brightness of their apparent disc accords remarkably well with a much condensed, luminous fluid; whereas, to suppose them to consist of clustering stars will not so completely account for the milkiness or soft tint of their light, to produce which it would be required that the condensation of the stars should be carried to an almost inconceivable degree of accumulation.

"How far the light that is perpetually emitted from millions of suns may be concerned in this shining fluid, it might be presumptuous to attempt to determine; but notwithstanding the inconceivable subtilty of the particles of light, when the number of the emitting bodies is almost infinitely great, and the time of the continual emission indefinitely long, the

quantity of emitted particles may well become adequate to the constitution of a shining fluid or luminous matter, provided a cause can be found that may retain them from *flying off, or reunite them*."—*Observations on Nebulous Stars*: Philosophical Transactions, vol. lxxxi. A.D. 1791.

In addition, the following Memoirs on the same subject, by Sir William Herschel, have been published in the Philosophical Transactions:—*Catalogue of 1000 Nebulæ and Clusters of Stars*, vol. lxxvi.; *Catalogue of another 1000, with remarks on the Heavens*, vol. lxxix.; *Catalogue of 500 more, with remarks as above*, vol. xcii.; *Of such as have a cometary appearance*, vol. ci.; *Of planetary nebulæ*, ibid.; *Of stellar nebulæ*, ibid.; *On the sidereal part of the heavens, and its connection with the nebulous*, vol. civ.; *On the relative distances of clusters of nebulous stars*, vol. cviii.

[15] Lord Rosse's beautiful telescopes have been formed upon principles which appear to embrace the best possible conditions for obtaining a reflecting surface which should reflect the greatest quantity of light, and retain that property little diminished for a length of time. The alloy used for this purpose consists of tin and copper in atomic proportions, namely, one atom of tin to four atoms of copper, or by weight 58·9 to 126·4.—*On the Construction of large Reflecting Telescopes*: by Lord Rosse. Report of the Fourteenth Meeting of the British Association, 1844, p. 79.

[16] The best description of the Zodiacal Light occurs in a letter furnished by Sir John Herschel to the *Times* newspaper in March, 1843:—"The zodiacal light, as its name imports, invariably appears in the zodiac, or, to speak more precisely, in the plane of the

sun's equator, which is 7° inclined to the zodiac, and which plane, seen from the sun, intersects the ecliptic in longitude 78° and 258°, or so much in advance of the equinoctial points: in consequence it is seen to the best advantage at, or a little after, the equinoxes; after sunset, at the spring, and before sunrise, at the autumnal equinox; not only because the direction of its apparent axis lies at those times more nearly perpendicular to the horizon, but also because at those epochs we are approaching the situation when it is seen most completely in section.

"At the vernal equinox the appearance of the zodiacal light is that of a pretty broad pyramidal, or rather lenticular, body of light, which begins to be visible as soon as the twilight decays. It is very bright at its lower or broader part near the horizon, and, if there be broken clouds about, often appears like the glow of a distant conflagration, or of the rising moon, only less red, giving rise, in short, to amorphous masses of light such as have been noticed by one of your correspondents as possibly appertaining to the comet. At higher altitudes, its light fades gradually, and is seldom traceable much beyond the Pleiades, which it usually, however, attains and involves, and (what is most to my present purpose) its axis at the vernal equinox is always inclined (to the northward of the equator) at an angle of between 60° and 70° to the horizon, and it is most luminous at its base, resting on the horizon, where also it is broadest, occupying, in fact, an angular breadth of somewhere about 10° or 12° in ordinary clear weather."

[17] "The assumption that the extent of the starry firmament is literally infinite has been

made by one of the greatest of astronomers, the late Dr. Olbers, the basis of a conclusion that the celestial spaces are, in some slight degree, deficient in *transparency*; so that all beyond a certain distance is, and must remain for ever, unseen; the geometrical progression of the extinction of light far outrunning the effect of any conceivable increase in the power of our telescopes. Were it not so, it is argued, every part of the celestial concave ought to shine with the brightness of the solar disc, since no visual ray could be so directed as not, in some point or other of its infinite length, to encounter such a disc."—*Edinburgh Review*, p. 185, for January, 1848; *Etudes d'Astronomie Stellaire*.

[18] In the *Astronomische Nachrichten* of July, 1846, appeared a Memoir by M. Mädler, *Die Centralsonne*. The conclusions arrived at by Mädler may be understood from the following quotation from a French translation, made by M. A. Gautier, in the *Archives des Sciences Physiques et Naturelles*, for October, 1846: —"Quoiqu'il résulte de ce qui précède que la région du ciel que j'ai adoptée satisfait à toutes les conditions posées plus haut, il n'en est pas moins convenable de la soumettre à toutes les épreuves possibles. Plusieurs essais de combinaisons différentes m'ont convaincu qu'on ne pourrait trouver aucun autre point dans le ciel qui pût tenir lieu, même d'une manière approchée, que celui que j'ai adopté. On pourrait maintenant m'addresser l'objection que, si la région du ciel où se trouve le centre de gravité de notre système d'étoiles fixes, est déterminée par ce qui précède entre certaines limites, il n'en résulte pas la nécessité de choisir Alcyone pour ce centre, attendu qu'il pourrait bien tomber sur quelqu'autre étoile située dans le groupe ou

dans son voisinage. Mais outre que c'est tout près de là que se trouve le groupe le plus brillant et le plus riche en étoiles de tout le ciel, et qu'il ne s'agit point ici d'un point arbitraire situé dans le voisinage peu apparent et qui n'ait rien qui le distingue, il ne se trouve nul part, même dans la région voisine, une aussi exacte concordance des mouvements propres qu'ici, et ces mouvements correspondent mieux que tous les autres aux conditions établies plus haut. Or si l'on doit considérer ce groupe central, entre les étoiles également éloignées, on peut présumer que la plus brillante de beaucoup présente la plus grande masse. Outre cela Alcyone, considérée optiquement, est au milieu du groupe des Pleïades; et son mouvement propre, déterminé par Bessel, est plus exactement en accord avec la moyenne de ceux des autres Pleïades; ainsi que des étoiles de cette région jusqu'à 10° de distance. *Je puis donc établir comme conséquence de tout ce qui précède, que le groupe des Pleïades est le groupe central de l'ensemble du système des étoiles fixes, jusqu'aux limites extérieures déterminées par la Voie Lactée; et que Alcyone est l'étoile de ce groupe qui paraît être, le plus vraisemblablement, le vrai Soleil central.*"

[19] See the article *On Gravitation*, Penny Cyclopædia, from the pen of the Astronomer-Royal.

[20] Delambre dates the commencement of modern astronomical observation in its most perfect form from Maskelyne, who was the first who gave what is now called a standard catalogue (A.D. 1790) of stars; that is, a number of stars observed with such frequency and accuracy, that their places serve as standard points of the heavens. His suggestion of the *Nautical Almanack*, and his

superintendence of it to the end of his life, from its first publication in 1767, are mentioned in the *Almanack* (vol. i. p. 364); his *Schehallion Experiment on Attraction* in vol. iii. p. 69; and the character of his *Greenwich Observations in Greenwich Observatory* in vol. ii. p. 442.

[21] *Experiments to determine the Density of the Earth.* By Henry Cavendish, Esq., F.R.S. and F.A.S.—Philosophical Transactions, 1798.

[22] Adams: *An Explanation of the observed irregularities in the motion of Uranus, on the hypothesis of disturbance caused by a more distant Planet.*—Appendix to Nautical Almanack for 1851.

[23] Le Verrier: *Premier Mémoire sur la théorie d'Uranus*, Comptes Rendus, vol. xxi.; *Sur la planête qui produit les anomalies observées dans le mouvement d'Uranus.—Ib.* vol. xxiii.

[24] The experiment alluded to is one of a series by M. Plateau, who thus describes his arrangement of the fluid:—"We begin by making a mixture of alcohol and distilled water, containing a certain excess of alcohol, so that when submitted to the trial of the test tube it lets the small sphere of oil fall to the bottom rather rapidly. When this point is obtained, the whole is thrown upon filters, care being taken to cover the funnels containing these last with plates of glass; this precaution is taken in order to prevent, as much as possible, the evaporation of the alcohol. The alcoholic liquor passes the first through the filters, ordinarily carrying with it a certain number of very minute spherules of oil When the greater part has thus passed, the spherules become more numerous; what still remains in the first filters, namely, the oil and a residue of alcoholic liquor, is then thrown

into a single filter placed on a new flask. This last filtration takes place much more slowly than the first, on account of the viscosity of the oil; it is considerably accelerated by renewing the filter once or twice during the operation. If the funnel has been covered with sufficient care, the oil will collect into a single mass at the bottom of the flask under a layer of alcoholic liquor."—*On the Phenomena presented by a free Liquid Mass withdrawn from the action of Gravity*. By Professor Plateau, of the University of Ghent. Translated from the *Memoirs of the Royal Academy of Brussels*, vol. xvi.; in the *Scientific Memoirs*, vol. iv. part 13.

CHAPTER IV.

MOLECULAR FORCES.

Conditions of Matter—Variety of organized Forms—Inorganic Forms—All matter reducible to the most simple conditions—Transmutation, a natural operation—Chemical Elementary Principles—Divisibility of Matter—Atoms—Molecules—Particles—Molecular Force includes several Agencies—Instanced in the Action of Heat on Bodies—All Bodies porous—Solution—Mixture—Combination—Centres of Force—Different States of Matter (Allotropic Conditions)—Theories of Franklin, Æpinus, and Coulomb—Electrical and Magnetic Agencies—Ancient Notions—Cohesive Attraction, &c.

In contemplating the works of nature, we cannot but regard, with feelings of religious admiration, the infinite variety of forms under which matter is presented to our senses. On every hand the utmost diversity is exhibited; through all things we trace the most perfect order; and over all is diffused the charm

of beauty. It is the uneducated or depraved alone who find deformities in the creations by which we are surrounded.

The three conditions of matter are—the solid, the fluid, and the aëriform; and these belong equally to the organic and the inorganic world.

In organic nature we have an almost infinite variety of animal form, presenting developments widely different from each other, yet in every case suited to the circumstances required by the position which the creature, occupies in the scale of being. Through the entire series, from the Polype to the higher order of animals, even to man, we find a uniformity in the progress towards perfection, and a continuity in the series, which betrays the great secret, that the mystery of life is the same in all,—a pervading spiritual essence associated with matter, and modifying it by the master-mechanism of an Infinite mind.

In the vegetable clothing of the surface of the earth, which fits it for the abode of man and animals—from the confervæ of a stagnant pool, or the lichen of the wind-beaten rocks, to the lordly oak or towering palm—a singularly beautiful chain of being presents itself to the contemplative mind, and we cannot but trace the gradual elevation in the scale of organization.

In the inorganic world, where the great phenomena of life are wanting, we have constantly exhibited the working of powers of a strangely complicated kind. The symmetrical arrangement of crystals—the diversified characters of mineral formations—the systematic aggregations of particles to form masses possessing properties of a peculiar and striking nature—all prove, that agencies, which science, with

all its refinements, has not yet detected, are unceasingly at work. Heat, electricity, chemical power—whatever that may be—and the forces of cohesion, are known to be involved in the production of the forms we see; but contemplation soon leads to the conviction that these powers are subordinate to others which we know not of. We know only the things belonging to the surface of our planet, and these but superficially. The geologist traces rock-formations succeeding each other (from the primary strata holding no traces of organized forms, through the Paleozoic series, in which, step by step, the history of animal life is recorded,) to the more recent formations, teeming with relics, which, though allied to some animal types still existing, are generally such as have passed away. The naturalist searches the earth, the waters, and the air, for their living things; and the diversity of form, the variety of condition, and the perfection of organization which he discovers as belonging to this our epoch—differing from, indeed bearing but a slight relation to, those which mark the earth's mutations—exhibit, in a most striking view, the endless variety of characters which matter can assume.

We are so accustomed to all these phenomena of matter, that it is with some difficulty we can bend ourselves to the study of the more simple conditions in which it exists.

The solid crusts of this telluric sphere—the waters and the atmosphere—the diversified fabrics of the vegetable kingdom—and the still more complicated structures of men and animals—are, altogether, but the aggregation of minute particles in accordance with certain fixed laws. By mechanical means all kinds of matter may be reduced to powder, the fine

particles of which would not appear very different from each other, but each atom has been impressed with properties peculiar to itself, which man has no power to change.

To nature alone belongs the mysterious property of transmutation. The enthusiastic alchemist, by the agency of physical forces, dissipates a metal in vapour; but it remains a metal, and the same metal still. By the Hermetic art he breaks up the combination of masses; but he cannot alter the principles of any one of the elements which form the mass upon which his skill is tried.

Every atom is invested with properties peculiar to all of its class; and each one possesses powers, to which in mute obedience it is compelled, by which these properties are modified, and the character of matter varied. What are those properties? Do we know anything of those powers?

The earth, so far as we are acquainted with it, is composed of about sixty principles, which we call elementary. These are the most simple states to which we can reduce matter, and from them all the forms of creation yet examined by the chemist are produced. These elementary principles are, some of them, permanently gaseous under the ordinary temperature, and others exist as solid masses; the difference between the two conditions being regulated, as it appears, by the opposing forces of heat and cohesive attraction.

Matter has been regarded by some as infinitely divisible; but the known conditions of chemical combinations lead to the conclusion that there are limits beyond which matter cannot be divided.[25] The theory of atoms having determinate characters, and possessing symmetric forms, certainly has the

advantage of presenting to the human mind a starting point—a sort of standing ground,—from which it can direct the survey of cosmical phenomena. The metaphysical hypothesis, which resolves all matter into properties, and refers all things to ideas, leaves the mind in a state of uncertainty and bewilderment.

Adapting the views of Dumas, with some modifications,[26] it will be found more satisfactory to regard the *ultimate atoms* of matter as points beyond the reach of our examination; which, according to a law, determined by the influences of the so-called imponderable forces, unite to form *molecules*. Again, these molecules combine to form the *particles* of the mass which we may regard as the limit of mechanical division. The particles of solid bodies are solid, those of fluids fluid, and those of gaseous bodies are themselves aëriform; but it does not follow that the molecules of any body should be necessarily solid, fluid, or aëriform, from the circumstance of their having formed the particles of a body in one of these states.

As this planet—a molecule in space—is formed of aggregated atoms, and enveloped by its own physical agencies—and as it is involved in the infinitely extending influences of other planetary molecules, and thus forms part of a system—so the molecules of any mass are grouped into a system or particle, which possesses the great characteristic features of the whole.

In an aëriform body the particles are in a state of extreme tenuity, the molecules being themselves, by the influence of some repulsive force, just on the verge where cohesion exerts its decaying power. In fluid bodies the attenuation of the particles is less—

the particles and also the molecules are nearer together,—whereas, in the solid body, the forces of cohesion are most strongly exerted, and all the molecular conditions brought more powerfully into action.

Under the term molecular force, we include several agencies,—not alike in the phenomena which they exhibit, but which are all-powerful in producing the general characteristics of bodies. These require a somewhat close examination. All the particles of even a solid mass may be brought under conditions on which they are free to move. By heat we can increase the length and thickness of a bar of iron, or any other metal, and at length produce the fluid state,—a melted metal flows as freely as water in a stream. Fluids, and gases in like manner obey the dispersive influence of caloric. From these and other analogous results we learn that all bodies have a greater or less degree of porosity. The distance at which the particles of fluid bodies are maintained is strikingly proved by the fact, that hydrated salts dissolved in water occupy no more space than that which is equal to the water contained in the crystalline body; while anhydrous salts dissolve without at all increasing the bulk of the fluid. All the solid matter of the salt must, in these cases, it would appear, go to fill up the interstitial spaces which we suppose to exist in the liquid.[27]

The conditions which regulate the solubility of bodies, and the power of solution, regarded either as a mechanical or a chemical process, are very obscure. We might be led to suppose, that those bodies possessing the largest amount of unoccupied space were capable of holding the greatest quantity of soluble matter dissolved. This, however, is far

from being the case, the denser fluids generally having the greatest solvent power.

The peculiar manner in which hydrogen gas appears to dissolve solid substances,—as iron, potassium, sodium, sulphur, phosphorus, selenium, and arsenic, may be explained by regarding the results as a manifestation of the powers of chemical affinity over the forms of bodies. In like manner, the solution of salt in water, or the mixture of alcohol in that fluid, may be viewed as chemical phenomena, although usually considered as simple cases of solution or mixture: alterations of temperature and other physical changes taking place in either. If two masses of metal,—either tin and copper, for example,—are melted and combined, the united mass will not equal the bulk of the two masses. If a pint measure of oil of vitriol and an equal quantity of water are mixed together, the combined fluids will not fill a two pint measure.[28]

In these instances a large quantity of heat is rendered sensible, as if it had been squeezed out by the force with which the particles combined, from interstices, which were filled with, what we may be allowed to call, an atmosphere of heat. Hence we conclude that, amongst the influences determining the molecular constitution of a body, heat performs an important part. All these facts go to prove that the atoms which form the compound body, whatever may be its character, are disposed of as so many centres of force, which act by influences of a peculiar character upon each other. That these influences are dependent upon known physical forces is certain; but the laws by which the powers of the ultimate atom are altered remain still unknown.

In the great operations of nature, changes are

produced which we cannot understand, and variations of condition do certainly occur, which may be regarded as instances of transmutation.

Amongst others, we may adduce the different states in which we know carbon to exist. We have the diamond with its beautiful light-refracting property, its hardness and high specific gravity, capable of being converted into graphite and coke.[29] Charcoal, graphite, and the diamond, are totally unlike each other, yet we know they are each composed of the same atoms. Charcoal is a black irregular substance, light, and readily inflammable; graphite is crystallizable; but the forms of its crystals cannot be referred to those of the diamond, and it burns with difficulty. The diamond occurs in the most regular and beautifully transparent forms; and it can be burned only at the highest artificial temperatures. We are, however, convinced by experiment that the brilliant and transparent gem is made up of the same atoms as those which go to form the dull black mass of charcoal. From diamonds, as is above stated, coke has been formed by the heat of the voltaic battery, and recent experiments have proved that the volatilized carbon constantly passing off from one of the poles of a sufficiently powerful battery, is deposited in a crystalline powder, possessing most of the properties, as it regards hardness, &c. of true diamond dust. What is the mystery of this? We know not. The peculiar conditions have been the subjects of anxious study; but science has not yet let in a ray of light upon the mystery. That a different state—it has been called an *allotropic* condition—is often induced in the same class of atoms is certain; and hence the variety of the resulting compounds. To continue our illustrations with carbon—may not its combinations, in uniform proportions with oxygen

and hydrogen,[30] owe their differences to some allotropic change in the ultimate atoms of this element.

We know that silicon—the metallic base of flint—is capable of assuming two or more different states; and that sulphur, selenium, phosphorus, and arsenic, are susceptible of these remarkable changes in which, without the slightest variation in the chemical character, a complete change in the physical condition is produced. Copper, iron, tin, and manganese, are known to exist in at least two states of physical dissimilarity, and many of the rarer metals exhibit the same peculiarity.[31] Hence, may we not infer that some of those substances, which we now term elementary, are but altered conditions of the same element? The resemblance between many of those bodies strengthens the supposition. Iridium and platinum,—iron and nickel,—chlorine, bromine, iodine, and probably fluorine,—are good examples of these similarities, although these bodies are all distinguished by physical and chemical differences.

The light-refracting gem, which glistens on the neck of beauty, and is valued for its transparency, differs only from the rude lump of coke in its molecular arrangement. Chemistry teaches us that we may, without producing any disarrangement of the affinities, but by merely setting up molecular disturbance, effect decided changes, as is strikingly shown in the colour of iodide of mercury changing from red to yellow under slight influences of heat, and back again to red by a gentle mechanical disturbance. By a slight change, merely molecular, iron may be made to resemble platinum in its physical properties.[32] An iron wire plunged into nitric acid is attacked by the acid with violence; but

if one extremity of the wire is heated in the flame of a spirit lamp, such a change of state is produced throughout the entire length of the wire, that if it be now plunged into nitric acid no effect is produced upon it. On studying this question, we find good reason for supposing that bodies which, though physically different, resemble each other in some of their properties, iodine, bromine, &c., are the results of different *allotropic* conditions which have been impressed upon the ultimate atoms, similar to those observed in the substances named. This hypothesis appears to be more in accordance with the great principles which we must conceive guided the labours of an Infinite Mind, than that which supposes a vast number of individual creations. It will be seen in the sequel that light, heat, electricity, and chemical action, have the power of producing yet more striking changes in the forms of bodies. Is it not probable that, according to the operations of these agents, either combined or separate, acting over different spaces of time, and under varying circumstances, in relation to the molecular forces, all those *allotropic* states may be produced? Hence bodies may be discovered, which,—from the imperfections of science,—resisting our means of analysis, must, for a time, be regarded as new elements, whereas they are possibly only altered states of the same substance.

The experiments of Faraday and of Plücker prove that all matter exists in certain polar conditions, having powers of mutual attraction and repulsion. [33] Are the molecular forces, so called, to be referred to any of those powers which are involved in the general term magnetic-polarity? Are they not probably the result of some ultimate principle of which these properties are but the modified

manifestations? These questions will now be generally answered in favour of magnetism; but in our ignorance we should pause; the next generation will without doubt find another solution for the problem.

Franklin supposed the ultimate atoms of bodies to be surrounded by a subtile fluid or ether, which they have the power of condensing upon their surfaces with great force—and we have experiments showing that this is probable[34]—whilst he regarded the atoms of the ether itself as mutually repellent, thus establishing an equilibrium of forces. Æpinus reduced the hypothesis of Franklin to a mathematical theory; and Coulomb *proved* that the force with which the repulsion of the ethereal atoms and the attraction of the material molecules are produced, is, like universal attraction,—to whatever power that may be due,—regulated by the law of the inverse ratio of the square of the distance. These views are found, upon minute examination, to hold true to the phenomena with which inductive science has made us acquainted; and the striking manner in which, when submitted to the rigorous investigations of geometers, they agree with known conditions of electricity, appears certainly to favour the opinion that this power may be materially connected with these molecular arrangements.

Many of the phenomena which are connected with the magnetic influences also bear in a remarkable manner upon this inquiry. But, without the necessary proof of direct experimental evidence, it were as unphilosophical to refer the binding together of the molecules of matter to the agency of electricity, as it would be to adopt the theory of the hooked atoms of Epicurus, or the astrological dream of the sympathies

of matter.[35]

Science, however, enables us to infer with safety that the mechanical powers which regulate the constitution of a cube of marble, or a granite mountain, are of a similar order to those which determine the earth's relation to the other planets in the solar system, and that solar system itself a unit, in the immensity of space, to the myriads of suns which spangle the stellar vault.

In fine, cohesion, or the attraction of aggregation, is a power employed in binding particle to particle. To cohesion, we find we have heat opposed as a repellent force; and the mysterious operations of those electrical phenomena, generally referred to as polar forces, are constantly, it is certain, interfering with its powers. In addition, we have seen that in nature there exists an agency which is capable of changing the constitution of the ultimate atoms, and of thus giving variety to each resulting mass. What this power may be, our science cannot tell; but our reason leads us, with firm conviction, to the belief that it is a principle which is, beyond all others in its subtile influences which equally universal with, appears to rise superior to gravitation; and which, like a spirituality, shadows forth to our dwarf conceptions the immensity of the divine power of the omniscient Creator.

The molecular forces involve a consideration of all the known physical powers, the study of which, in their operations on matter, will engage our attention. But it is pleasant to learn, as we advance step by step in our examination of the phenomena of creation, that we may study the grand in what externally appears the simple, and learn, in the mysteries of a particle, the high truths which science has to tell of a

planet.

It may appear that the forces of gravitation and cohesion are regarded as identical. Many phenomena, which we are enabled to reach by the refinements of inductive inquiry, certainly present to us a striking similarity in the laws which regulate the operations of these powers; but it must be remembered that their identity is not established. So far from this, we know the law of gravitating force. Newton determined with surprising accuracy, that the action of this power diminishes with the distance as the universe square, but cohesive force is exerted only at such distances that it is impossible to determine whether or not it is subjected to the same law. To quote the words of Young: "The whole of our inquiries respecting the intimate nature of forces of any kind must be considered merely as speculative amusements, which are of no further utility than as they make our views more general, and assist our experimental investigations."[36]

FOOTNOTES:

[25] "The divisibility of matter is great beyond the power of imagination, but we have no reason for asserting that it is infinite; for the demonstrations which have sometimes been adduced in favour of this opinion are obviously applicable to space only. The infinite divisibility of space seems to be essential to the conception that we have of its nature, and it may be strictly demonstrated that it is mathematically possible to draw an infinite number of circles between any given circle and its tangent, none of which shall touch either of

them except at the general point of contact; and that a ship following always the same oblique course with respect to the meridian,—for example, sailing north-eastwards,—would continue perpetually to approach the pole without ever completely reaching it. But when we inquire into the truth of the old maxim of the schools, that all matter is infinitely divisible, we are by no means able to decide so positively. Newton observes that it is doubtful whether any human means may be sufficient to separate the particles of matter beyond a certain limit; and it is not impossible that there may be some constitution of atoms, or single corpuscles, on which their properties, as matter, depend, and which would be destroyed if the units were further divided; but it appears to be more probable that there are no such atoms, and even if there are, it is almost certain that matter is never thus annihilated in the common course of matter."—*The Essential Properties of Matter*: Young's *Natural Philosophy*; ed. by Rev. P. Kelland.

[26] "Two very different hypotheses have been formed to explain the nature of matter, or the mode of its formation; the one known as the *atomic* theory, the other, the *dynamic*. The founder of the former and earlier was Leucippus: he considered the basis of all bodies to be extremely fine particles, differing in form and nature, which he supposed to be dispersed through space, and to which his follower Epicurus first gave the name of atoms. To these atoms he attributed a rectilinear motion, in consequence of which such as are homogeneous united, whilst the lighter were dispersed through space. The author of the second hypothesis was the famous Kant. He imagined all matter existed, or was originated, by two antagonist and

mutually counteracting principles, which he called attraction and repulsion, all the predicates of which he referred to motion. Most modern philosophers, and foremost amongst them Ampère and Poisson, have adopted an hypothesis combining the features of both the preceding. They regarded the atoms as data, deriving their origin from the Deity as the first cause, and consider their innate attractive and repulsive force as a necessary condition to their combination in bodies. The main features of this hypothesis are borrowed from Aristotle, inasmuch as he supposed the basis of all bodies to be the four elements known to the ancients, the particles of which, endued with certain powers, constituted bodies. According to Ampère, all bodies consist of equal particles, and they again of molecules that, up to a certain distance, attract each other. Their distance from each other he supposed to be regulated by the intensity of the attractive and repulsive forces, the latter of which preponderates."—Peschel's *Elements of Physics*; translated by E. West, 1845.

[27] This was first proved by the researches of Dr. Dalton: the subject will be again alluded to under the consideration of atomic volumes.

[28] These peculiar phenomena may be studied advantageously in the works of most of the eminent European chemists. In our own language the reader is referred to Dr. Thompson's *Outline of the Sciences of Heat and Electricity*, 2nd edition; Brande's *Manual of Chemistry*—Art. *Specific Heat*; Graham's *Elements of Chemistry*; and Daniell's *Introduction to the Study of Chemical Philosophy*.

[29] The conversion of the diamond into graphite and coke was first effected by the

agency of the galvanic arc of flame, by M. Jaquelini, and communicated to the Academy of Sciences in 1847, in a Memoir entitled, *De l'action calorifique de la pile de Bunsen, du chalumeau à gaz oxygène et hydrogène sur le carbon pur, artificiel et naturel*. See *Comptes Rendus*, 1847, vol. xxiv. p. 1050; also *Report of the British Association*, for 1847, (*Transactions of Sections*) p. 50.

[30] "In the annual report on the progress of chemistry, presented to the Royal Academy of Stockholm, in March 1840, I have proposed to designate by the term *allotropic state*, that dissimilar condition which is observed in certain elements, and long known examples of which are found in the different forms of carbon, as graphite and diamond.

"Although these dissimilar conditions, which I have here called allotropic, have long since attracted attention in one or two elements, still they have been regarded as exceptions to the general rule. It is at present my object to show that they are not so rare; that it is probably rather a general property of the elements to appear in different allotropic conditions; and that although we have hitherto been unable to obtain several of the elements when uncombined in their allotropic states, still their compounds indicate the same with tolerable distinctness."—*Berzelius on the Allotropy of the Elementary Bodies*, &c.: Poggendorff's Annalen, 1844. Scientific Memoirs, vol. iv. p. 240.

[31] "Copper, when reduced by hydrogen at a heat below that of redness, on exposure to air soon becomes converted throughout its mass into protoxide; and when it is triturated for some time with an equivalent quantity of sulphur, it combines with it according to Böttcher's experiments, producing flame, and

forming sulphuret of copper. If, however, the copper be reduced by hydrogen at a red heat, still considerably below the temperature at which it softens and begins to melt, it remains for years unchanged by exposure to air, and cannot be made to combine with sulphur without the application of heat. Iron, cobalt, and nickel, when reduced by hydrogen below a red heat, inflame after they have cooled, if exposed to the air; and if they are immediately placed in water to avoid their taking fire, they inflame when they are again removed, and have become nearly dry. If we compare this behaviour with that of iron reduced by heat, and with iron in that state in which it forms the conductor of a galvanic current without becoming oxidized, it would appear that these peculiarities depended upon something more than a difference of mechanical condition."—*Berzelius on the Allotropy of Elementary Bodies.* See *On the Isomeric Conditions of the Peroxide of Tin*: by Prof. H. Rose.—Chemical Gazette, Oct. 1848.

[32] On this curious subject, and its history, see Bergman's *Dissert. de Phlog. quantitate in Metallis*, 1764. Kirwan, *On the Attractive Powers of Mineral Acids*: Philosophical Transactions. Kier's *Experiments and Observations on the Dissolution of Metals in Acids*: Phil. Trans. 1790.

From these valuable papers it will be seen that the peculiar states of iron had already attracted attention, particularly those "inactive conditions" noticed in a "*Note sur la Manière d'agir de l'Acide nitrique sur le Fer, par J. F. W. Herschel*," Aug. 1833; and previously indicated by M. H. Braconnot, *Sur quelques Propriétés de l'Acide nitrique*, Annales de Chimie, vol. lii. p. 54. Reference should also be made to the Memoirs of Sir John Herschel, *On the Action of*

the Rays of the Solar Spectrum on Vegetable Colours, *&c.*: Phil. Trans. vol. cxxxiii. p. 221; and *On the Separation of Iron from other Metals*: Phil. Trans. vol. cxi. p. 293; and several papers by Schönbein, in the Philosophical Magazine, from 1837.

[33] Faraday, in his memoir *On new Magnetic Actions, and on the Magnetic Conditions of all Matter*, says:—"By the exertion of this new condition of force, the body moved may pass either along the magnetic lines or across them, and it may move along or across them in either or any direction, so that two portions of matter, simultaneously subject to this power, may be made to approach each other as if they were mutually attracted, or recede as if mutually repelled. All the phenomena resolve themselves into this, that a portion of such matter, when under magnetic action, tends to move from stronger to weaker places or points of force. When the substance is surrounded by lines of magnetic force of equal power on all sides, it does not tend to move, and is then in marked contradistinction with a linear current of electricity under the same circumstances."—Phil. Trans. for 1846, vol. cxxxvii.

[34] *New Experiments and Observations on Electricity made at Philadelphia, in America.*—Addressed to Mr. Collinson, from 1747 to 1754. By Benjamin Franklin. Of these Priestley remarks:—"It is not easy to say whether we are most pleased with the simplicity and perspicuity with which the author proposes every hypothesis of his own, or the noble frankness with which he relates his mistakes, when they were corrected by subsequent experiments."

[35] "The atomic philosophy of Epicurus, in its mere physical contemplation, allows of

nothing but matter and space, which are equally infinite and unbounded, which have equally existed from all eternity, and from different combinations of which every visible form is created. These elementary principles have no common property with each other; for whatever matter is, that space is the reverse of; and whatever space is, matter is the contrary to. The actual solid part of all bodies, therefore, are matter, their actual pores space, and the parts which are not altogether solid, but an intermixture of solidity and pore, are space and matter combined.

"The infinite groups of atoms, flying through all time and space in different directions and under different laws, have interchangeably tried and exhibited every possible mode of rencounter: sometimes repelled from each other by concussion, and sometimes adhering to each other from their own jagged or pointed construction, or from the casual interstices which two or more connected atoms must produce, and which may be just adapted to those of other figures,—as globular, oval, or square. Hence the origin of compound and visible bodies; hence the origin of large masses of matter; hence, eventually, the origin of the world itself."—Dr. Good's *Book of Nature*.

[36] Young's *Lectures on Natural Philosophy and the Mechanical Arts*. Lecture 49, *On the Essential Properties of Matter*.

CHAPTER V.

CRYSTALLOGENIC FORCES.

Crystallisation and Molecular Force distinguished—Experimental Proof—Polarity of Particles forming a Crystal—Difference between Organic and Inorganic Forms—Decomposition of Crystals in Nature—Substitution of Particles in Crystals—Pseudomorphism—Crystalline Form not dependent on Chemical Nature—Isomorphism—Dimorphism—Theories of Crystallogenic Attraction—Influence of Electricity and Magnetism—Phenomena during Crystallisation—Can a change of Form take place in Primitive Atoms?—Illustrative Example of Crystallisation.

“Crystallisation is a peculiar and most admirable work of nature’s geometry, worthy of being studied by all the power of genius, and the whole energy of the mind, not on account of the delight which always attends the knowledge of wonders, but because of its vast importance in revealing to us the secrets of

nature; for here she does, as it were, betray herself, and, laying aside all disguise, permits us to behold, not merely the results of her operations, but the very processes themselves."—Such is the language of an Italian philosopher, Gulielmini; and it is the striking peculiarity of beholding the process of the formation of the regular geometric figures of crystals, the gradual accretion of particle to particle, which induces us to separate crystallization from mere molecular aggregation. Without doubt the formation of a crystal and the production of an amorphous block are due to powers which bear a close resemblance in many points; but they present remarkable differences in others.

Let us take some simple case in illustration. In quiet water we have very finely divided matter suspended, and matter in a state of solution. The first is slowly precipitated, and in process of time consolidates into a hard mass at the bottom, presenting no particular character, unless it has been placed in some peculiar physical conditions; when, as in nature, we have a regular bedding which is intersected by lines of lamination or of cleavage, which we are, from experiment, enabled to refer to the influence of current electricity. The second—the matter in solution—is also slowly deposited; but it is accumulated upon nuclei which possess some peculiar disposing powers, and every particle is united by some particular face, and an angular figure of the most perfect character results. Many pleasing experiments would appear to show that electricity has much to do in the process of crystallization; but it is evident that it must be under some peculiarly modified conditions that this power is exerted, if, indeed, it has any direct action.

The same substances always crystallize in the same forms, unless the conditions of the crystallizing body are altered. It has been supposed that each particle of a crystalline mass has certain points or poles which possess definite properties, and that cohesion takes place only along lines which have some relation to the attracting or repelling powers of these poles. We shall have, eventually, to consider results which appear to prove that magnetism is universal in its influence, and that this polarity of the particles of matter may be referred to it.

Be the cause of crystallisation what it may, it presents to us in appearance a near approach in inorganic nature to some of the peculiar conditions of growth in the organised creation. In one, we have the gradual production of parts and the formation of members due to peculiar powers of assimilation, each individual preserving all its distinguishing features; and in the other, we have a regular order of cohesion occurring under the influence of a power which draws like to like, and arranges the whole into a form of beauty.

This appears to be the proper place for correcting an error too prevalent, relative to the formation of crystals, the development of cells, and the yet more fatal falsehood of referring the great phenomena of Life to any of the physical forces with which we are acquainted.

THE CRYSTAL *forms*, by the accretion of particle to particle, along lines determined by some yet unknown power. There is no change in the character of any particle—like coheres to like; the first atom and the last of the series being identical in character.

THE PLANT *grows*, not by the gathering together of similar particles of matter, but by the absorption of a

compound particle—by that one which must be regarded as the primary nuclear atom or cell. After this absorption—in virtue of a power which we call LIFE, excited into action by LIGHT—the compound particle is decomposed, and one constituent is retained to effect the formation of a new cell, whilst the other is liberated as an invisible air. Here we have a change of chemical constitution effected; and this takes place through the whole period of vegetable growth, from the development of the plumule up to the formation of the latest leaf upon the topmost branch of the most lordly tree.

Life has been referred to electricity and to chemical power—as the effect of a known cause. Without doubt, during the operations of life the whole of the physical powers are necessary to the production of all the phenomena of growth in the vegetable and the animal world. But these powers are ever subsidiary to vital force, and are like attendant spirits chained to do an enchanter's bidding.

Life is a force beyond the reach of human search, and he who fancies he has a hold upon the principle which produced biological phenomena, has committed himself to as wild a pursuit as he who rashly endeavours to catch a morass-meteor.

Subtile as are the forces of light, heat, and electricity —that of life, *vitality*, is infinitely more refined, and it must for ever elude the search of the philosopher.

Man is permitted to test and try all things which are created, and to apply to useful ends the discoveries which he may make. But man can never become a creator; and he who would attempt to give sense to an inert mass of matter, by electricity, heat, or light, will prove himself as ignorant of nature's truth as is the senseless mass upon which he works.

“So far shalt thou go, and no further,” was said equally to the great tide-wave of human intellect, as to the mighty surge of the earth-girdling ocean.

It must not be forgotten that a striking difference exists between the productions of the mineral and the other kingdoms of nature. Animals and vegetables arrive at maturity by successive developments, and increase by the assimilation of substances, having the power of producing the most important chemical changes upon such matter as comes within the range of their influence; but minerals are equally perfect in the earliest stages of their formation, and increase only, as previously said, by the accretion of particles without their undergoing any change.

The animal and vegetable tribes cease to continue the functions of life: death ensues, and a complete disorganisation takes place; but this is not the case in the mineral world: the crystal being the result of a constantly acting force is not necessarily liable to decomposition.

Nevertheless, we sometimes find in nature that crystals, after arriving at what may be regarded as, in some sort, their maturity, are, owing to a change of the conditions under which they were formed, gradually decomposed. In our mines we discover skeletons of crystals, and within the hollow shell thus formed, other crystals of a different constitution and figure find nuclei, and the conditions required for their development. Again, to give a striking instance, the felspar crystals of the granitic formations are liable to decomposition in a somewhat peculiar manner. In decomposing, these crystals leave moulds of their own peculiar forms, and it not unfrequently happens, in the stanniferous districts of Cornwall,

that oxide of tin gradually fills these moulds, and we procure this metallic mineral in the form of the earthy one. Then we have the curious instances of bodies crystallising in a false form under change of circumstances. We find, for example, Pseudomorphism, (or *false-form*), as this class of phenomena is named, occurring by the removal of the constituent atoms of one crystal, while another set—which naturally assumes a different form—takes their place, yet still preserving the original shape. It often happens that copper pyrites will, in this manner, exhibit the angles of an ordinary variety of crystallised carbonate of iron. These curious changes may be familiarised by supposing a beautiful statue of gold, from which some skilful mechanic removes particle by particle, and so skilfully substitutes a grain of brass for every one of gold removed, that the loss of the precious metal cannot be detected by any mere examination of its form.

Crystalline form is not strictly dependent upon the chemical nature of the parts forming the crystal. The same number of atoms, arranged in the same way, produce the same form. Substances much unlike each other will assume the same crystalline arrangement. Magnesia, lime, oxide of cadmium, the protoxides of iron, nickel, and cobalt, combined with the same acid, present similarly formed bodies. These Isomorphic (*like-form*)[37] peculiarities are exceedingly common, and the discoverer of the phenomena, Mitscherlich, announced the above law. It cannot, however, be regarded as a philosophical expression of the fact, and requires reconsideration—chemical elements of a dissimilar character may have the same law of aggregation, and thus produce the same form, without having any relation to the number of atoms.

We also find compounds which have two distinct systems of crystallisation. This property, Dimorphism, is very strikingly shown in carbonate of lime, which occurs in rhombohedrons, in calc spar, and in rhombic prisms in arragonite. The molecular arrangements here are not, however, of equal stability, and one form is evidently forced upon the other, and is abandoned by it on the slightest disturbance. When a prism of arragonite is heated it breaks up into the rhombs of common calc spar, at a temperature far below that at which the carbonate of lime is decomposed; but no alteration of temperature can convert calc spar into arragonite.

Crystals are found in the most microscopic character, and of an exceedingly large size. A crystal of quartz at Milan is three feet and a quarter long, and five feet and a half in circumference, and its weight is 870 pounds. Beryls have been found in New Hampshire measuring four feet in length.[38]

In the dark recesses of the earth, where the influences which produce organisation and life cease to act, a creative spirit still pursues its never-ending task of giving form to matter.

The science of crystallogeny,[39] embracing the theoretical and practical question of the causes producing these geometric forms, has in various ways attempted to explain the laws according to which molecules arrange themselves on molecules in perfect order, giving rise to a rigidly correct system of architecture. But it cannot be said that any theory yet propounded is sufficiently exact to embrace the whole of the known phenomena, and the questions, —What is crystallogenic attraction, and what is the physical nature of the ultimate particles of matter,— are still open for the inquiries of that genius which

delights in wrestling with the secrets of nature.

The great Epicurus speculated on the “plastic nature” of atoms, and attributed to this *nature* the power they possess of arranging themselves into symmetric forms. Modern philosophers satisfy themselves with attraction, and, reasoning from analogy, imagine that each atom has a polar system.

Electricity, and light, and heat, exert remarkable powers, and accelerate or retard crystallisation according to the conditions under which these forces are brought to bear on the crystallising mass. We have recently obtained evidence which appears to prove that some form of magnetism has an active influence in determining the natural forms of crystals, and we discover that magnetism exerts a peculiar influence in relation to the optic axes of crystals, which is not exerted in lines at right angles to these. Electricity appears to quicken the process of crystalline aggregation—to collect more readily together those atoms which seek to combine—to bring them all within the limits of that influence by which their symmetrical forms are determined; and strong evidence is now afforded, in support of the theory of magnetic polarity, by the refined investigations of Faraday and Plücker, which prove that magnetism has a *directing* influence upon crystalline bodies.[40]

It has been found that crystals of sulphate of iron, slowly forming from a solution which has been placed within the range of sufficiently powerful magnetic force, dispose themselves along certain magnetic curves, such as are formed around a magnet by steel filings; whereas the crystals of the Arbor Dianæ, or silver tree, forming under the same circumstances, take a position nearly at right angles

to these curves. Certain groups of crystals have been found in nature, which appear to show, by their positions, that terrestrial magnetism has been active in producing the phenomena they exhibit; indeed, nearly all our mineral formations indicate the influences of this, or some similarly acting power.[41]

During rapid crystallisation, some salts—as the sulphate of soda, boracic acid, and arsenious acid crystallising in muriatic acid—exhibit decided indications of electrical excitement; light is given out in flashes. We have evidence that crystals exhibit a tendency to move towards the light, and that crystallisation takes place more readily, and progresses with greater activity in the sunshine than in the shade. Professor Plücker has recently ascertained that certain crystals—in particular the cyanite—"point very well to the north, by the magnetic power of the earth only. It is a true compass needle; and, more than that, you may obtain its declination." We must remember that this crystal, the cyanite, is a compound of silica and alumina only. This is the amount of experimental evidence which science has afforded in explanation of the conditions under which nature pursues her wondrous work of crystal formation. We see just sufficient of the operation to be convinced that the luminous star which shines in the brightness of Heaven, and the cavern-secreted gem, are equally the result of forces which are known to us in only a few of their modifications.

Every substance, when placed under circumstances which allow of the free movement of its molecules, has a tendency to crystallise. All the metals may, by slowly cooling from the melting state, be exhibited with a crystalline structure. Of the metallic and

earthy minerals, nature furnishes us with an almost infinite variety of crystals, and, by a reduction of temperature, yet more simple bodies assume the most symmetric forms. Water, in the conditions of ice and snow, is a familiar and beautiful example; and, by such extreme degrees of cold as are artificially produced, many of the gases exhibit a tendency to a crystalline condition.

May not the solid elementary atoms be susceptible of change of form under different influences? May not the different states under which the same bodies are found—as, for example, silica, carbon, and iron—be due entirely to a change in the form of the primitive atom?

Admitting the probability of this, we then easily see that the central molecule, formed of an aggregation of such atoms, uniting by particular faces, would present a determinate form; and that the resulting crystal, a mass of such molecules, cohering according to a given law, at certain angles, would present such geometric figures as we find in nature, or produce in our laboratories, when we avail ourselves of processes which nature has taught us.

If we take a particle of marble, and place it in a large quantity of water acidulated with sulphuric acid, it dissolves, and a new compound results. The marble disappears—the eye cannot detect it by form or colour: the acid also has been disguised—the taste discovers nothing sour in the fluid. We have, in combination with the water, the lime and sulphuric acid; but that combination appears to the eye in no respect different from the water itself. It is colourless and perfectly transparent, although it holds a mass of solid matter which previously would not allow of the permeation of a ray of light. Let us expose this fluid

to such circumstances that the water will slowly evaporate, and we shall find forming in it, after a time, microscopic particles of solid, light-refracting matter. These particles gradually increase in size, and we may watch their growth until eventually we have a symmetric figure, beautifully shaped, the primary form of which is a right rhomboidal prism. Thus in nature, by the action, in all probability, of vegetable matter on the sulphates held in solution by the water of the great rivers and the ocean—aided by our oxidizing atmosphere—sulphuric acid is produced to do its work upon the limestone formations, and from this combination would result the well-known gypsum, or plaster of Paris, which ordinarily exists as an amorphous mass, but is often found in a crystalline form.[42]

This is a very perfect illustration of the wonderful process we have been considering, and in which, simple though it appears to be, we have set to work a large proportion of the known physical elements of the universe. By studying aright the result which we have it in our power to obtain in a watch-glass, we may advance our knowledge of gigantic phenomena, which are now progressing at the bottom of the ocean, or of the wondrous agencies which are in operation, producing light-refracting gems within the secret recesses of the rocky crust of our globe.

The force of crystallisation is a subject worthy of much consideration. If we examine our slate rocks, through which little veins filled with quartz crystals are spread, we shall see that the mechanical force exerted during the production of these crystals has been capable of rending those rocks in every direction. Those fissures formed by the first system of crystalline veins, in order of time, are filled in by

another set of crystalline bodies, which equally exert their mechanical power, and thus produce those curious intersections and dislocations which were long a puzzle to the geologist. The simplest power, slowly and constantly acting through a long period of time, may become sufficient, eventually, to rend the Andes from base to summit, or to lift a new continent above the waters of the ocean.

FOOTNOTES:

[37] "Gay Lussac first made the remark, that a crystal of potash alum, transferred to a solution of ammonia alum, continued to increase without its form being modified, and might thus be covered with alternate layers of the two alums, preserving its regularity and proper crystalline figure. M. Beudant afterwards observed that other bodies, such as the sulphates of iron and copper, might present themselves in crystals of the same form and angles, although the form was not a simple one, like that of alum. But M. Mitscherlich first recognised this correspondence in a sufficient number of cases to prove that it was a general consequence of similarity of composition in different bodies."—Graham's *Elements of Chemistry* (1842), p. 136.

The following remarks are from a paper by Dr. Hermann Kopp, *On the Atomic Volume and Crystalline Condition of Bodies, &c.*, published in the Philosophical Magazine for 1841:—"The doctrine of isomorphism shows us that there are many bodies which possess an analogous constitution, and the same crystalline form. Our idea of the volume (or, in other words, of

the crystalline form) of these bodies must therefore be the same. From this it follows that their specific weight is connected with mass contained in the same volume. From these considerations the following law may be deduced: *The specific weight of isomorphous bodies is proportional to their atomic weight, or isomorphous bodies possess the same atomic volume*."—page 255. A translation appears in the Cavendish Society, from Dr. Otto's Chemistry, *On Isomorphism*, which may be advantageously consulted. See also a paper by M. Rose, translated from the *Proceedings of the Royal Berlin Academy* for the *Chemical Gazette*, Oct. 1848, entitled, *On the Isomeric Conditions of the Peroxide of Tin.*

[38] *A System of Mineralogy, comprising the most recent discoveries*, by James D. Dana, A.M., New York, 1844.

[39] Crystallogeny, or the formation of crystals, is the term employed by Dana, in his admirable work quoted above: whose remarks on *Theoretical Crystallogeny*, p. 71, are well worthy of all attention.

[40] *On the Magnetic Relations of the Positive and Negative Optic Axes of Crystals*, by Professor Plücker, of Bonn.—Philosophical Magazine, No. 231 (3rd Series), p. 450. *Experimental Researches on Electricity; On the Crystalline Polarity of Bismuth and other bodies, and on its Relation to the Magnetic form of Force*: by Michael Faraday, Esq., F.R.S.—Transactions of the Royal Society for 1848.

[41] In the *Memoirs of the Geological Survey of the United Kingdom, and of the Museum of Economic Geology*, vol. i. 1846, will be found a paper, by the author of this volume, *On the Influences of Magnetism on Crystallisation, and other Conditions of Matter*, in which the subject

is examined with much care. See also *Magnétisme polaire d'une montagne de Chlorite schisteuse et de Serpentine*: Annales de Chimie, vol. xxv. p. 327; *Influence du Magnétisme sur les actions chimiques*, by l'Abbé Rendus; and also a notice of the experiments of Ritter and Hansteen, "Analysées par M. Œrsted;" also *Effets du Magnétisme terrestre sur la précipitation de l'Argent, observés par M. Muschman*: Annales de Chimie, vol. xxxviii. p. 196–201.

[42] The transparent varieties of sulphate of lime are distinguished by the name *Selenite*; and the fine massive varieties are called *Alabaster*. Gypsum forms very extensive beds in secondary countries, and is found in tertiary deposits; occasionally, in primitive rocks; it is also a product of volcanoes. The finest foreign specimens are found in the salt mines of Bex, in Switzerland; at Hall, in the Tyrol; in the sulphur-mines of Sicily; and in the gypsum formation near Ocana, in Spain. In England, the clay of Shotover Hill, near Oxford, yields the largest crystals.—See Dana's *Mineralogy*, second edition, p. 241.

CHAPTER VI.

HEAT—SOLAR AND TERRESTRIAL.

Solar and Terrestrial Heat—Position of the Earth in the Solar System—Heat and Light associated in the Sunbeam—Transparency of Bodies to Heat—Heating Powers of the Coloured Rays of the Spectrum—Undulatory Theory—Conducting Property of the Earth's Crust—Convection—Radiation—Action of the Atmosphere on Heat Rays—Peculiar Heat Rays—Absorption and Radiation of Heat by dissimilar Bodies—Changes in the Constitution of Solar Beam—Differences between Transmitted and Reflected Solar Heat—Phenomena of Dew—Action of Solar Heat on the Ocean—Circulation of Heat by the Atmosphere and the Ocean—Heat of the Earth—Mean Temperature—Central Heat—Constant Radiation of Heat Rays from all Bodies—Thermography—Action of Heat on Molecular Arrangements—Sources of Terrestrial Heat—Latent Heat of Bodies—Animal Heat—

Eremacausis—Spheroidal State Cold—Condensation—Freezing—Theories of Heat—Natural Phenomena—and Philosophical Conclusion.

We receive heat from the sun, associated with light; and we have the power of developing this important principle by physical, mechanical, and chemical excitation, from every kind of matter. Our convictions are, that the calorific element, whether derived from a solar or a terrestrial source, presents no essential difference in its physical characters; but as there are some remarkable peculiarities in the phenomena, as they arise from either one or the other source, it will assist our comprehension of this great principle, if we consider it under the two heads.

Untutored man finds health and gladness in the warmth and light of the sun; he rears a rugged altar, and bows his soul in prayer, to the principle of fire, which in his ignorance he regards as the giver and the supporter of life. The philosopher finds life and organization dependent upon the powers combined in the sunbeam; and, examining the phenomena of this wonderful band of forces, he is compelled to acknowledge that the flame upon the altar—on the Persian hills,—was indeed a dim shadow of the infinite wisdom which abides behind the veil.

The present condition of our earth is directly dependent upon the amount of heat we receive from the sun. It has frequently been said, that if it were possible to move this planet so much nearer that orb that the quantity of heat would be increased, the circumstances of life would necessarily be so far

changed, that all the present races of animals must perish; and that the same result would happen from any alteration which threw us yet further from our central luminary, when, owing to the extremity of cold and the wretchedness of gloom, all living creatures would equally fail to support their organization.

To move the earth nearer to, or more distant from the sun, is an impossibility; but it has been argued that those planets which are near to the sun must possess a temperature which would melt our solid rocks, and vaporize the ocean,—while Uranus and Neptune must, from their distance from the source of heat, have so small an amount, that water must become solid as the rock, and such an atmosphere as that of the earth exist as a dense liquid.

It will be shown that according to the physical condition of the material substances, so are their powers regulated of absorbing and retaining the heat which falls as a radiant power upon their surfaces. Heat rays, in passing through the attenuated medium of planetary space, lose none of their power—this we know from the fact that even the less dense upper region of the earth's atmosphere takes from the solar rays but an exceedingly small quantity of heat. Therefore, whether a solar heat ray traverses through one million, or one hundred million miles of space, it still retains its power equally of imparting warmth to the solid matter by which it is intercepted. There is no law of variation as the inverse square of the distance of those radiating powers. Consequently, there is no reason why the physical conditions, alike of the nearest and the most remote planetary bodies, should not be so adjusted that they all enjoy that life promoting temperature which belongs to the earth.

All the objects around us are adapted to the circumstances of the earth's position in relation to the sun, to which we are bound by the principle of gravitation; opposed to that centrifugal force which tends constantly to drive the moving planetary mass off from the centre of power. The balance maintains its perfect equilibrium, although we have one power constantly drawing the earth towards the sun, and the other as constantly exerting itself to move it off into space at a tangent to the orbit in which the planet moves. In our examination it will be found that one common system of harmony runs through all the cosmical phenomena, by which everything is produced that is so beautiful and joyous in this world.

Heat, and the other elementary radiant principles, are often combined as the common cause of effects evident to our senses. The warmth of the solar rays, and their luminous influence, are not, however, commonly associated in the mind as the results of a single cause. It is only when we come to examine the physical phenomena connected with these radiations that we discover the complexity of the inquiry. Yet it is out of these very subtle researches that we draw the most refined truths. The high inferences to which the analysis of the subtile agencies of creation leads us, render science, pursued in the spirit of truth, a great system of religious instruction.

Although we do not fear that heat and light can be confounded in the mind, so different are their phenomena,—we have heat rays, as from dark hot iron, which give no light, while in the full flood of the lunar rays the heat is scarcely appreciable by the most delicate instruments;—yet it is important to show how far these two principles have—been

separated from each other. Transparent bodies have varied powers of calorific transparency, or transcalescence: some obstructing the heat radiated from bodies of the highest temperatures almost entirely even in the thinnest layers; whilst others will allow the warmth of the hand to pass through a thickness of several inches. Liquid chloride of sulphur, which is of a deep red colour, will allow 63 out of 100 rays of heat to pass, and a solution of carmine in ammonia, or glass stained with oxides of gold, or copper, rather a greater number; yet these transparent media obstruct a large quantity of light. Colourless media obstructing scarcely any light, will, on the contrary, prevent the passage of calorific rays. Out of every hundred rays, oil of turpentine will only transmit 31, sulphuric ether 21, sulphuric acid 17, and distilled water only 11. Pure flint glass, however, is permeated by 67 per cent. of the thermic rays, and crown glass by 49 per cent. The body possessing the most perfect transparency to the rays of heat is diaphanous salt-rock, which transmits 92, while alum, equally translucent, admits the passage of only 12 per cent.[43]

Black mica, obsidian, and black glass, are nearly opaque to light, but they allow 90 per cent. of radiant heat to pass through them; whereas a pale green glass, coloured by oxide of copper,[44] covered with a layer of water, or a very thin plate of alum, will, although perfectly transparent to light, almost entirely obstruct the permeation of heat rays.

We thus arrive at the fact that heat and light may be separated from each other; and if we examine the solar beam by that analysis which the prism affords, we shall find that there is no correspondence between intense light and ardent heat. By careful

observation, it has been proved, when we have a temperature of 62° F. in the yellow ray, which ray has the greatest illuminating power; that below the red ray, out of the point of visible light, the temperature is found to be 79°, while at the other end of the spectrum, in the blue ray, it is 56°, and at the end of the violet ray no thermic action can be detected.[45]

From the circumstance, that as we, by artificial means, raise the temperature of any body, and produce intense heat, so after a certain point of thermic elevation has been obtained, we occasion a manifestation of *light*.[46] It has been concluded, somewhat hastily, that heat and light differ from each other only in the rapidity of the undulations of an hypothetical ether.

It must be admitted that the mathematical demonstrations of many of the phenomena of calorific and luminous power are sufficiently striking to convince us that a wave-movement is common to both heat and light. The undulatory theory, however, requires the admission of so many premises of which we have no proof; its postulates are, indeed, in many cases so gratuitous, that notwithstanding the array of talent which stands forward in its support, we must not allow ourselves to be deceived by the deductions of its advocates, or dazzled by the brilliancy of their displays of learning.

Radiant heat appears to move in waves; but that calorific effects in material bodies are established by any system of undulation, is a deduction without a proof; and the thermic phenomena of matter are as easily explained by the hypothesis of a diffusive subtile fluid.

We have not, however, to prove the correctness of

either of the opposing views; indeed, it is acknowledged that many phenomena require for their explanation conditions which are not indicated by either theory.

The earth receives its heat from the sun; a portion of it is *conducted* from particle to particle into the interior of the rocky crust. Another portion produces warmth in the atmosphere around us, by *convection*, or the circulation of particles; those warmed by contact with the surface becoming lighter, and ascending to give place to the colder and heavier ones. A third portion is radiated off into space, according to laws which have not been sufficiently investigated, but which are dependent upon the colour, chemical composition, and mechanical structure of the surface.

It cannot but be instructive to contemplate the indications which we have of the dependence of all that is beautiful on earth, on the heat and light radiations which we receive from the sun. Let us endeavour to realise some of the effects which arise from even the temporary deprivation of solar heat.

It is winter, the vegetable world appears chilled to its centre. The trees, except a few of the hardy evergreens, are bare of leaves, and stretching forth their branches into the cold air, they realise the condition of vegetable skeletons. The lowly plants of the hedge-row, and the grasses of the field, show that their vital power is subdued to that minimum degree of action which is but a few slight removes from death. The life of the running stream is suspended, it is cased in the “thick-ribbed ice,” and the waters beneath no longer send forth their joyous music to the genial breeze. Even within the temperate limits of our own land, the aspect of winter convinces the

ordinary observer, that the loss of heat has been followed by diminished activity in the powers of life; and the philosopher discovers that the lessened energies of solar light, and the weaker action of the radiant heat, have aided in producing that repose which is a little more than sleep—a little less than death.

It is night, and winter: the earth is parting with its heat,—with the absence of light, there is a still greater loss of vigour, a yet further diminution of the powers of life. Even the animal races, sustained by vital influences of a more exalted kind, sink under the temporary deprivation of the solar rays to a monotonous, a melancholy repose. All animals undergo different degrees of hybernation, and each in his winter retreat supports vitality by preying upon himself. The world is hung in mourning black; there is no play of colours to harmonize the human spirit by sending their ethereal pulsations to the human eye, and it is only the consciousness that when the night is at the darkest, the day is nearest, that even man's soul is sustained against the depressing influences of the absence of the sun.

The conditions which we must observe at our own doors cannot fail to convey as a conviction to the least imaginative mind, that a slightly prolonged continuance of darkness, with its consequent increase of coldness, would be fatal to the existence of the organic world.

The sun has entered Aries: it is spring. The length of the day and night are equal, the powers of light and darkness are now exactly balanced against each other, and light, like the Archangel, triumphs over the sombre spirit. The organic world awakes. Chemical action commences in the seed, the vital

spark is kindled in the embryo, and under the impulsive force of some solar radiations the plant struggles into light and life. The same invigorating force impels the circulation of the sap through the capillary tubes of the forest tree, until the topmost branch trembles with the new flow of life. The buds burst forth into leaf, and a fresh and lively covering spreads over those branches which, in their nakedness, could scarcely be distinguished from the dead.

The animal races are no less sensible of the new influence which is diffused around. The birds float joyously upon the breeze, and give to heaven their trilling songs of praise. The beasts come forth from the clefts of the rocks and the tangled shelters of the forests, and gambol in the full luxury of their renewed vigour. Man, even man, the inhabitant of cities, trained and tempered to an artificial state, awakes of a spring morning with a fuller consciousness of mind, and a deeper and more pleased sense of his intelligence, than when the fogs and gloom of winter hung like the charmed robe upon the limbs of the giant. Now, the dormant poetry of man seeks expression. As the morning sun is said to have awakened the musical undulations of the Memnonian statue, so the sun of the vernal morning produces in the mind of the most earthly, faint pulsations of that heaven-born music, which neither sin nor sorrow can entirely destroy. The psychologist, in studying the peculiar phenomena of the human mind, must associate himself with the natural philosopher, and learn to appreciate the influence of physical causes in determining effects which our elder philosophers and the poets of every age have attributed to spiritual agencies.

Summer, with its increased heat and light, reigns over the land. The work of life is now at its maximum, and every energy is quickened throughout the organic creation. The laws of nature are arranged on the principle of antagonistic forces, the constant struggle to maintain them in equilibrium constituting the sensible phenomena of existence. Heat and light, with chemical power and electricity, have been quickening the unknown principle of life, until it has become exhausted in the production of new parts—in the strange phenomenon of growth—the formation of organized matter from the inorganic stores of creation.

The autumn, with its tempered sunlight, comes, but in the solar radiance we discover new powers, and under the influence of these the flower and the fruit have birth. The store of a new life is centered in the seed, and though the leaf falls, and the flower fades, a new set of organisms are produced, by which the continuance of the species is secured.

Let any man examine himself as the seasons change, and he will soon be convinced that every alternation of light and darkness, of heat and its absence, produces new sets of influences equally on the mind and on the body, showing the entire dependence of the animal and vegetable kingdoms upon those causes which appear to flow from the centre of our planetary system.

The phenomena which connect themselves with the changes of the seasons cannot fail to convince the most superficial thinker that there is an intimate connection between the sun and the earth which deserves our close attention.

Indeed, if we examine the most ancient of histories, we find one great fact at the base of all their

philosophies. Moses connects darkness with a void and formless earth, and light with the creation of harmony and life. Menis sings of a fearful world by "many formed darkness encircled," and links the idea of a "life-breathing divinity" with the awakening of light upon created things. The Egyptian Isis, the Grecian Apollo, who,

The Lord of boundless light
Ascending calm o'er the empyrean sails,
And with ten-thousand beams his awful beauty veils,

the fire-worshipper of the Persian hills and the sun-god of the Peruvian mountains, exhibit, through time and space, the full consciousness of man to the influences of solar light and heat upon the organic creations of which he is himself the chief exemplar.

The investigations of modern philosophers have extended these influences to the inorganic masses which constitute the Planet EARTH:—and we now know that the physical forces, ever active in determining the chemical condition and the electrical relations of matter, are directly influenced by the solar radiations.

Few things within the range of our inquiry are more striking than the phenomena of calorific radiation and absorption. They display so perfectly the most refined system of order, and exhibit so strikingly the admirable adaptation of every formation to its particular conditions, and for its part in the great economy of being, that they claim most strongly the study of all who would seek to discover a poetry in the inferences of science.

Owing to the nature of our atmosphere, we are protected from the influence of the full flood of solar

heat. The absorption of caloric by the air has been calculated at about one-fifth of the whole in passing through a column of 6,000 feet. This estimate is, of course, made near the earth's surface; but we are enabled, knowing the increasing rarity of the upper regions of our gaseous envelope in which the absorption is constantly diminishing, to prove, that about one-third of the solar heat is lost by vertical transmission through the whole extent of our atmosphere.[47]

Experience has proved that the conditions of the sun's rays are not always the same; and there are few persons who have not observed that a more than usual scorching influence prevails under some atmospheric circumstances. This is also evidenced in the effects produced on the foliage of trees, which, though often attributed to electricity, is evidently due to heat. An examination of the solar radiations, as exhibited in the prismatic spectrum, has proved the existence of a class of heat rays, which manifest themselves by a very peculiar deoxidizing power quite independent of their caloric properties, to which the name of *parathermic rays* has been given. [48] We are protected from the severe effects of these rays by the ordinary state of the medium through which the solar heat passes. Our atmosphere is a mixture of gases and aqueous vapour; and it has been found, as already stated, that even a thin film of water, however transparent, prevents the passage of many calorific radiations, and the rays retarded are, for the most part, of that class which have this peculiar scorching power. The air is, in this way, the great equaliser of the solar heat, rendering the earth agreeable to all animals, who, but for this peculiar absorbent medium, would have to endure, even in

our temperate clime, the burning rays of a more than African sun.

The surface of the earth during the sunshine—and, though in a less degree, even when the sun is obscured by clouds—is constantly receiving heat; but the rate of its absorption varies. Benjamin Franklin showed, by a set of simple but most conclusive experiments, that a piece of black cloth was warmed much sooner than cloth of a lighter colour;[49] and we know, from observations of a similar class, that the bare brown soil receives heat more readily than the bright green grassy carpet of the earth. Consequently, during the winter season, relatively to the quantity poured from its source, more heat penetrates the uncovered soil, than during the spring or summer.

There is a constant tendency to an equilibrium; and, during the night, the surface is robbed of more heat, by the colder air, than by day; as, when the earth is not receiving heat, it is constantly radiating it back into space. Even in these processes of convection and radiation, a similar law prevails to that which is discovered in examining into the rate of calorific absorption.

Every tree spreading its green leaves to the sunshine, or exposing its brown branches to the air—every flower which lends its beauty to the earth—possesses different absorbing and radiating powers. The chalice-like cup of the pure white lily floating on the lake—the variegated tulip—the brilliant anemony—the delicate rose—and the intensely coloured peony or dahlia—have each powers peculiar to themselves for drinking in the warming life-stream of the sun, and for radiating it back again to the thirsting atmosphere. These are no conceits of a scientific

dreamer; they are the truths of direct induction; and, by experiments of a simple character, they may be put to a searching test.[50]

A thermometric examination of the various coloured flowers, by enclosing a delicate thermometer amongst their leaves, will readily establish the correctness of the one; and by a discovery of recent date, connected with calorific radiation, which must be particularly described presently, we can, with equal ease and certainty, test the truth of the other;[51] the absorption and radiation of heat being directly regulated by the colours of the surfaces upon which the sun rays fall.

It follows, as a natural consequence of the position of the sun, as it regards any particular spot on the earth at a given time, that the amount of heat is constantly varying during the year. This variation regulates the seasons.

When it is remembered that the earth is, in the winter, nearly three millions of miles nearer the sun than in the summer, some explanation is required to account for our suffering more cold when nearer the source of heat, than when at the remotest distance.

The earth in her path around the sun describes an ellipse, the sun's place being one of its foci. In obedience to the law, already described, of the conservation of the axis of rotation, the axis of the earth constantly points towards the star in the constellation of the Little Bear. Recollecting this, and also the two facts, that a dense solid body absorbs heat more readily than a fluid one, and that radiation from the surface is constantly going on when absorption is not taking place, let us follow the earth in her orbit.

It is the time of the vernal equinox—we have equal day and night—therefore the periods of absorption and radiation of heat are alike. But at this time of the year the southern hemisphere is opposite to the sun, consequently the degree of absorption by the wide-spread oceans small.

It is the summer solstice—we have sixteen hours of daylight, when the absorption of heat is going on—and but eight hours of night, during which heat is passing off. The northern hemisphere is now presented to the sun, and as here we have the largest portion of dry land, the powers of absorption are at their maximum.

The autumnal equinox has arrived, with its equal day and night, as in the spring, but now the whole northern hemisphere is opposite the sun; hence, according to the laws already explained, we see the causes of the increased heat of the autumnal season.

The winter solstice has come, with its long night and shortened day. The time during which radiation is going on is nearly twice that in which absorption takes place, and the earth is in her worst position for receiving heat, as that half which has the largest surface of water is towards the sun.

These are the causes which lead to the variations of the seasons, and through these we learn why we are colder when near the sun than when at a considerably greater distance.

An analysis of the spectrum shows us that there are some changes regularly taking place in the state of the solar beam, which cannot be referred to the mere alteration of position. It may be inferred, from facts by long-continued observations, that the three classes of phenomena—light, heat, and chemical power,

distinguished by the term Actinism—which we detect in the sun's rays, are constantly changing their relative proportions. In spring, the chemical agency prevails; in summer, the luminous principle is the most powerful; and in the autumn, the calorific forces are in a state of the greatest activity.[52] The importance of these variations, to the great economy of vegetable life, will be shown when we come to examine the phenomena connected with organisation.

A remarkable change takes place in the character of heat in being reflected from material substances. In nature we often see this fact curiously illustrated. Snow which lies near the trunks of trees or wooden poles melts much quicker than that which is at a distance from them, the sun shining equally on both —the liquefaction commencing on the side facing the sun, and gradually extending. We see, therefore, that the direct rays of solar heat produce less effect upon the snow than those which are radiated from coloured surfaces. By numerous experiments, it has been shown that these secondary radiations are more abundantly absorbed by snow or white bodies than the direct solar rays themselves. Here is one of the many very curious evidences, which science lays open to us, of the intimate connection between the most ethereal and the grosser forms of matter. Heat, by touching the earth, becomes more earth-like. The subtile principle which, like the spirit of superstition, has the power of passing, unfelt, through the crystal mass, is robbed of its might by embracing the things of earth; and although it still retains the evidences of its refined origin, its movements are shackled as by a clog of clay, and its wings are heavy with the dust of this rolling ball. It has, however, acquired new

properties, which fit it for the requirements of creation, and by which its great tasks are facilitated. Matter and heat unite in a common bond, and, harmoniously pursuing the necessities of some universal law, the result is the extension of beautiful forms in every kingdom of nature.

An easy experiment pleasingly illustrates this remarkable change. If a blackened card is placed upon snow or ice in the sunshine, the frozen mass underneath it will be gradually thawed, and the card sink into it, while that by which it is surrounded, although exposed to the full power of solar heat, is but little disturbed. If, however, we reflect the sun's rays from a metal surface, an exactly contrary result takes place; the uncovered parts are the first to melt, and the blackened card stands high above the surrounding portion.

The evidences of science all indicate the sun as the source, not only of that heat which we receive directly through our atmosphere, but even of that which has been stored by our planet, and which we can, by several methods, develope. We have not to inquire if the earth was ever an intensely heated sphere;—this concerns not our question; as we should, even were this admitted, still have to speculate on the origin—the primitive source of this caloric.

Before, however, we proceed to the examination of the phenomena of terrestrial heat, a few of the great results of the laws of radiation and convection claim our attention.

Nearly all the heat which the sun pours upon the ocean is employed in converting its water into vapour at the very surface, or is radiated back from it, to perform the important office of producing those

disturbing influences in the atmosphere, which are essential to the preservation of the healthful condition of the great aërial envelope in which we live.

Currents of air are generally due to the unequal degrees in which the atmosphere is warmed. Heat, by expanding, increases the elasticity, and lessens the density, of a given mass. Consequently, the air heated by the high temperature of the tropics, ascends charged with aqueous vapours, whilst the colder air of the temperate and the frigid zones flows towards the equator to supply its place. These great currents of the atmosphere are, independent of the minor disturbances produced by local causes, in constant flow, and by them a uniformity of temperature is produced, which could not in any other way be accomplished. By these currents, too, the equalisation of the constituents of the "breath of life" is effected, and the purer oxygen of the "land of the sunny south" is diffused in healthful gales over the colder climes of the north. The waters, too, evaporated from the great central Atlantic Ocean, or the far Pacific, are thus carried over the wide-spread continents, and poured in fertilising showers upon distant lands.

How magnificent are the operations of nature! The air is not much warmed by the radiations of caloric passing from the sun to the earth; but the surface soil is heated by its power of absorbing these rays. The temperature of the air next the earth is raised, and we thus have the circulation of those beneficial currents which are so remarkably regular in the Trade Winds. The air heated within the tropics would ascend directly to the poles, were the earth at rest, but being in motion, those great aërial currents

—the Trade Winds—are produced, and the periodical monsoons are due to the same cause. A similar circulation, quite independent of the ordinary tidal movement, takes place also in the earth-girdling ocean. The water, warmed, by convection, from the hot surface of the tropical lands, sets across the Atlantic from the Gulf of Mexico; and being under the influence of the two forces—gravity and motion —it illustrates the parallelogram of forces, and flowing along the diagonal, reaches our own shores: the genial influences of the gulf stream produce that tempered climate which distinguishes our insular home. Here we have two immense influences produced by one agency, rendering those parts of the earth habitable and fertile, which but for these great results would sorrow in the cheerless aspect of an eternal winter.

The beautiful phenomenon of the formation of dew is also distinctly connected with the peculiar properties which we have been studying. When from the bright blue vault of heaven, the sparkling constellations shower their mild light over the earth, the flowers of the garden and the leaves of the forest become moist with a fluid of the most translucid nature. Well might the ancients imagine that the dews were actually shed from the stars; and the alchemists and physicians of the middle ages conceive that this pure distillation of the night possessed subtile and penetrating powers beyond most other things; and the ladies of those olden times endeavour to preserve their charms in the perfection of their youthful beauty through the influences of washes procured from so pure a source.[53]

Science has removed the veil of mystery with which superstition had invested the formation of dew; and,

in showing to us that it is a condensation of vapour upon bodies according to a fixed law of radiation, it has also developed so many remarkable facts connected with the characters of material creations, that a much higher order of poetry is opened to the mind than that which, though beautiful, sprang merely from the imagination.

Upon the radiation of heat depends the formation of dew, and bodies must become colder than the atmosphere before it will be deposited upon them. At whatever temperature the air may be, it is charged to saturation with watery vapour, the quantity varying uniformly with the temperature. Supposing the temperature of the air to be 70° F., and that a bottle of water at 60° is placed in it, the air around the bottle will be cooled, and will deposit on the glass exactly that quantity of moisture which is due to the difference between the temperature of the two bodies. Different substances, independent of colour, have the property of parting with heat from their surfaces at different rates. Rough and porous surfaces radiate heat more rapidly than smooth ones, and are consequently reduced in temperature; and, if exposed, are covered with dew sooner than such as are smooth and dense. The grass parterre glistens with dew, whilst the hard and stony walk is unmoistened.[54]

Colourless glass is very readily suffused with dampness, but polished metals are not so, even when dews are heavily condensed on other bodies. To comprehend fully the phenomena of the formation of dew, we must remember that the entire surface of the earth is constantly radiating heat into space; and that, as by night no absorption is taking place, it naturally cools.[55] As the substances spread over the

earth become colder than the air, they acquire the power of condensing the vapour with which the atmosphere is always charged. The bodies which cover this globe are very differently constituted; they possess dissimilar radiating powers, and consequently present, when examined by delicate thermometers, varying degrees of temperature. By the researches of Dr. Wells,[56] which may be adduced as an example of the best class of inductive experiments, we learn that the following differences in sensible heat were observed at seven o'clock in the evening:—

The air four feet above the grass	60–3/4
Wool on a raised board	54–1/2
Swandown on ditto	53
The surface of the raised board	57
Grass plat	51

Dew is most abundantly deposited on clear, calm nights, during which the radiation from the surface of the earth is uninterrupted. The increased cold of such nights over those obscured by clouds is well known. The clouds, it has been proved, act in the same way as the screens used by gardeners to protect their young plants from the frosts of the early spring, which obstruct the radiation, and, in all probability, reflect a small quantity of heat back to the earth.

It is not improbable that the observed increase in grass crops, when they have been strewn with branches of trees or any slight shades, may be due to a similar cause.[57]

There are many remarkable results dependent entirely on the colours of bodies, which are not

explicable upon the idea of difference in mechanical arrangement. We know that different colours are regulated by the powers which structures have of absorbing and reflecting light; consequently a blue surface must have a different order of molecular arrangement from a red one. But there are some physical peculiarities which also influence heat radiation, quite independently of this *surface* condition. If we take pieces of red, black, green, and yellow glass, and expose them when the dew is condensing, we shall find that moisture will show itself first on the yellow, then on the green glass, and last of all upon the black or red glasses. The same thing takes place if we expose coloured fluids in white glass bottles or troughs, in which case the surfaces are all alike. If against a sheet of glass, upon which moisture has been slightly frozen, we place glasses similarly coloured to those already described, it will be found that the earliest heat-rays will so warm the red and the black glasses, that the ice will be melted opposite to them, long before any change will be seen upon the frozen film covered by the other colours.

The order in which heat permeates coloured media, it has already been shown, very nearly agrees with their powers of radiation.

These most curious results have engaged the attention of Melloni, to whose investigations we owe so much; and from the peculiar order of radiations, which present phenomena of an analogous character to those of the coloured rays of light, obtained by him from dissimilarly coloured bodies, he has been led to imagine the existence of a “heat-colouration.” That is, the heat-rays are supposed to possess properties like luminous colour although invisible;

and, consequently, that a blue surface has a strong affinity for the blue heat-rays, a red surface for the red ones, and so on through the scale. The ingenuity of this hypothesis has procured it much attention; but now, when the Newtonian hypothesis of the refrangibility of light is nearly overturned, we must not, upon mere analogy, rush to the conclusion that the rays of heat have different orders of refrangibility, which Melloni's hypothesis requires. [58]

Can anything be more calculated to impress the mind with the consciousness of the high perfection of natural phenomena, than the fact, that the colour of a body should powerfully influence the transmission of a principle which is diffused through all nature, and also determine the rate with which it is to pass off from its surface. Some recent experiments have brought us acquainted with other facts connected with these heat-radiations, and the power of heat, as influenced by the calorific rays, to produce molecular changes in bodies, which bear most importantly on our subject.

If we throw upon a plate of polished metal a prismatic spectrum (deprived, as nearly as possible, of its chemical power, by being passed through a deep yellow solution—which possesses this property in a very remarkable manner, as will be explained when we come to the examination of the chemical action of the sun's rays)—it will be found, if we afterwards expose the plate to the action of vapour, very slowly raised from mercury, that the space occupied by the red rays, and those which lie without the spectrum below it, will condense the vapour thickly, while the portion corresponding with the other rays will be left untouched. This affords us evidence of the power of solar heat to produce, very

readily, a change in the molecular structure of solid bodies. If we allow the sun's rays to permeate coloured glasses, and then fall upon a polished metallic surface, the result, on exposing the plate to vapourisation, will be similar to that just described. Under yellow and green glasses no vapour will be condensed; but on the space on which the rays permeating a red glass, or even a blackened one, fall, a very copious deposit of vapour will mark with distinctness the spaces these glasses covered. More remarkable still, if these or any other coloured bodies are placed in a box, and a polished metal plate is suspended a few lines above them, the whole being kept *in perfect darkness* for a few hours, precisely the same effect takes place as when the arrangement is exposed to the full rays of the sun. Here we have evidence of the radiating heat of bodies, producing even in darkness the same phenomena as the transmitted heat-rays of the sun. We must, however, return to the examination of some of these and other analogous influences under the head of actino-chemistry.

From these curious discoveries of inductive research we learn some high truths. Associated with light—obeying many of the same laws—moving in a similar manner—we receive a power which is essential to the constitution of our planet. This power is often manifested in such intimate combination with the luminous principle of the solar rays, that it has been suspected to be but another form of the same agency. While, however, we are enabled to show the phenomena of one without producing those which distinguish the other, we are constrained to regard heat as something dissimilar to light. It is true that we appear to be tending towards some point of proof on this problem; but we are not in a position to

declare them to be forms of one common power, or "particular solutions of one great physical equation."[59] In many instances it would certainly appear that one of these forces was directly necessary to the production of the other; but we have also numerous examples in which they do not stand in any such correlation.

We learn, from the scientific facts which we have been discussing, a few of the secrets of natural magic. In their relations to heat, every flower, which adds to the adornment of the wilds of nature or the carefully-tended garden of the florist, possesses a power peculiar to itself;

"Naiad-like lily of the vale,"

and,

"—— The pied wind-flowers, and the tulip tall,
And narcissi, the fairest among them all,"

are, by their different colours, prevented from ever having the same temperatures under the same sunshine.

Every plant bears within itself the measure of the heat which is necessary for its well-being, and is endued with functions which mutely determine the relative amount of dew which shall wet its coloured leaves. Some of the terrestrial phenomena of this remarkable principle will still further illustrate the title of this volume.

To commence with the most familiar illustrations, let us consider the consequences of change of temperature. However slight the additional heat may be to which a body is subjected, it expands under its influence; consequently, every atom which goes to

form the mass of the earth moves under the excitation, and the first heat ray of the morning which touches the earth's surface, sets up a vibration which is continued as a tremor to its very centre. The differences between the temperature of day and night are considerable; therefore all bodies expand under the influence of the higher, and contract under that of the lower temperature. During the day, any cloud obscuring the sun produces, in every solid, fluid, or aëriform body, within the range of solar influence, a check: the particles which had been expanding under the force of heat suddenly contract. Thus there must of necessity be, during the hours of sunshine, a tendency in all bodies to dilate, and during the hours of night they must be resuming their original conditions.

Not only do dissimilar bodies radiate heat in different degrees, but they conduct it also with constantly varying rates. Heat passes along silver or copper with readiness, compared to its progress through platinum. It is conducted by glass but slowly, and still more slowly by wood and charcoal. We receive some important intimations of the molecular structure of matter, from those experiments which prove that heat is conducted more readily along some lines than others. In some planes, wood and other substances are better conductors than in others. The metallic oxides or earths are bad conductors of heat, by which provision the caloric absorbed by the sun's rays is not carried away from the surface of this planet so rapidly as it would have been had it been of metal, but is retained in the superficial crust to produce the due temperature for healthful germination and vegetable growth. The wool and hair of animals are still inferior conductors, and thus, under changes of

climate and of seasons, the beasts of the field are secured against those violent transitions from heat to cold which would be fatal to them. Hair is a better conductor than wool: hence, by nature's alchemy, hair changed into wool in the animals of some countries on the approach of winter, and feathers into down.

It is therefore evident that the rate at which solar heat is conducted into the crust of the earth must alter with the condition of the surface upon which it falls. The conducting power of all the rocks which have been examined is found to vary in some degree. [60]

It follows, as a natural consequence of the position of the sun to the earth, that the parts near the equator become more heated than those remote from it. As this heat is conducted into the interior of the mass, it has a tendency to move to the colder portions of it, and thus the heat absorbed at the equator flows towards the poles, and from these parts is carried off by the atmosphere, or radiated into space. Owing to this, there is a certain depth beneath the surface of our globe at which an equal temperature prevails, the depth increasing as we travel north or south from the equator, and conforming to the contour of the earth's surface, the line sinking under the valleys and rising under the hills.[61]

A question of great interest, in a scientific point of view, is the temperature of the centre of the earth. We are, of course, without the means of solving this problem; but we advance a little way onwards in the inquiry by a careful examination of subterranean temperature at such depths as the enterprise of man enables us to reach. These researches show us, that where the mean temperature of the climate is 50°,

the temperature of the rock at 59 fathoms from the surface is 60°; at 132 fathoms it is 70°; at 239 fathoms it is 80°: being an increase of 10° at 59 fathoms deep, or 1° in 35·4 feet; of 10° more at 73 fathoms deeper, or 1° in 43·8 feet; and of 10° more at 114 fathoms still deeper, or 1° in 64·2 feet.[62]

Although this would indicate an increase to a certain depth of about one degree in every fifty feet, yet it would appear that the rate of increase diminishes with the depth. It appears therefore probable, that the heat of the earth, so far as man can examine it, is due to the absorption of the solar rays by the surface. The evidences of intense igneous action at a great depth cannot be denied, but the doctrine of a cooling mass, and of the existence of an incandescent mass, at the earth's centre, remains but one of those guesses which active minds delight in. The mean annual temperature of this planet is subject to variations, which are probably dependent upon some physical changes in the sun himself, or in the atmospheric envelope by which that orb is surrounded. The variations over the earth's surface are great. At the equator we may regard the temperature as uniformly existing at 80°, while at the poles it is below the freezing point of water; and as far as observations have been made, the subterranean temperatures bear a close relation to the thermic condition of the climate of the surface. The circulation of water through faults or fissures in the strata is, without doubt, one means of carrying heat downwards much quicker than it would be conducted by the rocks themselves. It is not, however, found that the quantity of water increases with the depth. In the mines of Cornwall, unless where the ground is very loose, miners find that, after about 150 fathoms (900 feet), the quantity of

water rapidly diminishes. That water must ascend from very much greater depths is certain, from the high temperatures at which many springs flow out at the surface. In the United Mines in Cornwall, water rises from one part of the lode at 90°; and one of the levels in these workings is so hot that, notwithstanding a stream of cold water is purposely brought into it to reduce the temperature, the miners work nearly naked, and will bathe in water at 80° to cool themselves. At the bottom of Tresavean Mine, in the same county, about 320 fathoms from the surface, the temperature is 100°.

One cause of the great heat of many of our deep mines, which appears to have been entirely lost sight of, is the chemical action going on upon large masses of pyritic matter in their vicinity. The heat, which is so oppressive in the United Mines, is, without doubt, due to the decomposition of immense quantities of the sulphurets of iron and copper known to be in this condition at a short distance from these mineral works.

The heat which man is enabled to measure beneath the earth's surface, appears to be alone due to the conducting powers of the rocks themselves; it has been observed that the line of equal temperature follows, as nearly as possible, the elevations and depressions which prevail upon the surface, and the diminishing rate of increase beyond this line, certainly is such as would arise, was all the heat so measured, the result of the passage of the heat by conduction through the crust of rocks.

Whether or not the subterranean bands of equal heat have any strict relation, upon a large scale, to the isothermic lines which have been traced around most portions of our globe, is a point which has not yet

been so satisfactorily determined as to admit of any general deductions.

The Oriental story-teller makes the inner world a place of rare beauty—a cavern temple, bestudded with self-luminous gems, in which reside the spiritual beings to whom the direction of the inorganic world is confided.

The Philosopher, in the height of his knowledge, has had dreams as absurd as this; and amid the romances of science, there are not to be found any more strange visions than those which relate to the centre of our globe. At the same time it must be admitted, that many of the peculiar phenomena which modern geological researches have brought to light, are best explained on the hypothesis of a cooling sphere, which necessarily involves the existence of a very high temperature towards the centre.

We have already noticed some remarkable differences between solar and terrestrial heat; but a class of observations by Delaroche[63] still requires our attention. Solar heat passes freely through colourless glass, whereas the radiations from a bright fire or a mass of incandescent metal are entirely obstructed by this medium. If we place a lamp or a ball of glowing hot metal before a metallic reflector, the focus of accumulated heat is soon discovered; but if a glass mirror be used, the light is reflected, but not the heat; whereas, with the solar rays, but little difference is detected, whether vitreous or metallic reflectors are employed. It is well known that glass lenses refract both the light and heat of the sun, and they are commonly known as burning-glasses: the heat accumulated at their focal point being of the highest intensity. If, instead of the solar beam, we employ, in our experiments, an intense heat

produced by artificial means, the passage of it is obstructed, and the most delicate thermometers remain undisturbed in the focus of the lens. Glass exposed in front of a fire becomes warm, and by conduction the heat passes through it, and a secondary radiation takes place from the opposite side.[64] It has been found that glass is transcalescent, or *diathermic*, to some rays of terrestrial heat, and *adiathemic*, or opaque for heat, to others[65]—that the capability of permeating glass increases with the temperature of the ignited body—and that rays which have passed one screen traverse a second more readily. It would, however, appear that something more than a mere elevation of temperature is necessary to give terrestrial heat-radiations the power of passing through glass screens, or, in other words, to acquire the properties of solar heat.

To give an example. The heat of the oxy-hydrogen flame is most intense, yet glass obstructs it, although it may be assisted by a parabolic reflector. If this flame is made to play upon a ball of lime, by which a most intense light is produced, the heat, which has not been actually increased, acquires the power of being refracted by a glass lens, and combustible bodies may be ignited in its focus.

It certainly appears from these results, that the undulatory hypothesis holds true, so far as the motion of the calorific power is concerned. At a certain rate the vibrations are thrown back or stopped by the opposing body, while in a state of higher excitation, moving with increased rapidity, they permeate the screen.[66] This does not, indeed, interfere with the refined theory of Prévost,[67] which supposes a mutual and equal interchange of

caloric between all bodies.

The most general effect of heat is the expansion of matter; solids, liquids, and airs, all expand under its influence. If a bar of metal is exposed to calorific action, it increases in size, owing to its particles being separated farther from each other: by continuing this influence, after a certain time the cohesion of the mass is so reduced that it melts, or becomes liquid, and, under the force of a still higher temperature, this molten metal may be dissipated in vapour. It would appear as if, under the agency of the heat applied to a body, its atoms expanded, until at last, owing to the tenuity of the outer layer or envelope of each atom, they were enabled to move freely over each other, or to interpenetrate without difficulty. That heat does really occasion a considerable disturbance in the corpuscular arrangement of bodies, may be proved by a very interesting experiment. A bar of heated metal is placed to cool, with one end supported upon a wedge or a ring of a different metal the other resting on the ground. In cooling, a distinct musical sound is given out, owing to the vibratory action set up among the particles of matter moving as the temperature declines.[68]

Heat is diffused through all bodies in nature, and, as we shall presently see, may be developed in many different ways. We may, therefore, infer, that in converting a sphere of ice into water, and that again into steam, we have done nothing more than interpenetrate the mass with a larger quantity of heat, by which its atoms are more widely separated, and that thus its molecules become free to move about each other. Hence, from a solid state, the water becomes fluid; and then, if the expansive force

is continued, an invisible vapour. If these limits are passed by the powers of any greatly increased thermic action, the natural consequence, it must be seen, will be the separation of the atoms from each other, to such an extent that the molecule is destroyed, and chemical decomposition takes place.

By the agency of the electricity of the voltaic battery, we are enabled to produce the most intense heat with which we are acquainted, and by a peculiarly ingenious arrangement Mr. Grove has succeeded in resolving water by the mere action of heat into its constituent elements—oxygen and hydrogen gases. That this decomposition is not due to the voltaic current, but to the heat produced by it, was subsequently proved by employing platina heated by the oxy-hydrogen flame.[69]

This interesting question has been examined with great care by Dr. Robinson of Armagh, who has shown that, as the temperature of water is increased, the affinity of its elements is lessened, until at a certain point it is eventually destroyed. This new and startling fact appears scarcely consistent with our knowledge that a body heated so as to be luminous has the power of causing the combination of the elements of water with explosive violence.[70] But as this acute experimental philosopher somewhat boldly but still most reasonably inquires: “Is it not probable that, if not light, some other actinic power (like that which accompanies light in the spectrum, and is revealed to us by its chemical effects in the processes of photography) is evolved by the heat, and, though invisible, determines, in conjunction with the affinity, that atomic change which transforms the three volumes of oxygen and hydrogen into two of steam?”[71]

This speculation explains, in a very satisfactory manner, some results which were obtained by Count Rumford, in 1798. In a series of experiments instituted for the purpose of examining "those chemical properties of light which have been attributed to it," he has shown that many cases of chemical decomposition occur in perfect darkness, under the influence of heat, which are precisely similar to those produced by exposure to the sun's rays.[72]

It must, however, be remembered, that both solar light and heat are sometimes found in direct antagonism to actinic power, and that the most decided chemical changes are produced by those rays in which neither heat nor light can be detected. The most remarkable phenomena of this class will be explained under the head of actinism.

One of the most curious relations which as yet have been discovered between light and heat is, that, the temperature at which all bodies become incandescent, excepting such as are phosphorescent, is uniform. The point on the thermometer (Fahrenheit's scale) when the eye by perfect repose is enabled to detect the first luminous influence, may probably be regarded as, or very near, 1000°. Daniel has fixed this point at 980°, Wedgwood at 947°, and Draper at 977°.[73] Dr. Robinson and Dr. Draper, by independent observations, have both arrived at the conclusion, that the first gleam of light which appears from heated platina is not red, but of a lavender gray, the same in character of colour as that detected by Sir John Herschel among the most refrangible rays of the solar spectrum.[74]

It must be admitted, that the question of the identity, or otherwise, of light and radiant heat, is beset with

difficulties. Many of their phenomena are very similar—many of their modes of action are alike: they are often found as allied agencies; but they as frequently exhibit extreme diversity of action, and they may be separated from each other.

We have now examined the physical conditions and properties of this most important element, and we must proceed to learn something of the means by which it may be developed, independently of its solar source.

This extraordinary principle exists in a latent state in all bodies, and may be pressed out of them. The blacksmith hammers a nail until it becomes red hot, and from it he lights the match with which he kindles the fire of his forge. The iron has by this process become more dense, and percussion will not again produce incandescence until the bar has been exposed in fire to a red heat. The only inference we can draw from this result is, that by hammering the particles have been driven closer together, and the heat driven out; now further hammering will not force the atoms nearer, and consequently no additional quantity of heat can be developed; the iron is made hot in a fire, it absorbs heat, the particles are restored to their former state, and we can now again by hammering develope both heat and light. The Indian produces a spark by the attrition of two pieces of wood. By friction, two pieces of ice may be made to melt each other; and could we, by mechanical pressure, force water into a solid state, an immense quantity of heat would be set free. By the condensation of hydrogen and oxygen gases, pulverulent platinum will become glowing red-hot, and, with certain precautions, even the compact metal, platinum, itself; the heat being

derived from the gases, the union of which it has effected. A body passing from the solid to the fluid state absorbs heat from all surrounding substances, and hence a degree of cold is produced. The heat which is thus removed is not destroyed—it is held combined with the fluid; it exists in a latent state. Fluids, in passing into a gaseous form, also rob all surrounding bodies of an amount of heat necessary to maintain the aëriform condition. From the air or from the fluid, this heat may, as we have shown above, be again extracted. Locked in a pint measure of air, there exists sufficient heat to raise several square inches of metal to glowing redness. By the compression of atmospheric air this may be shown, and with a small condensing syringe a sufficient quantity of heat may be set free to fire the *Boletus igniarius*, which, impregnated with nitre, is known as *amadou*. We are acquainted with various sources from which heat may be developed for artificial purposes: the flint-and-steel is an example of the production of heat by mechanical force, and the modern lucifer-match, of the combined action of friction and chemical affinity. These of themselves would admit of a lengthened discourse; but it is necessary that we carefully examine some of the less familiar phenomena of heat under the influences of changes of chemical condition.

If spirits of wine and water are mixed together, a considerable degree of heat is given out, and by mixing sulphuric acid and water, an infinitely larger quantity. If sulphuric acid (oil of vitriol) and spirit of wine, or nitric acid (aquafortis) and spirits of turpentine, at common temperatures, be suddenly mixed, so much heat is set free as to ignite the spirit. In each of these instances there is a condensation of the fluid. In nearly all cases of solution, cold is

produced by the absorption of the heat necessary to sustain the salt in a liquid form; but when potash dissolves in water, heat is given out, which is a fact we cannot yet explain. If potassium is placed on water, it seizes the oxygen of the water and sets fire to the hydrogen gas liberated by the heat produced in the change of form. Antimony and many other metals thrown into chlorine gas ignite and burn with brilliancy: the same phenomenon takes place in the vapours of iodine or bromine. Many chemical combinations, as the chloride of potassium and sulphur explode with a blow; whilst the slightest friction occasions the detonation of the fulminating salts of silver, mercury, and gold. Compounds of nitrogen and chlorine, or iodine, are still more delicately combined—the former exploding with fearful violence on the contact of any oleaginous body, and the latter by the smallest elevation of temperature: both of them destroying the vessels in which they may be contained.

Gun cotton presents some peculiar phenomena which may merit brief attention. This peculiar compound is prepared by the action of nitric acid on cotton fibre. The general appearance of the cotton is not altered, but a remarkable physical change has taken place. It is now soluble in ether, and forms a gelatinous compound:—it explodes violently at a temperature which is insufficient for the combustion of gunpowder. Indeed, from, as it would appear, slight electrical disturbances taking place in the gun cotton itself, it not unfrequently explodes spontaneously. These fearful disturbances of the forces which hold bodies in combination are explained with difficulty. May it not be, that an enormous quantity of the calorific and chemical principles is held in a state of extreme tension around the particles of the

compound, and that the equilibrium being destroyed, the whole is developed in destructive rapidity?

The fact of great heat being evolved during the conversion of a body from a solid to a gaseous state, as in the explosion of gunpowder or gun cotton, which is a striking exception to the law of latent heat, as it prevails in most cases, admits of no more satisfactory explanation.

As mechanical force produces calorific excitation, so we find that every movement of sap in vegetables, and of the blood and fluids in the animal economy, causes a sensible increase of heat. The chemical processes constantly going on in plants and animals are another source of heat, in addition to which nervous energy and muscular movement must be regarded as producing the caloric which is essential to the health and life of the latter. Digestion has been considered as a process of combustion; and the action between the elements of food, and the oxygen conveyed by the circulation of the blood to every part of the body, regarded as the source of animal heat; and, without doubt, it is one great source, although it can scarcely be regarded as the only one. [75]

The *vis vitæ*, or vital power, influences the delicate and beautiful system of nerves; and as life (an essence of the rarest and most subtile order, a diffusive influence) runs through them, from the brain to the extremities of the members of the body, it sets those tender threads in rapid vibration, and heat is developed. By this action, the circulation of the blood is effected; the muscle is maintained in an elastic condition, ready to perform the tasks of the will; and through these agencies is the warm and fluid blood fitted to receive its chemical restoratives

in the lungs, and the stomach to support changes for which it is designed—chemical also—by which more heat is liberated. Was digestion—*Eremacausis*, as the slow combustion produced by combination with oxygen is called—the only source of animal heat, why should the injury of one filmy nerve place a member of the body for ever in the condition of stony coldness? Or why, chemical action being most actively continued after a violent death, by the action of the gastric juices upon the animal tissues, should not animal heat be maintained for a much longer period than it is found to be after respiration has ceased?[76]

In studying the influences of caloric upon the conditions of matter, we must regard the effects of extreme heat, and also of the greatest degrees of cold which have been obtained.

There are a set of experiments by the Baron Cagniard de la Tour, which appear to have a very important bearing on some conditions that may be supposed to prevail in nature, particularly if we adopt the view of a constantly increasing temperature towards the centre of our earth. If water, alcohol, or ether, is put into a strong glass tube of small bore, the ends hermetically sealed, and the whole exposed to a strong heat, the fluid disappears, being converted into a transparent gas; but, upon cooling, it is again condensed, without loss, into its original fluid state. [77] In this experiment, fluid bodies have been converted into elastic transparent gases with but small change of volume, under the pressure of their own atmospheres. We can readily conceive a similar result occurring upon a far more extensive scale. In volcanic districts, at great depths, and consequently under the pressure of the superincumbent mass, the

siliceous rocks, or even metals, may, from the action of intense heat, be brought into a fluid, or even a gaseous condition, without any change of volume, since the elastic force of heat is opposed by the rigid resistance of the pressure of the surrounding rocks. Some beautiful experiments by Mr. Hopkins, of Cambridge, have proved that the temperature necessary to melt a body must be considerably elevated as the mechanical pressure to which it is subjected is increased.

Directly connected with the results of Cagniard de la Tour are a yet more remarkable set of phenomena, which have been investigated by M. Boutigny,[78] and generally known as the “spheroidal condition” of bodies. If water is projected upon very hot metal it instantly assumes a spheroidal form—an internal motion of its particles may be observed—it revolves with rapidity, and evaporates very slowly. If a silver or platinum capsule, when brought to a bright red heat, is filled with cold water, the whole mass assumes the spheroidal state, the temperature of the fluid remaining considerably below the boiling point, so long as the red heat is maintained. If we allow the vessel to cool below redness in the dark, the water then bursts into active ebullition, and is dissipated into vapour with almost explosive violence. An equal quantity of water being projected into two similar vessels, over the fire, one cold and the other red hot, it will be found that the water in the cold vessel will boil and evaporate long before that in the one which is red hot.

Another form of this experiment is exceedingly instructive. If a mass of white hot metal is suddenly plunged into a vessel of cold water, the incandescence is not quenched, the metal shines with

a bright white light, and the water is seen to circulate around, but at some distance from the glowing mass, being actually repelled by calorific agency. At length, when the metal cools, the water comes in contact with it, and boils with energy.

A result similar to this was observed by Perkins, but its correctness most unjustly doubted. Having made an iron shell containing water, and carefully plugged up, white hot, it was found that the steam never exerted sufficient force to burst the vessel, as it was expected it would do. He caused a hole to be drilled into the bottom of the white-hot shell, and he was surprised to find that no water flowed through the orifice, until the iron was considerably cooled, when it issued forth with violence in the form of steam. Here we have the *Cagniard de la Tour state* first induced, and the calorific repulsion of the spheroidal state supervenes. If water is poured upon an iron sieve, the wires of which are made red hot, it will not percolate; but on cooling, it runs through rapidly. M. Boutigny, pursuing this curious inquiry, has recently proved that the moisture upon the skin is sufficient to protect it from disorganization, if the arm is plunged into baths of melted metal. The resistance of the surfaces is so great, that little elevation of temperature is experienced.[79] Professor Plücker, of Bonn, has stated that by washing the arm with ether previously to plunging it into melted metal, the sensation produced, while in the molten mass, is that of freezing coldness.

We have now seen that heat at different degrees of intensity appears to produce chemical composition—that it decomposes combined elements—that it alters the conditions of bodies, and actually maintains so powerfully a repellent force, that fluids cannot touch

the heated body. More than this, it exerts a most powerful antagonistic influence over all chemical relations. If, to give one example, the volatile element iodine is put into a glowing hot capsule, it resolves itself immediately into a spheroid. Potash rapidly combines with iodine; but if a piece of this alkali is thrown upon it in the capsule, it also takes the spheroidal form, and both bodies revolve independently of each other, their chemical affinities being entirely suspended;—but allow the capsule to cool, and they combine immediately. Science teaches us that a temperature so exalted as not to burn organic bodies may be produced, and points to us this remarkable fact, that the destructive limits of heat are measured between certain degrees—beyond which a fire, by reason of its intensity, ceases to develope heat. What is the radiant force into which this principle changes?

The experiments of Cagniard de la Tour and of Boutigny (d'Evreux), connect themselves, in a striking manner, with those of Mr. Grove and Dr. Robinson; and they teach us that but a very slight alteration in the proportions of the calorific principle given to this planet would completely change the character of every material substance of which it is composed, unless there was an alteration in the physical condition of the elements themselves.

Supposing the ordeal of fiery purification to take place upon this earth, these experiments appear to indicate the mighty changes which would thence result. There would be no annihilation, but everything would be transformed from the centre of the globe to the verge of its atmosphere—old things would pass away, all things become new, and the beautiful mythos of the phœnix be realized in the

fresh creation.

The deductions to be drawn from the results obtained by abstracting heat from bodies are equally instructive. By taking advantage of the cooling produced by the rapid solution of salts of several kinds in water, an intense degree of coldness may be produced.[80] Indeed, the absorption of heat by liquefaction may be shown by the use of metallic bodies alone. If lead, tin, and bismuth, are melted together, and reduced to a coarse powder by being poured into water, and the alloy then dissolved in a large quantity of quicksilver, the thermometer will sink nearly 50 degrees. An intense amount of cold will result from the mixture of muriate of lime and snow, by which a temperature of 50° below the zero of Fahrenheit, or 82° below the freezing point of water, is produced. By such a freezing mixture as this, mercury will be rendered solid. A degree of cold, however, far exceeding it, has lately been obtained by the use of solid carbonic acid and ether.[81] Solid carbonic acid is itself procured from the gas liquefied by pressure; which liquid, when allowed to escape into the air, evaporates so rapidly that a large quantity of it is congealed by being robbed of its combined heat by the vaporizing portion. When this solid acid is united with ether, a bath is formed in which the carbonic acid will remain solid for twenty or thirty minutes. By a mixture of this kind, placed under the receiver of an air-pump, a good exhaustion being sustained, a degree of cold 166° below zero is secured. By this intense cold, many of the bodies which have hitherto been known to us only in the gaseous state have been condensed into liquids and solids. Olefiant gas, a compound of hydrogen and carbon, was brought into a liquid form. Hydriodic and hydrobromic acids

could be condensed into either a liquid or a solid form. Phosphuretted hydrogen, a gas which inflames spontaneously when brought into contact with the air or with oxygen, became a transparent liquid at this great reduction of temperature. Sulphurous acid may be condensed, by pressure and a reduction of temperature, into a liquid which boils at 14° Fahrenheit, but by the carbonic acid bath it is converted into a solid body, transparent and without colour. Sulphuretted hydrogen gas solidifies at 122° below zero, and forms a white substance resembling a mass of crystals of sea-salt.

A combination of the two gases, chlorine and oxygen, becomes solid at -75°, and the protoxide of nitrogen at -150°. Cyanogen, a compound of carbon and nitrogen—the base of prussic acid—is solidified at 30° below the zero of our thermometric scale. The well-known pungent compound, ammonia, so exceedingly volatile at common temperatures, is converted into a crystalline, translucent, white substance at the temperature of -103°. The difficulties which necessarily attend the exposure of a body to extreme cold and great pressure at the same time, appear to be the only obstacle to the condensation of oxygen, hydrogen, and nitrogen gases. A sufficient amount of condensation was, however, effected by Dr. Faraday, to lead him to the conclusion, arrived at also by other evidences, that hydrogen, the lightest of the ponderable bodies, partakes of the nature of a metal.[82]

During the solidification of water by freezing, some remarkable facts may be noticed.

Water, in cooling, gradually condenses in volume until it arrives at 40° Fahr., which appears to be the point of greatest density. From this temperature to

that of 32°, the point at which it begins to solidify, its volume remains unchanged,[82] as crystallisation (freezing) begins, the bulk increases, the mass becomes specifically lighter, and it swims on the surface of the fluid. From 40° to 32° the particles of water must be taking up that new position which is essential to the formation of the solid—ice; and while this is taking place, every substance held in solution by the water is rejected.

If we mix with water the deepest colouring matter—the strongest acid or the most acrid poison—they are each and all rejected during the process of freezing, and if the water has been kept in a state of agitation during the process—so that the liberated particles may not be mechanically entangled—the ice will be transparent, colourless, tasteless, and inert—the substances rejected being gathered together in the centre of the frozen mass in a state of intense concentration. In like manner, even the atmospheric air, which is always held in solution, is rejected, and hence the reason why all the ice which forms upon still ponds is full of air-bubbles, while the ice which is produced in agitated water is perfectly free from them. This in itself is a remarkable condition, the entire bearing of which is not clearly understood; but a still more singular fact has been discovered in intimate connection with the rejection of all matter from a freezing solution. Water, which in this way is freed entirely of air, will not boil at 212° F., the ordinary boiling point of water.

If a mass of ice formed in the manner described is placed in a vessel, and being just covered with a film of oil, to prevent the absorption of air, is melted over a lamp or fire, and the heat continued, it will, so far from being converted into steam at 212°, continue to

increase in temperature up to 270° or more, and then burst into ebullition with such explosive violence as to rend the vessel in which it is confined.

From this experiment we learn that did water exist in any other condition than that in which we find it—even with the apparently simple difference of containing no air—it would not be safe to employ it in any culinary or manufacturing operation, since its use would be followed by explosions as dangerous as those of gunpowder.

Such researches as these prove to us the admirable adaptation of all things to their especial ends—the beautiful adjustment of the balance of forces throughout creation.

The refinements of Grecian philosophy saw, without the aids of inductive science, that the outward vesture of nature covered a host of mysterious agencies to which its characteristics were directly due. In their dream of the four elements, fire, the external and visible form of heat, was regarded as the cause of vitality, and the disposer of every organised and unorganised condition of matter. Their idealisations have assumed another form, but the researches of modern science have only established their universality and truth.

The great agents at work in nature—the mighty spirits bound to never-ending tasks, which they pursue with unremitting toil, are of so refined a character, that they will probably remain for ever unknown to us. The arch-evocator, with the wand of induction, calls; but the only answer to his evocation is the manifestation of power in startling effects. Science pursues her inquiries with zeal and care: she tries and tortures nature to compel her to reveal her secrets. Bounds are, however, set to the powers of

mortal search: we may not yet have reached the limits within which we are free to exercise our mental strength; but, those limits reached, we shall find an infinite region beyond us, into which even conjecture wanders eyeless and aimless, as the blind Cyclops groping in his melancholy cave.[83]

All we know of heat is, that striking effects are produced which we measure by sensation, and by instruments upon which we have observed that given results will be produced under certain conditions: of anything approaching to the cause of these we are totally ignorant. The wonder-working mover of some of the grandest phenomena in nature—giving health to the organic world, and form to the inorganic mass—producing genial gales and dire tornadoes—earthquake strugglings and volcanic eruptions—ministering to our comforts in the homely fire, and to advancement in civilisation in the mighty furnace, and the ingenious engine which drains our mines, or traverses our country with bird-like speed,—will, in all probability, remain for ever unknown to man. The immortal Newton, many of whose guesses have a prophetic value, thus expresses himself:—"Heat consists in a minute vibratory motion in the particles of bodies, and this motion is communicated through an apparent vacuum by the undulations of a very subtile elastic medium, which is also concerned in the phenomena of light."

Our experimental labours and our mathematical investigations have considerably advanced our knowledge since the time of Newton; yet still each theory of heat strangely resembles the mystic lamp which the Rosicrucian regarded as a type of eternal life—a dim and flickering symbol, in the tongue-like flame of which imagination, like a child, can conjure

many shapes.

Modern theory regards heat as a manifestation of motion, and experiment proves that a body falling through a certain space generates a definite quantity of heat, while observation shows that the waters at the base of the Falls of Niagara possess a temperature 1° higher than when they first glide over the edge of the precipice.

This increase of temperature is due to the mechanical force due to the fall, and is no more an evidence of the conversion of motion into heat, than is the old experiment of rubbing a button until it becomes hot. At all events, the fact that a given amount of mechanical force always produces an equivalent of heat is as applicable to the idea of a "subtile elastic medium" which is diffused through all matter, as to the, at present, favourite hypothesis.

So far has this view been strained, that the temperature of the planets has been referred to their motions, and speculation has aided the mathematician in determining the cessation of planetary motion, by the conversion of it into heat. It is true that other theorists have supposed points in space upon which this heat might be concentrated and reflected back again to produce motion.

There may be much of the poetic element in such speculations, but it is of that order which belongs rather to the romantic than to the real.

A speculation which has more of truth, and which is, indeed, demonstrable, cannot fail to impress every mind with its beauty, and probable correctness.

In the growth of a tree, its wood and all its products are the result of certain external forces effecting chemical changes. Carbonic acid is decomposed, the

carbon is retained, and oxygen given off, and assimilations of a complex character are in constant progress to produce the various compounds of oxygen, hydrogen, nitrogen, and carbon.

Every condition of organised forms is due to the external excitation of light and heat, and in the chemical changes which take place, an equivalent of these principles, or powers—it signifies but little according to which view we may regard them—is absorbed, and retained as essential to the condition of the matter formed. Let us confine our attention to wood—although the position applies equally to every organic product. A cubic foot of wood is formed by the decomposition of a certain quantity of carbonic acid, by the vital function of the plant, excited by the solar rays, which are involved in the mass which nature by “her wondrous alchemy” has made. Eventually this cubic foot of wood is subjected to a process of chemical change—combustion; by the application of a single spark,—and in the disintegration of the wood, its carbon combining with oxygen to form carbonic acid, its hydrogen to form water, which is returned to the air, a large amount of light and heat is produced. This is exactly equivalent to the amount which was engaged in its formation. Indeed, the sunshine which fell upon the leaves of the forest tree, of which the log formed a part, has been hoarded up, and we again develope it in its original state of heat and light.

The vast coal beds of England were formed by the rapid growth and quick decay of a peculiar class of plants under the influence of a tropical sun. They have been buried myriads of ages, under hundreds of feet of sandy rock. By the industry of the miner the coal is brought again to the surface, and we develope

from it those powers by which it was formed.

In the fire which gives comfort to our homes—in the furnace which generates force for the purposes of manufacture, or to propel the railway engine and its ponderous train—in the gas with which we illumine our streets and gladden during the long winter nights our apartments, we are developing that heat and light which fell upon the earth with all its quickening influences millions of ages before yet the Creator had called into existence the monarch Man, for whose necessities these wondrous formations were designed.

FOOTNOTES:

[43] The following table of the rays penetrating coloured glass has been given by Melloni, in his memoir *On the Free Transmission of Radiant Heat through Different Bodies*:—

Deep violet	53
Yellowish red (flaked)	53
Purple red (flaked)	51
Vivid red	47
Pale violet	45
Orange red	44
Clear blue	42
Deep yellow	40
Bright yellow	34
Golden yellow	33
Deep blue	33

Apple green	26
Mineral green	23
Very deep blue	19

Translated in the Scientific Memoirs, vol. i. p. 30.

[44] “The physical characters of this species of glass, which acts so differently from the other species of coloured glass in all the phenomena of calorific absorption, are, 1st, its intercepting almost totally the rays which pass through alum; 2nd, its entirely absorbing the red rays of the solar spectrum. I have already stated that their colouration is produced almost entirely by the oxide of copper.

“Thus, the colouring matters of the coloured glasses, while they so powerfully affect the relations of quantity which the different rays of ordinary light bear to each other, exercise no elective action on the concomitant calorific rays. This curious phenomenon is the more remarkable as the colouring matters absorb almost always a very considerable portion of the heat *naturally transmitted by the glass*. The following are, in fact, the calorific transmissions of the seven coloured glasses referred to; the transmission of the common glass being represented by 100; red glass, 82·5; orange, 72·5; yellow, 55; bluish-green, 57·5; blue, 52·5; indigo, 30; violet, 85. The quantity of heat absorbed through the action of the colouring substances is, therefore, 17·5 in the red glass, 27·5 in the orange, 45 in the yellow, 42·5 in the green, 47·5 in the blue, 70 in the indigo, and 15 in the violet. Now, as these absorptions extinguish a proportional part of each of the rays which constitute the calorific stream transmitted by common glass, they may be compared, as we said before, with the

absorbent action exercised on light by matters more or less deeply brown or dark, when they are immersed in water, or some other colourless liquid which dissolves, but does not affect them chemically."—*Annales de Chimie et de Physique*, tom. xl. p. 382.

Guided by these principles, the author selected the glass employed in glazing the Royal Palm-House, at Kew Botanical Gardens, where it was desired to obstruct the passage of those rays which have a particular scorching influence. Of this glass a description was given at the meeting of the British Association at Oxford, which appears in the Transactions for that year. The result has been all that could be desired—not a single instance of scorching having occurred during the three years which have elapsed.

[45] In the *Philosophical Transactions*, vol. xc., the following papers, by Sir William Herschel, may be consulted:—

Investigation of the powers of the prismatic colours to heat and illuminate objects; with remarks that prove the different refrangibility of radiant heat. To which is added, an inquiry into the method of viewing the sun advantageously, with telescopes of large apertures and high magnifying powers, p. 255. *Experiments on the refrangibility of the invisible rays of the sun*, p. 284. *Experiments on the solar and on the terrestrial rays that occasion heat; with a comparative view of the laws to which light and heat, or rather the rays which occasion them, are subject; in order to determine whether they are the same or different*, pp. 293, 437.

In connection with this inquiry, Sir William Herschel remarks, that since a *red glass* stops no less than 692 out of 1,000 such rays as are of the refrangibility of red light, we have a

direct and simple proof, in the case of the red glass, that the rays of light are transmitted, while those of heat are stopped, and that thus they have nothing in common but a certain equal degree of refrangibility, which by the power of the glass must occasion them to be thrown together into the place which is pointed out to us by the visibility of the rays of light.

On the same subject, a Memoir, by Sir Henry Englefield, in the Journal of the Royal Institution for 1802, p. 202, may be consulted; and *Researches on Light*, by the Author.

[46] Dr. Draper, *On the production of light by heat*, in the Phil. Mag. for 1847.

Sir Isaac Newton fixed the temperature at which bodies become self-luminous at 635°; Sir Humphry Davy at 812°; Mr. Wedgewood at 947°; and Mr. Daniell at 980°; whilst Dr. Draper from his experiments gives 977°; and Dr. Robinson 865°.

In a review of the above paper by Melloni, entitled *Researches on the Radiations of Incandescent Bodies, and on the Elementary Colours of the Solar Spectrum*, translated for Silliman's Journal for August, 1847, he remarks:—

"I say that they conduct, as do others heretofore known on light and radiant heat, to a perfect analogy between the general laws which govern these two great agents of nature. I will add that I regard the theory of their identity as the only one admissible by the rules of philosophy; and that I consider myself obliged to adopt it, until it shall have been proved to me that there is a necessity of having recourse to two different principles, for the explanation of a series of phenomena

which at present appear to belong to a solitary agent."

Reference should also be made to a paper by Dr. Robinson, *On the effects of Heat in lessening the Affinities of the Elements of Water*, in the Transactions of the Royal Irish Academy, 1848, where he says that "when a platinum wire is traversed by a current gradually increased till it produces ignition, the first gleam that appears is not red, but of a colour which, when I first saw it, I compared to the 'lavender ray' discovered by Sir John Herschel beyond the violet, though I was surprised at seeing the tint of that most refrangible ray preceding the ray which is least so. It is quite conspicuous at about 865°; and as the mode in which it makes its appearance presents nothing abrupt or discontinuous, it seems likely that it is merely a transition from invisible rays excited at a lower temperature to ordinary light."—p. 310.

[47] In the *Bakerian Lecture* for 1842, *On the transparency of the Atmosphere, and the law of extinction of the solar rays in passing through it*, by James D. Forbes, Esq., F.R.S., &c., will be found a most complete investigation of this subject.

The experiments were, for the most part, made in Switzerland with Sir John Herschel's actinometer, and they prove satisfactorily, —"That the absorption of the solar rays by the strata of air to which we have immediate access, is considerable in amount for even moderate thicknesses."

[48] After referring to several curious and instructive experiments, in which peculiar chemical changes are produced under the influence of the solar rays by their HEAT, Sir John Herschel says:—

"These rays are distinguished from those of Light by being invisible; they are also distinguished from the pure calorific rays beyond the spectrum, by their possessing properties (*of a peculiar character, referred to in former papers*) either exclusively of the calorific rays, or in a much higher degree. They may perhaps not improperly be regarded as bearing the same relation to the calorific spectrum which the photographic rays do to the luminous ones. If the restriction to these rays of the term *thermic*, as distinct from *calorific*, be not (as I think, in fact, it is not) a sufficient distinction, I would propose the term *parathermic rays* to designate them. These are the rays which I conceive to be active in producing those singular molecular affections which determine the precipitation of vapours in the experiments of Messrs. Draper, Moser, and Hunt, and which will probably lead to important discoveries as to the intimate nature of those forces resident on the surfaces of bodies, to which M. Dutrochet has given the name of epipolic forces."—*On certain improvements in Photographic Processes, described in a former communication* (Phil. Trans, vol. cxxxiii.); and *On the Parathermic Rays of the Solar Spectrum*, Phil. Trans, vol. cxxxiv.

The experiments of Mrs. Somerville, *On the Action of the Rays of the Spectrum on Vegetable Juices* (Phil. Transactions, vol. cxxxvii.), appear to connect themselves with this particular class of rays in a curious manner.

[49] Experiments on the influence of heat on differently-coloured bodies were first made by Dr. Hooke; and it was not until long after that Franklin made his ingenious experiments. Davy exposed to sunshine six equal pieces of

copper, painted white, yellow, red, green, blue, and black, in such a manner that one side only was illuminated. To the dark side he attached a bit of cerate, ascertained by experiment to melt at 700. The cerate attached to the black became fluid first, the blue next, then the green and red, and lastly the yellow and white.—Beddoes's *Contributions to Physical Knowledge*, and collected works of Sir Humphry Davy, vol. ii. p. 27.

[50] By reference to the Treatise on Heat, in the *Encyclopædia Metropolitana*, numerous suggestive experiments will be found, all bearing on this subject. Peschel's *Elements of Physics* may also be consulted with advantage. The fact is, however, simply proved, as stated in the text, by placing the bulbs of delicate thermometers, so as to be completely involved in the petals of flowers exposed to sunshine, shading the upper portion of the stem of the instrument.

[51] Moser, *On Vision, and on the Action of Light on Bodies*: and also *On Latent Light*: Scientific Memoirs, vol. iii. Draper, *On certain Spectral Appearances, and on the Discovery of Latent Light*: Phil. Mag., Nov. 1842.

[52] A particular examination of this curious question will be found in the Author's report *On the Influence of the Solar Rays on the Growth of Plants*: Reports of the British Association for 1847.

[53] Ammianus Marcellinus ascribes the longevity and robust health of mountaineers to their exposure to the dews of night. Dew was employed by the alchemists in their experiments on the solution of gold. The ladies of old collected the "celestial wash," which they imagined had the virtue of preserving their fine forms, by exposing heaps of wool to

the influences of night radiation. It was supposed that the lean features of the grasshopper arose from that insect feeding entirely on dew: “Dumque thymo pascentur apes, dum rore cicadæ,” Virgil, Eclog.

See some curious remarks by Boyle, *On the Power of Dew in Working on Solid Bodies*: Works of the Honourable R. Boyle, vol. v. p. 121. 1744.

[54] See the *Researches on Heat*, by Professor James Forbes, in the Transactions of the Royal Society of Edinburgh; also Melloni’s papers on the same subject in the *Annales de Chimie*, several of which have been translated into the *Scientific Memoirs*, edited by Mr. Richard Taylor.

[55] The phenomena of dew have constantly engaged the attention of man. Aristotle, in his book *De Mundo*, puts forth some just notions on its nature. An opinion has almost always prevailed that dew falls. Gersten appears to have been the first who opposed this motion. He was followed by Musschenbroek, and then by Du Fay. The researches of Leslie were of a far more exact character. Dr. Wilson, in the Transactions of the Royal Society of Edinburgh, 1st vol., published a *Memoir on Hoar Frost* of much interest; but the questions involved remained unsettled until the researches of Dr. Wells, which were published in his *Essay on Dew*.

[56] By far the most complete set of experiments on the radiation of heat from the surface at night, which have been published since Dr. Wells’s memoir *On Dew*, are those of Mr. Glaisher, of the Royal Observatory at Greenwich. Instruments of the most perfect kind were employed, and the observations made with sedulous care. The results will be

found in a memoir *On the Amount of the Radiation of Heat, at night, from the Earth, and from various bodies placed on or near the Surface of the Earth*, by James Glaisher, Esq., Philosophical Trans. for 1847, part 2.

[57] Dr. Wells noticed the practical fact that very light shades protected delicate plants from frost, by preventing radiation. Mr. Goldsworthy Gurney has made a series of interesting experiments, and he imagines that by shading grasslands with boughs of trees, or any light litter, a more abundant crop is produced. The subject has been discussed in the journals of the Royal Agricultural Society. May not the apparent increase be due entirely to the succulent condition in which a plant always grows in the shade?

[58] This paper of Melloni's will be found in the *Bibliothèque Universelle de Genève*, for 1843. The conclusions are highly ingenious, but they rest entirely on the analogy supposed to be discovered between the relations of heat, like light, to the coloured rays of the spectrum. This, it must be remembered, is not the case, since even Sir William Herschel showed that red light might exist with only a minimum of calorific power, notwithstanding the fact, that the maximum heat-ray of the spectrum coincides with the red rays.

[59] Dr. Robinson, of Armagh, in his Memoir *On the Effects of Heat in lessening the Affinities of the Elements of Water*.—Transactions of the Royal Irish Academy, vol. xxi. part 2.

[60] On this subject consult Robert Were Fox, *On the Temperature of the Mines of Cornwall*.—Cornwall Geological Transactions, vol. ii.; W. J. Henwood, on the same subject, *Ib.* vol. v.; Reports of the British Association, 1840, p. 315; Edinburgh New Philosophical Journal,

vol. xxiv. p. 140.

[61] *On the causes of the temperature of Hot and Thermal Springs; and on the bearings of this subject as connected with the general question regarding the internal temperature of the Earth*: by Professor Gustav Bischoff, of Bonn.—Edinburgh New Philosophical Journal, vol. xx. p. 376; vol. xxiii. p. 330. Some interesting information on the temperature of the ground will be found in Erman's *Travels in Siberia*, translated by W. D. Cooley, vol. i. p. 339; vol. ii. p. 366. *Sur la Profondeur à laquelle se trouve la couche de Température invariable entre les Tropiques*, by Boussingault: Annales de Chimie et de Physique, 1833, p. 225. Reference may also be made to Humboldt's *Cosmos*, Otto's translation; and to the excellent article on *Meteorology*, by George Harvey, in the Encyclopædia Metropolitana. These chthonisothermal lines, as they are called, have been traced by Humboldt and others over extensive districts.

[62] These results are obtained from the valuable observations of Robert Were Fox, Esq., made with great care by that gentleman in several of the Cornish mines: *Report on some observations on Subterranean Temperature*.—British Association Reports, vol. ix. p. 309; Philosophical Magazine, 1837, vol. ii. p. 520.

[63] From his experiments, the following conclusions were arrived at by M. Delaroche:—

1. Invisible radiant heat may, in some circumstances, pass directly through glass.

2. The quantity of radiant heat which passes directly through glass is so much greater, relative to the whole heat emitted in the same direction, as the temperature of the source of

heat is more elevated.

3. The calorific rays which have already passed through a screen of glass, experience, in passing through a second glass screen of a similar nature, a much smaller diminution of their intensity than they did in passing through the first screen.

4. The rays emitted by a hot body differ from each other in their faculty to pass through glass.

5. A thick glass, though as much or more permeable to light than a thin glass of worse quality, allows a much smaller quantity of radiant heat to pass. The difference is so much the less as the temperature of the radiating source is more elevated.

6. The quantity of heat which a hot body yields in a given time, by radiation to a cold body situate at a distance, increases, *cæteris paribus*, in a greater ratio than the excess of temperature of the first body above the second.—Journal de Physique, vol. lxxv.

[64] Sir David Brewster differs from the conclusions arrived at by Delaroche. He thus explains his views:—"The inability of radiant heat to pass through glass, may be considered as a consequence of its refusing to yield to the refractive force; for we can scarcely conceive a particle of radiant matter freely permeating a solid body, without suffering some change in its velocity and direction. The ingenious experiments of M. Prévost, of Geneva, and the more recent ones of M. Delaroche, have been considered as establishing the permeability of glass to radiant heat. M. Prévost employed moveable screens of glass, and renewed them continually, in order that the result which he obtained might not be ascribed to the heating

of the screen; but such is the rapidity with which heat is propagated through a thin plate of glass, that it is extremely difficult, if not impossible, to observe the state of the thermometer before it has been affected by the secondary radiation from the screen. The method employed by M. Delaroche, of observing the difference of effect, when a blackened glass screen and a transparent one were made successively to intercept the radiant heat, is liable to an obvious error. The radiant heat would find a quicker passage through the transparent screen; and, therefore, the difference of effect was not due to the transmitted heat, but to the heat radiated from the anterior surface. The truth contained in M. Delaroche's fifth proposition is almost a demonstration of the fallacy of all those that precede it. He found that 'a thick plate of glass, though as much or more permeable to light than a thin glass of worse quality, allowed a much smaller quantity of radiant heat to pass.' If he had employed very thick plates of the purest flint glass, or thick masses of fluid that have the power of transmitting light copiously, he would have found that not a single particle of heat was capable of passing directly through transparent media."—Sir D. Brewster, *On new properties of heat as exhibited in its propagation along plates of glass*. Philosophical Transactions, vol. cvi. p. 107.

[65] *Proposal of a New Nomenclature for the Science of Calorific Radiations*, by M. Melloni. Bibliothèque Universelle de Genève, No. 70. Scientific Memoirs, vol. iii. part 12. Many of the terms, as *Diathermasy*, or transparency for heat; *Adiathermasy*, opacity for heat; *Thermochroic*, coloured for heat, and others, are valuable suggestions of forms of expression which are required in dealing with these

physical phenomena.

[66] For a careful examination of the several theories of heat consult Dr. Young's Course of Lectures on Natural Philosophy, &c., Lecture 52, *On the Measures and the Nature of Heat*; also Powell's very excellent *Reports on Radiant Heat* —Reports of the British Association, 1832, 1840. The transcendental view which the immaterial theory leads to, cannot be better exemplified than by the following quotation from that inexplicable dream of a talented man, *Elements of Physiophilosophy*, by Lorenz Oken, M.D. (translated for the Ray Society, by Alfred Tulk):—

"Heat is not matter itself any more than light is; but it is only the act of motion in the primary matter. In heat, as well as in light, there certainly resides a material substratum; yet, this substratum does not give out heat and light; but the *motion* only of the substratum gives out heat, and the *tension* only of the substratum light. There is no body of heat; nitrogen is the body of heat, just as oxygen may be called the body of fire. Heat is real space; into it all forms have been resolved, as all materiality has been resolved into gravity, and all activity, all polarity, into light. Heat is the universal form, consequently the want of form."

[67] Mémoires de la Société Physique, &c., de Genève, tom. ii. art. 2.

[68] This curious phenomenon was first observed by Mr. Trevelyan, whose *Notice regarding some Experiments on the Vibration of Heated Metals* will be found in the Transactions of the Royal Society of Edinburgh, vol. xii., 1837. In a Memoir in the same volume, entitled *Experimental Researches regarding certain vibrations which take place between*

metallic masses having different temperatures, Professor Forbes draws the following conclusions:—

1. “The vibrations never take place between substances of the same nature.

2. “Both substances must be metallic. (This is now proved not to be necessary.)

3. “The vibrations take place with an intensity proportional (within certain limits) to the difference of the conducting powers of the metals for heat or electricity; the metal having the least conducting power being necessarily the coldest.

4. “The time of contact of two points of the metals must be longer than that of the intermediate portions.

5. “The impulse is received by a distinct and separate process at each contact of the bar and block, and in no case is the metallic connection of the bearing points in the bar, or those of the block, in any way essential.

6. “The intensity of the vibration is (under certain exceptions) proportional to the difference of temperature of the metals.”—Transactions of the Royal Society of Edinburgh, vol. xii.

[69] The Bakerian Lecture. *On certain Phenomena of Voltaic Ignition, and the Decomposition of Water into its Constituent Gases by Heat*: by W. R. Grove, Esq.—Philosophical Transactions, 1847. Part 1.

[70] Davy’s *Researches on Flame*. Works, vol. vi.—Philosophical Transactions for 1817.

[71] *On the Effect of Heat in lessening the affinities of the Elements of Water*: by the Rev. Thomas Romney Robinson, D.D.—Transactions

of the Royal Irish Academy, vol. xxi. part 2.

[72] *An Inquiry concerning the Chemical Properties that have been attributed to Light*: by Benjamin, Count of Rumford.—Philosophical Transactions, vol. lxxxviii. p. 449.—The results obtained by Count Rumford were probably due to the non-luminous heat-rays—parathermic rays—which are known to be given off by boiling water.

[73] For Dr. Drapers paper, see Philosophical Magazine for May, 1847, vol. xxx. 3rd series.

[74] *On the Action of the Rays of the Solar Spectrum on Vegetable Colours*: by Sir J. F. W. Herschel, Bart.

The proof of the continuation of the visible prismatic spectrum beyond the extreme violet may be witnessed in the following manner:—"Paper stained with tincture of turmeric is of a yellow colour; and, in consequence, the spectrum thrown in it, if exposed in open daylight, is considerably affected in its apparent colours, the blue portion appearing violet, and the violet very pale and faint; but beyond the region occupied by the violet rays, is distinctly to be seen a faint prolongation of the spectrum, terminated laterally, like the rest of it, by straight and sharp outlines, and which, in this case, affects the eye with the sensation of a pale yellow colour."—Philosophical Transactions, p. 133.

[75] The most complete exposition of the theory that animal heat is derived from chemical action only, will be found in *Animal Chemistry, or Chemistry in its applications to Physiology and Pathology*, by Justus Liebig: translated by Dr. Gregory. The conclusions arrived at by the author, notwithstanding his high—and deservedly high—position in

chemical science, must, however, be received with great caution, many of them being founded on most incorrect premises, and his generalizations being of the most hasty and imperfect character. At page 22 the following passage occurs:—"If we were to go naked, like certain savage tribes, or if in hunting or fishing we were exposed to the same degree of cold as the Samoiedes, we should be able, with ease, to consume ten pounds of flesh, and, perhaps, a dozen of tallow candles into the bargain, daily, as warmly clad travellers have related with astonishment of these people. We should then also be able to take the same quantity of brandy or train-oil without bad effects, because the carbon and hydrogen of these substances would only suffice to keep up the equilibrium between the external temperature and that of our bodies."

A brief examination will exhibit the error of this. The analysis of Beef, by D. Lyon Playfair, is as follows:—

Carbon	51·83
Hydrogen	7·57
Nitrogen	15·01
Oxygen	21·37
Ashes	4·23

And the following has been given by Chevreul as the composition of mutton tallow:—

Carbon	96
Hydrogen	16
Nitrogen	16
Oxygen	48

About three times the quantity of oxygen to the carbon eaten, is required to convert it into

carbonic acid; hence, the Samoiede, eating more highly carbonized matter, must inspire 288 oz. of oxygen daily, or nearly eight times as much as the “ordinary adult.” By the lungs he must take into the body 2,304 cubic feet of air besides what will be absorbed by the skin. His respirations must be so much quickened, that at the lowest possible calculation he must have 500 pulsations a minute. Under such conditions it is quite clear man could not exist. There is no disputing the fact of the enormous appetites of these people; but all the food is not removed from the system as carbonic acid gas.

[76] An interesting paper by Dr. Davy, *On the Temperature of Man*, will be found in the Philosophical Transactions, vol. cxxxvi. p. 319. —Sir Humphry Davy, in his *Consolations in Travel, or the Last Days of a Philosopher*, in his fourth dialogue, *The Proteus*, has several ingenious speculations on this subject.

[77] *Exposé de quelques résultats obtenus par l’action combinée de la chaleur et de la compression sur certains liquides, tels que l’eau, l’alcool, l’éther sulfurique, et l’essence de pétrole rectifiée*: par M. le Baron Cagniard de la Tour.

The three following conclusions are arrived at: —

1. Que l’alcool à 36 degrés, l’essence de pétrole rectifiée à 42 degrés, et l’éther sulfurique soumis à l’action de la chaleur et de la compression, sont susceptibles de se réduire complètement en vapeur sous un volume un peu plus que double de celui de chaque liquide.

2. Qu’une augmentation de pression, occasionnée par la présence de l’air dans plusieurs des experiences qui viennent d’être

citées, n'a point apporté d'obstacle à l'évaporation du liquide dans le même espace; qu'elle a seulement rendu sa dilatation plus calme et plus facile à suivre jusqu'au moment où le liquide semble s'évanouir tout-à-coup.

3. Que l'eau, quoique susceptible sans doute d'être réduite en vapeur très-comprimée, n'a pu être soumise à des experiences complètes, faute de moyens suffisans pour assurer l'exacte fermeture de la marmite de compression, non plus que dans les tubes de verre dont elle altère la transparence en s'emparant de l'alcali qui entre dans leur composition.—Annales de Chimie, vol. xxi.

[78] *Sur les phénomènes qui présentent les corps projetés sur des surfaces chaudes*: par M. Boutigny (d'Evreux).—Annales de Chimie et de Physique, vol. xi. p. 16. *Congélation du mercure en trois secondes, en vertu de l'état sphéroïdal dans un creuset incandescent*: by M. Faraday.—Ibid., vol. xix. p. 383.

Spheroidal Condition of Bodies (Extrait d'une Note de M. Boutigny d'Evreux).

"Au nombre des propriétés des corps à l'état sphéroïdal, il en est cinq qui me paraissent caractéristiques et fondamentales, et c'est sur ces cinq propriétés que je base la définition que je soumets aujourd'hui au jugement de l'Académie. Ces cinq propriétés sont:—

"1. La forme arrondie que prend la matière sur une surface chauffée à une certaine température.

"2. Le fait de la distance permanente qui existe entre le corps à l'état sphéroïdal et le corps sphéroïdalisant.

"3. La propriété de réfléchir le calorique rayonnant.

"4. La suspension de l'action chimique.

"5. La fixité de la température des corps à l'état sphéroïdal.

"Cela posé, voici la définition que je propose: un corps projeté sur une surface chaude est à l'état sphéroïdal quand il revêt la forme arrondie et qu'il se maintient sur cette surface au delà du rayon de sa sphère d'activité physique et chimique; alors il réfléchit le calorique rayonnant, et ses molécules sont, quant à la chaleur, dans un état d'équilibre stable; c'est-à-dire, à une température invariable, ou qui ne varie que dans des limites étroites."—Comptes Rendus, 6 Mars, 1848.

[79] *Some Facts relative to the Spheroidal State of Bodies, Fire Ordeal, Incombustible Man, &c.*: by P. H. Boutigny (d'Evreux), Philosophical Magazine, No. 233 (third, series), p. 80; Comptes Rendus, May 14, 1849.

[80] The theory of freezing mixtures is deduced from the doctrine of latent caloric. These are mixtures of saline substances which, at the common temperature, by their mutual chemical action, pass rapidly into the fluid form, or are capable of being rapidly dissolved in water, and, by this quick transition to fluidity, absorb caloric, and produce degrees of cold more or less intense.—Rev. Francis Lunn, *On Heat*: Encyclopædia Metropolitana.

[81] *Propriétés de l'Acide Carbonique liquide*, par M. Thilorier, Annales de Chimie, vol. lx. p. 427. *Solidification de l'Acide Carbonique*: Ibid. p. 432.

[82] *On the Liquefaction and Solidification of Bodies generally existing as Gases*, by Michael Faraday, D.C.L., F.R.S., &c.; Philosophical Transactions, vol. cxxxvi, p. 155.

[83] Burns, in one of his most natural and pathetic letters.

CHAPTER VII.

LIGHT.

Theories of the Nature of Light—Hypotheses of Newton and Huygens—Sources of Light—The Sun—Velocity of Light—Transparency—Dark Lines of the Spectrum—Absorption of Light—Colour—Prismatic Analysis—Rays of the Spectrum—Rainbow—Diffraction—Interference—Goethe's Theory—Polarisation—Magnetisation of Light—Vision—The Eye—Analogy—Sound and Light—Influence of Light on Animals and Vegetables—Phosphorescence arising from several Causes—Artificial Light—Its Colour dependent on Matter.

Light, the first creation, presents to the enquiring mind a series of phenomena of the most exalted character. The glowing sunshine, painting the earth with all the brilliancy of colour, and giving to the landscape the inimitable charm of every degree of illumination, from the grey shadow to the golden glow;—the calm of evening, when, weary of the "excess of splendour," the eye can repose in

tranquillity upon the “cloud-land” of the west, and watch the golden and the ruddy hues fade slowly into the blue tincture of night;—and the pale refulgence of the moon, with the quiet sparkle of the sun-lit stars,—all tend to impress upon the soul, the great truth that, where there is light, organisation and life are found, and beyond its influence death and silence hold supreme dominion.[84] Through all time we have evidences that this has been the prevailing feeling of the human race, derived, of course, from their observation of the natural phenomena dependent upon luminous agency. In the myths of every country, impersonations of light prevail, and to these are referred the mysteries of the perpetual renewal of life on the surface of the earth.

This presentiment of a philosophic truth, in the instance of the poet sages of intellectual Greece, was advanced to the highest degree of refinement; and the sublime exclamation of Plato: “Light is truth, and God is light,” approaches nearly to a divine revelation.

As the medium of vision—as the cause of colour—as a power influencing in a most striking manner all the forms of organisation around us, light presented to the inquiring minds of all ages a subject of the highest interest.

The ancient philosophers, although they lost themselves in the metaphysical subtleties of their schools, could not but discover in light an element of the utmost importance in natural operations. The alchemists regarded the luminous principle as a most subtile fluid, capable of interpenetrating and mingling with gross matter: gold being supposed to differ from the baser metals only in containing a larger quantity of this ethereal essence.[85] Modern

science, after investigating most attentively a greater number of the phenomena of light, has endeavoured to assist the inquiry by the aid of hypotheses. Newton, in a theory, which exhibits the refined character of that great philosopher's mind, supposes luminous particles to dart from the surfaces of bodies in all directions—that these infinitely minute particles are influenced by the attracting and repelling forces of matter, and thus turned back, or reflected, from their superficies in some cases, and absorbed into their interstitial spaces in others.

Huyghens, on the contrary, supposes light to be caused by the waves or vibrations of an infinitely elastic medium—ETHER—diffused through all space, which waves are propagated in every direction from the luminous body. In the first theory, a luminous particle is supposed actually to come from the sun to the earth; in the other, the sun only occasions a disturbance of the *ether*, which extends with great rapidity, in the same manner as a wave spreads itself over the surface of a lake.

Nearly all the facts known in the time of Newton, and those discovered by him, were explained most satisfactorily by his hypothesis; but it was found they could be interpreted equally as the effects of undulation, with the exception of the production of colour by prismatic refraction. Although the labours of many gifted minds have been given, with the utmost devotion, to the support of the vibratory theory, this simple fact has never yet received any satisfactory explanation; and there are numerous discoveries connected with the molecular and chemical disturbances produced by the sun's rays, which do not appear to be explained by the hypothesis of emission or of undulation.

In both theories a wave motion is admitted, and every fact renders it probable that this mode of progression applies not only to light, but to the so-called *imponderable forces* in general. Admitting, therefore, the undulatory movement of luminous rays, we shall not stop to consider those points of the discussion which have been so ably dealt with by Young, Laplace, Fresnel, Biot, Fraunhofer, Herschel, Brewster, and others, but proceed at once to consider the sources of light, and its more remarkable phenomena.[86]

The sun is the greatest permanently luminous body we are acquainted with, and that orb is continually pouring off light from its surface in all directions at the rate, through the resisting medium of space and of our own atmosphere, of 192,000 miles in a second of time. It has been calculated, however, that light would move through a vacuum with the speed of 192,500 miles in the same period. We, therefore, learn that a ray of light requires eight minutes and thirteen seconds to come from the sun to us. In travelling from the distant planet Uranus, nearly three hours are exhausted; and from the nearest of the fixed stars each ray of light requires more than six years to traverse the intervening space between it and the earth. Allow the mind to advance to the regions of nebulæ, and it will be found that hundreds of years must glide away during the passage of their radiations. Consequently, if one of those masses of matter, or even one of the remote fixed stars, was "blotted out of heaven" to-day, several generations of the finite inhabitants of this world would fade out of time before the obliteration could be known to man. Here the immensity of space assists us in our conception, limited though it be, of the for-ever of eternity.[87]

All the planets of our system shine with reflected light, and the moon, our satellite, also owes her silvery lustre to the sun's radiations. The fixed stars are, in all probability, suns shining from the far distance of space, with their own self-emitted lights. By the photometric researches of Dr. Wollaston, we learn, however, that it would take 20,000 millions of such orbs as Sirius, the brightest of the fixed stars, to afford as much light as we derive from the sun. The same observer has proved that the brightest effulgence of the full moon is yet 801,072 times less than the luminous power of our solar centre.

The cultivators of modern science are a bold race; not contented with endeavouring to understand the physical earth, they are endeavouring to comprehend the condition of the solar surface. The mind of man can penetrate far into nature, and, as it were, feel out the mysteries of untraversed space. The astronomer learns of a peculiar condition of light, which is termed polarisation, and he learns by this, too, that he can determine if from a bright luminous disc the light is derived from a solid mass in a state of intense ignition, or from vapour in an incandescent condition. He adds a polarising apparatus to his telescopes, and he determines that the light we derive from the sun is due to an envelope of vapour —burning, in all probability—only with greater intensity, as the gas which we now employ. This *Photosphere*—as it has been called by the late French philosopher Arago, is found to be subjected to violent disturbances, and the dark spots seen on the sun's disc are now known to be openings through this mysterious envelope of light, which enable us to look in upon the dark body of the sun itself.

Luminous phenomena may be produced by various

means—chemical action is a source of light; and, under several circumstances in which the laws of affinity are strongly exerted, a very intense luminous effect is produced. Under this head all the phenomena of combustion are included. In the electric spark we have the development of light; and the arc which is formed between charcoal points at the poles of a powerful voltaic battery affords us the most intense artificial illumination with which we are acquainted. In addition to these, we have the peculiar phenomena of phosphorescence arising from chemical, calorific, electrical, actinic, and vital excitation, all of which must be particularly examined.

From whatever source we procure light, it is the same in character, differing only in intensity. In its action upon matter, we have the phenomena of transmission, of reflection, of refraction, of colour, of polarisation, and of vision, to engage our attention.

A beam of white light falls upon a plate of colourless glass, and it passes freely through it, losing but little of its intensity; the largest portion being lost by reflection from the first surface upon which the light impinges. If the glass is roughened by grinding, we lose more light by absorption and by reflection from the asperities of the roughened surface; but if we cover that face with any oleaginous fluid, as, for instance, turpentine, its transparency is restored. We have thus direct proof that transparency to light is due to molecular condition. This may be most strikingly shown by an interesting experiment of Sir David Brewster's:—

If a glass tube is filled with nitrous acid vapour, which is of a dull red colour, it admits freely the passage of the red and orange rays with some of the

others, and, if held upright in the sunshine, casts a red shadow on the ground; by gently warming it with a spirit-lamp, whilst in this position, it acquires a much deeper and blacker colour, and becomes almost impervious to any of the rays of light; but upon cooling it again recovers its transparency.

It has also been stated by the same exact experimentalist, that having brought a purple glass to a red heat, its transparency was improved, so that it transmitted green, yellow, and red rays, which it previously absorbed; but the glass recovered its absorptive powers as it cooled. A piece of yellowish-green glass lost its transparency almost entirely by being heated. Native yellow orpiment becomes blood-red upon being warmed, when nearly all but the red rays are absorbed; and pure phosphorus, which is of a pale yellow colour, and transmits freely all the coloured rays upon being melted, becomes very dark, and transmits no light.

Chemistry affords numerous examples of a very slight change of condition, producing absolute opacity in fluids which were previously diaphanous. [88]

Charcoal absorbs all the light which falls upon it, but in some of its states of combination, and in the diamond, which is pure carbon, it is highly transparent. Gold and silver beaten into thin leaves are permeated by the green and blue rays, and the metals in combination with acids are all of them more or less transparent. What becomes of the light which falls upon and is absorbed by bodies, is a question which we cannot yet, notwithstanding the extensive observations that have been made by some of the most gifted of men, answer satisfactorily. In all probability, as already stated, it is permanently

retained within their substances; and many of the experiments of exciting light in bodies when in perfect darkness, by the electric spark and other means, appear to support the idea of light becoming latent or hidden.

No body is absolutely transparent; some light is lost in passing even through ethereal space, and still more in traversing our atmosphere.

Amongst the most curious instances of absorption is that which is uniformly discovered in the solar spectrum, particularly when we examine it with a telescope. We then find that the coloured rays are crossed by a great number of dark bands or lines, giving no light; these are generally called Fraunhofer's dark lines, as it was to the indefatigable exertions of that experimentalist, and by the aid of his beautiful instruments, that most of them were discovered and measured, and enumerated, although they were previously noticed by Dr. Wollaston. It is quite clear that those lines represent rays which have been absorbed in their passage from the sun to the earth: although some of them have no doubt undergone absorption within the limits of the earth's atmosphere, we have every reason to believe, with Sir John Herschel, that the principal absorption takes place in the atmosphere of the sun.[89]

It has been proved by Dr. Miller, that the number of those dark lines is continually varying with the alteration of atmospheric conditions;[90] and the evidences which have been afforded, of peculiar states of absorption by the gaseous envelope of the earth,—during the prosecution of investigations on the chemical agencies of the sun's rays,—are of a sufficiently convincing character.

It has been calculated by Bouguer, that if our

atmosphere, in its purest state, could be extended rather more than 700 miles from the earth's surface instead of nearly 40, as it is at present, the sun's rays could not penetrate it, and this globe would roll on in darkness and silence, without a vestige of vegetable form or of animal life. In the Hebrew version of the Mosaic History, the reading is, "Let light appear:" may not this really mean that the earth's atmosphere was so cleared of obstructing vapours, that the solar rays were enabled to reach the earth? The same calculation supposes that sea-water loses all its transparency at the depth of 730 feet; but a dim twilight must prevail much deeper in the ocean.

The researches of Professor Edward Forbes have proved, that at the depth of 230 fathoms in the Ægean sea, the few shelled animals that exist are colourless: no plants are found within that zone; and that industrious naturalist fixes the zero of animal life of those waters at about 300 fathoms.[91] Since these zones mark the rapidly diminishing light, it is evident that where life ceases to be must be beyond the limits to which life can penetrate.

Our atmosphere, charged with aqueous vapour, serves to shield us from the intense action of the solar powers. By it we are protected from the destructive influences of the sun's light and heat; enjoy those modified conditions which are most conducive to the healthful being of organic forms; to it we owe "the blue sky bending over all," and those beauties of morning and evening twilight of which

—— Sound and motion own the potent sway.
Responding to the charm with its own mystery.

To defective transparency, or rather to the different degrees of it, we must attribute, in part, the colours of permeable media. Thus, a glass or fluid appears yellow to the eye, because it has the property of admitting the permeation of a larger quantity of the yellow rays than of any others;—red, because the red rays pass it with the greatest freedom; and so on for every other colour. In most cases the powers of transmission and of reflection are similar; but it is not so in all; a variety of fluor spar, which, while it transmits green light, reflects blue, and the precious opal, are striking instances to the contrary. Some glasses, which transmit yellow light have the singular power of dispersing blue rays from one surface; and a solution of quinine in water acidulated with sulphuric acid, although perfectly transparent and colourless when held between the eye and the light, exhibits, if viewed in a particular direction, a lively cerulean tint. These effects being supposed to be due to the conditions of the surface, have been called *epipolic* phenomena.[92]

The careful investigation of these phenomena has made us acquainted with some very interesting facts, and indeed discovered to us a set of luminous rays which were previously unknown. The dispersion of blue light from the surface of some yellow glasses—such as have been coloured by the oxide of silver—is of a different order from that which takes place with the solution of sulphate of quinine, or with the fluor spar. The first depends upon a peculiar condition of the surface, while the latter phenomena are due to a dispersion which takes place *within* the solid or fluid. In addition to the sulphate of quinine, and the fluor spar, we obtain the same results in a very marked manner by a canary yellow glass, coloured with the oxide of uranium, and by a decoction of the inner

bark of the horse-chesnut tree. Mr. Stokes, who has investigated this class of phenomena, and proposes to call it *Fluorescence*, from its being naturally seen in fluor-spar, has shown that the peculiar internal dispersion, and the consequent alteration of the colour of the ray, is due to an alteration in its refrangibility. Whether this hypothesis prove to be the correct one or not, it is certain that there exists a set of rays of far higher refrangibility than those seen in the ordinary Newtonian spectrum. This may be shown in the following manner: taking either of the solutions named, or a block of uranium glass, throw upon one face, by means of a prism, a very pure spectrum. On looking *into* the glass or fluid there will be seen, commencing amidst the most refrangible rays, a new set of spectral rays, struggling to make their way through the absorbent medium. These are of a blue colour in the quinine or chesnut solution, and green in the uranium glass, and are seen extending themselves far beyond the most refrangible rays of the ordinary Newtonian spectrum. This is the space over which those rays which have the power of producing chemical changes, such as are rendered familiar by the practice of Photography, are detected in their greatest activity. It has, therefore, been supposed that these fluorescent rays are the chemical rays rendered luminous by the alteration of their refrangibility. This view has received much support from the fact that the extra spectral rays are crossed with numerous dark lines, and that in the chemical impressions these lines are marked by unchanged spaces which exactly coincide with them. There is, however, much doubt of the correctness of this, since, in the uranium glass of such a thickness that these visible rays are quite absorbed, the chemical rays still pass.

However, the whole question requires, and is receiving, the most searching investigation. The discovery of these phenomena, which are included under the term of Fluorescence, is of that interesting and important character, that it must be ranked as the most decided advance which has been made in physical optics since the days of Newton.

It is not improbable that those rays of such high refrangibility may, although they are under ordinary circumstances invisible to the human eye, be adapted to produce the necessary degree of excitement upon which vision depends in the optic nerves of the night-roaming animals. The bat, the owl, and the cat, may see in the gloom of night by the aid of rays which are invisible to, or inactive on the eyes of man, or of those animals which require the light of day for perfect vision.

It is a general law of the radiant forces, that whenever they fall upon any surface, a portion is thrown back or reflected at the same time as other portions are absorbed or transmitted. Upon this peculiarity appear to depend the phenomena of natural colour in bodies.

The white light of the sun is well known to be composed of several coloured rays. Or rather, according to the theory of undulations, when the rate at which a ray vibrates is altered, a different sensation is produced upon the optic nerve. The analytical examination of this question shows, that to produce a red colour the ray of light must give 37,640 undulations in an inch, and 458,000000,000000 in a second. Yellow light requires 44,000 undulations in an inch, and 535,000000,000000 in a second; whilst the effect of blue results from 51,110 undulations within an inch,

and 622,000000,000000 of waves in a second of time.[93] The determination of such points as these is among the highest refinements of science, and, when contrasted with the most sublime efforts of the imagination, they must appear immeasurably superior.

If a body sends back white light unchanged, it appears white; if the surface has the property of altering the vibration to that degree which is calculated to produce redness, the result is a red colour: the annihilation of the undulations produces blackness. By the other view, or the corpuscular hypothesis, the beam of white light is supposed to consist of certain coloured rays, each of which has physical properties peculiar to itself, and thus is capable of producing different physiological effects. These rays falling upon a transparent or an opaque body suffer more or less absorption, and being thus dissevered, we have the effect of colour. A red body absorbs all the rays but the red; a blue surface, all but the blue; a yellow, all but the yellow; and a black surface absorbs the whole of the light which falls upon it.

That natural colours are the result of white light, and not innate properties of the bodies themselves, is most conclusively shown by placing coloured bodies in monochromatic light of another kind, when they will appear either of the colour of that light, or, by absorbing it, become black; whereas, when placed in light of their own character, the intensity of colour is greatly increasing.

Every surface has, therefore, a peculiar constitution, by which it gives rise to the diversified hues of nature. The rich and lively green, which so abundantly overspreads the surface of the earth, the

varied colours of the flowers, and the numberless tints of animals, together with all those of the productions of the mineral kingdom, and of the artificial combinations of chemical manufacture, result from powers by which the relations of matter to light are rendered permanent, until its physical conditions undergo some change.

There is a remarkable correspondence between the geographical position of a region and the colours of its plants and animals. Within the tropics, where

"The sun shines for ever unchangeably bright,"

the darkest green prevails over the leaves of plants; the flowers and fruits are tinctured with colours of the deepest dye, whilst the plumage of the birds is of the most variegated description and of the richest hues. In the people also of these climes there is manifested a desire for the most striking colours, and their dresses have all a distinguishing character, not of shape merely, but of chromatic arrangement. In the temperate climates everything is of a more subdued variety: the flowers are less bright of hue; the prevailing tint of the winged tribes is a russet brown; and the dresses of the inhabitants of these regions are of a sombre character. In the colder portions of the earth there is but little colour; the flowers are generally white or yellow, and the animals exhibit no other contrast than that which white and black afford. A chromatic scale might be formed, its maximum point being at the equator, and its minimum at the poles.[94]

The influence of light on the colours of organized creation is well shown in the sea. Near the shores we find sea-weeds of the most beautiful hues,

particularly on the rocks which are left dry by the tides; and the rich tints of the actiniæ, which inhabit shallow water, must have been often observed. The fishes which swim near the surface are also distinguished by the variety of their colours, whereas those which live at greater depths are grey, brown, or black. It has been found that after a certain depth, where the quantity of light is so reduced that a mere twilight prevails, the inhabitants of the ocean become nearly colourless. That the sun's ray alone gives to plants the property of reflecting colour is proved by the process of blanching, or *etiolation*, produced by artificially excluding the light.

By a triangular piece of glass—a prism,—we are enabled to resolve light into its ultimate rays. The white pencil of light which falls on the first surface of the prism is bent from its path, and coloured bands of different colours are obtained. These bands or rays observe a curious constancy in their positions: the red ray is always the least bent out of the straight path: the yellow class comes next in the order of refrangibility; and the blue are the most diverted from the vertex of the prism. The largest amount of illuminating power exists in the yellow ray, and it diminishes towards either end.[95] It is not uninteresting to observe something like the same variety of colour occurring at each end of the prismatic spectrum. The strict order in which the pure and mixed coloured rays present themselves is as follows:—

1. The *extreme red*: a ray which can only be discovered when the eye is protected from the glare of the other rays by a cobalt blue glass, is of a crimson character—a mixture of the *red* and the *blue*, red predominating.[96]

2. The *red*: the first ray visible under ordinary circumstances.

3. The *orange*: red passing into and combining with yellow.

4. The *yellow*: the most intensely luminous of the rays.

5. The *green*: the yellow passing into and blending with the blue.

6. The *blue*: in which the light very rapidly diminishes.

7. The *indigo*: the dark intensity of blue.

8. The *violet*: the *blue* mingled again with the *red*—blue being in excess.

9. The *lavender grey*: a neutral tint, produced by the combination of the red, blue, and yellow rays, which is discovered most easily when the spectrum is thrown upon a sheet of turmeric paper.

10. The fluorescent rays: which are either a *pure silvery blue* or a delicate *green*.

Newton regarded the spectrum as consisting of seven colours of definite and unvarying refrangibility. Brewster and others appear to have detected a great diffusion of the colours over the spectrum, and regard white light as consisting only of three rays, which in the prismatic images overlap each other; and from these—red, yellow, and blue—all the others can be formed by combination in varying proportions. The truth will probably be found to be, that the ordinary prismatic spectrum is a compound of two spectra:—that is, as we have the ordinary rainbow, and a supplementary bow, the colours of which are inverted, so the extraordinary may be

somewhat masked by the intense light of the ordinary spectrum; and yet by overlapping produce the variations of colour in the rays. We have already examined the heating power found in these coloured bands, which, although shown to be in a remarkable manner in constant agreement with the colour of a particular ray, is not directly connected with it; that is, not as the effect of a cause, or the contrary. The chemical action of the solar rays, to which from its important bearings we shall devote a separate chapter, has, in like manner with heat, been confounded with the sun's luminous power; but although associated with light and heat, and modified by their presence, it must be distinguished from them.

We find the maximum of heat at one end of the spectrum, and that of chemical excitation at the other—luminous power observing a mean point between them. Without doubt we have these powers acting reciprocally, modifying all the phenomena of each other, and thus giving rise to the difficulties which beset the inquirer on every side.

We have beautiful natural illustrations of luminous refraction in the rainbow and in the halo: in both cases the rays of light being separated by the refractive power of the falling rain drop, or the vesicles which form the moisture constituting a fog. In the simple toy of the child—the soap-bubble floating upon the air—the philosopher finds subjects for his contemplation; and from the unrivalled play of colours which he discovers in that attenuated film, he learns that the varying thicknesses of surfaces influence, in a most remarkable manner, the colours of the sunbeam. Films of oil floating upon water present similar appearances; and the colours

developed in tempering steel are due entirely to the thickness of the oxidized surface produced by heat. There have lately been introduced some beautiful specimens of paper rendered richly iridescent by the following process:—A solution of a gum resin in chloroform is floated upon water, where it forms a film giving all the colours of Newton's rings. A sheet of paper which has been previously sunk in the water is carefully lifted, and the film thus removed adheres with great firmness to the paper, and produces this rich and curious play of colour. The rich tints upon mother-of-pearl, in the feathers of many birds, the rings seen in the cracks of rock-crystal, or between the unequal faces of two pieces of glass, and produced by many chemical and indeed mechanical operations—are all owing to the same cause;—the refraction of the luminous pencil by the condition of the film or surface. If we take one of those steel ornaments which are formed by being covered with an immense number of fine lines, it will be evident that these striæ present many different angles of reflection, and that, consequently, the rays thrown back will, at some point or another, have a tendency to cross each other. The result of this is, that the quantity of light is augmented at some points of intersection, and annihilated at others.[97] Out of the investigation of the phenomena of diffraction, of the effects of thin and thick plates upon light, and the results of interference, has arisen the discovery of one of the most remarkable conditions within the range of physical science.

Two bright lights may be made to produce darkness.—If two pencils of light radiate from two spots very close to each other in such a manner that they cross each other at a given point, any object placed at that line of interference will be illuminated with the sum of

the two luminous pencils. If we suppose those rays to move in waves, and the elevation of the wave to represent the maximum of luminous effect, then the two waves meeting, when they are both at the height of their undulation, will necessarily produce a spot of greater intensity. If now we so arrange the points of radiation, that the systems of luminous waves proceed irregularly, and that one arrives at the screen half an undulation before the other, the one in elevation falling into the depression of the other, a mutual annihilation is the consequence. This fact, paradoxical as it may appear, was broadly stated by Grimaldi, in the description of his experiments on the inflection of light, and has been observed by many others. The vibratory hypothesis, seizing upon the analogy presented by two systems of waves in water, explains this plausibly, and many similar phenomena of what is called the *interference of light*; but still upon examination it does not appear that the explanation is quite free from objection.[98]

Another theory, not altogether new to us, it being indicated in Mayer's hypothesis of three primary colours (1775), and to be found as a problem in some of the Encyclopædias of the last century, has been put forth, in a very original manner, by that master-mind of intellectual Germany, Goethe; and from the very comprehensive views which this poet-philosopher has taken of both animal and vegetable physiology (views which have been adopted by some of the first naturalists of Europe), we are bound to receive his theory of colours with every respect and attention.

Goethe regards colour as the "thinning" of light; for example, by obstructing a portion of white light, yellow is produced; by reducing it still farther, red is

supposed to result; and by yet farther retarding the free passage of the beam, we procure a blue colour, which is the next remove from blackness, or the absence of light. There is truth in this; it bears about it a simplicity which will satisfy many minds; by it many of the phenomena of colour may be explained: but it is insufficient for any interpretation of several of those laws to which the other theories do give us some insight.

Newton may have allowed himself to be misled by the analogy presented between the seven rays of the spectrum and the notes in an octave. The mystic number, seven, may have clung like a fibre of the web of superstition to the cloak of the great philosopher; but the attack made by Goethe upon the Newtonian philosophy betrays the melancholy fact of his being diseased with the lamentable weakness of too many exalted minds—an overweening self-esteem.

The polarization of light, as it has been unfortunately called—unfortunately, as conveying an idea of determinate and different points or poles, which only exists in hypothetical analogy—presents to us a class of phenomena which promise to unclose the mysterious doors of the molecular constitution of bodies.

This remarkable condition, as produced by the reflection of light from glass at a particular angle, was first observed by Malus, in 1808,[99] when amusing himself by looking at the beams of the setting sun, reflected from the windows of the Luxembourg Palace through a double refracting prism. He observed that when the prism was in one position, the windows with their golden rays were visible; but that turned round a quarter of a circle

from that position, the reflected rays disappeared although the windows were still seen.

The phenomenon of double refraction was noticed, in the first instance, by Erasmus Bartholin, in Iceland-spar, a crystal the primary form of which is a rhombohedron; who perceived that the two images produced by this body were not in the same physical conditions.[100] It was also studied by Huyghens and Sir Isaac Newton, and to our countryman we owe the singular idea that a ray of light emerging from such a crystal has *sides*. This breaking up of the beam of light into two,—which is shown by looking through a pin-hole on a card through a crystal of Iceland spar, when two holes become visible, is due to the different states of tension in which the different layers constituting the crystal exist.

In thus separating the ray of light into two rays, the condition called polarisation has been produced, and by experiment we discover that the single ray has properties different from those of the compound or ordinary ray.

It is somewhat difficult to explain what is meant by, and what are the conditions of, *polarised light*. In the first instance let us see by what methods this peculiar state may be brought about.

If we reflect a ray of light from the surface of any body, fluid or solid, but not metallic, at an angle between 53° and 68° it undergoes what has been called *plane polarisation*. It may also be produced by the refraction of light from several refracting surfaces acting upon the pencil of light in succession; as by a bundle of plates of glass. Each surface polarises a portion of the pencil, and the number of plates necessary to polarise a whole beam depends upon the intensity of the beam and the angle of incidence.

Thus, the light of a wax candle is wholly polarised by forty-seven plates of glass at an angle of 40° 41'; while at an angle of 79° 11' it is polarised by eight plates. Again, plane polarisation may be produced by the double refraction of crystals. Each of the two pencils is polarised, like light reflected from glass at an angle of 56° 45', but in opposite planes.

Non-scientific readers will still ask,—What is this mysterious condition of light which is produced by reflection and refraction at peculiar angles to the incident ray. It is one of the most difficult of problems to express in popular language. The conditions are, however, these:—

An ordinary ray of light will be reflected from a reflecting surface at whatever angle that surface may be placed in relation to the incident beam.

A polarised ray of light is not reflected in all positions of the reflecting surface.

An ordinary ray of light is freely transmitted through a transparent medium, as glass, in whatever position it may be placed relative to the source of light.

A polarised ray of light is not transmitted in all the positions of the permeable medium.

Supposing a plate of glass is presented at the angle 56° to a polarised ray, and the plane of incidence or reflexion is at right angles to the plane of polarisation of the ray, *no light is reflected*. If we turn the plate of glass round through 90°, when the plane of reflexion is parallel to that of polarisation *the light is reflected*. If we turn the plate round another 90°, so that the plane of reflexion and of polarisation are parallel to each other, again *no light is reflected*; and if we turn it through another 90° the reflection of the ray again takes place.

Precisely the same result takes place when, instead of being reflected, the polarised ray is transmitted.

Some substances have peculiar polarizing powers: *the tourmaline* is a familiar example. If a slice of tourmaline is taken, and we look at a common pencil of light through it, we see it in whatever position we may place the transparent medium. If, however, we look at a pencil of polarised light, and turn the crystal round, it will be found that in two positions the light is stopped, and that in two other positions it passes freely through it to the eye.

By way of endeavouring to conceive something of what may be the conditions which determine this very mysterious state, let us suppose each ray of light to vibrate in two planes at right angles to each other: one wave being vertical and the other horizontal. We have many examples of this compound motion. The mast of a ship, by the force with which she is urged through the water, describes a vertical wave, while by the roll of the billows across which she sails, a lateral undulation is produced at the same time. We may sometimes observe the same thing when a field of corn is agitated by a shifting wind on a gusty day.

The hypothesis therefore is, that every ray of ordinary light consists of two rays vibrating in different planes; and that these rays, separated one from the other, have the physical conditions which we call *polarized*.

The most transparent bodies may be regarded as being made up of atoms arranged in certain planes. Suppose the plane of lamination of any substance to be vertical in position, it would appear that the ray which has a vertical motion passes it freely, whereas if we turn the body round so that the planes of

lamination are at right angles to the plane of vibration of the ray, it cannot pass.

That some action similar to that which it is here endeavoured to express in popular language does take place, is proved by the correctness of the results deduced by rigid mathematical analyses founded on this hypothesis.

There are two other conditions of the polarization of light—called *circular* and *elliptical* polarization. The first is produced by light when it is twice reflected from the second surface of bodies at their angle of maximum polarization, and the second by reflexions from the surfaces of metals at angles varying from 70° 45' to 78° 30'. The motion of the wave in the first is supposed to be circular, or to be that which is represented by looking along the centre of a corkscrew as it is turned round. At every turn of the medium effecting *circular polarization* the colour of the ray of light is changed after a uniform order. If turned in one direction, they change through red, orange, yellow, green, and violet; and if in the other direction, the colours appear in the contrary order.

The variety of striking effects produced by the polarization of light; the unexpected results which have sprung from the investigation of the laws by which it is regulated; and the singular beauty of many of its phenomena, have made it one of the most attractive subjects of modern science.

Ordinary light passes through transparent bodies without producing any very striking effects in its passage; but this *extraordinary* beam of light has the power of insinuating itself between the molecules of bodies, and by illuminating them, and giving them every variety of prismatic hue, of enabling the eye to detect something of the structure of the mass. The

chromatic phenomena of polarized light are so striking, that no description can convey an adequate idea of their character.

Spectra more beautiful and intense than the prismatic image,—systems of rings far excelling those of thin plates,—and forms of the most symmetric order, are constantly presenting themselves, as the polarized ray is passed through various transparent substances; the path of the ray indicating whether the crystal has been formed round a single nucleus or axis, or whether it has been produced by aggregation around two axes. The coloured rings, and the dark or luminous crosses which distinguish the path of the polarized ray, are respectively due to different states of tension amongst the particles, although those differences are so slight, that no other means is of sufficient delicacy to detect the variation.

The poetry which surrounds these, in every way, mysterious conditions of the solar beam, is such, that it is with difficulty that imagination is restrained by the stern features of truth. The uses of this peculiar property in great natural phenomena are not yet made known to us; but, since we find on every side of us the natural conditions for thus separating the beam of light, and effecting its polarization, there must certainly be some most important end for which it is designed by Him who said, “Let there be Light.”

It must not be forgotten that we have at command the means of showing that the chromatic phenomena of polarized light are due to atomic arrangement. By altering the molecular arrangement of transparent bodies, either by heat or by mere mechanical pressure, the unequal tension or strain of the

particles is at once indicated by means of the polarized ray of light and its rings of colour. Differences in the chemical constitution of bodies, too slight to be discovered by any other mode of analysis, can be most readily and certainly detected by this luminous investigator of the molecular forces. [101]

Although we cannot enter into an examination of all the conditions involved in the polarization of, and the action of matter on, ordinary light, it will be readily conceived, from what has been already stated, that some most important properties are indicated, beyond those which science has made known.

Almost every substance in nature, in some definite position, appears to have the power of producing this change upon the solar ray, as may be satisfactorily shown by examining them with a polarizing apparatus.[102] The sky at all times furnishes polarized light, which is most intense where it is blue and unclouded, and the point of maximum polarization is varied according to the relative position of the sun and the observer. A knowledge of this fact has led to the construction of a "Solar Clock,"[103] with which the hour can be readily determined by examining the polarized condition of the sky. It has been stated, that chemical change on the Daguerreotype plates and on photographic papers is more readily produced by the polarized than by the ordinary sunbeam.[104] If this fact be established by future investigations, we advance a step towards the discovery so much desiderated of the part it plays in natural operations.

The refined and accurate investigations of Dr. Faraday stand prominently forward amid those

which will redeem the present age from the charge of being superficial, and they will, through all time, be referred to as illustrious examples of the influence of a love of truth for truth's sake, in entire independence of the marketable value, which it has been unfortunately too much the fashion to regard. The searching examination made by this "interpreter of nature" into the phenomena of electricity in all its forms, has led him onward to trace what connexion, if any, existed between this great natural agent and the luminous principle.

By employing that subtile analyzer, a polarized ray, Dr. Faraday has been enabled to detect and exhibit effects of a most startling character. He has proved magnetism to have the power of influencing a ray of light in its passage through transparent bodies. A polarized ray is passed through a piece of glass or a crystal, or along the length of a tube filled with some transparent fluid, and the line of its path carefully observed; if, when this is done, the solid or fluid body is brought under powerful magnetic influence, such as we have at command by making a very energetic voltaic current circulate around a bar of soft iron, it will be found that the polarized light is disturbed; that, indeed, it does not permeate the medium along the same line.[105] This effect is most strikingly shown in bodies of the greatest density, and diminished in fluids, the particles of which are easily moveable over each other, and has not hitherto been observed in any gaseous medium. The question, therefore, arises,—does magnetism act directly upon the ray of light, or only indirectly, by producing a molecular change in the body through which the ray is passing? This question, so important in its bearings upon the connexion between the great physical powers, will, no doubt, before long receive a

satisfactory reply. A medium is necessary to the production of the result, and, as the density of the medium increases, the effect is enlarged: it would therefore appear to be due to a disturbance by magnetic force of the particles which constitute the medium employed.

Without any desire to generalize too hastily, we cannot but express a feeling,—amounting to a certainty in our own mind,—that those manifestations of luminous power, connected with the phenomena of terrestrial magnetism, which are so evident in all the circumstances attendant upon the exhibition of Aurora Borealis, and those luminous clouds which are often seen, independent of the Northern Lights, that a very intimate, relation exists between the solar radiations and that power which so strangely gives polarity to this globe of ours.

In connexion with the mysterious subject of solar light, it is important that we should occupy a brief space in these pages with the phenomena of vision, which is so directly dependent upon luminous radiation.

The human eye has been rightly called the “masterpiece of divine mechanism;” its structure is complicated, yet all the adjustments of its parts are as simple as they are perfect. The eye-ball consists of four coats. The cornea is the transparent coat in front of the globe; it is the first optical surface, and this is attached to the sclerotic membrane, filling up the circular aperture in the white of the eye; the choroid coat is a very delicate membrane, lining the sclerotic, and covered with a perfectly black pigment on the inside; and close to this lies the most delicately reticulated membrane, the retina, which is, indeed,

an extension of the optic nerve. These coats enclose three humours,—the aqueous, the vitreous, and the crystalline humours.

The eye, in its more superficial mechanical arrangements, presents exactly the same character as a camera obscura, the cornea and crystalline lens receiving the images of objects refracting and inverting them; but how infinitely more beautiful are all the arrangements of the organ of vision than the dark chamber of Baptista Porta![106] The humours of the eye are for the purpose of correcting the aberrations of light, which are so evident in ordinary lenses, and for giving to the whole an achromatic character. Both spherical and chromatic aberration are corrected, the latter not entirely, and by the agency of the cornea and the crystalline lens perfect images are depicted on the retina, in a similar way to those very charming pictures which present themselves in the table of the camera obscura.

The seat of vision has been generally supposed to be the retina; but Mariotte has shown that the base of the optic nerve, which is immediately connected with the retina, is incapable of conveying an impression to the brain. The choroid coat, which lies immediately behind the retina, is regarded by Mariotte and Bernoulli as the more probable seat of vision. The retina, being transparent, offers no obstruction to the passage of the light onward to the black surface of the choroid coat, from which the vibrations are, in all probability, communicated to the retina and conveyed to the brain. Howbeit, upon one or the other of these delicate coats a distinct image is impressed by light, and the communication made with the brain possibly by a vibratory action. We may trace up the phenomena of vision to this

point; we may conceive undulations of light, differing in velocity and length of wave, occasioning corresponding tremors in the neuralgic system of the eye; but how these vibrations are to communicate correct impressions of length, breadth, and thickness, no one has yet undertaken to explain.

It has, however, been justly said by Herschel:—

"It is the boast of science to have been able to trace so far the refined contrivances of this most admirable organ, not its shame to find something still concealed from scrutiny; for, however anatomists may differ on points of structure, or physiologists dispute on modes of action, there is that in what we *do* understand of the formation of the eye, so similar, and yet so infinitely superior to a product of human ingenuity; such thought, such care, such refinement, such advantage taken of the properties of natural agents used as mere instruments for accomplishing a given end, as force upon us a conviction of deliberate choice and premeditated design, more strongly, perhaps, than any single contrivance to be found whether in art or nature, and renders its study an object of the greatest interest."[107]

Has the reader ever asked himself why it is, having two eyes, and consequently two pictures produced upon the tablets of vision, that we see only one object? According to the law of visible direction, all the rays passing through the crystalline lenses converge to one point upon the retina,—and as the two images are coincident and nearly identical, they can only produce the sensation of one upon the brain.

When we look at any round object, as the ornamented moderator lamp before us, first with one eye, and then with the other, we discover that, with

the right eye, we see most of the right-hand side of the lamp, and with the left eye more of the left-hand side. These two images are combined, and we see an object which we know to be round.

This is illustrated in a most interesting manner by the little optical instrument, *the Stereoscope*. It consists either of two mirrors placed each at an angle of 45°, or of two semi-lenses turned with their curved sides towards each other. To view its phenomena, two pictures are obtained by the camera obscura on photographic paper of any object in two positions, corresponding with the conditions of viewing it with the two eyes. By the mirrors or the lenses these dissimilar pictures are combined within the eye, and the vision of an actually solid object is produced from the pictures represented on a plane surface. Hence the name of the instrument; which signifies, *Solid I see*.

Analogy is often of great value in indicating the direction in which to seek for a truth; but analogical evidence, unless where the resemblance is very striking, should be received with caution. Mankind are so ready to leap to conclusions without the labour necessary for a faithful elucidation of the truth, that too often a few points of resemblance are seized upon, and an inference is drawn which is calculated to mislead.

There is an idea that the phenomena of sound bear a relation to those of light,—that there exists a resemblance between the chromatic and the diatonic scales. Sound, we know, is conveyed by the beating of material particles—the air—upon the auditory membrane of the ear, which have been set in motion by some distant disturbance of the medium through which it passes. Light has been supposed to act on

the optic nerve in the same manner. If we imagine colour to be the result of vibrations of different velocities and lengths, we can understand that under some of these tremors, first established on the nerves, and through them conveyed to the brain, sensations of pain or pleasure may result, in the same way as sharp or subdued sounds are disagreeable or otherwise. Intensely coloured bodies do make an impression upon perfectly blind men; and those who, being born blind, know no condition of light or colour, will point out a difference between strongly illuminated red and yellow media. When the eyes are closed we are sensible to luminous influence, and even to differences of colour. We must consequently infer that light produces some peculiar action upon the system of nerves in general; this may or may not be independent of the chemical agency of the solar radiations; but certainly the excitement is not owing to any calorific influence. The system of nerves in the eye is more delicately organized, and of course peculiarly adapted to all the necessities of vision.

Thus far some analogy does appear to exist between light and sound; but the phenomena of the one are so much more refined than those of the other—the impressions being all of them of a far more complicated character, that we must not be led too far by the analogical evidence in referring light, like sound, to mere material motion.

It was a beautiful idea that real impressions of external objects are made upon the seat of vision, and that they are viewed, as in a picture, by something behind the screen,—that these pictures become dormant, but are capable of being revived by the operations of the mind in peculiar conditions; but we can only regard it as a philosophical speculation

of a poetic character, the truth or falsehood of which we are never likely to be enabled to establish.[108]

That which sees will never itself be visible. The secret principle of sensation,—the mystery of the life that is in us,—will never be unfolded to finite minds.

Numerous experiments have been made from time to time on the influence of light upon animal life. It has been proved that the excitement of the solar rays is too great for the healthful growth of young animals; but, at the same time, it appears probable that the development of the functional organs of animals requires, in some way, the influence of the solar rays. This might, indeed, have been inferred from the discovery that animal life ceases in situations from which light is absolutely excluded. The instance of the Proteus of the Illyrian lakes may appear against this conclusion. This remarkable creature is found in the deep and dark recesses of the calcareous rocks of Adelsburg, at Sittich; and it is stated, also in Sicily, and in the Mammoth caves of Kentucky. Sir Humphry Davy describes the Proteus anguinus as “an animal to whom the presence of light is not essential, and who can live indifferently in air and in water, on the surface of the rock, or in the depths of the mud.” The geological character of rocks, however, renders it extremely probable that these animals may have descended with the water, percolating through fissures from very near the surface of the ground. All the facts with which science has made us acquainted —and both natural and physical science has been labouring with most untiring industry in the pursuit of truth—go to prove that light is absolutely necessary to organization. It is possible the influence of the solar radiations may extend beyond the powers of the human senses to detect luminous or

thermic action, and that consequently a development of animal and vegetable forms may occur where the human eye can detect no light; and under such conditions the Proteus may be produced in its cavernous abodes, and also those creatures which live buried deep in mud. Some further consideration of the probable agency of light will occupy us, when we come to examine the phenomena of vital forces.

Light is essentially necessary to vegetable life; and to it science refers the powers which the plant possesses of separating carbon from the air breathed by the leaves, and secreting it within its tissues for the purpose of adding to its woody structure. As, however, we have, in the growing plant, the action of several physical powers exerted to different ends at the same time, the remarkable facts which connect themselves with vegetable chemistry and physiology are deferred for a separate examination.

The power of the solar rays to produce in bodies that peculiar gleaming light which we call phosphorescence, and the curious conditions under which this phenomenon is sometimes apparent, independent of the sun's direct influence, present a very remarkable chapter in the science of luminous powers.

The phosphorescence of animals is amongst the most surprising of nature's phenomena, and it is not the less so from our almost entire ignorance of the cause of it. Many very poetical fancies have been applied in description of these luminous creations; and imagination has found reason why they should be gifted with these extraordinary powers. The glow-worm lights her lamp to lure her lover to her bower, and the luminous animalcules of the ocean are employed in lighting up the fathomless depths where

the sun's rays cannot penetrate, to aid its monsters in their search for prey. "The lamp of love—the pharos —the telegraph of the night,—which scintillates and marks, in the silence of darkness, the spot appointed for the lover's rendezvous,"[109] is but a pretty fiction; for the glow-worm shines in its infant state, in that of the larva, and when in its aurelian condition. Of the dark depths of the ocean it may be safely affirmed that no organized creation lives or moves in its grave-like silence to require this fairy aid. Fiction has frequently borrowed her creations from science. In these cases science appears to have made free with the rights of fiction.

The glow-worms (*lampyris noctiluca*), it is well known, have the power of emitting from their bodies a beautiful pale bluish-white light, shining during the hours of night in the hedge-row, like crystal spheres. It appears, from the observations of naturalists, that these insects never exhibit their light without some motion of the body or legs;—from this it would seem that the phosphorescence was dependent upon nervous action, regulated at pleasure by the insect; for they certainly have the power of obscuring it entirely. If the glow-worm is crushed, and the hands or face are rubbed with it, luminous streaks, similar to those produced by phosphorus, appear. They shine with greatly increased brilliancy in oxygen gas and in nitrous oxide. From these facts may we not infer that the process by which this luminosity is produced, whatever it may be, has a strong resemblance to that of respiration?

There are several varieties of flies, and three species of beetles of the genus *Elater*, which have the power of emitting luminous rays. The great lantern-fly of South America is one of the most brilliant, a single

insect giving sufficient light to enable a person to read. In Surinam a very numerous class of these insects are found, which often illuminate the air in a remarkable manner. In some of the bogs of Ireland a worm exists which gives out a bright green light; and there are many other kinds of creatures which, under certain circumstances, become luminous in the dark. This is always dependent upon vitality; for all these animals, when deprived of life, cease to shine.

At the same time we have many very curious instances of phosphorescence in dead animal and vegetable matter; the lobster among the Crustacea, and the whiting among fishes, are striking examples; decayed wood also emits much light under certain conditions of the atmosphere. This development of light does not appear to be at all dependent upon putrefaction; indeed, as this process progresses, the luminosity diminishes. We cannot but imagine that this light is owing, in the first place, to direct absorption by, and fixation within, the corpuscular structure of those bodies, and that it is developed by the decomposition of the particles under the influence of our oxygenous atmosphere.

The pale light emitted by phosphorus in the dark is well known; and this is evidently only a species of slow combustion, a combination of the phosphorus with the oxygen of the air. Where there is no oxygen, phosphorus will not shine; its combustion in chlorine or iodine vapour is a phenomenon of a totally different character from that which we are now considering. This phosphorescence of animal and vegetable matter has been regarded as something different from the slow combustion of phosphorus; but, upon examination, all the chemical conditions are found to be the same, and it is certainly due to a

similar chemical change.

The luminous matter of the dead whiting or the mackerel may be separated by a solution of common salt or of sulphate of magnesia; by concentrating these solutions the light disappears; but it is again emitted when the fluid is diluted. The entire subject is, however, involved in the mystery of ignorance, although it is a matter quite within the scope of any industrious observer. The self-emitted light of the carbuncle of the romancer is realized in these remarkable phenomena.

The phosphorescence of some plants and flowers is not, perhaps, of the same order as that which belongs to either of the conditions we have been considering. It appears to be due rather to an absorption of light and its subsequent liberation. If a nasturtium is plucked during sunshine, and carried into a dark room, the eye, after it has reposed for a short time, will discover the flower by a light emitted from its leaves.

The following remarkable example, and an explanation of it by the poet Goethe, is instructive:—

“On the 19th of June, 1799, late in the evening, when the twilight was deepening into a clear night, as I was walking up and down the garden with a friend, we very distinctly observed a flame-like appearance near the oriental poppy, the flowers of which are remarkable for their powerful red colour. We approached the place, and looked attentively at the flowers, but could perceive nothing further, till at last, by passing and repassing repeatedly, while we looked side-ways on them, we succeeded in renewing the appearance as often as we pleased. It proved to be a physiological phenomenon, and the apparent corruscation was nothing but the spectrum of the

flower in the complementary blue-green colour. The twilight accounts for the eye being in a perfect state of repose, and thus very susceptible, and the colour of the poppy is sufficiently powerful in the summer twilight of the longest days to act with full effect, and produce a complementary image."[110]

The leaves of the *œnothera macrocarpa* are said to exhibit phosphoric light when the air is highly charged with electricity. The agarics of the olive-grounds of Montpelier have been observed to be luminous at night; but they are said to exhibit no light, even in darkness, *during the day*. The subterranean passages of the coal mines near Dresden are illuminated by the phosphorescent light of the *rhizomorpha phosphoreus*, a peculiar fungus. On the leaves of the Pindoba palm, a species of agaric grows which is exceedingly luminous at night; and many varieties of the lichens, creeping along the roofs of caverns, lend to them an air of enchantment by the soft and clear light which they diffuse. In a small cave near Penryn, a luminous moss is abundant; and it is also found in the mines of Hesse. According to Heinzmann, the *rhizomorpha subterranea* and *aidulæ* are also phosphorescent.

It is but lately that a plant which abounds in the jungles in the Madura district of the East Indies was sent to this country, which, although dead, was remarkably phosphorescent; and, when in the living state, the light which it emitted was extraordinarily vivid, illuminating the ground for some distance. Those remarkable effects may be due, in some cases, to the separation of phosphuretted hydrogen from decomposing matter, and, in others, to some peculiar electric manifestation.

The phosphorescence of the sea, or that condition

called by fishermen *brimy*, when the surface, being struck by an oar, or the paddle-wheels of a steamer, gives out large quantities of light, has been attributed to the presence of myriads of minute insects which have the power of emitting light when irritated. The night-shining nereis (*Nereis noctiluca*) emits a light of great brilliancy, as do several kinds of the mollusca. The nereides attach themselves to the scales of fishes, and thus frequently render them exceedingly luminous. Some of the crustaceæ possess the same remarkable property;—twelve different species of *cancer* were taken up by the naturalists of the Zaire in the Gulf of Guinea.[111] The *cancer fulgens*, discovered by Sir Joseph Banks, is enabled to illuminate its whole body, and emits vivid flashes of light. Many of the medusæ also exhibit powerful phosphorescence.[112] These noctilucous creatures are, many of them, exceedingly minute, several thousands being found in a tea-cup of sea water. They float near the surface in countless myriads, and when disturbed they give out brilliant scintillations, often leaving a train of light behind them.[113] By microscopic examination no other fact has been elicited than that these minute beings contain a fluid which, when squeezed out, leaves a line of light upon the surface of water. The appearance of these creatures is almost invariably on the eve of some change of weather, which would lead us to suppose that their luminous phenomena must be connected with electrical excitation; and of this, the investigations of Mr. C. Peach, of Fowey, communicated to the British Association at Birmingham, furnish the most satisfactory proofs we have as yet obtained.

Benvenuto Cellini gave a curious account of a carbuncle which shone with great brilliancy in the

dark.[114] The same thing has been stated of the diamond; but it appears to be necessary to procure these emissions of light, that the minerals should be first warmed near a fire. From this it may be inferred that the luminous appearance is of a similar character to that of fluor spar, and of numerous other earthy minerals, which, when exposed to heat, phosphoresce with great brilliancy. Phosphorescent glow can also be excited in similar bodies by electricity, as was first pointed out by Father Beccaria, and confirmed by Mr. Pearsall.[115] These effects, it must be remembered, are distinct from the electric spark manifested upon breaking white sugar in the dark, or scratching sulphuret of zinc.

In the instances adduced there is not necessarily any exposure to the sunshine required. It is probable that two, if not three, distinct phenomena are concerned in the cases above quoted, and that all of them are distinct from animal phosphorescence, or the luminous appearance of vegetables. They, however, certainly prove, either that light is capable of becoming latent, or that it is only a condition of matter, in which it may be made manifest by any disturbance of the molecular forces. We have, in answer to this, very distinct evidence that some bodies do derive this property from the solar rays. Canton's phosphorus, which is a sulphuret of calcium, will, having been exposed to the sun, continue luminous for some time after it is carried into the dark; as will also the Bolognian stone,—a sulphuret of barium. This result appears to be due to a particular class of the solar rays; for it has been found, if these sulphurets, spread smoothly on paper, are exposed to the influence of the solar spectrum for some little time, and then examined in the dark, that luminous spaces appear, exactly corresponding with

the most refrangible rays, or those which excite chemical change; and one very remarkable fact must not be forgotten—the dark rays of the spectrum beyond the violet produce a lively phosphorescence, which is *extinguished* by the action of the rays of least refrangibility, or the heat rays—whilst artificial heat, such as a warm iron, produces a very considerable elevation of the phosphorescent effect.[116] It is not improbable, that the fluorescent rays of Mr. Stokes may be materially concerned in producing the phenomena of phosphorescence: experiments are, however, required to prove this.

In these allied phenomena we have effects which are evidently dependent upon several dissimilar causes. The phosphorescence of the living animal is due, without doubt, to nervous excitation: that of the living vegetable to solar luminous influence; and in the case of the mosses of caverns, &c. to the chemical agency of the sun's rays, which appears to be capable of conduction. In the dead organic matter we have a purely chemical action developing the light, and in the inorganic bodies we have peculiar molecular constitution, by which an absorption of light appears to take place.

The subject is one of the greatest difficulty; the torch of science is too dim to enable us to see the causes at work in producing these marvellous effects. The investigation leads, to a certain extent, to the elucidation of many of the secrets of luminous action; and the determination of the question, whether light is an emanation from the sun, or only a subtile principle diffused through all matter, which is excited by solar influence, is intimately connected with the inquiry.

It has been stated that matter is necessary to the

development of light; that no luminous effect would be produced if it were not for the presence of matter. Of this we not only have no proof, but such evidence as we have is against the position. There is no loss of light in the most perfect vacuum we can produce by any artificial means, which should be the case if matter was concerned in the phenomena of light, as a cause.

Colour is certainly a property regulated by material bodies; or rather, the presence of matter is necessary to the production of colour. Chlorine gas is a pale yellow, and nitrous vapour a yellowish red. These and one or two other vapours, which are near the point of condensation into fluids, are the only coloured gaseous or vaporiform bodies. The sky is blue, because the material particles of the atmosphere reflect back the blue rays. But we have more practical illustrations than this. The flame of hydrogen burning with oxygen gives scarcely any light; allow it to impinge on lime, a portion of which is carried off by the heat of the flame, and the most intense artificial light with which we are acquainted is produced. Hydrogen gas alone gives a flame in which nearly all but the blue rays are wanting: place a brush of steel or asbestos in it, and many of the other rays are at once produced. An argand lamp, and more particularly the lamp in which camphine—a purified turpentine,—is burnt, gives a flame which emits most of the rays found in sunlight. Spirit of wine mixed with water, warmed and ignited, gives only yellow rays; add nitrate of strontian and they become red; but nitrate of barytes being mixed with the fluid, they are changed to green and yellow; salts of copper afford fine blue rays, and common salt intense yellow ones. Many of these coloured rays and others can be produced in great power by the use of

various solid bodies introduced into flame. This has not been sufficiently pointed out by authors; but it is clear from experiments that light requires the presence of matter to enable it to diffuse its coloured glories. How is it that the oxygen and hydrogen flame gives so little light, and with a solid body present, pours forth such a flood of brilliancy?

The production of artificial light by electrical and chemical agencies will necessarily find some consideration under their respective heads. There are numerous phenomena which connect themselves with luminous power, or appear to do so, which, in the present state of our knowledge, cannot come immediately under our attention. We are compelled to reserve our limited space for those branches of science which we are enabled to connect with the great natural operations constantly going on around us. Many of these more abstruse results will, however, receive some incidental notice when we come to examine the operation of the combined physical forces on matter.

We see in light a principle which, if it has not its source in the sun, is certainly dependent upon that luminary for its manifestations and powers. From that “fountain of light” we find this principle travelling to us at a speed which almost approaches the quickness of thought itself; yet by the refinements of science we have been enabled to measure its velocity with the utmost accuracy. The immortal poet of our own land and language, in his creations of Ariel, that “tricksy spirit,” who could creep like music upon the waters, and of the fantastic Puck, who could girdle the earth in thirty minutes, appears to have approached to the highest point to which mere imagination could carry the human mind

as to the powers of things ethereal. Science has, since then, shown to man that this “spirit, fine spirit,” was a laggard in his tasks, and a gross piece of matter, when compared with the subtile essences which man, like a nobler Prospero, has now subdued to do him service.

Light is necessary to life; the world was a dead chaos before its creation, and mute disorder would again be the consequence of its annihilation. Every charm which spreads itself over this rolling globe is directly dependent upon luminous power. Colours, and probably, forms, are the result of light; certainly the consequence of solar radiations. We know much of the mysterious influences of this great agent, but we know nothing of the principle itself. The solar beam has been tortured through prismatic glasses and natural crystals; every chemical agent has been tried upon it, every electrical force in the most excited state brought to bear upon its operations, with a view to the discovery of the most refined of earthly agencies; but it has passed through every trial without revealing its secrets, and even the effects which it produces in its path are unexplained problems, still to tax the intellect of man.

Every animal and every plant alike proclaim that life and health are due to light; and even the crystallizing forms of inorganic matter, by bending towards it, confess its all-prevailing sway. From the sun to each planet revolving around that orb, and to the remotest stars which gleam through the vast immensity of heaven, we discover this power still in its brightness, giving beauty and order to these unnumbered creations; no less completely than to this small island of the universe which we call our Earth. Through every form of matter we can mark its

power, and from all, we can, under certain conditions, evoke it in lustre and activity. Over all and through all light spreads its ethereal force, and manifests, in all its operations, powers which might well exalt the mind of Plato to the idea of an omniscient and omnipresent God. Science, with her Ithuriel wand, has, however, shown that light is itself the effect of a yet more exalted cause, which we cannot reach.

Indeed, the attentive study of the fine abstractions of science lifts the mind from the grossness of matter, step by step, to the refinements of immateriality, and there appear, shadowed out beyond the physical forces which man can test and try, other powers still ascending, until they reach the Source of every good and every perfect gift.

FOOTNOTES:

[84] "These—oxygen, hydrogen, nitrogen, and carbon—are the four bodies, in fact, which, becoming animated at the fire of the sun, the true torch of Prometheus, approve themselves upon the earth the eternal agents of organisation, of sensation, of motion and of thought."—Dumas, *Leçons de Philosophie Chimique*, p. 100. Paris, 1837.

[85] It will be found in examining any of the works of the alchemists,—particularly those of Geber, *De inveniendi arte Auri et Argenti*, and his *De Alchemiâ*; Roger Bacon's *Opus Majus, or Alchymia Major*; Helvetius' *Brief of the Golden Calf*; or Basil Valentine's *Currus Triumphalis*,—that in the processes of transmutation the solar light was supposed to be marvellously

effective. In Boyle's *Sceptical Chemist* the same idea will be found pervading it.

Amid all their errors, the alchemists were assiduous workmen, and to them we are indebted for numerous facts. Of them, and of their age, as contrasted with our own, Gibbon remarks:—"Congenial to the avarice of the human heart, it was studied in China, as in Europe, with equal eagerness and equal success. The darkness of the middle ages ensured a favourable reception to every tale of wonder; and the revival of learning gave new vigour to hope, and suggested more specious arts of deception. Philosophy, with the aid of experience, has at length banished the study of alchemy; and the present age, however desirous of riches, is content to seek them by the humbler means of commerce and industry."—*Decline and Fall*, vol. ii. p. 137.

[86] On the two theories the following maybe consulted:—Young, *Supplement to Encyclopædia Britannica*, article *Chromatics*; Fresnel, *Supplément à la Traduction Française de la 5ième édition du Traité de Chimie de Thomson*, par Riffault, Paris, 1822; Herschel's Article, *Light*, in the Encyclopædia Metropolitana, and the French Translation of it by Quetelet and Verhulst; Airy's *Tract on the Undulatory Theory*, in his Tracts, 2nd edition, Cambridge, 1831; Powel, *The Undulatory Theory applied to Dispersion*, &c. p. 184; Lloyd's *Lectures*, Dublin, 1836–41; Cauchy, *Sur le Mouvement des Corps élastiques*, Mémoires de l'Institut, 1827, vol. ix. p. 114; *Théorie de la Lumière*, Ibid. vol. x. p. 293; M'Cullagh, *On Double Refraction*, Ibid., vol. xvi.; *Geometrical Propositions applied to the Wave Theory of Light*, Ibid., vol. xvii.; Sir David Brewster's papers in the Transactions of the Royal Society of Edinburgh, and the

Philosophical Magazine.

[87] *Results of Astronomical Observations made during the years 1834–38, at the Cape of Good Hope, &c.* By Sir John Herschel, Bart., K.H., D.C.L., F.R.S.—"In the contemplation of the infinite, in number and in magnitude, the mind ever fails us. We stand appalled before this mighty spectre of boundless space, and faltering reason sinks under the load of its bursting conceptions. But, placed as we are on the great locomotive of our system, destined surely to complete at least one round of its ethereal course, and learning that we can make no apparent advance on our sidereal journey, we pant with new ardour for that distant bourne which we constantly approach without the possibility of reaching it. In feeling this disappointment, and patiently bearing it, let us endeavour to realise the great truth from which it flows. It cannot occupy our mind without exalting and improving it."—*Sir D. Brewster*: North British Review.

[88] For examples of this, consult Graham's *Elements of Chemistry*; Brande's *Manual of Chemistry*; or, indeed, any work treating of the science. The formation of ink, by mixing two colourless solutions, one of gallic acid and another of sulphate of iron, may be taken as a familiar instance.

[89] Sir John Herschel, in his paper *On the Chemical Action of the Rays of the Solar Spectrum on Preparations of Silver*, remarks that, "it may seem too hazardous to look for the cause of this very singular phenomenon in a real difference between the chemical agencies of those rays which issue from the central portion of the sun's disc, and those which, emanating from its borders, have undergone the absorptive action of a much greater depth

of its atmosphere; and yet I confess myself somewhat at a loss what other cause to assign for it. It must suffice, however, to have thrown out the hint; remarking only, that I have other, and, I am disposed to think, decisive evidence (which will find its place elsewhere) of the existence of an absorptive solar atmosphere, extending beyond the luminous one. The breadth of the border, I should observe, is small, not exceeding 0·5 or 1/7 part of the sun's radius, and this, from the circumstances of the experiment, must necessarily err in excess."—Philosophical Transactions, 1840.

[90] *Experiments and Observations on some Cases of Lines in the Prismatic Spectrum, produced by the passage of Light through Coloured Vapours and Gases, and from certain Coloured Flames.* By W. A. Miller, M.D., F.R.S., Professor of Chemistry in King's College, London.—Philosophical Magazine, vol. xxvii.

[91] *Report on the Mollusca and Radiata of the Ægean Sea, and on their distribution, considered as bearing on Geology*. By Edward Forbes, F.R.S., &c.—Reports of the British Association, vol. xii. Professor Forbes remarks:—"A comparison of the testacea, and other animals of the lowest zones, with those of the higher, exhibits a very great distinction in the hues of the species, those of the depths being, for the most part, white or colourless, while those of the higher regions, in a great number of instances, exhibit brilliant combinations of colour. The results of an enquiry into this subject are as follows:—

"The majority of shells of the lowest zone are white or transparent; if tinted rose is the hue, a very few exhibit markings of another colour. In the seventh region, white species are also very abundant, though by no means forming a

proportion so great as the eighth. Brownish red, the prevalent hue of the brachiopoda, also gives a character of colour to the fauna of this zone; the crustacea found in it are red. In the sixth zone the colours become brighter, reds and yellows prevailing,—generally, however, uniformly colouring the shell. In the fifth region many species are banded or clouded with various combinations of colours, and the number of white species has greatly diminished. In the fourth, purple hues are frequent, and contrasts of colour common. In the second and third, green and blue tints are met with, sometimes very vivid; but the gayest combinations of colour are seen in the littoral zone, as well as the most brilliant whites.

"The animals of Testacea, and the Radiata of the higher zones, are much more brilliantly coloured than those of the lower, where they are usually white, whatever the hue of the shell may be. Thus the genus *Trochus* is an example of a group of forms mostly presenting the most brilliant hues both of shell and animal; but whilst the animals of such species as inhabit the littoral zone are gaily chequered with many vivid hues, those of the greater depth, though their shells are almost as brightly covered as the coverings of their allies nearer the surface, have their animals, for the most part, of a uniform yellow or reddish hue, or else entirely white. The chief cause of this increase of intensity of colour as we ascend is, doubtless, the increased amount of light above a certain depth."—p. 172.

[92] Ἀμόρφωτα. *On the Epipolic Dispersion of Light*, being a paper entitled, *On a case of Superficial Colour presented, by a homogeneous liquid internally colourless*. By Sir J. F. W. Herschel, Bart, K.H., F.R.S., &c.—*An epipolized*

beam of light (meaning thereby a beam which has once been transmitted through a quiniferous solution, and undergone its dispersing action) *is incapable of further undergoing epipolic dispersion*. In proof of this the following experiment may be adduced,—

A glass jar being filled with a quiniferous solution, a piece of plate glass was immersed in it vertically, so as to be entirely covered, and to present one face directly to the incident light. In this situation, when viewed by an eye almost perpendicularly over it, so as to graze either surface very obliquely, neither the anterior nor posterior face showed the slightest trace of epipolic colour. Now, the light, at its egress from the immersed glass, entered the liquid under precisely the same circumstances as that which, when traversing the anterior surface of the glass jar, underwent epipolic dispersion on first entering the liquid. It had, therefore, lost a property which it originally possessed, and could not, therefore, be considered *qualitatively* the same light.—Philosophical Transactions, vol. cxxxvi.

[93] In connection with this view, the Newtonian theory should be consulted, for which see—*A Letter of* Mr. Isaac Newton, *Professor of the Mathematicks in the University of Cambridge; containing his new Theory about Light and Colors: sent by the Author to the Publisher, from Cambridge, Feb. 6, 1671–72, in order to be communicated to the Royal Society*.

[94] In that admirable work, *The Physical Atlas* of Dr. Berghaus, of which a very complete edition by Alexander Keith Johnstone is published in this country, the following order of the distribution of plants is given:—

1. The region of palms and bananas	Equatorial zone.
2. Tree ferns and figs	Tropical zone.
3. Myrtles and laurels	Sub-tropical zone.
4. Evergreen trees	Warm temperate zone.
5. European trees	Cold temperate zone.
6. Pines	Sub-arctic zone.
7. Rhododendrons	Arctic zone.
8. Alpine plants	Polar zone.

Consult Humboldt, *Essai sur la Géographie des Plantes*, Paris, 1807; *De Distributione Geographicâ Plantarum*, Paris, 1817. Schouw, *Grundzüge der Pflanzengeographie*. Also his *Earth, Plants, and Man*; translated by Henfrey, in *Bohn's Scientific Library*. Lamouroux, *Géographie Physique*. *The Plant, a Biography*: by Schleiden; translated by Henfrey. *Physical Geography*: by Mrs. Somerville.

[95] Fraunhofer's measure of illuminating power is as follows:—

At the	22nd degree of the red	0·032
"	34th degree of the red	0·094
"	22nd degree of the orange	0·640
"	10th degree of the yellow	1·000
"	42nd degree of the yellow	0·480
"	2nd degree of the blue	0·170
"	16th degree of the indigo	0·031
"	43rd degree of the violet	0·0056

[96] Herschel, *On the Action of Crystallized Bodies on Homogeneous Light, and on the causes*

of the deviation from Newtons scale in the tints which many of them develope on exposure to a polarized ray.—Phil. Trans., vol. cx., p. 88.

[97] *On the Nature of Light and Colours*: Lecture 39, in Young's *Lectures on Natural Philosophy*, Kelland's Edition, p. 373, and the authorities there quoted.

[98] Brewster's *Optics*: Lardner's Cabinet Cyclopædia. Herschel, *On Light*: Encyclopædia Metropolitana.

[99] Malus, *Sur une Propriété de la Lumière Réfléchie*: Mémoires d'Arcueil. Numerous memoirs by Sir David Brewster, in the Philosophical Transactions.

[100] Bartholin, *On Iceland Crystals*: Copenhagen, 1669. *An Accompt of sundry Experiments made and communicated by that Learn'd Mathematician* Dr. Erasmus Bartholin, *upon a Chrystal like Body sent to him out of Island*: in connection with which Dr. Matthias Paissenius writes:—The observations of the excellent Bartholin upon the Island Chrystal are, indeed, considerable, as well as painful. We have here, also, made some tryals of it upon a piece he presented me with, which confirm his observations. Mean time he found it somewhat scissile and reducible by a knife into thin laminas or plates, which, when single, shew'd the object single, but laid upon one another shew'd it double; the two images appearing the more distant from one another, the greater the number was of those thin plates laid on one another. With submission to better judgements I think it to be a kind of Selenites. Some of our curious men here were of opinion that the Rhomboid figure proper to this stone was the cause of the appearances doubled thereby. But having tryed whether in other transparent bodies of the like figure the

like would happen, we found no such thing in them, which made us suspect some peculiarity in the very Body of the stone.—Phil. Trans. for 1670, vol. v.

[101] *On the Application of the Laws of Circular Polarization to the Researches of Chemistry*: by M. Biot.—Nouvelles Annales du Muséum d'Histoire Naturelle, vol. iii., and Scientific Memoirs, vol. i. p. 600. *On Circular Polarization*: by Dr. Leeson.—Memoirs of the Chemical Society.

[102] In Sir David Brewster's Treatise *On Optics*, chap, xviii., *On Polarization*, the best arrangements for a polarizing apparatus will be found described.

[103] This beautiful application was recently made by Professor Wheatstone, the particulars of which will be found in his interesting communication.—*On a means of determining the apparent Solar Time by the diurnal changes of the Plane of Polarization at the Northern Pole of the Sky*: Report of the Eighteenth Meeting of the British Association.

[104] *On the Polarization of the Chemical Rays of Light*: by John Sutherland, M.D., in which the author refers to the following experiment of M. J. E. Bérard—"I received the chemical rays directed into the plane of the meridian on an unsilvered glass, under an incidence of 35° 61'. The rays reflected by the first glass were received upon a second, under the same incidence. I found that when this was turned towards the south, the muriate of silver exposed to the invisible rays which it reflected was darkened in less than half an hour; whereas, when it was turned towards the west, the muriate of silver exposed in the place where the rays ought to have been reflected, was not darkened, although it was left exposed

for two hours. It is consequently to be presumed that the chemical rays can undergo double refraction in traversing certain diaphanous bodies; and lastly, we may say that they enjoy the same physical properties as light in general."—Philosophical Magazine, vol. xx.

Dr. Leeson has stated that Daguerreotype pictures can be taken more readily under the influence of polarized light, than by ordinary radiation.

[105] *On the Magnetization of Light, and the Illumination of Magnetic Lines of Force*: by Michael Faraday, D.C.L., F.R.S.—Philosophical Transactions, vol. cxxxvii.—The following remarks are to the point of doubt referred to in the text.—"The magnetic forces do not act on the ray of light directly and without the intervention of matter, but through the mediation of the substance in which they and the ray have a simultaneous existence; the substances and the forces giving to and receiving from each other the power of acting on the light. This is shown by the non-action of a vacuum, of air or gases, and it is also further shown by the special degree in which different matters possess the property. That magnetic force acts upon the ray of light always with the same character of manner, and in the same direction, independent of the different varieties of substance, or their states of solid or liquid, or their specific rotative force, shows that the magnetic force and the light have a direct relation; but that substances are necessary, and that these act in different degrees, shows that the magnetism and the light act on each other through the intervention of the matter. Recognising or perceiving *matter* only by its powers, and

knowing nothing of any imaginary nucleus abstract from the idea of these powers, the phenomena described must strengthen my inclination to trust in the views I have advanced in reference to its nature."—Phil. Mag. vol. xxiv.

[106] The invention of the camera obscura certainly belongs to Giambattista Porta, and is described in his *Magiæ Naturalis, sive de Miraculis Rerum Naturalium, Libri Viginti*; Antwerp, 1561. An English translation made in 1658 exists, but I have not seen it.

Hooke, in one of the earliest volumes of the Philosophical Transactions, describes as new many of the phenomena mentioned by Porta, and particularly the images of the dark chamber.

[107] Herschel, *On Light*,—Encyclopædia Metropolitana.

[108] "I would here observe that a consideration of many such phenomena (the obliteration and revival of photographic drawings) has led me to regard it as not impossible that the retina itself may be *photographically* impressed by strong light, and that some at least of the phenomena of visual spectra and secondary colours may arise from the sensorial perception of actual changes in progress in the physical state of that organ itself subsequent to the cessation of the direct stimulant."—*On the action of the Rays of the Solar Spectrum on Vegetable Colours, &c.*: by Sir J. F. W. Herschel, Bart.

[109] Dumeril.

[110] *Theory of Colours*: by Goethe; translated by Eastlake.

[111] See Tuckey's Narrative of the Expedition

of the Zaire.

[112] The most complete examination of this subject will be found in two Memoirs:—

1. *Experiments and observations on the light which is spontaneously emitted with some degree, of permanency from various bodies.*—Phil. Trans., vol. xc.

2. *A continuation of the above, with some experiments and observations on solar light, when imbibed by Canton's phosphorus*: by Nathaniel Hulm, M.D.—Phil. Trans., vol. xci.; and in the *Monograph of the British Naked-eyed Medusæ*, by Professor Edward Forbes (published for the Ray Society). See Wilson's note to the account of *Pennalata phosphorea* in Johnston's Zoophytes, 2nd edition.

[113] *A General Outline of the Animal Kingdom*: by Thomas Rymer Jones, F.L.S.—Acalephæ, p. 64. *Lettre à M. Dumas sur la Phosphorescence des Vers luisants*: par M. Ch. Matteucci.—Annales de Chimie, vol. ix. p. 71, 1843.

[114] *Memoirs of Benvenuto Cellini—Bohn's Standard Library*. See also his Treatise on his Art as a Sculptor and Engraver. Florence, 1568. 4to.

[115] *Phosphorescence of the Diamond*: by M. Reiss (Revue Scientifique et Industrielle, vol. xxiii. p. 185).—"The diamond, phosphorescent by insulation, lost rapidly its phosphorescence when submitted to the action of the red rays of the solar spectrum. On the contrary, the blue rays are those which render the diamond the most luminous in the dark. It is probable that the phosphorescence produced by heat is equally diminished by the action of the red rays of the solar spectrum." Giovanni Battista Beccaria published his experiments in 1769. See Priestley's *History of Electricity*; and *On the*

Effects of Electricity upon Minerals which are Phosphorescent by Heat; and *Further Experiments on the communication of Phosphorescence and Colour to bodies of Electricity*; by Thomas J. Pearsall.—Journal of the Royal Institution of Great Britain, Oct. 1830, Feb. 1831.—These two memoirs contain the most complete set of experiments on this subject which have yet been made; see *Placidus Heinrich*, *Phosphorescenz der Körper*, vol. iv.; Gmelin's *Handbuch der Chemie*, part 1.;—*On the Phosphorescence of Minerals*, Brewster: Edinburgh Philosophical Journal, vol. i. p. 137.;—*The Aërial Noctiluca, or some New Phenomena, and a process of a factitious self shining substance*: Boyle's Works, vol. iv.

[116] *Des Effets produits sur les corps par les Rayons Solaires*: par M. Edmond Becquerel.—Annales de Chimie, vol. ix. p. 257. 1843.

M. Becquerel has applied the term *phosphorogénique* to those rays producing phosphorescence.

CHAPTER VIII.

ACTINISM—CHEMICAL RADIATIONS.

The Sun-ray and its Powers—Darkening of Horn Silver—Niepce's Discovery—Prismatic Spectrum—Refrangibility of Light, Heat, and Actinism—Daguerre's Discovery—Photography—Chemical Effects produced by Solar Radiations—Absorption of Actinism—Phenomena of the Daguerreotype—Chemical Change produced upon all Bodies—Power of Matter to restore its Condition—Light protects from Chemical Change—Photographs taken in Darkness—Chemical Effects of Light on organized Forms—Chemical Effects of Solar Heat—Influence of Actinism on Electricity—Radiations in Darkness—Moser's Discoveries, &c.

Heat and light are derived from the sun, and we have attempted to show, not only that the phenomena of these two principles are different, but that they can scarcely, in the present condition of our knowledge, be regarded as modified manifestations of *one*

superior power. Associated with these two remarkable elements, others may exist in the solar rays. Electrical phenomena are certainly developed by both heat and light, and peculiar electric changes are produced by exposure to sunshine. Electricity may be merely *excited* by the solar rays, or it may *flow* like light from the sun. Chemical action may be only due to the disturbance of some diffused principle; or it may be directly owing to some agency which is radiated at once from the sun.

A sun ray is a magical thing: we connect it in our fancy with the most ethereal of possible creations. Yet in its action on matter it produces colour; it separates the particles of solid masses farther from each other, and it breaks up some of the strongest forces of chemical affinity. To modern science is entirely due the knowledge we have gained of the marvellous powers of the sunbeam; and it has rendered us familiar with phenomena, to which the incantation scenes of the Cornelius Agrippas of the dark ages were but ill-contrived delusions, and their magic mirrors poor instruments. The silver tablets of the photographic artist receiving fixed impressions of the objects represented in the dark chamber by a lens, are far superior as examples of natural magic.

In the dark ages, or rather as the earliest gleams of the bright morning of inductive research were dispelling the mists of that phantom-peopled period, it was observed, for the first time, that the sun's rays turned a white compound black. Man must have witnessed, long before, that change which is constantly taking place in all vegetable colours: some darkening by exposure to sunlight, while others were bleached by its influence. Yet those phenomena excited no attention, and the world knew nothing of

the mighty changes which were constantly taking place around them. The alchemists—sublime pictures of credulous humanity—toiling in the smoke of their secret laboratories, waiting and watching for every change which could be produced by fire, or by their "royal waters," caught the first faint ray of an opening truth; and their wild fancy, that light could change silver into gold, if they but succeeded in getting its subtile beams to interpenetrate the metal, was the clue afforded to the empirical philosopher to guide him through a more than Cretan labyrinth. [117]

The first fact recorded upon this, point was, that horn silver blackened when exposed to the light. Without doubt many anxious thoughts were given by these alchemists to that fact. Here was, as it appeared, a mixing up of light and matter, and behold the striking change! It was a step towards the realization of their dreams. Alas! poor visionaries! in pursuing an ideality they lost the reality which was within their grasp.

Truths come slowly upon man, and long it is before these angel visits are acknowledged by humanity. The world clings to its errors, and avoids the truth, lest its light should betray their miserable follies.

At length a man of genius announced that "*No substance can be exposed to the sun's rays without undergoing a chemical change*;" but his words fell idly upon the ear. His friends looked upon his light-produced pictures as singular; they preserved them in their cabinets of curiosities; but the truths which he enunciated were soon forgotten. Howbeit his words were recorded, and it is due to the solitary experimentalist of Châlons on the Saône, to couple the name of Niepce with the discovery of a fact

which is scarcely second to the development of the great law of universal gravitation.[118] But an examination awaits us, which, for its novelty, has more charms than most branches of science, and which, for the extensive views it opens to the inquirer, has an interest in nowise inferior to any other physical investigation.

The prismatic spectrum affords us the means of examining the conditions of the solar rays with great facility. In bending the ray of white light out of its path, by means of a triangular piece of glass, we divide it in a remarkable manner. We learn that heat is less refracted by the glass than the other powers; we find the maximum point of the calorific rays but slightly thrown out of the right line, which the solar pencil would have taken, had it not been interrupted by the prism; and the thermic action is found to diminish with much regularity on either side of this line. We discover that the luminous power is subject to greater refraction, and that its maximum lies considerably above that of heat; and that, in like manner, on each side the light diminishes, producing orange, red, and crimson colours below the maximum point, and green, blue, and violet above it. Again, we find that the radiations which produce chemical change are more refrangible than either of the others, and the maximum of this power is found at the point where light rapidly diminishes, and where scarcely any heat can be detected: it extends in full activity, above its maximum, to a considerable distance, where no trace of light under ordinary conditions exists, and below that point, until light, appearing to act as an interfering agent, quenches its peculiar properties. These are strong evidences that *light* and *actinism*—as this principle has been named —are not identical: and we may separate them most

easily and effectually from each other. Certain glasses, stained dark blue, with oxide of cobalt, admit scarcely any light; but they offer no interruption to the passage of actinism or the chemical rays; on the contrary, a pure yellow glass, or a yellow fluid, which does not sensibly reduce the intensity of any one colour of the chromatic band of luminous rays, completely cuts off this chemical principle, whatever it may be. In addition to these, there are other results which we shall have to describe, which prove that, although associated in the solar beam, light and actinism are in constant antagonism.

When Daguerre first published his great discovery, the European public regarded his metal tablets with feelings of wonder: we have grown accustomed to the beautiful phenomena of this art, and we have become acquainted with a number of no less beautiful processes on paper, all of which, if studied aright, must convince the most superficial thinker, that a world of wonder lies a little beyond our knowledge, but within the reach of industrious and patient research. Photography is the name by which the art of sun-painting will be for ever known. We regard this as unfortunate, conveying as it does a false idea,—the pictures not being *light-drawn*. Could we adopt the name given by Niepce to the process, the difficulty would be avoided, since Heliography involves no hypothesis, and strictly tells the undeniable truth, that our pictures are *sun-drawn*. That pictures can be produced by the rays from artificial sources, presents no objection to this; these rays were still originally derived from the sun.

By whatever name we determine to convey our ideas of these phenomena, it is certain that they involve a

series of effects which are of the highest interest to every lover of nature, and of the utmost importance to the artist and the amateur. By easy manipulation we are now enabled to give permanence to the charming pictures which are produced by means of that pleasing invention of Baptista Porta, the *Camera Obscura*. Any image, which being refracted by the lens of this instrument falls upon the table in its dark chamber, may be secured with its most delicate gradations of shadows, upon either a metallic or a paper tablet.

But let us proceed to the examination of a few of the more striking phenomena of these chemical changes. To commence with some of the more simple but no less important results.

Chlorine and hydrogen will not unite in darkness, nor will chlorine and carbonic oxide; but, if either of those gaseous mixtures is exposed to sunshine, they combine rapidly, and often with explosion. A solution of the sulphate of iron in ordinary water may be preserved for a long time in the dark without undergoing any change; expose it to the sunshine, and a precipitation of oxide of iron is very rapidly produced. The mineral chameleon, the *manganesiate of potash* in solution, is almost instantly decomposed in daylight; but it is a long time before it undergoes any change in darkness. The same thing occurs with a combination of platinum and lime: indeed, it appears that precipitation is at all times, and under all circumstances, accelerated by the solar rays. As these precipitations are in exact agreement with the quantity of actinic radiation to which the solutions have been exposed, we may actually weigh off the relative quantities, representing in grains the equivalent numbers to the amount of actinism which

has influenced the chemical compound.[119]

We have evidence which appears to prove that this chemical agent may be absorbed by simple bodies, and that by this absorption an actual change of condition, is produced, in many respects analogous to those allotropic changes which we have previously considered. Chlorine, in its ordinary state, does not combine with hydrogen in the dark. If we employ the yellow medium of chlorine gas, for the purpose of analyzing the sun's rays previously to their falling upon some chemical compound which is sensitive to actinic power, we shall find that the chlorine obstructs all this actinism, and, however unstable the compound, it remains unchanged. But the chlorine gas which has interrupted this wonderful agent, appears to have absorbed it, and it is so far altered in its constitution that *it will unite with hydrogen in the dark*.[120] In like manner, if, of two portions of the same solution of sulphate of iron, one is kept in the dark and the other exposed to the sunshine, it will be found that the solution which has been exposed will precipitate gold and silver from their combinations much more speedily than that which has been preserved in darkness—the temperature and every other condition being the same.

The phenomena of the Daguerreotype involve many strange conditions. A plate of silver, on which a slight chemical action has been established by the use of iodine, is exposed to the lenticular image in the camera obscura. If allowed to remain under the influence of these radiations for a sufficient length of time, a faithful picture of the illuminated objects is delineated on the plate, as shown by the visible decomposition and darkening of the iodized surface. The plate is not, however, in practice allowed to

assume this condition; after an exposure of a few seconds the radiant influence is cut off, and the eye cannot detect any evidence of change upon the yellow plate. It is now exposed to the vapour of mercury, and that metal in a state of exceedingly fine division is condensed upon the plate; but the condensation is not uniformly spread upon its face. The deposit of mercurial vapour is in exact proportion to the amount of chemical action produced. Is the change, by which this peculiar power of condensation is effected, a chemical, calorific, electrical, or merely a molecular one? The evidences, at present, are not sufficient to determine the question. It has lately been suggested, that the mercury acts chemically only, and effects the full decomposition of the iodide of silver; and that the picture is due to this, and not to the deposition actually of the mercury vapour. In all probability we have the involved action of several forces. We have some experiments which show, clearly enough, that mercury is deposited in proportions which correspond with the intensity of solar action. A chemically prepared surface is not necessary to exhibit this result. A polished plate of metal, of glass, of marble, or a piece of painted wood, being partially exposed, will, when breathed upon, or presented to the action of mercurial vapour, show that a disturbance has been produced upon the portions which were illuminated, whereas no change can be detected upon the parts which were kept in the dark. It was thought, until lately, that a few chemical compounds, such as the iodide of silver, the material employed in the Daguerreotype and Calotype,—chloride of silver, the ordinary photographic agent,—a few salts of gold, and one or two of lead and iron, were the only materials upon which these very

remarkable changes were produced. We now know that it is impossible to expose any body, simple or compound, to the sun's rays, without its being influenced by this chemical and molecular disturbing power. To take our examples from inorganic nature, the granite rock which presents its uplifted head in firmness to the driving storm, the stones which genius has framed into forms of architectural beauty, or the metal which is intended to commemorate the great acts of man, and which in the human form proclaims the hero's deeds and the artist's talent, are all alike destructively acted upon during the hours of sunshine, and, but for provisions of nature no less wonderful, would soon perish under the delicate touch of the most subtile of the agencies of the universe.

Niepce was the first to show that all bodies which underwent this change during daylight possessed the power of restoring themselves to their original conditions during the hours of night, when this excitement was no longer influencing them. Resins, the Daguerreotype plate, the unprepared metal tablet, and numerous photographic preparations, prove this in a remarkable manner.[121]

The picture which we receive to-day, unless we adopt some method of securing its permanency, fades away before the morrow, and we try to restore it in vain. With some of our chemical preparations this is very remarkably shown, but by none in so striking a manner as by paper prepared with the iodide of platinum, which, being impressed with an image by heliographic power, which is represented by dark brown tints, restores itself in the dark, in a few minutes, to its former state of a yellow colour, and recovers its sensibility to sunshine.[122] The

inference we alone can draw from all the evidences which the study of actino-chemistry affords, is, that the hours of darkness are as necessary to the inorganic creation as we know night and sleep to be to the organic kingdom. But we must not forget that there does exist in the solar rays a balance of forces which materially modifies the amount of disturbing influence exerted by them on matter. Not only do we find that the chemical action is not extended over the whole length of the prismatic spectrum, but we discover that over spaces, which correspond with the maximum points of light and heat, a protective action is exerted. That is, that highly sensitive photographic agents, which blacken rapidly under exposure to diffused daylight, are entirely protected from change in full sunshine, if at the same time as a strong light is thrown upon them by reflection, the yellow and extra red rays are brought to bear upon their surface. Not only so, but by employing media which will cut off all the chemical rays of the spectrum, admitting freely at the same time the luminous and calorific rays, we find that a protected band, the length of the spectrum, remains white, whilst every other portion has blackened.[123]

Among the many curious instances of natural magic, none are more remarkable than an experiment not long since proposed, by which Daguerreotype pictures may be taken in absolute darkness to the human eye. This is effected in the following manner:—A large prismatic spectrum is thrown upon a lens fitted into one side of a dark chamber; and as we know that the actinic power resides in great activity beyond the violet ray, where there is no light, the only rays which we allow to pass the lens into the chamber are those which are extra-spectral and non-luminous. These are directed upon, any white object,

and from that object radiated upon a highly sensitive plate in a camera obscura. Thus a copy of the subject will be obtained by the agency of radiations which produce no sensible effect upon the optic nerve. This experiment is the converse of those which show us that we may illuminate any object with the strongest sunlight which has passed through yellow glass, the yellow solution of sulphuret of calcium, or of the bichromate of potash—these being non-transparent to the chemical rays—and yet fail to secure any Daguerreotype copy of it, even upon the most exquisitely sensitive plate. Indeed, the image of the sun itself, when setting through an atmosphere which reduces its light to a red or rich yellow colour, not only produces no chemical change, but protects an iodized plate from it; and whilst every other part of the tablet gives a picture of surrounding objects in the ordinary character, the bright sun itself is represented by a spot upon which no change has taken place.[124] In tropical climes, where a brilliant sun is giving the utmost degree of illumination to all surrounding objects, all photographic preparations are acted upon relatively more slowly than in the climate of England, where the light is less intense. As a remarkable instance of this fact, a circumstance may be mentioned, which is curiously illustrative of the power of light to interfere with actinism:—

A gentleman, well acquainted with the Daguerreotype process, obtained in the city of Mexico all the necessary apparatus and chemicals, expecting, under the bright light and cloudless skies of that climate, to produce pictures of superior excellence. Failure upon failure was the result; and although every care was used, and every precaution adopted, it was not until the rainy season set in that he could secure a good Daguerreotype of any of the

buildings of that southern city.

The first attempts, which were made at the instigation of M. Arago, by order of the French Government, to copy the Egyptian tombs and temples, and the remains of the Aztecs in Central America, were failures. Although the photographers employed succeeded to admiration in Paris, in producing pictures in a few minutes, they found often that an exposure of an hour was insufficient under the bright and glowing illumination of a southern sky.

Experiments with the spectrum have been made in different latitudes, and it is found, that, as we proceed towards the equator, a band which is always left unchanged, corresponding exactly with the rays of greatest illuminating power, regularly enlarges in size, thus proving the increase of light over actinism —and the interfering power of the former.

By increasing the sensibility of the photographic preparation, this difficulty is overcome, and particularly when any organic compound enters into the preparation. So that we are now enabled to copy nature in all her varying moods, whether we employ our photographic tablets in temperate Europe, or in tropical Africa.

The degree of sensibility which has been attained is remarkable. Mr. Fox Talbot, by uniting a process devised by Dr. Woods, of Parsonstown, and another which was first introduced by the author of this volume, and combining them with an ether, obtains a most unstable compound, which he thus employs. A glass plate is covered with albumen united with the above solution, and then with nitrate of silver: this forms the sensitive surface. The plate being placed in the dark, in a camera, it is so adjusted that

the image of a printed bill fixed upon a wheel may fall upon it when uncovered, and the wheel illuminated. The wheel is made to revolve with the utmost rapidity, in a perfectly dark room, and the sensitive plate uncovered. Then the whirling bill is illuminated for an inappreciably short space of time by the discharge of a Leyden jar. Notwithstanding the rapid rate at which the pointed paper is moving, and the instantaneous nature of the illumination—a miniature flash of lightning—the bill is found to be copied with unfailing fidelity upon the photographic plate. It unfortunately happens, that the preparation by which this extraordinary degree of sensibility is obtained, is very uncertain in its action—and hence it is not generally useful; but here we have the evidence to show that at a speed as rapid as that of a rifle-ball an impression may be made upon a photographic plate. There are, however, some new processes which promise eventually to rival the above for sensibility, and to be by no means of difficult manipulation. Of this character is the collodion process. The gun cotton dissolved in ether possesses some very great accelerating properties, and in combination with the silver salts, and one of the vegetable acids, it forms a sensitive surface upon which pictures may be obtained in less than a second of time.

Colour, natural colour too, has been very decidedly secured. The sun has been solicited to display his palette, and the answer has been a picture in which colour for colour in all their fidelity have been impressed. The plate upon which this result has been obtained is of a dark brown colour, and the chromatic variety is, as it were, eaten out by the solar rays. These colours have not yet been permanently fixed upon the plate employed, but

from the temporary degree of fixedness which has been obtained, we may fairly hope that in a short time colour may be rendered as permanent on the productions of the photographer as on those of the painter. It is a curious and striking fact, that in the preparation of these plates, salts are used which give colours to flame; and according to the colour which is produced by them when burning, so, on the photographic plate, is that colour impressed with greater intensity than the others. To what is this leading us? Mysteries surround our advances on the domain of truth. We dare not speculate upon them: the time of their full development will arrive.

By the aid of this beautiful art, we are enabled to preserve the lineaments of those who have benefited their race by their intellect, or their heroism. We can hand down to future ages portraits of our own Wellington, and the illustrious Arago, unerring in their truthfulness. How great would be the joy of all, could we now obtain a daguerreotype portrait of a Greek poet, or of a Roman philosopher, of a Sophocles, or of a Seneca! How much discussion would be prevented did we possess a calotype portrait of the Bard of Avon, or of the Philosopher of Grantham!

By the agency of those very rays which give life and brilliancy to the laughing eye and the roseate cheek, we can at once correctly trace the outline of the features we admire, with all those shadowy details which give a reality to the “presentment.” The objects of our love may be for ever present with us in these self-painted pictures. The vicious, whom we would avoid, may be made known to us by this unerring painter. The process which nature employs is perfect; the imperfections are those of man, and

these being few, he may soon learn to remedy.

To the traveller, how valuable are the processes of photography! He secures representations of those remains of temples which were in their glory when Moses wrote. He copies by one operation a tomb at Karnac, covered with myriads of hieroglyphics, or an inscribed stone in Arabia, which it would occupy him days to trace. These he can carry to his home and read at his leisure. The relics of hoar antiquity speaking to the present of the past, and recording the histories of races which have fleeted away like shadows, are thus preserved to tell their wondrous tales.

The admirer of nature may copy her arrangements with the utmost fidelity. Every modulation of the landscape, each projecting rock or beetling tor—the sinuous river in its rapid flow—the meandering stream, "gliding like happiness away;" and the spreading plains over which are scattered the homes of honest industry and domestic peace, intermingled with the towers of those humble temples in which simple-hearted piety delights to "bow the head and bend their knee;" these, all of these, may, by the sunbeam which illuminates the whole, be faithfully pencilled upon our chemical preparations.

Our art enables us to do more even than this; we have but to present our sensitive tablet to the moon, and she, by her own light, prints her mountains and her valleys, and indicates with all truth the physical conditions of her surface.

Any reference to the *chemical agency* of LIGHT—*the luminous rays* as distinguished from the *chemical and calorific rays*—has been avoided until we came to the consideration of this particular question of chemical change.

Upon organic compounds, as, for instance, upon the colouring matter of leaves and flowers, *light* does exert a chemical power: and it is found that vegetable colours are bleached, not by rays of their own colour, but by those which are *complementary* to them. A red dye fades under the influence of a green ray, and a yellow under that of a violet one, much more speedily than when exposed to rays of any other colour; and this, it must be remembered, is due to the coloured ray itself, and not to any *actinic* power masked, as it were, behind the colour, as is generally believed.[125] It was long a question whether the decomposition of carbonic acid by plants was due to the luminous or the chemical rays. It is now clearly established that the luminous rays are the most active in producing this effect; which they do indirectly, by exciting the vital powers of the organized structures. Therefore we would refer this phenomenon of gaseous decomposition to a vital power quickened by luminous excitement.[126]

We have already noticed some chemical phenomena due to heat, particularly those experiments of Count Rumford's, which appeared to him to prove that the chemical agency of the sun's rays was due to its calorific power. Certain chemical phenomena, we know, may be produced by thermic action; but the only variety of thermo-chemical action which connects itself immediately with the solar radiations, belongs to a class of rays to which the name of *Parathermic* has been given, and to which the scorching, as it is called, of plants, the browning of the autumnal leaves, and the ripening of fruits, appear to be due.[127] When we come to the consideration of those physical phenomena which belong to the growth of plants, all these peculiarities

of solar action must be attended to in detail.

The manner in which we find the actinic power influencing electrical action, also shows us that the equilibrium of forces is continued through all the great principles of nature. If a galvanic arrangement is made, by which small quantities of metals may be slowly precipitated at one of the poles in the dark, and a similar arrangement be exposed to sunshine, it will be found that no metal is deposited: the sun's rays have interfered with the decomposing power of the electrical current. At the same time we learn, that by throwing a beam of light upon a plate of copper which forms one of a galvanic pair, whilst it is under the influence of an acidulated solution, an additional excitation takes place, and the galvanometer will indicate the passage of an increased current of electricity. These two dissimilar actions appear enigmatical; but they may, there is no doubt, receive some solution from the influence of different rays on the contrary poles of the battery. One thing is quite evident,—electricity suffers a disturbance of one order, by light; and an excitement of another by its associated principles in the sunbeam. If a yellow glass is interposed between the galvanic arrangement and the sun, the electro-chemical precipitation goes on in the same manner as it would in perfect darkness, and no extra excitement is produced upon the plates of the battery. From this it would appear that actinism and not light is to be regarded as the disturbing power. [128] It has already been shown that yellow media possess the power of stopping back the chemical agent.

We have already, detailed many of the peculiarities of the different varieties of Phosphori, which would

seem to be the result of light. Phosphorescence is probably excited by those rays which produce no direct effect upon the eye. If we spread sulphuret of calcium upon paper, and expose it to the action of the solar spectrum, it is found to glow (in the dark) only over those spaces occupied by the violet rays and the ordinarily dark rays beyond them; proving that the excitation necessary to the development of the phenomena of phosphorescence is due to a class of rays distinct from the true light-giving principle, and more nearly allied to that principle or power which sets up chemical decomposition. Whether the fluorescent rays, before mentioned, which are found so abundantly over the space which produces the greatest phosphorescent effect, are active in producing the phenomena, is as yet an unsolved problem.

Vision and colour, calorific action, chemical change, molecular disturbance, electrical phenomena, and phosphorescent excitation, all, each one with a strange duality, are connected with the sunbeam.

We find, when we receive solar spectra upon iodized plates, or on several kinds of photographic paper, that a line, over which no action takes place, is preserved at the top and bottom of the impressed image, and in many cases along the sides also. The only way in which this can be accounted for, as the spectrum represents the sun in a distorted form, is by supposing that rays come from the edges of the sun of a different character from those which proceed from the centre of that orb.[129]

Light from the centre of the solar disc is under different conditions from that which comes from the edge of the sun: this is due to the varying angle, which is presented to us by a circular body: calorific

action seems to be more strongly manifested when the envelope of light, extending like an atmosphere to the sun, is thrown into great agitation, and waves, and great hollows—solar spots—are produced. There is some indication of the existence of a third condition on the sun's surface, to which probably belongs the mighty chemical power which we call actinism. Electricity may be, as some have speculated, the exciting agent; a constant and violent Aurora Borealis may exist on the sun, and under the excitation of this force the others named may be quickened into full activity.

That actinism is one of the great powers of creation we have abundant proof. Nearly all the phenomena of chemical change which have been referred to light, are now proved to be dependent upon actinic power; and beyond the influence which has been ascertained to be exerted by it upon all inorganic bodies, we shall have occasion to show still further the dependence of the vegetable and animal worlds upon its agency. The influence of the solar beams on vegetation is proved by common experience; the closer examination of its action on vegetable life is reserved for the chapter devoted to its phenomena. Of its influence on animals nothing is very correctly known; but some early experiments prove that they, like other organised bodies, are subject to all the radiant forces, as indeed, independent of experiment, every observation must teach. Certain it is, that organisation can take place only where the sun's rays can penetrate: where there is unchanging darkness, there we find all the silence of death. Prometheus stole fire from heaven, and gave the sacred gift to man, as the most useful to him of all things in his necessities: by the aid of it he could temper the severities of climate, render his food more digestible

and agreeable, and illuminate the hours of darkness. So says the beautiful fiction of the Grecian mind,—which appears as the poetic dream or prophetic glance of a gifted race, who felt the mysterious truth they were yet unable to describe. Pheaton and Apollo are only other foreshadowings of the creative energies which dwell in the glorious centre of our universe. The poetry of the Hellenic people ascended above the littlenesses of merely human action, and sought to interpret the great truths of creation. Reflective, they could not but see that some mysterious powers were at work around them; imaginative, they gave to fine idealisations the government of those inexplicable phenomena. Modern science has shown what vastly important offices the solar rays execute, and that the principles discovered in a sunbeam are indeed the exciters of organic life, and the disposers of inorganic form.

It must not be forgotten that we have already alluded to a speculation which supposes this actinic influence to be diffused through all nature, to be indeed the element to which chemical force in all its forms is to be referred, and that it is merely excited by the solar rays. This hypothesis receives some support from the very peculiar manner in which chemical action once set up is carried on, independent of all extraneous excitement, after the first disturbance has been produced. If any of the salts of gold are exposed in connection with organic matter, as on paper, to sunshine for a moment, an action is begun, which goes on unceasingly in the dark, until the gold is reduced to its most simple state.[130] The same thing occurs with chromate of silver, some of the salts of mercury, argentine preparations combined with protosulphate of iron or gallic acid, and some other chemical combinations. These progressive influences

point to some law not yet discovered, which seems to link this radiant actinism with the chemical agent existing in all matter.

This problem also connects itself with another class of facts which, although due, in all probability, to a great extent, to calorific radiations, and hence known under the general term of Thermography, appear to involve both chemical and electrical excitation. From the investigations of Moser and of others, we learn the very extraordinary fact, that even inanimate masses act and react upon each other by the influence of some dark radiations, and seem to exchange some of the peculiarities which they possess. This appears generally in the curious experiments which have been referred to, as confined merely to form or structure. Thus an engraved plate will give to a polished surface of metal or glass placed near it, after a very little time, a neat distinct image of itself; that is, produce such a structural disturbance as will occasion the plate to receive vapour differently over those spaces opposite to the parts in cameo or in intaglio, from what it does over the opposite. If a piece of wood is used instead of a metal, there will, by similar treatment, be produced a true picture of the wood, even to the representation of its fibres.[131]

It is also probable that chemical decomposition is produced by the mere juxtaposition of different bodies. Iodide of gold or silver, perfectly pure, has been placed upon a plate of glass, and a plate of copper covered with mercury suspended over it: a gradual decomposition of those salts is said to have been observed, iodide of mercury to be formed, and the gold or silver salts reduced to a finely divided metallic state.[132]

A body whose powers of radiating heat are low, being brought near another whose radiating powers are more extensive, will, in the course of a short time, undergo such an amount of molecular disturbance as will effect a complete change in the arrangement of its surface, and an impression of the body having the highest radiating powers will be made upon the other. This impression is dormant, but may be developed under the influence of vapour, or of oxidation.[133] A body, such as charcoal, of low conducting power, being placed near another, such as copper, which is a good conductor, will, in a very short time, produce, in like manner, an impression of itself upon the metal plate. Thus any two bodies, whose conducting or radiating powers are dissimilar, being brought near each other, will occasion a molecular disturbance, or impress the one with the image of the other. However small the difference may be, an effect is perceived, and that of the most extraordinary kind, giving rise to the production of actual images upon each surface exposed. It is thus that a print on paper may be copied on metal, by merely suspending it near a well-polished plate of silver or copper for a few days. The white and black lines radiate very differently; consequently an effect is produced on the bright metal in the parts corresponding to the black lines, dissimilar to that which takes place opposite to the white portions of the paper; and, on the application of vapour, a true image of the one is found impressed upon the other. [134]

Bodies which are in different electrical states act upon each other in an analogous manner. Thus arsenic, which is highly electro-negative, will, when placed near a piece of electro-positive copper, readily impart to its surface an impression of itself, and so in

like manner will other bodies if in unlike conditions. Every substance physically different (it signifies not whether as it regards colour, chemical composition, mechanical structure, calorific condition, or electrical state,) has a power of radiation by which a sensible change can be produced in a body differently constituted.

Fable has told us that the magicians of the East possessed mirrors in which they could at will produce images of the absent. Science now shows us that representations quite sufficient to deceive the credulous can be produced on the surface of polished metals without difficulty. A highly polished plate of steel may be impressed with images of any kind, which would remain invisible, the polished surface not being in the least degree affected, as it regards its reflecting powers; but by breathing over it, the dormant images would develope themselves, and fade away again as the condensed moisture evaporated from the surface.[135]

These, which are but a few selected from a series of results of an equally striking character, serve to convince us that nature is unceasingly at work, that every atom is possessed of properties by which it influences every other atom in the universe, and that a most important class of natural phenomena appear to connect themselves directly with the radiant forces.

The alchemists observed that a change took place in chloride of silver exposed to sunshine. Wedgwood first took advantage of that discovery to copy pictures. Niepce pursued a physical investigation of the curious change, and found that all bodies were influenced by this principle radiated from the sun. Daguerre produced effects from the solar pencil

which no artist could approach to; and Talbot and others extended the application. Herschel took up the inquiry; and he, with his usual power of inductive search and of philosophical deduction, presented the world with a class of discoveries which showed how vast a field of investigation was opening for the younger races of mankind,—a field in which a true spirit may reap the highest reward in the discovery of new facts, and to which we must look for a further development of those great powers with which we have already some slight acquaintance, and for the discovery of higher influences which are not yet dreamed of in our philosophy.

If music, with its mysteries of sound,
  Gives to the human heart a heavenward feeling;
The beauty and the grandeur which are found
Spread like a vesture this fair earth around,
  Creation's wond'rous harmonies revealing,
  And to the soul in truth's strong tongue appealing,
With all the magic of those secret powers,
  Which, mingling with the lovely band of light,
The sun in constant undulation showers
To mould the crystals, and to shape the flowers,
  Or give to matter the immortal might
Of an embracing soul—should, from this sod,
Exalt our aspirations all to God.

FOOTNOTES:

[117] See *Researches on Light*, by the Author.—Reference to any of the works of the alchemists will prove the prevalence of the idea expressed in the text. We find that gold was considered to be always under the

influence of light and solar heat.—"It is said of gold that it waxeth cold towards daylight, insomuch that they who wear rings of it may perceive when the day is ready to dawn."—*Speculum Mundi, or a Glass representing the face of the World*. Cambridge, 1643.

[118] Daguerre's Report to the Academy of Sciences: *La Daguerréotype Historique, et description des procédés du Daguerréotype et du Diorama* (Paris, 1839); particularly the description of *Heliography*, by M. Niepce. See also the letters by Niepce, published for the first time in *Researches on Light*.

[119] "If a solution of peroxalate of iron be kept in a dark place, or if it be exposed to 212° of Fahr. for several hours, it does not undergo any sensible change in its physical properties, nor does it exhibit any phenomenon which may be considered as the result of any elementary action.

"If, however, it be exposed to the influence of solar light in a glass vessel provided with a tube, the concentrated solution of oxalate of iron soon presents a very interesting phenomenon: in a short time the solution receiving the solar rays, developes an infinite number of bubbles of gas, which rise in the liquor with increasing rapidity, and give the solution the appearance of a syrup undergoing strong fermentation. This ebullition always becomes stronger, and almost tumultuous, when an unpolished glass tube is immersed in it with a small piece of wood; the liquid itself is afterwards thrown into ascending and descending currents, becomes gradually yellowish, turbid, and eventually precipitates protoxalate of iron, in the form of small brilliant crystals of a lemon-yellow colour, gas continuing to evolve." *Chemical action of light,*

and formation of Humboldtine by it; Phil. Mag., 1832, second series.—"When a solution of platinum in nitro-muriatic acid, in which the excess of acid has been neutralized by the addition of lime, and which has been well cleared by filtration, is mixed with lime-water in the dark, no precipitation to any considerable extent takes place for a long while,—indeed, none whatever, though after very long standing a slight flocky sediment is formed, after which the action is arrested entirely. But if the mixture, either freshly made or when cleared by subsidence of this sediment, is exposed to sunshine, it instantly becomes milky, and a copious formation of a white precipitate (or a pale yellow one, if the platinic solution be in excess) takes place, which subsides quickly and is easily collected. The same takes place more slowly in cloudy daylight."—*On the action of light in determining the precipitation of Muriate of Platinum by Lime water*; being an extract from a letter from Sir John F. W. Herschel, K.H., F.R.S., &c., to Dr. Daubeny.—Phil. Mag. 1832.

[120] *On a change produced by Exposure to the Beams of the Sun, in the properties of an elementary substance*, by Professor Draper; *On the changes which bodies undergo in the dark*, by Robert Hunt: Report of the Thirteenth Meeting of the British Association, vol. xii,—*Description of the Tithonometer, an instrument for measuring the chemical force of the Indigo-tithonic rays*: by J. W. Draper, M.D.—Philosophical Magazine, Dec. 1843, vol. xxiii.

[121] For several illustrations of this remarkable phenomenon, see *On the Action of the Rays of the Solar Spectrum on Vegetable Colours, and on some new Photographic Processes*; by Sir John F. W. Herschel, Bart.,

K.H., F.R.S.—Phil. Trans. June, 1842, vol. cxxxiii.; *On certain improvements on Photographic Processes described in a former communication, and on the Parathermic Rays of the Solar Spectrum*; by Sir John F. W. Herschel, Bart., K.H., F.R.S., &c., in a letter addressed to S. Hunter Christie.—Phil. Trans. 1843, vol. cxxxiv.

[122] Sir J. F. W. Herschel; see also *Researches on Light*, by the Author.

[123] Attention has been directed to the protecting action of certain rays of the spectrum by Sir John Herschel and others. See the Eighteenth Report of the British Association for an experiment by the Author, in which it was proved that all the LIGHT rays protected photographic papers from chemical change, and, therefore, convincingly show that light and actinism were not similar powers.

[124] "Having noticed, one densely foggy day, that the disc of the sun was of a deep red colour, I directed my apparatus towards it. After ten seconds of exposure, I put the prepared plate in the mercury box, and I obtained a round image perfectly black;—the sun had produced no photogenic effect. In another experiment, I left the plate operating for twenty minutes; the sun had passed over a certain space of the plate, and there resulted an image seven or eight times the sun's diameter in length; it was black throughout, so that it was evident, wherever the red disc of the sun had passed, not only was there a want of photogenic action, but the red rays had destroyed the effect produced previous to the sun's passage. I repeated these experiments during several days successively, operating with a sun of different tints of red and yellow. These different tints produced nearly the same

effect; wherever the sun had passed, there existed a black band."—Mr. Claudet, *On different properties of Solar Radiation, modified by coloured glass media, &c.*: Phil. Trans. 1847. Part 2.

[125] "It may also be observed that the rays effective in destroying a given tint are, in a great many cases, those whose union produces a colour complementary to the tint destroyed, or at least one belonging to that class of colours to which such complementary tint may be referred. For example, yellows tending towards orange are destroyed with more energy by the blue rays; blue by the red, orange, and yellow rays; purples and pinks by yellow and green rays."—Sir J. F. W. Herschel, *On the action of the rays of the Solar Spectrum on Vegetable Colours*: Phil. Trans., vol. cxxxiii. 1842.

[126] The following memoirs and works are necessary to a complete history of the inquiry: —*Experiments and observations relating to various branches of natural philosophy, with a continuation of the observation on air*: by Dr. Priestley. London, 1779. *Mémoires Physico-chimiques, &c.*: by J. Senebier. *Expériences sur les végétaux*, by De la Ville: Paris, 1782; and Phil. Trans. 1782. *Observations sur les expériences de M. Ingenhousz*: by De la Ville; Roz. obs. 23, 290. *Expériences propres à développer les effets de la lumière sur certaines plantes*: by Tessier; Mém. de l'Ac. des Sc. de Paris, 1783, p. 132; Licht. Mag. iv. 4, 146. *Sur la vertu de l'eau impregnée d'air fixe pour en obtenir, par le moyen des plantes et de la lumière du soleil, de l'air déphlogistiqué*: by Ingenhousz; Roz. obs. 24, 337. *Expériences sur l'action de la lumière solaire dans la végétation*: by Senebier; Genève et Paris, 1788, p. 61. *Extrait des*

expériences de M. Senebier sur l'action de la lumière solaire dans la végétation: by Hasenfratz; Ann. Chim. iii. 2nd. ser. 266. *Expériences relatives à l'influence de la lumière sur quelques végétaux*: by De Candolle; Jour. de Ph. lii. 124: Voigt's Mag. ii. 483; Gilb. Ann. xiii. 372; Mém. des Sav. Etr. i. 329. *Recherches chimiques sur la végétation*: by Saussure; Ann. Chim. l. 225; Jour. de Ph. lvii. p. 393; Gilb. Ann. xviii 208. *Recherches sur la respiration des plantes exposées à la lumière du soleil*; by Ruhland; Ann. Ch. Ph. iii. 411; Jour. de Ph. 1816. *On the action of light upon plants, and of plants upon the atmosphere*: by Dr. Daubeny; Phil. Trans. cxxvii January, 1836. *On the action of yellow light in producing the green colour, and of indigo light on the movements of plants*: by P. Gardner; Phil. Mag. xxiv.; Bibl. Univ. xlix. p. 376, and lii. p. 381. *On the influence of light on plants*: by R. Hunt; Phil. Mag. xxiv. p. 96; Bibl. Univ. xlix. p. 383; Athen. 1844. *Note on the decomposition of carbonic acid by the leaves of plants, under the influence of yellow light*: by Draper; Phil. Mag. xxv. p. 169. *On the action of the yellow rays of light on vegetation*: by Harkness; Phil. Mag. xxv. p. 339. *Influence des rayons solaires sur la végétation*: by Zantedeschi; Inst. No. 541, p. 157.

[127] Sir John Herschel's Memoirs already referred to; and *Reports on the influence of the Solar Rays on the growth of Plants*, by Robert Hunt: Report of the British Association for the Advancement of Science, for 1847.

[128] *Memoir on the Constitution of the Solar Spectrum*, presented at the meeting of the Academy of Sciences, 1842, by M. Edmond Becquerel; *Des effets produits sur les corps par les rayons solaires*, par M. Edmond Becquerel, aide au Muséum d'Histoire Naturelle: Mémoire

présenté à l'Académie des Sciences, le 23 Octobre, 1843.—"Dans le courant de ce mémoire, j'ai employé les noms de rayons lumineux, chimiques, et phosphorogéniques, pour désigner, dans chaque cas, la portion des rayons solaires qui agit pour produire, en particulier, les effets lumineux, chimiques, et phosphorogéniques; mais cela est sans préjudice de l'opinion que je viens d'émettre touchant l'existence d'un seul et même rayonnement."

"My reply is this," says M. Arago, in his paper entitled *Considerations relative to the action of Light*: "It is by no means proved that the photogenic modifications of sensitive substances result from the action of the solar light itself. The modifications are, perhaps, engendered by invisible radiations mixed with light properly so called, proceeding with it, and being similarly refracted. In this case, the experiment would prove not only that the spectrum formed by these invisible rays is not continuous, that there are solutions of continuity as in the visible spectrum, but also that in the two superposed spectra these solutions correspond exactly. This would be one of the most curious, one of the most strange results of physics."—Taylor's Scientific Memoirs.

[129] The chemical evidence of this will be found in Sir John Herschel's Memoir *On the Solar Spectrum*, and particularly as exemplified in the changes produced on the tartrate of silver. Similar influences are described as observed on a Daguerreotype plate, in a paper entitled *Experiments and Observations on Light which has permeated coloured media, and on the Chemical Action of the Solar Spectrum*; by Robert Hunt.—Philosophical Magazine, vol.

xxvi. 1840.

[130] This peculiar continuance of an effect has frequently been observed in many of the photographic processes. In a note to a memoir *On certain improvements in Photographic processes*, Sir John Herschel thus refers to this property:—"The excitement is produced on such paper by the ordinary moisture of the atmosphere, and goes on slowly working its effect in the dark, apparently without other limit than is afforded by the supply of ingredients present. In the case of silver it ultimately produces a perfect *silvering* of all the sunned portions. Very singular and beautiful photographs, having much resemblance to Daguerreotype pictures, are thus produced; the negative character changing by keeping, and by quite insensible gradations to positive, and the shades exhibiting a most singular *chatoyant* change of colour from ruddy-brown to black, when held more or less obliquely. No doubt, also, gold pictures with the metallic lustre might be obtained by the same process, though I have not tried the experiment."

[131] The details of this curious subject may be studied in the following memoir and communications:—*On vision and the action of light on all bodies*: by Professor Ludwig Moser, of Königsberg; from Poggendorff's Annalen, vol. lvi. p. 177, No. 6, 1845. *Some remarks on Invisible Light*: by Professor Ludwig Moser, of Königsberg; from Poggendorff's Annalen, vol. lvi. p. 569, No. 8. *On the power which light possesses of becoming latent*: by Professor Ludwig Moser, of Königsberg; from Poggendorff's Annalen, vol. lvii. No. 9, p. 1. 1842. *On certain spectral appearances, and on the discovery of latent light*: by J. W. Draper, M.D., Professor of Chemistry in the University

of New York; Phil. Mag. p. 348, Nov. 1842. *On a new imponderable substance, and on a class of chemical rays analogous to the rays of dark heat*: by Professor Draper; Phil. Mag., Dec. 1842. *On the action of the rays of the solar spectrum on the Daguerreotype plate*; by Sir J. F. W. Herschel, Bart.; Phil. Mag., Feb. 1843. See remarks in this paper on the use which Moser has made of coloured glasses: also a communication by Professor Draper, *On the rapid Detithonizing power of certain gases and vapours, and on an instantaneous means of producing spectral appearances*: Phil. Mag., March 1843; and *On the causes which concur in the production of the images of Moser*: Comptes Rendus, Nov. 1842. See *Scientific Memoirs*, vol. iii.

[132] This fact was first observed by myself, and described in the paper already referred to, Philosophical Magazine, vol. xxii. p. 270. It does not, however, appear to have attracted the attention of any other observer.

[133] *On Thermography, or the Art of copying Engravings or any printed characters from paper or plates of metal, and on the recent discovery of Moser, relative to the formation of images in the dark*, by Robert Hunt: Reports of the Royal Cornwall Polytechnic Society for 1842, and Philosophical Magazine, vol. xxi. p. 462.—*On the Spectral Images of M. Moser*, by Robert Hunt: Philosophical Magazine, vol. xxiii. p. 415.

[134] *Catalytic force, or attraction of surface concerned in the diffusive power of gases: an occult energy or power in saturated saline solutions*; Prater.—Mechanic's Magazine, vol. xlv. p. 106. *Ueber elektrische Abbildungen*; by G. Karsten.—Poggendorff's Annalen, vol. lvii. p. 402.—Melloni and Brewster may be consulted for much that is most remarkable connected

with radiation from coloured surfaces.

[135] Cornelius Agrippa is said to have possessed such a mirror. The Chinese make mirrors which, when placed in a particular light, show upon their polished faces the pattern on the back of the metal, although it is invisible in every other position. This is effected by giving different degrees of hardness to the various parts of the metal. In *Natural Magic*, by Sir David Brewster, several curious experiments belonging to this class are named.

CHAPTER IX.

ELECTRICITY.

Discovery of Electrical Force—Diffused through all Matter—What is Electricity?—Theories—Frictional Electricity—Conducting Power of Bodies—Hypothesis of two Fluids—Electrical Images—Galvanic Electricity—Effects on Animals—Chemistry of Galvanic Battery—Electricity of a Drop of Water—Electro-chemical Action—Electrical Currents—Thermo-Electricity—Animal Electricity—Gymnotus—Torpedo—Atmospheric Electricity—Lightning Conductors—Earth's Magnetism due to Electrical Currents—Influence on Vitality—Animal and Vegetable Development—Terrestrial Currents—Electricity of Mineral Veins—Electrotype—Influence of Heat, Light, and Actinism on Electrical Phenomena.

If a piece of amber, *electrum*, is briskly rubbed, it

acquires the property of attracting light bodies. This curious power excited the attention of Thales of Miletus; and from the investigations of this Grecian philosopher we must date our knowledge of one of the most important of the natural forces—Electricity.

If an inquiring mind had not been led to ask why does this curious natural production attract a feather, the present age, in all probability, would not have been in possession of the means by which it is enabled to transmit intelligence with a rapidity which equals the poet's dream of the "swift-winged messengers of thought." To this age of application a striking lesson does this amber teach. Modern utility would have regarded Thales as a madman. Holding a piece of yellow resin in his hand, rubbing it, and then picking up bits of down, or catching floating feathers, the old Greek would have appeared a very imbecile, and the *cui bono* generation would have laughed at his silly labours. But when he announced to his school that this amber held a soul or essence, which was awakened by friction, and went forth from the body in which it previously lay dormant, and brought back the small particles floating around it, he gave to the world the first hint of a great truth which has advanced our knowledge of physical phenomena in a marvellous manner, and ministered to the refinements and to the necessities of civilisation. Each phenomenon which presents itself to us, however simple it may appear to be, is an outward expression of some internal truth, the interpretation of which is only to be arrived at by assiduous study, but which, once discovered, directs the way to new knowledge, and gives to man a great increase of power. There is no truth so abstract that it will not find its useful application, and every example of the ministration of Physical Science to

the purposes of humanity is an evidence of the value of abstract study, and a reply to the utilitarian in his own language.

Electricity appears to be diffused through all nature; and it is, beyond all doubt, one of the most important of the physical forces, in the great phenomena of creation. In the thunder-cloud, swelling with destruction, it resides, ready to launch its darts and shake the earth with its explosions: in the aërial undulations, silent and unseen, it passes, giving the necessary excitement to the organisms around which it floats. The rain-drop—the earth-girdling ocean—and the ringing waters of the hill-born river, hold locked this mighty force. The solid rocks—the tenacious clays which rest upon them—the superficial soils—and the incoherent sands, give us evidence of the presence of this agency; and in the organic world, whether animal or vegetable, the excitement of electrical force is always to be detected.

In the solar radiations we have perhaps the prime mover of this power. In our atmosphere, when calm and cloudless, a great ocean of light, or when sombre with the mighty aspect of the dire tornado, we can constantly detect the struggle between the elements of matter to maintain an equilibrium of electrical force.

Diffused throughout matter, electricity is ever active; but it must be remembered that although it is evidently a necessary agent in all the operations of nature, that it is not the agent to which everything unknown is to be referred. Doubtless the influence of this force is more extensive than we have yet discovered; but that is an indolent philosophy which refers, without examination, every mysterious

phenomenon to the influence of electricity.

The question, what is electricity? has ever perplexed, and still continues to agitate, the world of science. While one set of experimentalists have endeavoured to explain the phenomena they have witnessed, upon the theory that electricity is a peculiar subtile fluid pervading matter, and possessing singular powers of attraction and repulsion, another party find themselves compelled to regard the phenomena as giving evidence of the action of two fluids which are always in opposite states; while again, electricity has been considered by others as, like the attraction of gravitation, a mere property of matter.[136] Certain it is, that in the manifestations of electrical phenomena we have, as it appears, the evidence of two conditions of force; but of the states of *positive* or *negative*, of *vitreous* or *resinous* electricity, we have a familiar explanation in the assumption of some current flowing into or out of the material body,—of some principle which is ever active in maintaining its equilibrium, which, consequently, must act in two directions, and always exhibit that duality which is a striking characteristic of this subtile agent. It is a curious, and it should be an instructive fact, that each of the three theories of electricity is capable of proof, and has, indeed, been most ably supported by the rigorous analysis of mathematics. When we remember that some of the most enlightened investigators of this and the past age have severally maintained, in the most able manner, these dissimilar views, we should hesitate before we pronounce an opinion upon the cause or causes of the very complicated phenomena of electrical force.

Although we discover, in all the processes of nature, the manifestations of this principle or force in its

characteristic conditions, it will be necessary, before we regard the great phenomena, to examine the known sources from which we can most readily evoke the mighty power of electricity. If we rub a piece of glass or resin, we readily render this agent active; these substances appear, by this excitement, to become surrounded by an attractive or a repellent atmosphere. Let us rub a strip of writing paper with Indian rubber, or a strip of Gutta Percha with the fingers, in the dark, and we have the manifestation of several curious phenomena. We have a peculiar attracting power; we have a luminous discharge in the shape of a spark; and we have very sensible evidence of muscular disturbance produced by applying the knuckle to the surface of the material. In each case we have the development of the same power.

Every substance in nature is an electric, and, if so disposed that its electricity may not fly off as it is developed, we may, by friction, manifest its presence, and, indeed, measure its quantity or its force. All bodies are not, however, equally good electrics; shell-lac, amber, resins, sulphur, and glass, exhibiting more powerfully the phenomena of frictional or mechanical electricity, than the metals, charcoal, or plumbago. Solid bodies allow this peculiar principle to pass along them also in very different degrees. Thus electricity travels readily through copper and most other metals, platinum being the worst metallic conductor. It also passes through living animals and vegetables, smoke, vapour, rarified air, and moist earth; but it is obstructed by resins and glass, paper when dry, oils, and dry metallic oxides, and in a very powerful manner by Gutta Percha.[137]

If, therefore, we place an electric upon any of those non-conducting bodies, the air around being well dried, we are enabled to gather a large quantity of the force for the production of any particular effect. Taking advantage of this fact, arrangements are made for the accumulation and liberation at pleasure of any amount of electricity.

A Leyden phial,—so called from its inventor, Musschenbroek, having resided at Leyden,—is merely a glass bottle lined within and without, to within a few inches of the top, with a metal coating. If a wire or chain, carrying an electric current, is allowed to dip to the bottom of the bottle, the inner coat of the jar becomes charged, or gathers an excess, whilst the outer one is in its natural condition —one is said to be in a *positive*, and the other in a *negative* state. If the two coatings are now connected by a good conductor, as a piece of copper wire, passing from one to the other, the outside to the inside, a discharge, arising from the establishment of the equilibrium of the two coatings, takes place; and, if the connection is made through the medium of our bodies, we are sensible of a severe disturbance of the nervous system.

The cause of the conducting and non-conducting powers of bodies we know not; they bear some relation to their conducting powers for caloric; but they are not in exact obedience to the same laws. When we consider that resin, a comparatively soft body, in which, consequently, cohesive attraction is not very strong, is an imperfect conductor, and that copper, in which cohesion is much more powerful, is a good conductor, we may be disposed to consider that it is regulated by the closer approximation of the particles of matter. But in platinum the corpuscular

arrangement must be much more dense than it is in copper, and yet it is, compared with it, a very bad conductor.[138]

We have now learnt that we may, by friction, excite the electricity in a vitreous substance; but it must not be forgotten that we cannot increase the quantity which is, under ordinary conditions, natural to the electric; to do so, we must in some way establish a channel of communication with the earth, from which, through the medium we excite, we draw our supply. We have the means of confining this mighty force within certain limits of quantity and of time. If we place bodies which are susceptible of electrical excitation in a sensible degree upon insulating ones, we may retain for a considerable time the evidences of the excitement, in the same way as with the Leyden jar; but there is a constant effort to maintain a balance of conditions, and the body in which we have accumulated any extraordinary quantity by conduction soon returns to its natural state.

A very simple means may be adopted of showing what is thought to be one of the many evidences in favour of two electricities. If the wire carrying the current flowing from the machine, is passed over paper covered with nitrate of silver, it produces no change upon it; but if the wire which conveys the current to the instrument, when it is excited, is passed over the same paper, the silver salt is decomposed.[139] We may, however, explain this result in a satisfactory manner, upon the hypothesis that the decomposition is produced by the abstraction of electricity, rather than by any physical difference in the fluid itself. By frictional electricity we may produce curious molecular disturbances, and give rise to molecular re-arrangements, which have

been called “electrical images,” in glass, in stone, and in the apparently less tractable metals: these images are rendered visible by the manner in which, according to their electrical states, some lines receive any particular powder, or vapour, which is repelled from other spaces. Many of the great natural phenomena, such as Lightning and Thunder, the Aurora Borealis, and Meteors, may be imitated in a curiously exact manner by the electrical machine and a few familiar arrangements.[140]

Voltaic electricity, as the active force produced by chemical change is commonly called, in honour of the illustrious Volta, is now to be considered. It differs from frictional electricity in this:—the electricity developed by friction of the glass plate or cylinder of the electrical machine is a discharge with a sort of explosion. It is electricity suddenly liberated from the highest state of tension, whereas that which is generated by chemical action in the voltaic battery is a steady flowing current. We may compare one to the ignition of a mass of gunpowder at once, and the other to the slow burning of the same quantity spread out into a very prolonged train.

There are numerous ways in which we may excite the phenomena of Voltaism, but in all of them the decomposition of one of the elements employed appears to be necessary. This is the case in the arrangements of batteries in which two dissimilar metals, zinc and copper, silver and platinum, or the like, is immersed in fluids; the zinc or the silver are gradually converted into soluble salts, which are dissolved, whilst the copper or platinum is protected from any action. The most simple manner of illustrating the development of this electricity is by placing a piece of silver on the tongue, and a piece of

zinc or lead underneath it. No effect will be observed so long as the two metals are kept asunder, but when their edges are brought together, a slight tremulous sensation will pass through the tongue, a saline taste be distinguished by the palate, and if in the dark, light will be observed by the eye.

This, the germ of the most remarkable of the sciences, was noticed by Sulzar, fifty years before Galvani observed the convulsions in the limbs of frogs, when excited by the action of dissimilar metals; but the former paid little attention to the phenomenon, and the discovery led to no results.

When Galvani's observant mind was directed to the remarkable fact that the mere contact of two dissimilar metals with the moist surface of living muscles produced convulsions, there was an awakening in the soul of that philosopher to a great fundamental truth, which was nurtured by him, tried and tested, and preserved to work its marvels for future ages.

Although the world of science looks back to Volta as the man who gave the first true interpretation of this discovery, yet the ordinary world will never disconnect this important branch of physical science from the name of Galvani, and chemical electricity in all its forms will for ever be known under the familiar name of Galvanism. And it must not be forgotten, that the phenomena of the manifestation of electricity, in connection with the conditions of vitality, are entirely due to Galvani.

Let us examine the phenomena of Galvanism in its most simple phases:—

If we place a live flounder upon a plate of zinc, put a shilling on its back, and then touch both metals with

the ends of a metallic wire, the fish will exhibit painful convulsions. The zinc becomes oxidized by the separation of oxygen from the fluid on the surface with which it is in contact, whilst hydrogen gas is liberated at that surface touched by the other metal. Here we have, in the first place, a chemical change effected, then a peculiar muscular disturbance. Each successive combination or decomposition, like a pulsation, is transmitted along the circuit from one extremity to the other. How the impulse which is derived from the zinc is transmitted through the body of the animal, or the tongue, to the silver or copper is the next consideration.

We can only understand this upon the supposition that a series of impulses are communicated in the most rapid manner along the connecting line; the idea of a current, although the term is commonly employed, tends to convey an imperfect impression to the mind. It would seem rather that a disturbance throughout the entire circuit is at once set up by a series of vibrations or impulses communicated from particle to particle, and along the strange net-work of nerves. One set of chemical elements have a tendency to develope themselves at that point where vibration is first communicated to the mass from a better conductor than it is, and another set at the point where it passes from the body to a better conductor than itself. The cause of this is to be sought for in the laws which regulate molecular constitution—by which chemical affinity is disturbed,—and a new attractive force exerted, in obedience to which the vital energy is itself agitated. We must not, however, forget that it is probable after all, although not yet susceptible of proof, that the electricity does nothing more than disturb or quicken the unknown principles upon which chemical and

vital phenomena depend; being, indeed, a secondary agent.[141]

Notwithstanding our long acquaintance with the phenomena of galvanism, there are but few who entertain a correct idea of the enormous amount of electricity which is necessary to the existing conditions of matter. To Faraday we are indebted for the first clear set of deductions from a series of inductive researches, which are of the most complete order. He has proved, by a series of exceedingly conclusive experiments, that if the electrical power which holds a grain of water in combination, or which causes a grain of oxygen and hydrogen to unite in the right proportions to form water, could be collected and thrown into the condition of a voltaic current, it would be exactly the quantity required to produce the decomposition of that grain of water, or the liberation of its elements, hydrogen and oxygen. [142]

By direct experiment it has been proved that one equivalent of zinc in a voltaic arrangement evolves such a quantity of electricity in the form of a current, as, passing through water, will decompose exactly one equivalent of that fluid. The law has been thus expressed:—The electricity which decomposes, and that which is evolved by the decomposition of a certain quantity of matter, are alike. The equivalent weights of bodies are those quantities of them which contain equal quantities of electricity; electricity determining the equivalent number, because it determines the combining force.[143]

The same elegant and correct experimentalist has shown that zinc and platinum wires, one-eighteenth of an inch in diameter, and about half an inch long, dipped into water in which is mixed sulphuric acid

so weak that it is not sensibly sour to the tongue, will evolve more electricity in one-twentieth of a minute than is given by thirty turns of a large and powerful plate electrical machine in full action, a quantity which, if passed through the head of a cat, is sufficient to kill it as by a flash of lightning. Pursuing this interesting inquiry yet further, it is found that a single grain of water contains as much electricity as could be accumulated in 800,000 Leyden jars, each requiring thirty turns of the large machine of the Royal Institution to charge it,—a quantity equal to that which is developed from a charged thunder-cloud. "Yet we have it under perfect command,—can evolve, direct, and employ it at pleasure; and when it has performed its full work of electrolisation, it has only separated the elements of a single grain of water."

It has been argued by many that the realities of science will not admit of anything like a poetic view without degrading its high office; that poetry, being the imaginative side of nature, has nothing in common with the facts of experimental research, or with the philosophy which generalises the discoveries of severe induction. If our science was perfect, and laid bare to our senses all the secrets of the inner world; if our philosophy was infallible, and always connected one fact with another through a long series up to the undoubted cause of all—then poetry, in the sense we now use the term, would have little business with the truth; it would, indeed, be lost or embodied, like the stars of heaven, in the brightness of a meridian sun. But to take our present fact as an example, how important a foundation does it offer upon which to build a series of thoughts, capable of lifting the human mind above the materialities by which it is surrounded,—of exalting

each common nature by the refinement of its fresh ideas to a point higher in the scale of intelligence,—of quickening every impulse of the soul,—and of giving to mankind the most holy longings.

What does science tell us of the drop of water? Two gases, the one exciting life and quickening combustion, the other a highly inflammable air, are, by the influence of a combination of powers, brought into a liquid globe. We can, from this crystal sphere, evoke heat, light, electricity, and actinism in enormous quantities; and beyond these we can see powers or forces, for which, in the poverty of our ideas and our words, we have not names; and we learn that each one of these principles is engaged in maintaining the conditions of the drop of water which refreshes organic nature, and gives gladness to man's dwelling-place.

Has poetry a nobler theme than this? Agencies are seen like winged spirits of infinite power, each one working in its own peculiar way, and all to a common end,—to produce, under the guidance of omnipotent rule, the waters of the rivers and the seas. As the great ocean mirrors the bright heaven which overspreads it, and reflects back the sunlight and the sheen of the midnight stars in grandeur and loveliness; so every drop of water, viewed with the knowledge which science has given to us, sends back to the mind reflections of yet distant truths which, rightly followed, will lead us upwards and onwards in the tract of higher intelligences,—

"To the abodes where the eternals are."

In the discoveries connected with electricity, we have results of a more tangible character than are as

yet connected with the other physical forces; and it does appear that this science has advanced our knowledge of nature and of the mysteries of creation far more extensively than any other department of purely experimental inquiry.

The phenomena of electro-chemical action are so strange that we must return for a moment to the consideration of the decomposition of water, and the appearance of hydrogen at one pole, and of oxygen at the other. It appears that some confusion of our ideas has arisen from the views which have been received of the atomic constitution of bodies. We have been accustomed to regard water,—to take that body as an example of all,—as a compound of two gases, hydrogen and oxygen; an equivalent, or one atom of the first, united to an equivalent or one atom of the last, forming one atom of water. This atom of water we regard as infinitely small; consequently a drop of water is made up of many hundreds of these combined atoms, and a pint of water of not less than 10,000 drops. Now, if this pint of water is connected with the wires of a galvanic battery, although their extremities may be some inches apart, for every atom of oxygen liberated at one pole, an atom of hydrogen is set free at the other. It has been thought that an atom has undergone decomposition at one point, its oxygen being torn from it, and then there has arisen the difficulty of sending the atom of hydrogen through all the combined atoms of water across to the other pole. A series of decompositions and recompositions have been supposed to take place, and the communication of effects from particle to particle.

An attracting power for one class of bodies has been found in one pole, which is repellent to another

class; and the reverse order has been detected at the opposite pole of a galvanic arrangement.[144] That is, the wire which carries the current from an excited zinc plate has a relation to all bodies, which is directly opposite to that which is exhibited by the wire conveying the current from, or completing the circuit with, the copper plate. The one, for instance, collects and carries acids and the like, the other the metallic bases. At the extremity of one galvanic wire, placed into a drop of water, oxygen is always liberated; and at the end of the other, necessary to complete the circuit with the battery, hydrogen is set free.

It appears necessary, to a clear understanding of what takes place in this experiment, that we should regard each mass, howsoever large, as the representative of a single atom. Nor is this difficult, as the following illustration will show.

Let us take one particle of common salt (*chloride* of *sodium*) weighing less than a grain, and put it into a hundred thousand grains of distilled water. In a few minutes the salt has diffused itself through the whole of the fluid, and in every drop we can detect chlorine and soda. We cannot believe that this grain of salt has split itself up into a hundred thousand parts; we conceive rather that the phenomenon of solution is one of diffusion. One infinitely elastic body has interpenetrated with another.

Instead of an experiment with a pint of water, let us take our stand on Dover heights, and, with a gigantic battery at our command, place one wire into the ocean on our own shores, and convey the other through the air across the channel, and let its extremity dip into the sea off Calais pier—the experiment is a practicable one—we have now an

electrical circuit of which the British channel forms a part, and the result will be exactly the same as that which we may observe in a watch-glass with a drop of water.

We cannot suppose that the instantaneous and simultaneous effect which takes place in the water at Calais and at Dover, is due to anything like what we have studied under the name of convection, when considering Heat.

A thousand balls are placed in a line touching each other; the first ball receives a blow, and the last ball flies off with a force exactly equal to the power applied to the first; none of the intermediate balls being moved.

We cannot conceive that the particle *A* excites the particle *B* next it, and so on through the series between the two shores; but regarding the channel as one large drop, charged with the electric principle as we know it to be, it is excited by undulation or tremor throughout its width, and we have an equivalent of oxygen thrown off on one side of the line, and an exact equivalent of hydrogen at the other, the electro-chemical influence being exerted only where the current or motion is transferred from one medium to another.[145] The imperfect character of this view is freely admitted; no other, consistent with known facts, presents itself by which the effect can be explained. The fact stands as a truth; the hypothesis by which it is attempted to be interpreted is open to doubt, and it is opposed to some favourite theories.

Before we pass to the consideration of the other sources of electricity, it is important we should understand that no chemical or physical change, however slight it may be, can occur without the

development of electrical power. If we dissolve a salt in water, if we mix two fluids together, if we condense a gas, or convert a fluid into vapour, electricity is disturbed, and may be made manifest to our senses.[146]

It has been shown that this power may be excited by friction (machine electricity) and by chemical action (voltaic electricity, galvanism); it now remains to speak of the electricity developed by heat (thermo-electricity), the electricity exhibited under nervous excitement by the gymnotus and torpedo (animal electricity); magnetism and its phenomena being reserved for a separate consideration.

If a bar of metal is warmed at one end and kept cool at the other, an electrical current circulates through the bar, and may be carried off by connection with any good conductor, and shown to exhibit the properties of ordinary electricity. The metals best suited for showing the effects of thermo-electricity appear to be bismuth and antimony. By binding two bars of these metals together at one end, and connecting the other ends with a galvanometer, it will be discovered that an electric current passes off through the instrument by the slightest variation of temperature. Merely clasping the two metals, where bound together, with the finger and thumb, is sufficient to exhibit the phenomenon. By a series of such arrangements,—which form what have been called thermo-electric multipliers,—we obtain the most delicate measurers of heat with which philosophers are acquainted, by the aid of which Melloni has been enabled to pursue his beautiful researches on radiant caloric.

That this electricity is identical with the other forms has been proved by employing the current thus

excited for the purpose of producing chemical decomposition, magnetism, and electric light.[147]

The phenomenon of thermo-electricity—the discovery of Seebeck, is another proof of the very close connection of the physical forces. We witness their being resolved as it were into each other, electricity producing heat, and heat again electricity; and it is from these curious results that the arguments in favour of their intimate relations and actual identity have been drawn. It will, however, be found to be the best philosophy to regard these forces as dissimilar, until we are enabled to prove them to be only modified forms of one principle or power. At the same time it must not be forgotten that in natural operations we invariably find the combined action of several forces producing a single phenomenon. The important fact to be particularly regarded is, that we have evidence that every substance which is unequally heated becomes the source of this very remarkable form of electricity. [148]

There exist a few fishes gifted with the very extraordinary power of producing electrical phenomena by an effort of muscular or nervous energy.

The *Gymnotus electricus*, or electrical eel, and the *Raia torpedo*, a species of ray, are the most remarkable. This power is, it would appear, given to these curious creatures for purposes of defence, and also for enabling them to secure their prey. The *Gymnotus* of the South America rivers, will, it is said, when in full vigour, send forth a discharge of electricity sufficiently powerful to knock down a man, or to stun a horse; while it can destroy fishes, through a considerable space, by exerting its strange

artillery.[149]

Faraday's description of a *Gymnotus*, paralyzing and seizing its prey, is too graphic and important to be omitted.

"The *Gymnotus* can stun and kill fish which are in very various positions to its own body; but on one day, when I saw it eat, its action seemed to me to be peculiar. A live fish, about five inches in length, caught not half a minute before, was dropped into the tub. The *Gymnotus* instantly turned round in such a manner as to form a coil, inclosing the fish, the latter representing a diameter across it; a shock passed, and there, in an instant, was the fish struck motionless, as if by lightning, in the midst of the waters, its side floating to the light. The *Gymnotus* made a turn or two to look for its prey, which, having found, he bolted, and then went about searching for more. A second smaller fish was given him, which being hurt in the conveyance, showed but little signs of life, and this he swallowed at once, apparently without shocking it. The coiling of the *Gymnotus* round its prey had, in this case, every appearance of being intentional on its part, to increase the force of the shock, and the action is evidently well suited for that purpose, being in full accordance with the well-known laws of the discharge of currents in masses of conducting matter; and though the fish may not always put this artifice in practice, it is very probable he is aware of its advantages, and may resort to it in cases of need."[150]

Animal electricity has been proved to be of the same character as that derived from other sources. The shock and the spark are like those of the machine; and the current from the animal, circulating around

soft iron, like galvanic electricity, has the property of rendering it magnetic.

It is important that we should now review these conditions of electrical force in connexion with the great physical phenomena of nature.

It is sufficiently evident, from the results which have been examined, that all matter, whatever may be its form or condition, is for ever under the operation of the physical forces, in a state of disturbance. From the centre to the surface all is in an active condition: a state of mutation prevails with every created thing; and science clearly shows that influences are constantly in action which prevent the possibility of absolute repose.

Under the excitement of the several agencies of the solar beams, motion is given to all bodies by the circulation of heat, and a full flow of electricity is sent around the earth to perform its wondrous works. The solar influences, which regulate, and possibly determine, every physical force with which we are acquainted, are active in effecting an actual change of state in matter. The sunbeam of the morning falls on the solid earth, and its influence is felt to the very centre. The mountain-top catches the first ray of light, and its base, still wrapt in mists and darkness, is disturbed by the irradiating power. The crystalline gems, hidden in the darkness of the solid rock, are dependent, for that form which makes them valued by the proud and gay, on the influence of those radiations which they are one day to refract in beauty. The metals locked in the chasms of the rifted rocks are, for all their physical peculiarities, as dependent on solar influence as is the flower which lifts its head to the morning sun, or the bird which sings “at heaven’s high gate.”

Let us, then, examine how far electricity, as distinguished from the other powers, acts in producing any of these effects.

We find electricity in the atmosphere, which the electrical kite of Dr. Franklin proved to be identical with that principle produced by the friction of glass. In the grandeur and terror of a thunderstorm, many see nothing but manifestations of Almighty wrath. When the volleys of the bursting cloud are piercing the disturbed air, and the thunders of the discharge are pealing their dreadful notes above our heads, the chemical combinations of the noxious exhalations arising from the putrefying animal and vegetable masses of this earth are effected, elements fitted for the purposes of health and vegetation are formed, and brought to the ground in the heavy rains which usually follow these storms. Science has taught man this—has shown him that the "partial evil" arising from the "winged bolt" is a "universal good;" and, more than this, it has armed him with the means of protecting his life and property from the influence of lightnings. So that, like Ajax, he can defy the storm. By metallic rods, carried up a chimney, a tower, or a mast, we may form a channel through which the whole of the electricity of the most terrific thunder-cloud may be carried harmlessly into the earth or the sea; and it is pleasing to observe that at length prejudice has been overcome, and "conductors" are generally attached to high buildings, and to most of the ships of our navy.[151] It was discovered that the devastating hailstorms of the south of France and Switzerland, so destructive to the vineyards and crops, were accompanied by evidences of great electrical excitation, and it was proposed to discharge the electricity from the air by means of

pointed metallic rods. These have been adopted, and, it is said, with real advantage—each rod protecting an area of one hundred yards. Thus it is that science ministers to our service; and how much more pleasing is it to contemplate the lightning, with the philosopher, as an agent destroying the elements of pestilence, and restoring the healthfulness of the air we breathe, than with the romancer, to see in it only the dreaded aspect of a demon of destruction.

The laws which regulate the spread of a pestilence are unknown. The difficulties of the investigation are great, but they are by no means insurmountable. A plague passes from the east to the west across the world—it spreads mourning over the gayest cities, and sorrow sitteth in the streets. The black death rises in the Orient: it goes on in unchecked strength, and only finishes its course when it has made the circuit of the civilized world. The cholera spreads its ebon wings—mankind trembles—watches its progress, and looks upon the path which is marked by the myriads of the dead, who have fallen before the dire fiend. The diseases pass away—the dead are buried, and all is forgotten. The rush and the riot of life are pursued: and until man is threatened with another advent, he cares not to trouble himself. Accompanying the last visitation, there appear certain peculiar meteorological conditions, which point a line of inquiry. It may or may not be the path which leads to the truth, but certainly its indications are worthy of careful examination. It may be asked, can weak man stop a pestilence; can a mortal's puny hand retard the afflictions of the Almighty? The question asked—it must be answered in reverence, yet without fear. No human power can produce a change in the physical conditions of the earth, or of the air; and if our diseases are connected with those

changes, as beyond all doubt a number of them are, they lie above man's control. But when there are indications that causes secondary to these are producing some dire effect, and when we know that these secondary causes may be modified, it is sufficient evidence to prove that man is permitted to control thus far the afflictions which are sent to try his powers.

We find a disease winging its way from lane to alley and closed court, sweeping with destructive violence its way through damp cellars and crowded attics; it is rife with mischief along the banks of reeking ditches, and on the borders of filthy streams. Certain it is, therefore, that some ultimate connexion exists between the conditions of dirt and this speedy death. Can science tell of these? has it yet searched out the connecting link? Let the question be answered by a few facts.

When the cholera first made its appearance, and subsequently, it has been observed that the electrical intensity of the atmosphere was unusually low.

The disease has departed, and it is then found that the electricity of the air has been restored to its ordinary condition.

This appears to show some connexion; but how do these conditions link this physical force with the ditch-seeking disease?

From all stagnant places, from all the sinks of overcrowded humanity, from fermenting vegetable and from putrefying animal matter, there are constantly arising poisonous exhalations to do their work of destruction.

Where death and decay is a law, this must of necessity constantly occur; but the poisonous reek

may be diffused, or it may be concentrated, and Nature has provided for this, and ordered the means for rendering the poison harmless.

By the agency of electricity,—probably, too, by the influence of light,—the oxygen in the air undergoes a peculiar change, by which it is rendered far more energetic than it is in its ordinary state. This is the condition to which the name of *ozone* has been applied. Now, this ozone, or this peculiar oxygen, always exists in the air we breathe; but its quantity is subject to great and rapid variations. It is found that when electrical intensity is high the quantity of this principle is great; when the electrical intensity is low, as in the cholera years, the proportion of ozone is relatively low.

This remarkable chemical agent possesses the power of instantly combining with organic matter,—of removing with singular rapidity all noxious odours; and it would appear to be the most active of all known disinfectants.

May we not infer from the facts stated that the pestilence we dread is the result of organic poison, which from a deficiency of ozone,—its natural antidote,—exerts its baneful influences on humanity. This deficiency is due to alterations in the electrical character of the air, possibly dependent upon phenomena taking place in the sun itself, or it may be still more directly influenced by variations in the character of solar light, which we have not yet detected, by which the conditions of the electric power are determined.

This may be a line along which it is fair to push enquiry. But such an enquiry must be made in all the purity of the highest inductive philosophy, and speculation must be held firmly in the controlling

chains of experiment and observation. In the truths, however, which are known to us, there is so much harmony and consistence that even the melancholy theme links itself—a tragedy—with the Poetry of Science.

It has been thought, and much satisfactory evidence has been brought forward to support the idea, that the earth's magnetism is due to currents of electricity circulating around the globe; as a great natural current from east to west—that, indeed, it has an unvarying reference to the motion of the earth in relation to the sun.[152]

These terrestrial currents, as they have without doubt a very important bearing on the structural conditions of the rock-formations and the distribution of minerals, require an attentive consideration; but we must, in the first place, examine, as far as we know, the influences exerted, or supposed to be exerted, by electricity, in its varied forms.

The phenomena of vitality have, by many, been considered as immediately dependent upon its influence; and a rather extensive series of experiments has been made in support of this hypothesis. The researches of Philip on the action of the organs of digestion, when separated from their connection with the brain, but united with a galvanic battery, have been proved by Dr. Reid to be delusive; [153] since, as the organ is not removed from the influence of the living principle, it is quite evident that the electricity here is only secondary to some more important power. Matteucci has endeavoured to show that nervous action is intimately connected with electric excitation, and that electricity may be made a measurer of nervous irritability.[154] There

can be no doubt that a peculiar susceptibility to excitement exists in some systems, and this is very strikingly shown in the disturbances produced by electric action; but in the experiments which have been brought forward we have only the evidence that a certain number of muscular contractions are exhibited in one animal by a current of electricity, giving a measured effect by the voltameter, which are different from those produced upon another by a current of the same power. An attempt has recently been made by Mr. A. Smee to reduce the electrical phenomena connected with vitality to a more exact system than had hitherto been done. We cannot, however, regard the attempt as successful. The author has trusted almost entirely to analogical reasoning, which is in science always dangerous.[155] In the development of electricity during the operation of the vital force, we see only the phenomena produced by the action of any two dissimilar chemical compounds upon each other. It has been thought that the structure of the brain presents an analogy to that of the galvanic battery, and the nerves represent the conducting wires. Although, however, some of the conditions appear similar, there are many which have no representatives in either the mechanical structure or the physical properties of the brain, so far as we know it. That the brain is the centre, the source, and termination of sensation is very clearly proved by physiological investigations. That the nerves are the media by which all sensation is conveyed to the brain, and also the instruments by which the will exerts its power over the muscles, is equally well established. But to say that we have any evidence to support the idea that electricity has aught to do directly with these great physiological phenomena,

would be a bold assertion, betraying a want of due caution on the part of the investigator. That electric effects are developed during the operations of vitality is most certain. Such must be the case, from the chemical changes taking place during respiration and digestion, and the mechanical movements by which, even during external repose, the necessary functions of the body are carried on. Whether electricity is the cause of these, or an effect arising from them, we need not stop to examine, as this is, in the present state of our knowledge, a mere speculation. We have no evidence that electricity is an exciting power, but rather that it is one of those forces which tend to establish the equilibrium of matter. When disturbed—when its equilibrium is overset—it does, in its efforts to regain its stability, produce most remarkable effects. An electrical machine must be rubbed to exhibit any force. In all galvanic arrangements, even the most simple, dissimilar bodies are brought together, and the latent electricity of both is disturbed; and, even in the magnet, it is only when this takes place that its electrical powers are developed. In the *Gymnotus*, electricity appears to be dependent upon the power of the will of the animal; but even in this extraordinary fish, it is only under peculiar conditions that the electrical excitement takes place, and “what they inflict, they feel” during the restoration of that equilibrium which is necessary to their healthy state. In every case, therefore, we see that some power far superior to this is the ultimate cause; indeed, light and heat, and probably actinism, appear to stand superior to this principle; and on these, in some combined mode of action, in all probability, sensible electricity is dependent. Beyond even these elements, largely as they are engaged in

the organic and inorganic changes of this world, there are occult powers which may never be understood by finite beings. We advance step by step from the most solid to the most ethereal of material creations, and we examine a series of extraordinary effects produced by powers which we know not whether to regard as material or immaterial, so subtile are they. On these, it appears, we may exhaust our inductive investigations—we may discover the laws by which these principles act upon the grosser elements, and develope phenomena of a very remarkable kind which have been unobserved or misunderstood. Whether light, heat, and electricity are modifications of one power, or different powers very closely united in action, is a problem we may possibly solve; but to know what they are, appears to be beyond the hopes of science; and it were idle to dream of elucidating the causes hidden beyond these forces, and by which they are regulated in all their actions on dead or living matter.

M. Du Bois Raymond, from a series of researches remarkable alike for their difficulty and the delicacy with which they have been pursued, draws the following, amongst many others, as his conclusions as to the connection of electricity and vital phenomena.

The muscles and nerves, including the brain and the spinal chord, are endowed during life with an electromotive power, which acts according to a definite law.

The electromotive power *lasts after death*, or in dissected nerves and muscles after separation from the body of the animal, as long as the excitability of the nervous and muscular fibre; whether these fibres

are permitted to die gradually from the cessation of the conditions necessary to the support of life, or whether they are suddenly deprived of their vital properties by heat or chemical action.

Let us not suppose for a moment that these conclusions indicate in the remotest degree that electricity is life,—that vital power is due to electricity.

During life, with every motion, and, indeed, with every emotion, whether we move a muscle or exert the mind, there is a change of state. The result of this is chemical phenomena,—heat and electricity; but these are not life. We excite them equally by giving motion to a dead mass.

Notwithstanding the assertions of those who have zealously followed the path of Mesmer, and examined, or they have thought so, the psychological effects dependent upon some strange physiological conditions, there is not an experiment on record,—there is not an observation worthy of credit, which shows that electricity has any connection with their results. All around their subject is uncertainty: doubt involves every experiment, and deception clouds a large number. Some few grains of truth, and these are sufficiently strange, are mixed up in an enormous mass of error.

All the phenomena of life,—of the *vis vitæ* or vitality, are beyond human search. All the physical forces, or elements, we may examine by the test of experiment: but the principle on which sensation depends, the principle even upon which vegetable *life* depends, cannot be tested. Life is infinitely superior to every physical force; it holds them all in control, but is not itself controlled by them; it keeps its state sacred from human search,—the invisible hidden behind the

veil of mortality.

During changes in the electrical conditions of the earth and atmosphere, vegetables give indications of being in a peculiar manner influenced by this power. It is proved by experiments that the leaves of plants are among the best conductors of electricity, and it has hence been inferred that it must necessarily be advantageous to vegetation. That vegetable growth is, equally with animal growth, subject to electricity, as one of its quickening powers, must be admitted; but all experiments which have been fairly tried with the view of stimulating the growth of plants by its agency, have given results of a negative character. [156] That a galvanic arrangement may produce chemical changes in the soil, which may be advantageous to the plant, is probable; but that a plant can be brought to maturity sooner, or be made to develope itself more completely, under the direct action of electrical excitation, appears to be one of those dreams of science which will have a place amongst the marvels of alchemy and the fictions of astrology. An attentive examination of all the conditions necessary for the satisfactory development of the plant, will render it evident, that although the ordinary electrical state of the earth and atmosphere must influence the processes of germination and vegetable growth, yet that any additional excitement must be destructive to them. The wonders wrought by electrical power are marvellous; a magic influence is exerted by it, and naturally the inquiring mind is led at first to believe that electricity is the all-powerful principle of creation; but a little reflection will serve to convince us that it is a subordinate agent, although a powerful one.

In proceeding with our examination of the

phenomena which present themselves in connection with the terrestrial currents, we purposely separate magnetism from those more distinct electro-chemical agencies which play so important a part in the great cosmical operations.

Electricity, we have already stated, flows through or involves all bodies; but, like heat, it appears to undergo a very remarkable change in becoming associated with some forms of matter. We have the phenomena of magnetism when an electric current circulates through a metallic wire, and it would appear that all other bodies acquire a peculiar polar condition under the influence of this principle, which will be explained in the next chapter.

The rocks, taken as masses, will not conduct an electric current when dry: granite, porphyry, slate, and limestone, obstructing its passage even through the smallest spaces. But all the metallic formations admit of its circulating with great freedom. This fact it must, however, be remembered does not in any way interfere with the hypothesis of the existence of electricity in all bodies, in what we must regard as its latent state, from which, under prescribed conditions, it may be readily liberated. Neither does it affect the question of circulation, in relation to the great diffusion of electricity which we suppose to exist through all nature, and to move in obedience to some fixed law. We know that through the superficial strata electric currents circulate freely, whether they are composed of clay, sand, or any mixture of these with decomposed organic matter; indeed, that with any substance in a moist state they suffer no interruption.

The electricity of mineral veins has attracted much attention, and numerous investigations into the

phenomena which these metalliferous formations present, have been made from time to time.[157]

By inserting into the mass of a copper *lode*, or vein, in situ, a metallic wire, which shall be connected with a measurer of galvanic action, a wire also from the instrument being brought into contact with another *lode*, an immediate effect is generally produced, showing that a current is traversing through the wires from one *lode* to the other, and completing the circulation probably over the dark face of the rock in which the fissures forming the mineral veins exist.[158] The currents thus detected are often sufficiently active to deflect a magnetic needle powerfully, to produce, slowly, electro-chemical decomposition, and to render a bar of iron magnetic. These currents must not be confounded with the great electrical movements around the earth. They are only to be detected in those mineral formations in which there is evidence of chemical action going on, and, the greater the amount of this chemical operation, the more energetic are the electrical currents.[159] We have, however, very good evidence that these local currents have, of themselves, many peculiar influences. It not unfrequently happens that owing to some great disturbance of the crust of the earth, a mineral vein is dislocated, and one part either sinks below, or is lifted above its original position; the fissures formed between the two being usually filled in with clay or with crystalline masses of more recent formation than the fissure itself. It is frequently found that these "*cross courses*," as they are called in mining language, contain ores of a different character from those which constitute the mineral vein; for instance, in them nickel, cobalt, and silver are not unfrequently discovered. When these metals are so

found, they almost invariably occur between the ends of the dislocated lode, and often take a curvilinear direction, as if they were deposited along a line of electrical force.[160]

In the laboratory such an arrangement has been imitated, and in a mass of clay fixed between the galvanic plates, after a short period a distinct formation of a mineral vein has taken place.[161] By the action, too, of weak electrical currents, Becquerel, Crosse, and others, have been successful in imitating nature so far as to produce crystals of quartz and other minerals. In addition to this evidence, in support of the electrical theory of the origin of mineral veins, it can be experimentally shown that a schistose structure may be given to clays and sandstone by voltaic action.[162]

There is often a very remarkable regularity in the direction of mineral veins: throughout Cornwall, for instance, they most commonly have a bearing from the E. of N. to the W. of S. It has hence been inferred that they observe some relation to the magnetic poles of the earth. However this may be, it is certain that the ore in any lodes which are in a direction at right angles, or nearly so, to this main line, differs in character from that found in these, so called, east and west lobes.[163]

The sources of chemical action in the earth are numerous. Water percolating through the soil, and finding its way to great depths through fissures in the rocks, carries with it oxygen and various salts in solution. Water again rising from below, whether infiltrated from the ocean or derived from other sources, is usually of a high temperature, and it always contains a large quantity of saline matter. [164] By these causes alone chemical action must be

set up. Chemical change cannot take place without a development of electricity: and it has been proved that the quantity of electricity required for the production of any change is equal to that contained in the substances undergoing such change. Thus a constant activity is maintained within the caverns of the rock by the agency of the chemical and electrical elements, and mutations on a scale of great grandeur are constantly taking place under some directive force.

The mysterious gnome, labouring—ever labouring—in the formation of metals, and the mischievous Cobalus of the mine, are the poor creations of superstition. A vague fear is spread amongst great masses of mankind relative to the condition of the dark recesses of the earth; a certain unacknowledged awe is experienced by many on entering a cavern, or descending a mine: not the natural fear arising from the peculiarity of the situation, but the result of a superstitious dread, the effect of a depraved education, by which they have been taught to refer everything a little beyond their immediate comprehension to supernatural causes. The spirit of demon worship, as well as that of hero worship, has passed from the early ages down to the present; and under its influence the genii of the East and the demons of the West have preserved their traditionary powers.

Fiction has employed itself with the utmost license in giving glowing pictures of treasures hidden in the earth's recesses. The caverns of Chilminar, the cave of Aladdin, the abodes of the spirits of the Hartz, and the dwellings of the fairies of England, are gem-bespangled and gold-glistening vaults, to which man has never reached. The pictures are pleasing; but

although they have the elements of poetry in them, and delight the young mind, they want the sterling character of scientific truth; and the wonderful researches of the plodding mineralogist have developed more beauty in the caverns of the dark rock than ever fancy painted in her happiest moments.

In all probability the action of the sun's rays upon the earth's surface, producing a constantly varying difference of temperature, and also the temperature which has been observed as existing at great depths, give rise to thermo-electrical currents, which may play an important part in the results thus briefly described.

In connection with these great natural operations, explaining them, and being also, to some extent, explained by them, we have the very beautiful application of electricity to the deposition of metals, called the Electrotype.

Applying the views we have adopted to this beautiful discovery,[165] the whole process by which these metallic deposits are produced will be yet more clearly understood. By the agency of the electric fluid, liberated in the galvanic battery, a disturbance of the electricity of the solution of copper, silver, or gold, is produced, and the metal is deposited; but, instead of allowing the acid in combination to escape, it has presented to it some of the same metal as that revived, and, consequently, it combines with it, and this compound, being dissolved, maintains the strength of the solution.[166] A system of revival, or decomposition, is carried on at one pole, and one of abrasion, or more correctly speaking, of composition and solution, at the other. By taking advantage of this very extraordinary power of electricity, we now

form vessels for ornament or use, we gild or silver all kinds of utensils, and give the imperishability of metal to the most delicate productions of nature—her fruits, her flowers, and her insects;—and over the finest labours of the loom we may throw coatings of gold or silver to add to their elegance and durability. Nor need we employ the somewhat complex arrangement of the battery: we may take the steel magnet, and, by mechanically disturbing the electricity it contains, we can produce a current through copper wires, which may be used, and is extensively employed, for gilding and silvering.[167] The earth itself may be made the battery, and, by connecting wires with its mineral deposits, currents of electricity have been secured, and used for the production of electrotype deposit.[168]

The electrotype is but one of the applications of electricity to the uses of man. This agent has been employed as the carrier of thought; and with infinite rapidity, messages of importance, communications involving life, and intelligences outstripping the speed of coward crime, have been communicated. There will be no difficulty in understanding the principle of this, although many of the nice mechanical arrangements, to ensure precision, are of a somewhat elaborate character. The entire action depends on the deflection of a compass-needle by the passage of an electric current along its length. If at a given point we place a galvanic battery, and at twenty or one hundred miles distance from it a compass-needle, between a wire brought from, and another returning to the battery, the needle will remain true to its polar direction so long as the wires are unexcited; but the moment connection is made, and the circuit is complete, the electricity of the

whole extent of wire is disturbed, and the needle is thrown at right angles to the direction of the current. Provided a connection between two points can be secured, however remote they are from each other, we thus, almost instantaneously, convey any intelligence. The effects of an electric current would appear at a distance of 576,000 miles in a second of time; and to that distance, and with that speed, it is possible, by Professor Wheatstone's beautiful arrangements, to convey whispers of love or messages of destruction.

The enchanted horse of the Arabian magician, the magic carpet of the German sorcerer, were poor contrivances, compared with the copper wires of the electrician, by which all the difficulties of time and the barriers of space appear to be overcome. In the Scandinavian mythology we find certain spiritual powers of evil enabled to pass with imperceptible speed from one remote point to another, sowing the seeds of a common ruin amongst mankind. Such is the morbid creation of a wild yet highly endowed imagination. The spirit of evil diffuses itself in a remarkable manner, and, indeed, we might almost assign to it the power of ubiquity; but in reality its advance is progressive, and time enters as an element into any calculation on its diffusion. Electricity is instantaneous in action; as a spirit of peace and good-will it can overtake the spirit of evil, and divert it from its designs. May we not hope that the electrical telegraph, making, as it must do, the whole of the civilized world enter into a communion of thought, and, through thought, of feeling with each other, will bind us up in one common brotherhood, and that, instead of misunderstanding and of misinterpreting the desires and the designs of each other, we shall learn to know that such things

as “natural enemies” do not exist? To hope to break down the great barrier of language is perhaps too much; but assuredly we may hope that, as we must do when closer and more intimate relations are secured by the aids of science, the barrier of prejudice may be razed to the ground, and not one stone left to stand upon another? Our contentions, our sanguinary wars, consecrated to history by the baptism of blood, have in every, or in nearly every, instance sprung from the force of prejudice, or the mistakes of politicians, whose minds were narrowed to the limits of a convention formed for perpetuating the reign of ignorance.

And can anything be more in accordance with the spirit of all that we revere as holy, than the idea that the elements employed by the All Infinite in the works of physical creation shall be made, even in the hands of man, the ministering angels to the great moral redemption of the world? Associate the distant nations of the earth, and they will find some common ground on which they may unite. Mortality compels a dependence; and there are charities which spring up alike in the breast of the savage and the civilized man, which will not be controlled by the cold usages of pride, but which, like all truths, though in a still small voice, speak more forcibly to the heart than errors can, and serve as links in the great chain which must bind mankind in a common brotherhood. “None are all evil,” and the best have much to learn of the amenities of life from him who yet lives in a “state of nature,” or rather from him whose sensualities have prevailed over his intellectual powers, but who still preserves many of the noblest instincts, to give them no higher term, which other races, proud of their intelligence, have thrown aside. Time and space have hitherto

prevented the accomplishment of this; electricity and mechanics promise to subdue both; and we have every reason to hope those powers are destined to accelerate the union of the vast human family.

Electrical power has also been employed for the purpose of measuring time, and by its means a great number of clocks can be kept in a state of uniform correctness, which no other arrangement can effect. A battery being united with the chief clock, which is itself connected by wires with any number of clocks arranged at a distance from each other, has the current continually and regularly interrupted by the beating of the pendulum, which interruption is experienced by all the clocks included in the electric circuit; and, in accordance with this breaking and making contact, the indicators or hands move over the dial with a constantly uniform rate. Instead of a battery the earth itself has supplied the stream of electric fluid, with which the rate of its revolutions has been registered with the utmost fidelity.[169]

Electricity, which is now employed to register the march of time, rushes far in advance of the sage who walks with measured tread, watching the falling sands in the hour-glass.

The earth is spanned and the ocean pierced by the wires of the electric telegraph. Already, from the banks of the Thames to the shores of the Adriatic, our electric messenger will do our bidding. The telegraph is making its way through Italy, and it is dipping its wires in the Mediterranean, soon to reach the coast of Africa. They will then run along the African shores to Egypt and Turkey, and still onward until they unite with the telegraphs of India, of which three thousand miles are in progress. From Hindostan these wondrous wires will run from island

to island in the Indian Archipelago, and thus connect Australia and New Zealand with Europe.

In a few years we may expect to have an instantaneous report in London of the extraordinary "nugget" discovered by some fortunate gold-digger; and the exile from his native land in the Islands of the South Pacific Ocean, may learn every hour, if he will, of the doings of his family and friends in some village home of England.

FOOTNOTES:

[136] *Traité de Physique*: M. Biot, vol. vii. Becquerel: Annales de Chimie, vol. xlvi.-xlix. Faraday's *Experimental Researches in Electricity*, 2 vols., 1830–1844. *A Speculation touching Electric Conduction and the Nature of Matter*: by Michael Faraday, D.C.L., F.R.S.; Philosophical Magazine, vol. xxiv., 1836. *Objections to the theories severally of Franklin, Dufay, and Ampère, with an attempt to explain Electrical Phenomena by statical or undulatory polarization*: by Robert Hare, M.D., Emeritus Professor of Chemistry in the University of Pennsylvania.

[137] "A good piece of gutta percha will insulate as well as an equal piece of shell-lac, whether it be in the form of sheet, or rod, or filament; but being tough and flexible when cold, as well as soft when hot, it will serve better than shell-lac in many cases where the brittleness of the latter is an inconvenience. Thus it makes very good handles for carriers of electricity in experiments on induction; not being liable to fracture in the form of thin band or string, it makes an excellent insulating

suspender; a piece of it in sheet makes a most convenient insulating basis for anything placed on it. It forms excellent insulating plugs for the stems of gold-leaf electrometers, when they pass through sheltering tubes, and larger plugs form good insulating feet for electrical arrangements; cylinders of it, half an inch or more in diameter, have great stiffness, and form excellent insulating pillars. In these and in other ways its power as an insulator may be useful."—*On the use of Gutta Percha in Electrical Insulation*: by Dr. Faraday; Philosoph. Mag., March, 1848.

The following deductions have been given by Faraday, in his *Researches in Electricity*, a work of most extraordinary merit, being one of the most perfect examples of fine inductive philosophy which we possess in the English language:—

"All bodies conduct electricity in the same manner from metals to lacs and gases, but in very different degrees.

"Conducting power is in some bodies powerfully increased by heat, and in others diminished, yet without one perceiving any accompanying essential electrical difference, either in the bodies, or in the change occasioned by the electricity conducted.

"A numerous class of bodies insulating electricity of low intensity, when solid, conduct it very freely when fluid, and are then decomposed by it.

"But there are many fluid bodies which do not sensibly conduct electricity of this low intensity; there are some which conduct it and are not decomposed; nor is fluidity essential to decomposition.

"There are but two bodies (sulphuret of silver

and fluoride of lead) which, insulating a voltaic current when solid, and conducting it when fluid, are not decomposed in the latter case.

"There is no strict electrical distinction of conduction which can as yet be drawn between bodies supposed to be elementary, and those known to be compounds."

[138] Faraday's *Speculation on the Nature of Matter*, already referred to.

[139] *Experimental Researches*: by Dr. Faraday. *Chemical Decomposition*, p. 151.

[140] Karsten; Poggendorff's *Annalen*, vol. lvii.

[141] *Traité Expérimental de l'Électricité et du Magnétisme*: Becquerel, 1834, Priestley's *Introduction to Electricity*. *On Electricity in Equilibrium*: Dr. Young's Lectures.

[142] Faraday's *Experimental Researches on Electricity*. This philosopher has shown, by the most conclusive experiments, "that the electricity which decomposes, and that which is evolved by the decomposition of, a certain quantity of matter, are alike. What an enormous quantity of electricity, therefore, is required for the decomposition of a single grain of water! We have already seen that it must be in quantity sufficient to sustain a platinum wire 1/104 of an inch in thickness, red hot, in contact with the air, for three minutes and three quarters. It would appear that 800,000 charges of a Leyden battery, charged by thirty turns of a very large and powerful plate machine, in full action—a quantity sufficient, if passed at once through the head of a rat or cat, to have killed it as by a flash of lightning—are necessary to supply electricity sufficient to decompose a single grain of water; or, if I am right, to equal the

quantity of electricity which is naturally associated with the elements of that grain of water, endowing them with their mutual chemical affinity."

[143] *Experimental Researches*: Faraday.

[144] The appearance of acid and alkaline matter, in water acted on by a current of electricity, at the opposite electrified metallic surfaces, was observed in the first chemical experiments made with the column of Volta—(see Nicholson's Journal, vol. iv. p. 183, and vol. iv. p. 261, for Mr. Cruickshank's Experiments; and Annales de Chimie, tom. xxxvii. p. 233, for those of M. Desormes): *On some Chemical Agencies in Electricity*: by Sir Humphry Davy.—Philosophical Transactions for 1807. The various theories of electro-chemical decomposition are carefully stated by Faraday, in his fifth series of *Experimental Researches on Electricity*, in which he thus states his own views:—"It appears to me that the effect is produced by an *internal corpuscular action* exerted according to the direction of the electric current, and that it is due to a force either *superadded to* or *giving direction to the ordinary chemical affinity* of the bodies present. The body under decomposition may be considered as a mass of acting particles, all those which are included in the course of the electric current contributing to the final effect; and it is because the ordinary chemical affinity is relieved, weakened, or partly neutralized by the influence of the electric current in one direction parallel to the course of the latter, and strengthened or added to in the opposite direction, that the combining particles have a tendency to pass in opposite courses."

[145] "This capital discovery (chemical decomposition of electricity) appears to have

been made in the first instance by Messrs. Nicholson and Carlisle, who observed the decomposition of water so produced. It was speedily followed up by the still more important one of Berzelius and Hisinger, who ascertained it as a general law, that, in all the decompositions so effected, the acids and oxygen become transferred and accumulated around the positive, and hydrogen, metals, and alkalies around the negative, pole of a voltaic circuit; being transferred in an invisible, and, as it were, a latent or torpid state, by the action of the electric current, through considerable spaces, and even through large quantities of water or other liquids, again to reappear with all their properties at their appropriate resting-places."—*Discourse on the Study of Natural Philosophy*: by Sir John Herschel, Bart., F.R.S.

[146] Numerous beautiful illustrations of this fact will be found in Becquerel's *Traité Expérimental de l'Électricité et du Magnétisme*.

[147] See *Le Feu élémentaire* of l'Abbé Nollet; Leçons de Physique, tom. vi. p. 252; *Du Pouvoir thermo-électrique*, by M. Becquerel—Annales de Chimie, vol. xli. p. 353; also a Memoir by Nobili, Bibliothèque Universelle, vol. xxxvii. p. 15; *Experimental Contributions towards the theory of Thermo-Electricity* by Mr. J. Prideaux—Philosophical Magazine, vol. iii., Third Series; *On the Thermo-Magnetism of Homogeneous Bodies, with illustrative experiments*, by Mr. William Sturgeon—Philosophical Magazine, vol. x. p. 1–116, New Series. Botto made magnets and obtained chemical decomposition. Antinori produced the spark. Mr. Watkins heated a wire in Harris's Thermo-Electrometer.

[148] A very ingenious application of the

knowledge of this fact was suggested by Mr. Solly, by which the heat of a furnace could be constantly registered at a very considerable distance from it. See *Description of an Electric Thermometer*: by E. Solly, Jun., Esq. Philosophical Magazine, vol. xx. p. 391. New Series.

[149] Humboldt; *Personal Narrative*, Chap. xvii.—Annales de Chimie, vol. xiv. p. 15.

[150] *Experimental Researches on Electricity*. Series xv. Consult Sir Humphry Davy: *An Account of some Experiments on the Torpedo*.—Philosophical Transactions, 1829, p. 15. John Davy, M.D., F.R.S.: *An Account of some Experiments and Observations on the Torpedo*, ibid., 1832, p. 259; and the same author's *Observations on the Torpedo, with an Account of some Additional Experiments on its Electricity*; and Matteucci, Bibliothèque Universelle, 1837, vol. xii. p. 174.

[151] *On Lightning Conductors*, by Sir William Snow Harris; *Observations on the Action of Lightning Conductors*, by W. Snow Harris, Esq., F.R.S.—London Electrical Society's Transactions. Numerous valuable papers *On Electricity*, by Sir William Harris, will be found in the Philosophical Transactions.

[152] Adopting, to a certain extent, this view, Faraday, in his *Electrical Nomenclature*, proposed for the word pole to substitute *anode* (ανω, *upwards*, and ὁδος, *a way*), the way which the sun rises; and *cathode* (κατα, *downwards*, and ὁδος, *a way*), the way which the sun sets. The hypothesis belongs essentially to Ampère. *Objections to the Theories severally of Franklin, Dufay, and Ampère, with an Effort to Explain Electrical Phenomena by Statical or Undulatory Polarisation*, by Robert Hare, M.D., Pennsylvania, will well repay an attentive

perusal.

[153] *Inquiry into the Laws of the Vital Functions.*—Philosophical Transactions, 1815, 1822; *Some Observations relating to the Functions of Digestion*, ibid., 1829: *On the Powers on which the Functions of Life in the more perfect animals depend, and on the manner in which they are associated in the production of their more complicated results*, by A. P. W. Philip, M.D., F.R.S., L. and E.—The following extract from the last-quoted of Dr. Philip's Memoirs, will give a general view of the conclusions of that eminent physiologist: —"With respect to the nature of the powers of the living animal which we have been considering, the sensorial and muscular powers, and the powers peculiar to living blood, we have found belong to the living animal alone, all their peculiar properties being the properties of life. The functions of life may be divided into two classes, those which are affected by the properties of this principle alone, and those, by far the most numerous class, which result from the co-operation of these properties with those of the principles which operate in inanimate nature. The nervous power we have found to be a modification of one of the latter principles, because it can exist in other textures than those to which it belongs in the living animal, and we can substitute for it one of those principles without disturbing the functions of life.

"Late discoveries have been gradually evincing how far more extensive than was supposed, even a few years ago, is the dominion of electricity. Magnetism, chemical affinity, and (I believe from the facts stated in the foregoing paper, it will be impossible to avoid the

conclusion) the nervous influence, the leading power in the vital functions of the animal frame, properly so called, appear all of them to be modifications of this apparently universal agent; for I may add we have already some glimpses of its still more extensive dominion."

Refer to Dr. Reid's papers.

[154] *Electro-physiological Researches*: by Signor Carlo Matteucci; Phil. Trans. 1845, p. 293, and subsequent years.

[155] Electro-Biology: by Alfred Smee, Esq.

[156] *Observations of Electric Currents in Vegetable Structures*: by Golding Bird, Esq., F.L.S.; Magazine of Natural History, vol. x. p. 240. In this paper Dr. Bird remarks that his experiments lead to the conclusion that vegetables cannot become so charged with electricity as to afford a spark; that electrical currents of feeble tension are always circulating in vegetable tissues; and that electrical currents are developed during germination from chemical action.

[157] *On Mineral Veins*: by Robert Were Fox, Esq.; Fourth Report of the Royal Cornwall Polytechnic Society. *On the Electro-magnetic Properties of Metalliferous Veins in the mines of Cornwall*: by Robert W. Fox, Esq.; Phil. Trans. 1830, p. 399.

[158] *Experiments and Observations on the Electricity of Mineral Veins*: by Robert Hunt and John Phillips; Reports of the Royal Cornwall Polytechnic Society for 1841–42. *On the Electricity of Mineral Veins*: by Mr. John Arthur Phillips; Ibid., 1843.

[159] In the lead lodes of *Lagylas* and *Frongoch*, electrical currents were detected by Mr. Fox, but none in those of *South Mold* and

Milwr, in Flintshire: Cornwall Geological Transactions, vol. iv. In the lead veins of *Coldberry* and *Skeers*, in Teasdale, Durham, the currents detected were very feeble: Reports of the Bristol Association, 1838. Von Strombeck could detect no electric currents in the veins worked in the clay slate near Saint Goar, on the Rhine: Archiv. für Mineralogie, Geognosie, &c., von Dr. C. J. B Karsten, 1833. Professor Reich, however, obtained very decided results at *Frisch Glück*, *Neue Hoffnung*, *Gottlob*, and in other mineral veins in the mining districts of Saxony: Edinburgh New Philosophical Journal, vol. xxviii. 1839. The irregularities are all to be explained by the presence or absence of chemical excitation.

[160] This was remarkably the case at *Huel Sparnon*, near Redruth, where the cobalt was discovered between two portions of a dislocated lode; and the same was observed by Mr. Percival Johnson in a small mine worked for nickel, near St. Austell.

[161] *On the process used for obtaining artificial veins in clay*: by T. B. Jordan; Sixth Annual Report of the Royal Cornwall Polytechnic Society. See also my memoir, already referred to, in the Memoirs of the Geological Survey and Museum of Practical Geology, vol. i.

[162] See Becquerel, *Traité Experimental de l'Electricité, &c. Electrical Experiments on the formation of Artificial Crystals*: by Andrew Crosse, Esq.; British Association Reports, vol. v., 1836. The lamination of clay and other substances is described in my memoir referred to, Note p. 226.

[163] Report on the Geology of Cornwall, Devon, and West Somerset, by Sir Henry T. De la Beche: *Theoretical observations on the formation and filling of Mineral Veins and*

Common Faults, p. 349.

[164] The following analyses of waters from deep mines were made by me in 1840, and, with many others, published in the Reports of the Royal Cornwall Polytechnic Society.

Consolidated Mines, Gwennap, Cornwall.	**In 1,000 grains of water.**
Muriate of soda	1·5
Sulphate of lime	·5
Sulphate of iron	·15
Sulphate of copper	1·25
Silica	·15
Alumina	·3
Total	3·7

United Mines, Gwennap.	
Muriate of soda	1·10
Muriate of lime	·15
Sulphate of soda	·50
Sulphate of lime	1·5
Sulphate of iron	·75
Alumina	·5
Silica	·15
Total	4·65

Great St. George.	
Muriate of soda	1·35
Sulphate of lime	·74

Carbonate of iron	·70
Alumina	·50
Carbonate of lime	·10
Total	3·4

[165] The discovery of the electrotype has been disputed, as all valuable discoveries are. Without, however, at all disparaging the merits of what had been done by Mr. Jordan, I am satisfied, after the most careful search, that the first person who really employed electro-chemical action for the precipitation of metals in an ornamental form, was Mr. Spencer, of Liverpool.

[166] See Spencer, *Instructions for the Multiplication of works of Art in Metal by Voltaic Electricity*. *Novelties in Experimental Science*: Griffin, Glasgow, *Elements of Electro-Metallurgy*: by Alfred Smee, Esq.

[167] The magneto-electrical machine is employed in Birmingham for this purpose; but I am informed by Messrs. Elkington that they do not find it economical, or rather that the electro-precipitation is carried on too slowly.

[168] This has been done by Mr. Robert Were Fox, at a mine near Falmouth. By connecting two copper wires with two lodes, and bringing them, at the surface, into a cell containing a solution of sulphate of copper, this gentleman obtained an electrotype copy of an engraved copper-plate.

[169] This has been most effectually accomplished by Mr. Bain. Mr. Hobson has had an electric clock, thus excited, in action for several years.

CHAPTER X.

MAGNETISM.

Magnetic Iron—Knowledge of, by the Ancients—Artificial Magnets—Electro-Magnets—Electro-Magnetism—Magneto-Electricity—Theories of Magnetism—The Magnetic Power of soft Iron and Steel—Influence of Heat on Magnetism—Terrestrial Magnetism—Declination of the Compass-needle—Variation of the Earth's Magnetism—Magnetic Poles—Hansteen's Speculations—Monthly and Diurnal Variation—Dip and Intensity—Thermo-Magnetism—Aurora Borealis—Magnetic Storms—Magnetic conditions of Matter—Diamagnetism, &c.

Agreeably with the view now generally received, that magnetism and electricity are but modifications of one force, since they are found to stand to each other in the relation of cause and effect, the separation which is here adopted, of the consideration of their several phenomena, may appear inappropriate. The importance, however, of all that is connected with magnetism, and the very decided difference which is presented by true magnetic action, and that of frictional or chemical electricity, is so great that it has been thought advantageous to adopt the present

arrangement in reviewing the influence of terrestrial magnetism with which science has made us acquainted.

From a very early period a peculiar attractive force has been observed in some specimens of iron ore. Masses of this kind were found in Magnesia, and from that locality we derive the name given to iron in its polar condition. This is confirmed by the following lines by Lucretius:—

Quod superest agere incipiam, quo fœdere fiat
Natura lapis hic ut ferrum ducere possit,
Quem magnêta vocant patrio de nomine Graii
Magnêtum, quia sit patriis in finibus ortus.

Again we find Pliny employing the term *magnetic*, to express this singular power. It was known to the ancients that the magnetic power of iron, and the electric property of amber, were not of the same character, but they were both alike regarded as miraculous. The Chinese and Arabians seem to have known Magnetism at a period long before that at which Europeans became acquainted with either the natural loadstone or the artificial magnet. Previously to A.D. 121, the magnet is distinctly mentioned in a Chinese dictionary; and in A.D. 419 it is stated in another of their books that ships were steered south by it.[170]

The earliest popularly received account of its use in Europe is, that Vasco de Gama employed a compass in 1427, when that really adventurous navigator first explored the Indian seas. It is highly probable, however, that the knowledge of its important use was derived from some of the Oriental nations at a much earlier period.

We have some curious descriptions of the *leading stone* or loadstone, in the works of an Icelandic historian, who wrote in 1068. The mariner's compass is described in a French poem of the date of 1181; and from Torfæus's History of Norway, it appears to have been known to the northern nations certainly in 1266.

We have not to deal with the history of magnetic discovery, but so far as it tells of the strange properties which magnets are found to possess, and the application of this knowledge to the elucidation of effects occurring in nature.

A brown stone, in no respect presenting anything by which it shall be distinguished from other rude stones around it, is found, upon close examination, to possess the power of drawing light particles of iron towards it. If this stone is placed upon a table, and iron filings are thrown lightly around it, we discover that these filings arrange themselves in symmetric curves, proceeding from some one point of the mass to some other; and upon examining into this, we shall find that the iron which has once clung to the one point will be rejected by the other. If this stone is freely suspended, we shall learn also that it always comes to rest in a certain position,—this position being determined by these points, and some attractive force residing in the earth itself. These points we call its poles; and it is now established that this rude stone is but a small representative of our planet. Both are magnetic: both are so in virtue of the circulation of currents of electricity, or of lines of magnetic force, as seen in the curves formed by the iron dust, and the north pole of the one attracts the south pole of the other, and the contrary. By a confusion of terms we speak of the north pole of a

compass-needle, meaning that point which is always opposite to the north pole of the earth: the truth being that the pole of the compass-needle, which is so forcibly drawn to the north, is a point in a contrary state, or, as we may express it, really a south pole.

There is a power of a peculiar kind, differing from gravitation, or any other attracting or aggregating force with which we are acquainted, which exists permanently in the magnetic iron stones, and also in the earth. What is this power?

Magnetism may be produced in any bar of steel, either by rubbing it with a loadstone, or by placing it in a certain position in relation to the magnetic currents of the earth, and, by a blow or any other means, disturbing its molecular arrangement. This principle appears to involve the iron as with an atmosphere, and to interpenetrate it. By one magnet we may induce magnetism in any number of iron bars without its losing any of its original force. As we have observed of the electrical forces already considered, the magnet constantly presents two points in which there is a difference manifested by the circumstance that they are always drawn with considerable power towards the north or south poles of the earth. That this power is of the same character as the electricity which we have been considering, is now most satisfactorily proved. By involving a bar of soft iron which, being without any magnetic power, is incapable of sustaining even an ounce weight, with a coil of copper wire, through which a galvanic current is passing, the bar will receive, by induction from the current, an enormous accession of power, and will, so long as the current flows around it, sustain many hundred pounds weight, which, the

moment the current is checked, fall away from it in obedience to the law of gravity. Thus the mere flow of this invisible agent around a mass of metal possessing no magneto-attractive power, at once imparts this life-like influence to it, and as long as the current is maintained, the iron is endowed with this surprising energy.

This discovery, which we owe to the genius of Oersted, and which has, indeed, given rise to a new science, electro-magnetism, may be regarded as one of the most important additions made to our knowledge.

Current electricity is magnetic; iron is not necessary to the production of magnetic phenomena, although by its presence we secure a greater amount of power. The copper wires which complete the circuit of a galvanic battery, will attract and hold up large quantities of iron filings, and the wires of the electric telegraph will do the same, while any signal is being conveyed along them. Again, all the phenomena common to galvanic electricity can be produced by merely disturbing the power permanently secured in the ordinary magnet. It was thought that magnets would become weakened by this constant disturbance of their magnetism; but, since its application to the purpose of manufacture, and magneto-electricity has been employed in electro-plating, it has been found that continued action for many years, during which enormous quantities of electricity have been thus given out and employed in producing chemical decomposition, has not, in the slightest degree, altered their powers. Thus a small bar of metal is shown to be capable of pouring out, for any number of years, the principle upon which the phenomena of magnetism depend.

There are, however, differences, and striking ones, between ordinary and magnetic electricity. In the magnet we have a power at rest, and in the electrical machine or galvanic battery, a power in motion. Ordinary electricity is stopped in its passage by a plate of glass, of resin, and many other substances; but magnetism passes these with freedom, and influences magnetic bodies placed on the other side. It would appear, though we cannot explain how, that magnetism is due to some lateral influence of the electric currents. A magnetic bar is placed over a copper wire, and it hangs steadily in the direction of its length; an electric current is passed along it, and the magnet is at once driven to place itself across the wire. Upon this experiment, in the main, Ampère founds his theory of terrestrial magnetism. He supposes electrical currents to be traversing our globe from east to west, and thus, that the needle takes its direction, not from the terrestrial action of any fixed magnetic poles, but from the repulsion of these currents, as is the case with the wire.

It has been found that wires, freely suspended, along which currents were passing in opposite directions, revolve about each other, or have an inclination to place themselves at right angles; thus exhibiting the same phenomenon as the magnet and the conducting wire. So far the hypothesis of Ampère leads us most satisfactorily. We see in the magnet one form of electricity, and in the machine or battery another. But why should not the electricity of the magnet, electricity at rest, exhibit the same powers as this force in motion?

Oersted, whose theory led him to the discovery of the fact of the magnetic power of an electric current, of the establishment indeed of the new science—

ELECTRO-MAGNETISM, regards the phenomena of a current passing a wire, and its action on a needle, as evidence of two fluids, positive and negative, traversing in opposite directions, and mutually attracting and repelling. He conceives that they pass the wires in a series of spirals; that in the magnet, by some peculiar property of the iron, this conflict of the currents is reduced to an equilibrium, and its power becomes manifested in its attractive force. [171] This does not, however, convey a clear idea to the mind.

It is curious that iron becomes magnetic in a superior degree to any other metal; that steel retains permanently any magnetism imparted to it; but that soft iron rapidly loses its magnetic power. This must be in virtue of some peculiar arrangement of the molecules, or some unknown physical condition of the atoms of the mass, by which a continued influence is retained by the steel, probably in a state of constant internal circulation. It has, however, been shown that soft iron, under certain circumstances, may be made to retain a large amount of magnetic force.[172]

If a horse-shoe shaped bar of soft iron is rendered magnetic by the circulation of an electric current around it, while its two ends are united by an armature of soft iron, so that it is capable of supporting many hundred pounds weight; and we then, by breaking the circuit, stop the current, taking care the armature is kept in contact, the iron will not lose its magnetic property, but will retain this power for many years. If the connecting piece of iron, the armature, is removed, the bar immediately loses all its magnetism, and will not support even the armature itself. This fact appears to confirm the idea

that magnetism is due to the retention of electricity, and that steel possesses the property of equalizing the opposing forces, or of binding this principle to itself like an atmosphere.

The influence of heat on magnetism is so remarkable a proof of the dependence of this power upon molecular arrangement, that it must not escape our notice. To select but one of many experiments by Mr. Barlow, it was found that in a bar of malleable iron, in which, when cold, the magnetic effect was + 30° 0', all polarity ceased at a white heat, that it was scarcely appreciable at a red heat, but that at a blood-red heat it was equal to + 41° 0'.[173]

The more closely we examine the peculiarities of the magnetic power, and particularly as they are presented to us in its terrestrial action, the more surprising will its influence appear to be. We have discovered a natural cause which certainly exercises a very remarkable power over matter, and we have advanced so far in our investigations as to have learnt the secret of converting one form of force into another, or of giving to a principle, produced by one agency, a new character under new conditions; of changing, in fact, electricity into magnetism, and from magnetism again evolving many of the effects of electrical currents.

If a magnetic bar is freely suspended above the earth, it takes, in virtue of some terrestrial power, a given direction, which is an indication of the earth's magnetic force. Whether this is the consequence of the currents of electricity, which Ampère supposes to circulate around the globe, from east to west, or the result of points of attraction in the earth itself, the phenomenon is equally wonderful. To whatever cause we may refer the visible effects, it appears

certain that this earth is composed of particles in a magnetic state, the character varying with physical conditions, and that terrestrial magnetic force is the collective action of all the atoms of this planetary mass.[174]

The remarkable connexion which has been observed between the changes in the physical condition of the surface of the sun and terrestrial phenomena, must not escape our notice. Sir William Herschel thought he perceived a link connecting the dark spots on the sun's face with the variations of the earth's temperature. This has not, however, been confirmed by the observations which have been made since the time of Herschel. The careful examinations of the solar spots which have been made by Schwabe,[175] prove a well-defined order of progress in them. He has discovered that they move in cycles of ten years —from the smallest number visible in a given year, they regularly increase for five years, when they reach their maximum; they then as regularly decrease, and at the end of another five years they are at their maximum number. The magnetic observations which have been carried on by the British and other governments for some years, over every part of the world, have elicited the fact that the order of variation in the earth's magnetic intensity is in cycles of ten years, and the law of increase and decrease which is found to prevail with the solar spots distinctly marks the variations of terrestrial magnetism. Few more interesting facts than this are within the range of our knowledge, proving as it does the direct dependence of terrestrial phenomena on solar force.

The constancy with which a magnetised needle points along a certain line which varies a little from

the earth's axial line, renders it one of the most important instruments to the practical and the scientific man. The wanderer of the ocean or of the desert is enabled, without fear of error, to pursue his path, and in unknown regions to determine the azimuth of objects. The miner or the surveyor finds in the magnetic compass the surest guide in his labours, and the experiment is for ever studying its indications.

"True as the needle to the pole,"

has passed into a proverb among mankind, but the searching inquiry of modern observers has shown that the expression is correct only with certain limitations. There are two lines on the surface of the earth along which the needle points true north, or where the magnetic and the geographical north correspond. These are called lines of *no variation*, or, as they have also been designated, *agonic lines*, and one is found in the eastern and the other in the western hemisphere. The American line is singularly regular, passing in a south-east direction from the latitude 60° to the west of Hudson's Bay, across the American lakes, till it reaches the South Atlantic ocean, and cuts the meridian of Greenwich in about 65° south latitude. The Asiatic line of *no variation* is very irregular, owing, without doubt, to local interferences; it begins below New Holland, in latitude 60° south, it bends westward across the Indian ocean, and from Bombay has an inflection eastward through China, and then northward across the sea of Japan, till it reaches the latitude of 71° north, when it descends again southward, with an immense semicircular bend, which terminates in the White Sea.

Hansteen has thought that there are two points in each hemisphere which may be regarded as stronger and weaker poles on opposite sides of the poles of revolution. These are called the magnetic poles of the earth, or by Hansteen *magnetic points of convergence*. These four points are considered to have a regular motion round the globe, the two northern ones from west to east, and the two southern ones from east to west. By the assistance of recorded observations, Hansteen has calculated the periods of these revolutions to be as follows:—

The weakest north pole in 860 years.
The strongest north pole in 1746 years.
The weakest south pole in 1304 years.
The strongest south pole in 4609 years.

There are some points of speculation on which Hansteen has ventured which have been smiled at as fanciful; but they may rather indicate an amount of knowledge in the Brahminical and Egyptian priesthood, beyond what we are usually disposed to allow them, and prove that their observations of nature had led them to an appreciation of some of the most remarkable harmonies of this mysterious creation.

The above terms are exceedingly near 864, 1246, 1728, 4320, and those numbers are equal to the mystic number of the Indians, Greeks, and Egyptians, 432 multiplied by 2, 3, 4, and 10. On these the ancients believed a certain combination of natural events to depend, and, according to Brahminical mythology, the duration of the world is divided into four periods, each of 432,000 years. Again, the sun's mean distance from the earth is 216 radii of the sun, and the moon's mean distance 216 radii of the moon,

each the half of 432. Proceeding with this very curious examination, Hansteen says, 60 multiplied by 432 equals 15,920, the smallest number divisible at once by all the four periods of magnetic revolution, and hence the shortest time in which the four poles can complete a cycle, and return to their present state, and *which coincides exactly with the period in which the precession of the equinoxes will amount to a complete circle*, reckoning the precession at a degree in seventy-two years.[176]

When we consider the phenomena of terrestrial magnetism carefully, it appears to indicate the action of a power external to the earth itself, and, as Hansteen conceives, having its origin from the action of the sun, heating, illuminating, and producing a magnetic tension, in the same manner as it produces electrical excitation and actino-chemical action.

The movements of these magnetic poles have been the subject of extensive and most accurate observation in every quarter of the globe. In London, during 1657–1662, there was no magnetic variation; the agonic line passing through it. The variation steadily increased, until, in 1815, it amounted to 24° 15' 17", since which time it has been slowly diminishing. In addition to this great variation, we have a regular annual change dependent on the position of the sun, in reference to the equinoctial and solstitial points, which was discovered by Cassini, and investigated by Arago and others. Also a diurnal variation, which movement appears to commence early in the morning, moving eastward until half-past seven, A.M., when it begins to move westward until two, P.M., when it again returns to the east, and in the course of the night reaches the point from which it started twenty-four hours before.

We have also remarkable variations in what is termed the *dip* of the needle. It is well known that a piece of unmagnetized steel, if carefully suspended by its centre, will swing in a perfectly horizontal position, but, if we magnetize this bar, it will immediately be drawn downwards at one end. The force of the earth's polarity, attracting the dissimilar pole, has caused it to *dip*.

There is, in the neighbourhood of the earth's equator, and cutting it at four points, an irregular curve, called the magnetic equator, or *aclinic* line, where the needle balances itself horizontally. As we proceed from this line towards either pole the dip increases, until, at the north and south poles, the needle takes a vertical position. The *intensity* of the earth's magnetism is also found to vary with the position, and to increase in a proportion which corresponds very closely with the dip. But the *intensity* is not a function of the dip, and the lines of equal intensity, *isodynamic lines*, are not parallel to those of equal dip. We have already remarked on the diurnal variation of the declination of the needle; we know, also, that there exists a regular monthly and daily change in the magnetic intensity. The greatest monthly change appears when the earth is in its perihelion and aphelion, in the months of December and June,—a maximum then occurs; and about the time of the equinoxes a minimum is detected.[177]

The daily variation of intensity is greatest in the summer, and least in the winter. The magnetism is generally found to be at a minimum when the sun is near the meridian; its intensity increasing until about six o'clock, when it again diminishes.[178]

What striking evidences all these well-ascertained facts give of the dependence of terrestrial magnetism

on solar influence! and in further confirmation of this view, we find a very remarkable coincidence between the lines of equal temperature—the isothermal lines, and those of equal dip and magnetic intensity.

Sir David Brewster first pointed out that there were in the northern hemisphere two poles of maximum cold; these poles agree with the magnetic points of convergence; and the line of maximum heat, which does not run parallel to the earth's equator, is nearly coincident with that of magnetic power. Since Seebeck has shown us that electrical and magneto-electrical phenomena can be produced by the action of heat upon metallic bars, we have, perhaps, approached towards some faint appreciation of the manner in which the solar calorific radiations may, acting on the surface of our planet, produce electrical and magnetic effects. If we suppose that the sun produces a disturbance of the earth's electricity along any given line, in all directions at right angles to that line, we shall have magnetic polarity induced.[179] That such a disturbance is regularly produced every time the sun rises, has been sufficiently proved by many observers.

In 1750, Wargentin noticed that a very remarkable display of *Aurora borealis* was the cause of a peculiar disturbance of the magnetic needle; and Dr. Dalton[180] was the first to show that the luminous rays of the Aurora are always parallel to the dipping-needle, and that the Auroral arches cross the magnetic meridian at right angles. Hansteen and Arago have attended with particular care to these influences of the northern lights, and the results of their observations are:—

That as the crown of the Aurora quits the usual

place, the dipping-needle moves several degrees forward:—

That the part of the sky where all the beams of the Aurora unite, is that to which a magnetic needle directs itself, when suspended by its centre of gravity:—

That the concentric circles, which show themselves previously to the luminous beams, rest upon two points of the horizon equally distant from the magnetic meridian; and that the most elevated points of each arch are exactly in this meridian.[181]

It does not appear that every Aurora disturbs the magnetic needle; as Captains Foster and Back both describe very splendid displays of the phenomenon, which did not appear to produce any tremor or deviation upon their instruments.[182]

Some sudden and violent movements have been from time to time observed to take place in suspended magnets; and since the establishment of magnetic observatories in almost every part of the globe, a very remarkable coincidence in the time of these agitations has been detected. They are frequently connected with the appearance of Aurora borealis; but this is not constantly the case. These disturbances have been called *magnetic storms*; and over the Asiatic and European continent, the islands of the Atlantic and the western hemisphere, they have been proved to be simultaneous.

From observations made at Petersburg by Kupffer, and deductions drawn from the observations obtained by the Magnetic Association, it appears probable that these *storms* arise from a sudden displacement in the magnetic lines of the earth's surface; but the cause to which this may be due is

still to be sought for.

In the brief and hasty sketch which has been given of the phenomena of terrestrial magnetism, enough has been stated to show the vast importance of this very remarkable power in the great operations of nature. We are gradually reducing the immense mass of recorded observations, and arriving at certain laws which are found to prevail. Still, the origin of the force, whether it is strictly electrical, whether it is the circulation of a magnetic fluid, or whether it is merely a peculiar excitation of some property of matter, are questions which are open for investigation.

In the beautiful Aurora borealis, with its trembling diffusive lights, and its many-coloured rays, we have what may be regarded as a natural exhibition of magnetism, and we appear to have within our grasp the explanation we desire. But we know not the secret of even these extraordinary meteorological displays. If we pass an electric spark from a machine through a long cylinder, exhausted of air as far as possible, we have a mimic representation of the Northern Lights—the same attenuation of brightness, almost dwindling into phosphorescence; and by the slightest change of temperature we may produce that play of colours which is sometimes so remarkably manifested in Aurora. Dr. Dalton considered Aurora borealis *as a magnetic phenomenon, and that its beams are governed by the earth's magnetism*. We know that the arc of light produced between the poles of a powerful galvanic battery is readily deflected by a good magnet; and we have lately learned that every vapour obeys the magnetic force.[183] It is, therefore, yet a question for our consideration, does the earth's magnetism produce the peculiar phenomena of

Aurora by acting upon electricity in a state of glow? or have we evidence in this display of the circulation of the magnetic fluid around our globe, manifesting itself by its action on the ferruginous and other metallic matter, which Fusinieri has proved to exist in the upper regions of our atmosphere.[184] That magnetic radiations do exist, has been proved by Faraday, and that they form lines of force perpendicular to the earth's surface, has been experimentally shown. Parallelograms of wire moved upon a central axis, and connected with a galvanometer, give at every revolution indication of an electric disturbance in all respects analogous to the production of a current by moving wires in front of a steel magnet.

The alteration in the properties of heat, when it passes from the radiant state into combination with matter, exhibits to us something like what we may suppose occurs in the conversion of magnetism into electricity or the contrary. We have a subtile agent, which evidently is for ever busy in producing the necessary conditions of change in this our earth: an element to which is due the development of many of the most active powers of nature; performing its part by blending with those principles which we have already examined; associating itself with every form of matter; and giving, as we shall presently see, in all probability, the first impulses to combination, and regulating the forms of aggregating particles.

As electricity has the power of altering the physical conditions of the more adherent states of matter, thus giving rise to variations of form and modes of combination, so gross matter appears to alter the character of this agency, and thus disposes it to the several modifications under which we have already

detected its presence. We have mechanical electricity and chemical electricity, each performing its great work in nature; yet both manifesting conditions so dissimilar, that tedious research was necessary before they could be declared identical. Magnetic electricity is a third form; all its characteristics are unlike the others, and the office it appears to perform in the laboratory of creation is of a different order from that of the other states of electrical force. In the first two we have decomposing and recombining powers constantly manifested—in fact, their influences are always of a chemical character; but in the last it appears we have only a directive power. It was thought that evidence had been detected of a chemical influence in magnetism; it did appear that sometimes a retarding force was exerted, and often an accelerating one. This has been again denied, and we have arrayed in opposition to each other some of the first names among European experimentalists. The question is not yet to be regarded as settled; but, from long and tedious investigation, during which every old experiment has been repeated, and numerous new ones tried, we incline to the conclusion that chemical action is not directly affected by magnetic power. It is highly probable that magnetism may, by altering the structural arrangement of the surface, vary the rate of chemical action; but this requires confirmation.[185]

There is no substance to be found in nature existing independently of magnetic power. But it influences bodies in different ways: one set acting with relation to magnetism, like iron, and arranging themselves along the line of magnetic force,—these are called magnetic bodies; another set, of which bismuth may be taken as the representative, always placing themselves at right angles to this line,—these are

called *diamagnetic bodies*.[186] This is strikingly shown by means of powerful electro-magnets; but the magnetism of the earth is sufficient, under proper care, to exhibit the phenomena.

Every substance in nature is in one or other of these conditions. The rocks, forming the crust of the earth, and the minerals which are discovered in them; the surface soil, which is by nature prepared as the fitting habitation of the vegetable world, and every tree, shrub, and herb which finds root therein, with their carbonaceous matter, in all its states of wood, leaf, flower, and fruit; the animal kingdom, from the lowest monad through the entire series up to man,—have, all of them, distinct magnetic or diamagnetic relations.

"It is a curious sight," says Dr. Faraday, "to see a piece of wood or of beef, or an apple, or a bottle of water repelled by a magnet, or, taking the leaf of a tree, and hanging it up between the poles, to observe it take an equatorial position. Whether any similar effects occur in nature among the myriads of forms which, upon all parts of its surface, are surrounded by air, and are subject to the action of lines of magnetic force, is a question which can only be answered by future observation."[187]

At present, the bodies which are known to exhibit decided ferro-magnetic properties are the following, which stand arranged in the order of their intensity:—

Iron, Nickel, Cobalt, Manganese,
Chromium, Cerium, Titanium,
Palladium, Platinum, Osmium.

It is interesting to know that there are evidences that

two bodies which, when separate, are not magnetic, as iron is, become so when combined. Copper and zinc are both of the diamagnetic class, but many kinds of brass are discovered to be magnetic.

The salts of the above metals are, to a greater or less extent, ferro-magnetic, but they may be rendered neutral by water, which is a diamagnetic body, being repelled by the magnet. It will be unnecessary, here, to enumerate the class of bodies which are diamagnetic; indeed, all not included in the preceding list may be considered as belonging to that class, with the exception of gases and vapours, which appear to exist, relatively to each other, sometimes in the one, and sometimes in the other condition. [188]

To endeavour to reduce our knowledge of these facts to some practical explanation, we must bear in mind that particular spaces around the north and south geographical poles of the earth, are regarded as circles to which all the magnetic lines of force converge. Under circumstances which should prevent any interference with what is called ferro-magnetic action, all bodies coming under that class would arrange themselves according to the laws which would regulate the disposition of an infinite number of magnets, free to move within the sphere of each other's influence. The north and south pole of one magnetic body would attach itself to the south and north pole of another, until we had a line of magnets of any extent; the two ends being in opposite states, like the magnetic points of convergence of the earth.

Every body, not ferro-magnetic, places itself across such a line of magnetic force as we have conceived; and if the earth were made up of separate layers of ferro-magnetic and diamagnetic bodies, the result

would be the formation of bands at right angles to each other. This is not the case, by reason of the intermingling of the two classes of substances. Out of the known chemical elements we find only about ten which are actively ferro-magnetic; the others combining with these give rise to either a weaker state, a neutral condition, or the balance of action is turned to the diamagnetic side. Sulphate of iron, for instance, is a magnetic salt; but in solution, water being diamagnetic, it loses its property. The yellow prussiate of potash dissolved in water is a diamagnetic body; but the red prussiate, which contains an atom less of potassium, is magnetic: but in the solid state they are both diamagnetic.[189]

From this it would appear that the chemical composition of a body regulated its relation to magnetism. The following facts will show, however, that the molecular structure is more particularly concerned in determining the molecular condition of substances.

M. Plücker, being desirous of finding the extent to which the *direction of the fibres* in organic bodies might influence their magnetic or diamagnetic properties, was led to inquire whether in crystals the direction of the optic axes, which itself depends upon the arrangement of the particles, might not also exercise some influence. The first submitted to the action of the electro-magnet a thin plate of tourmaline, such as is employed in experiments upon polarization, having its optic axis parallel to its longest length. It was very quickly perceived that the plate was magnetic, by the effect of the iron that it contains; but it was suspended successively in three ways,—first, so that its longest side was vertical, then as that the shortest side was vertical, and finally

so that the plate itself was horizontal. In the first case it is directed between the two points of the conical curvatures of the poles like a magnetic body; but, in the other two cases, on the contrary, it took the direction assumed by diamagnetic bodies—that is to say, a direction such that its longest length was perpendicular to the line joining the poles. This direction indicated that the optical axis was repelled by the two poles, and that this repulsion outweighed the magnetic properties of the crystal.[190]

The relation of structure to physical phenomena of essentially different characters is remarkable. Savart, when making crystalline plates of quartz and carbonate of lime vibrate, succeeded in determining a relation between the acoustic figures that are produced in them, and the particular mode of the crystallization of the substance. He found that the direction of the optical axis is constantly connected with that of the principal forms of the acoustic figures.

Mitscherlich has remarked that crystals do not expand uniformly by heat, but that this dilatation is greater in one direction than in another; and that this difference is connected with their crystalline form. M. de Sénarmont has shown that conductibility for heat, which is equal in all directions for the crystals of the regular system, acquires in others a maximum or a minimum value, according to directions parallel to the crystallographic axes; so that the isothermic surfaces, which are spheres in the former case, are, in the other, ellipsoids elongated or flattened in the same direction. The optical axes do not altogether coincide with the principal axes of conductibility for heat; but this appears to be due merely to slight differences in the rate of

progression, or the refrangibility of the luminous and calorific rays.

Wiedemann, by employing a fine point through which he made electricity arrive upon a surface that he had powdered with licopodium or red lead, succeeded in determining, by means of the form assumed by this light powder, the conductibility of crystals in different directions.

On a surface of glass, the powder which disperses itself around the points, in consequence of electric repulsion, forms a circular figure traversed by radii. When a plate of gypsum is used instead of glass the figure is found to be elliptical, and the great axis of the ellipse forms a right angle with the principal crystallographic axis, which proves that the electricity distributes itself more easily in a direction perpendicular to the axis than in any other. M. Wiedemann comes to the conclusion that crystals which possess a better conductibility in the direction of the principal axis, all belong to the class of negative crystals: while those which have a better conductibility in the direction perpendicular to the axis are positive, which indicates that the direction of best conductibility for electricity is also that according to which light is propagated relatively with greater velocity.

Tyndale has shown, that if gutta percha which has been rendered fibrous in manufacture is cut so that the fibres are in the direction of this greatest length, or in a direction perpendicular to this greatest length, and placed under the influence of a magnet, they direct themselves equatorially. Ivory cut in the same direction manifests the same conditions, though both these substances are diamagnetic.

The fibrous structure, and the planes of cleavage,

thus determine the magnetic condition of a substance. The special properties presented by crystals, in regard to the action exercised upon them by magnets, is due to a particular mode of grouping their particles. This is also the cause of unequal dilatability, and of unequal conductibility for heat and for electricity.

How curiously, therefore, does molecular structure determine the relation of a body to any of the forms of physical force!

We still search in the dark, and see but dimly the evidences; yet it becomes almost a certainty to us, that this stone of granite, with its curious arrangement of felspar, mica, and quartz, presents its peculiar condition in virtue of some law of magnetic force. The crystal, too, of quartz, which we break out of the mass, and which presents to us a beautifully regular figure, is, beyond a doubt, so formed, because the atoms of silica are each one impelled in obedience to one of these two conditions of magnetism to set themselves in a certain order to each other, which cannot be altered by human force without destruction.

All the laws which regulate the forms of crystals and amorphous bodies are, to the greatest degree, simple. In nature the end is ever attained by the easiest means; and the complexity of operation, which appears sometimes to the observer, is only so because he cannot see the spring by which the machine is moved.

The gaseous envelope, our atmosphere, is in a neutral state. Oxygen is strikingly magnetic in relation to hydrogen gas, whilst nitrogen is as singularly the contrary; and the same contrasts present themselves when these gases are examined in

their relation to common air. Thus, oxygen being magnetic, and nitrogen the contrary, we have an equilibrium established, and the result is a compound neutral in its relations to all matter. All gases and vapours are found to be diamagnetic, but in different degrees.[191] This is shown by passing a stream of the gas, rendered visible by a little smoke, within the influence of a powerful magnet.

These bodies are, however, found relatively to each other,—or even to themselves, under different thermic conditions,—to change their states, and pass from the magnetic to the diamagnetic class. Heat has a very remarkable influence in altering these relations; and atmospheric air at one temperature is magnetic to the same fluid at another: thus, by thermic variations, attraction or repulsion may be alternately maintained. By this it must be understood that a stream of air, at a temperature elevated but a few degrees above that of an atmosphere of the same kind into which it is passing, is deflected in one way by a magnet; whereas, if the stream is colder than the bulk through which it flows, it is bent in another way by the same force. In this respect magnetism and diamagnetism show equally the influence of another physical force, heat; and we may safely refer many meteorological phenomena to similar alterations of condition in the atmosphere, relative to the magnetic relations of the aërial currents.

That magnetism has a directive power is satisfactorily shown by the formation of crystals in the neighbourhood of the poles of powerful magnets. The common iron salt, the protosulphate, ordinarily crystallizes so that the crystals unite by their faces; but when crystallizing under magnetic influence, they have a tendency to arrange themselves with

regard to each other so that the acute angle of one crystal unites with one of the faces of another crystal, near to, but never actually at, its obtuse angle. In addition to this, if a magnet of sufficient power is employed, the crystals arrange themselves in magnetic curves from one pole to the other, a larger crop of crystals being always formed at the north than at the south pole. Here we have evidence of an actual turning round of the crystal, in obedience to the directive force of the magnet; and we have the curious circumstance of a difference in some way, which is not clearly explained, between the two opposite poles. If, instead of an iron or a ferro-magnetic salt, we employ one which belongs to the other, or diamagnetic, class, we have a curious difference in the result. If into a glass dish, fixed on the poles of a strong electro-magnet, we pour a quantity of a solution of nitrate of silver, and place in the fluid, over the poles of the magnet, two globules of mercury (an arrangement by which that arborescent crystallization, called the *Arbor Dianæ*, is produced,) we have the long needle-shaped crystals of silver, arranging themselves in curves which would cut the ordinary magnetic lines at right angles.[192]

In the first example given we have an exhibition of magnetic force, while in the last we have a striking display of the diamagnetic power.

The large majority of natural formations appear to group themselves under the class of diamagnetics. These bodies are thought to possess poles of mutual repulsion among themselves, and which are equally repelled by the magnetic points of convergence. Confining our ideas to single particles in one condition or the other, we shall, to a certain extent,

comprehend the manifold results which must arise from the exercise of these two modes of force. At present, our knowledge of the laws of magnetism is too limited to allow of our making any general deductions relative to the disposition of the molecules of matter; and the amount of observation which has been given to the great natural arrangements, is too confined to enable us to infer more than that it is probable many of the structural conditions of our planet are due to polarity.

Mountain ranges observe a singular uniformity of direction, and the cleavage planes of rock are evidently determined by some all-pervading power. Mineral bodies are not distributed in all rocks indiscriminately. The primary formations hold one class of metalliferous ores, and the more recent ones another. This is not to be regarded as in any way connected with their respective ages, but with some peculiar condition of the stone itself. The granite and slate rocks, at their junctions, present the required conditions for the deposit of copper ore, while we find the limestones have the characteristic physical state for accumulating lead ore. Again, on examining any mineral vein, it will be at once apparent that every particle of ore, and every crystal of quartz or limestone, is disposed in a direction which indicates the exercise of some powerful directive agency.[193]

It appears, from all the results hitherto obtained, that the magnetic and diamagnetic condition of bodies is equally due to some peculiar property of matter in relation to the other forms of electricity. We have not yet arrived at the connecting link, but it does not appear to be far distant.

We have already referred to the statement made by talented experimentalists, that magnetism has a

powerful influence in either retarding or accelerating chemical combination. Beyond a doubt chemical action weakens the power of a magnet; but the disturbance which it occasions in soft iron, on the contrary, appears to tend to its receiving magnetism more readily, and retaining it more permanently. Further investigations are, however, required, before we can decide satisfactorily either of these problems, both of which bear very strongly upon the subject we have just been considering.

We have seen that heat and electricity act strangely on magnetic force, and that this statical power reacts upon them: and thus the question naturally arises, Do light and magnetism in any way act upon each other?

Morichini and Carpi on the continent, and Mrs. Somerville in England, have stated that small bars of steel can be rendered magnetic by exposing them to the influence of the violet rays of light. These results have been denied by others, but again repeated and apparently confirmed. In all probability, the rays to which the needles were exposed, being those in which the maximum actinic power is found, produced an actual chemical change; and then, if the position were favourable, it is quite evident that magnetism would be imparted. Indeed we have found this to be the case when the needles, exposed to solar radiations, were placed in the direction of the dip. The supposed magnetization of light by Faraday has already been mentioned. If the influence in one case is determined, it will render the other more probable.[194]

“In seeking for a cause,” writes Sir David Brewster, “which is capable of inducing magnetism on the ferruginous matter of our globe, whether we place it

within the earth, or in its atmosphere, we are limited to the SUN, to which all the magnetic phenomena have a distinct reference; but, whether it acts by its heat, or by its light, or by specific rays, or influences of a magnetic nature, must be left to future inquiry."[195]

We have learnt that magnetism is not limited to ferruginous matter; we know that the ancient doctrine of the universality of the property is true. Kircher, in his strange work on Magnetism, published in the early part of the seventeenth century[196]—a curious exemplification of the most unwearying industry and careful experiment, combined with the influences of the credulity and superstitions of his age—attributes to this power nearly all the cosmical phenomena with which, in his time, men were acquainted. He curiously anticipates the use of the supposed virtue of magnetic traction in the curative art; and as the titles of his concluding chapters sufficiently show, he was a firm believer in animal magnetism.[197] But it is not with any reference to these that we refer to the work of *Athanasii Kircheri, Societatis Jesu, Magnes, sive de Magnetivâ Arte*, but to show that two hundred years since, man was near a great truth; but the time of its development being not yet come, it was allowed to sleep for more than two centuries, and the shadow of night had covered it. In speaking of the vegetable world, and the remarkable processes by which the leaf, the flower, and the fruit are produced, this sage brings forward the fact of the diamagnetic character of the plant, which has been, within the last two years, re-discovered; and he refers the motions of the Sun-flower, the closing of the Convolvulus, and the directions of the spiral, formed by twining plants, to this particular

influence.

This does not appear as a mere speculation, a random guess, but is the result of deductions from experiment and observation. Kircher doubtless leaped over a wide space to come to his conclusion; but the result is valuable in a twofold sense. In the first it shows us that, by neglecting a fact which is suggestive, we probably lose a truth of great general application; and secondly, it proves to us, that by stepping beyond the point to which inductive logic leads, and venturing on the wide sea of hypothesis, we are liable to sacrifice the true to the false, and thus to hinder the progress of human knowledge.

Magnetism, in one or other of its forms, is now proved to be universal, and to its power we are disposed to refer the structural conditions of all material bodies, both organic and inorganic. This view has scarcely yet been recognised by philosophers; but as we find a certain law of polarity prevailing through every atom of created matter, in whatever state it may be presented to our senses, it is evident that every particle must have a polar and directing influence upon the mass, and every coherent mass becomes thus only a larger and more powerful representative of the magnetic unit. Thus we see the speculation of Hansteen, that the sun is, to us, a magnetic centre, and that it is equally influenced by the remoter suns of the universe,[198] is supported by legitimate deductions from experiment.

The great difficulty is not, however, got rid of by this speculation; the cause by which the earth's magnetism is induced is only removed further off.

The idea of a magnetic fluid is scarcely tenable; and

the ferruginous nature of the Aurora borealis receives no proof from any investigation; indeed, we have procured evidence to show that iron is not at all necessary for the production of magnetic phenomena. The leaf of a tree, a flower, fruit, a piece of animal muscle, glass, paper, and a variety of similar substances, have the power of repelling the bar of iron which we call a magnet, and of placing it at right angles to the direction of the force exerted by them. This is a point which must be constantly borne in mind when we now consider the mysteries of magnetic phenomena.

Any two masses of matter act upon each other according to this law, and although by the power of cohesion the force may be brought to an equilibrium, or to its zero point, it is never lost, and may be readily and rapidly manifested by any of the means employed for electrical excitation.

Reasoning by analogy, the question fairly suggests itself: If two systems of inorganic atomic constitution are thus invested with a power of influencing each other through a distance, why may not two more highly developed organic systems equally, or to a greater extent, produce an influence in like manner? Upon such reasoning as this is founded the phenomenon known as Animal Magnetism. There is no denying the fact that one mass of blood, muscle, nerves, and bone, must, magnetically, influence another similar mass. This is, however, something totally different from that abnormal condition which is produced through some peculiar and, as yet, unexplained physiological influences.

With the mysterious operations of vital action, the forces which we have been considering have nothing whatever in common. The powers which are

employed in the arrangements of matter are, notwithstanding their subtile character, of far too gross a nature to influence the psychological mysteries which present themselves to the observant mind. It cannot be denied that, by placing a person of even moderate nervous sensibility in a constrained position, and under an unnatural influence of the mind, as acquired by the disciples of Mesmer, a torpor affecting only certain senses is produced. The recognised and undoubted phenomena are in the highest degree curious—but in these the marvels of charlatanry and ignorance are not included;—and the explanation must be sought for by the physiologist among those hidden principles upon which depends all human sensation.[199]

Man, like a magician, stands upon a promontory, and surveying the great ocean of the physical forces which involve the material creation, and produce that infinite variety of phenomena which is unceasingly exhibited around him, he extends the wand of intelligence, and bids the “spirits of the vasty deep” obey his evocation.

The phenomena recur—the great processes of creation go on—the external manifestations of omnipotent power proceed—effects are again and again produced; but the current of force passes undulating onwards;—and to the proud bidding of the evocator there is no reply but the echo of his own vain voice, which is lost at last in the vast immensity of the unknown which lies beyond him.

We see how powerfully the physical forces, in their various modes of action, stir and animate this planetary mass; and amongst these the influence of magnetism appears as a great directing agent, though its origin is unknown to us.

That power which, like a potent spirit, guides
The sea-wide wanderers over distant tides,
Inspiring confidence where'er they roam,
By indicating still the pathway home;—
Through nature, quicken'd by the solar beam,
Invests each atom with a force supreme,
Directs the cavern'd crystal in its birth,
And frames the mightiest mountains of the earth;
Each leaf and flower by its strong law restrains,
And binds the monarch Man within its mystic chains.

FOOTNOTES:

[170] *Treatise on Magnetism*, by Sir David Brewster. *Cosmos: a Sketch of a Physical description of the Universe*; by Alexander Von Humboldt.—Otté's Translation.

[171] *Expérience Electro-Magnétique.* par M. Œrsted.—Annales de Chimie, vol. xxii. p. 201. De la Rive, *Recherches sur la Distribution de l'Electricité dyn. dans les Corps*.—Genève, 1825.

[172] *On the Magnetic power of Soft Iron*: by Mr. Watkins.—Philosophical Transactions, 1833.

[173] Cavallo, *On Magnetism*.—Cavallo was the first who noticed the influence of heat on Magnetism. Consult *On the anomalous Magnetic Action of Hot Iron between the white and blood-red heat*: by Peter Barlow, Esq.—Philosophical Transactions, 1822, p. 124. *Treatise on Magnetism*: by Barlow.—Encyclopædia Metropolitana.

[174] "The foundation of our researches is the assumption that the terrestrial magnetic force is the collective action of all the magnetised

particles of the earth's mass. We represent to ourselves magnetisation as the separation of the magnetic fluids. Admitting the representation, the mode of action of the fluids (repulsion of similar, and attraction of dissimilar, particles inversely as the square of the distance) belongs to the number of established truths. No alteration in the results would be caused by changing this mode of representation for that of Ampère, whereby, instead of magnetic fluids, magnetism is held to consist in constant galvanic currents in the minutest particles of bodies. Nor would it occasion a difference if the terrestrial magnetism were ascribed to a mixed origin, as proceeding partly from the separation of the magnetic fluids in the earth, and partly from galvanic currents, in the same; inasmuch as it is known that for each galvanic current may be substituted such a given distribution of the magnetic fluids in a surface bounded by the current, as would exercise in each point of external space precisely the same magnetic action as would be produced by the galvanic current itself."—*General Theory of Terrestrial Magnetism*, by Professor Carl Friedrich Gauss, of the University of Göttingen.—Scientific Memoirs, vol. ii. p. 188.

[175] Humboldt's *Cosmos*.—Otté's translation.

[176] Hansteen: *Untersuchungen über den Magnetismus der Erde*, Christïana, 1819. Humboldt: *Exposé des Variations Magnétiques*.—Gilbert's Annales. Brewster's Magnetism: Encyclopædia Metropolitana.

[177] Hansteen; as above.

[178] *On the effects of temperature on the intensity of magnetic forces, and on the diurnal variations of the terrestrial magnetic intensity*; by Samuel Hunter Christie, Esq.—Philosophical

Transactions, vol. cxv. 1825.

[179] It has been observed by Mr. Barlow, in England, and some eminent observers in Austria, that an electric current constantly traverses the wires of the electric telegraph wherever there are two earth connections.

[180] *Meteorological Observations and Essays*: by Dr. Dalton. *On the Height of the Aurora Borealis above the surface of the Earth*: by John Dalton, F.R.S.—Philosophical Transactions, vol. cxiv. p. 291.

[181] Arago: Annales de Chimie, vol. xxxix. p. 369. *On the variable Intensity of Terrestrial Magnetism and the Influence of the Aurora Borealis upon it*; by Robert Were Fox.—Philosophical Transactions, 1831, p. 199.

[182] "Brilliant and active coruscations of the Aurora Borealis," says Captain Back, "when seen through a hazy atmosphere, and exhibiting the prismatic colours, almost invariably affected the needle. On the contrary, a very bright Aurora, though attended by motion, and even tinged with a dullish red and a yellow in a clear blue sky, seldom produced any sensible change, beyond, at the most, a tremulous motion. A dense haze or fog, in conjunction with an active Aurora, seemed uniformly favourable to the disturbance of the needle, and a low temperature was favourable to brilliant and active coruscations. On no occasion during two winters was any sound heard to accompany the motions. The Aurora was frequently seen at twilight, and as often to the eastward as to the westward; clouds, also, were often perceived in the day-time, in form and disposition very much resembling the Aurora."—*Narrative of the Arctic Land Expedition.*

[183] Faraday: *On the Diamagnetic character of Flame and Gases*.

[184] "The Aurora Borealis is certainly in some measure a magnetical phenomenon; and if iron were the only substance capable of exhibiting magnetic effects, it would follow that some ferruginous particles must exist in the upper regions of the atmosphere. The light usually attending this magnetical meteor may possibly be derived from electricity, which may be the immediate cause of a change in the distribution of the magnetic fluid, contained in the ferruginous vapours which are imagined to float in the air."—Lecture on Magnetism: Young's *Lectures on Natural Philosophy*, p. 533.

[185] *On the supposed influence of Magnetism and Chemical Action*; by Robert Hunt.—Philosophical Magazine, vol. xxxii. No. 215, 1849.

[186] Those bodies which are attracted by a magnet, as iron is, are called *magnetic bodies*. Those which are, on the contrary, repelled by the same power, are termed *diamagnetic bodies*. On these Dr. Faraday remarks:—"Of the substances which compose the crust of the earth, by far the greater portion belong to the diamagnetic class; and though ferruginous and other magnetic matters, being more energetic in their action, are more striking in their phenomena, we should be hasty in assuming that, therefore, they over rule entirely the effect of the former bodies. As regards the ocean, lakes, rivers, and the atmosphere, they will exert their peculiar effect almost uninfluenced by any magnetic matter in them, and as respects the rocks and mountains, their diamagnetic influence is perhaps greater than might be anticipated. I mentioned that by adjusting water and a salt of iron together, I

obtained a solution inactive in air; that is, by a due association of the forces of a body, from each class, water and a salt of iron, the magnetic force of the latter was entirely counteracted by the diamagnetic force of the former, and the mixture was neither attracted nor repelled: To produce this effect, it required that more than 48·6 grains of crystallised protosulphate of iron should be added to ten cubic inches of water (for these proportions gave a solution which would set equatorially), a quantity so large, that I was greatly astonished on observing the power of the water to overcome it. It is not, therefore, at all unlikely that many of the masses which form the crust of this our globe, may have an excess of diamagnetic power, and act accordingly."—*On new magnetic actions, and on the magnetic condition of all matter*; by Michael Faraday, D.C.L., F.R.S., &c.—Philosophical Transactions, Jan. 1846, vol. cxxxvii. p. 41.

[187] Ibid.

[188] *On the Diamagnetic conditions of Flame and Gases*, by Michael Faraday. F.R.S.; and *On the motions presented by Flame when under Electro-Magnetic Influence*, by Professor Zantedeschi.—Philosophical Magazine, 1847, pp. 401–421.

[189] *On Diamagnetism*; by Professor Plücker, of Bonn.—Philosophical Magazine, July, 1848.

[190] For a detailed account of the experiments of Faraday, Plücker, Becquerel, Tyndale, and Knoblauch, see De La Rive's *Treatise on Electricity in Theory and Practice*.

[191] A few examples taken from Dr. Faraday's paper will show this:—

Nitrogen being acted on was manifestly diamagnetic in relation to common air when

both were of the same temperature. Oxygen appears to be magnetic in common air. Hydrogen proved to be clearly and even strongly diamagnetic. Its diamagnetic state shows, in a striking point of view, that gases, like solids, have peculiar and distinctive degrees of diamagnetic force. Carbonic acid gas is diamagnetic in air. Carbonic oxide was carefully freed from carbonic acid before it was used, and it appears to be more diamagnetic than carbonic acid. Nitrous oxide was moderately, but clearly, diamagnetic in air. Olefiant gas was diamagnetic. The coal gas of London is very well diamagnetic, and gives exceedingly good and distinct results. Sulphurous acid gas is diamagnetic in air. Muriatic acid gas was decidedly diamagnetic in air.—*On the Diamagnetic Conditions of Flame and Gases*: Philosophical Magazine, 1847, p. 409.

[192] For illustration of this I must refer to my own Memoir, *Researches on the Influence of Magnetism and Voltaic Electricity on Crystallization, and other conditions of matter*, in the Memoirs of the Geological Survey of Great Britain, &c., vol. i.

[193] In a work published by Mr. Evan Hopkins, entitled *On the Connexion of Geology with Terrestrial Magnetism*, will be found many valuable practical observations made in this country and the gold and silver districts of America; but the views taken by the author are open to many objections.

[194] See a notice by Faraday of Morichini's Experiments in *Relations of Light to Magnetic Force*—Philosophical Transactions, vol. cxxxvii. p. 15. See also Mr. Christie *On Magnetic Influence in the Solar Rays*—Philosophical Transactions, vol. cvii. p. 219;

vol. cxix. p. 379.

[195] Sir David Brewster *On Magnetism*; republished from the Encyclopædia Britannica.

[196] The whole of the title of Kircher's book will convey some idea of the subjects embraced:—Athanasii Kircheri Societatis Jesu Magnes, sive de Arte Magneticâ; opus tripartitum, quo Universa Magnetis Natura ejusque in omnibus Scientiis et Artibus usus novâ methodo explicatur: ac præterea e viribus et prodigiosis effectibus Magneticarum aliarumque abditarum Naturæ Motionum in Elementis, Lapidibus, Plantis, Animalibus elucescentium: multa hucusque incognita Naturæ Arcana, per Physica, Medica, Chymica, et Mathematica omnis generis Experimenta recluduntur Editio Tertia: ab ipso Authore recognita emendataque, ac multis novorum Experimentorum Problematibus aucta. Romæ, 1654.

[197] The following are the titles of the concluding chapters of Kircher's book:—*De magnetismo solis et lunæ in maria. De magneticâ vi plantarum. De insitionis magneticis miraculis. De magnetismo virgulæ auriferæ seu divinatoriæ. De plantis heliotropiis eorumque magnetismo. De magnetismo rerum medicinalium. De vi attractivâ potentiæ imaginativæ. De magnetismo musicæ. De magnetismo amoris.*

[198] "For these reasons it appears most natural to seek their origin in the sun, the source of all living activity, and our conjecture gains probability from the preceding remarks on the daily oscillations of the needle. Upon this principle the sun may be conceived as possessing one or more magnetic axes, which, by distributing the force, occasion a magnetic difference in the earth, in the moon, and all those planets whose internal structure admits

of such a difference. Yet, allowing all this, the main difficulty seems not to be overcome, but merely removed from the eyes to a greater distance; for the question may still be asked, with equal justice, whence did the sun acquire its magnetic force? And if from the sun we have recourse to a central sun, and from that again to a general magnetic direction throughout the universe, having the Milky Way for its equator, we but lengthen an unrestricted chain, every link of which hangs on the preceding link, no one of them on a point of support. All things considered, the following mode of representing the subject appears to me most plausible. If a single globe were left to move alone freely in the immensity of space, the opposite forces existing in its material structure would soon arrive at an equilibrium conformable to their nature, if they were not so at first, and all activity would soon come to an end. But if we imagine another globe to be introduced, a mutual relation will arise between the two; and one of its results will be a reciprocal tendency to unite, which is designated and sometimes thought to be explained by the merely descriptive word Attraction. Now would this tendency be the only consequence of this relation? Is it not more likely that the fundamental forces, being drawn from their state of indifference or rest, would exhibit their energy in all possible directions, giving rise to all kinds of contrary action? The electric force is excited, not by friction alone, but also by contact, and probably also, though in smaller degrees, by the mutual action of two bodies at a distance; for contact is nothing but the smallest possible distance, and that, moreover, only for a few small particles. Is it not conceivable that magnetic force may

likewise originate in a similar manner? When the natural philosopher and the mathematician pay regard to no other effect of the reciprocal relation between two bodies at a distance, except the tendency to unite, they proceed logically, if their investigations require nothing more than a moving power; but should it be maintained that no other energy can be developed between two such bodies, the assertion will need proof and the proof will be hard to find."—The above is a translation from Hansteen's work *On Magnetism*.

[199] See article *Animal Magnetism*, Encyclopædia Britannica, and Mr. Braid's papers *On Hypnotism*, published in the "Medical Times."

CHAPTER XI.

CHEMICAL FORCES.

Nature's Chemistry—Changes produced by Chemical Combination—Atomic Constitution of Bodies—Laws of Combination—Combining Equivalents—Elective Affinity—Chemical Decomposition—Compound Character of Chemical Phenomena—Catalysis or action of Presence—Transformation of Organic Bodies—Organic Chemistry—Constancy of Combining Proportions—The Law of Volumes, the Law of Substitutions, Isomeric States, &c.

All things on the earth are the result of chemical combination. The operations by which the commingling of molecules and the interchange of atoms take place, we can imitate in our laboratories; but in nature they proceed by slow degrees, and, in general, in our hands they are distinguished by suddenness of action. In nature chemical power is distributed over a long period of time, and the process of change is scarcely to be observed. By art we concentrate chemical force, and expend it in

producing a change which occupies but a few hours at most. Many of the more striking phenomena of nature are still mysterious to us, and principally because we do not, or cannot, take the element time into calculation. The geologist is compelled to do this to explain the progress of the formation of the crust of the earth, but the chemist rarely regards the effects of time in any of his operations. The chemical change which within the fissure of the rock is slowly and silently at work, displacing one element or molecule, and replacing it by another, is in all probability the operation of a truly geological period. Many, however, of the changes which are constantly going on around us, are of a much more rapid character, and in these nature is no slower in manipulating than the chemist.

Had it been that the elements which are now found in combination could exist in a free state, the most disastrous consequences would necessarily ensue. There must have been a period when many of the combinations known to us were not yet created. Their elements either existed in other forms, or were uncombined. Our rocks are compounds of oxygen with certain peculiar metals which unite with oxygen so rapidly that incandescence is produced by their combination. Let us suppose that any of these metals existed in purity, and that they were suddenly brought into contact with water, the atmospheric air, or any body containing oxygen, the result would be a convulsion of the most fearful kind; the entire mass of metal would glow with intensity of heat, and the impetuosity of the action would only be subdued when the whole of the metal had become oxidized. Volcanic action has been referred to some such cause as this, but there is not sufficient evidence to support the hypothesis; indeed, it is contrary to the opinion

of most philosophers.[200] Such a condition may possibly have existed at one time, during that period when darkness was upon the face of the deep, when the earth was a chaos; but it is only adduced here as an example of the violent nature of some chemical changes. Potassium thrown on water bursts into flame, and sodium does so under certain conditions. If these, or the metals proper in a state of fine division, are brought into an atmosphere of chlorine, the intensity of chemical action is so great that they become incandescent, many of them glowing with extreme brilliancy. If hydrogen gas is mixed with this element (chlorine) they unite, under the influence of light, with explosive violence, giving rise to a compound, muriatic acid, which combines with water in an almost equally energetic manner. Nitrogen, as it exists in the atmosphere, mixed with oxygen, appears nearly inert; with hydrogen it forms the pungent compound, ammonia; with carbon, the poisonous one, cyanogen, the base of prussic acid; with chlorine it gives rise to a fluid, oily in its appearance, but which, when merely touched by an unctuous body, explodes more violently than any other known compound, shivering whatever vessel it may be contained in, to atoms; with iodine it is only slightly less violent; and in certain combinations with silver, mercury, gold, or platinum, it produces fulminating compounds of the most dangerous character.[201] Here we have elements harmless when uncombined, exhibiting the most destructive effects if their combinations are at all disturbed; and in the other case we have inert masses produced from active and injurious agents.

We regard a certain number of substances as *elementary*; that is to say, not being able, in the present state of our knowledge, to reduce them to

any more simple condition, they are considered as the elements which by combination produce the variety of substances found in the three kingdoms of nature.

We have already spoken of the atomic constitution of bodies. It remains now to explain the simplicity and beauty which mark every variety of combination under chemical force. As a prominent and striking example, water is a compound of two gaseous bodies, oxygen and hydrogen:—

If we decompose water by means of galvanic electricity, or determine its composition by direct chemical analysis, we shall find it consists of two volumes of hydrogen gas, united to one volume of oxygen, or, by weight, of one part of hydrogen combined with eight of oxygen. In 100 parts, therefore, we should find—

Oxygen	88·9
Hydrogen	11·0

It is found in the same way that the theoretical weight of the atom of carbon is 6, and that of nitrogen 14; whilst the atom of iron is 28, that of silver 108, of gold 199, and that of platinum and iridium each 98.[202] Now, as these are the relative weights of the ultimate indivisible atom, it follows that all combinations must be either atom to atom, or one to two, three, or four; but that in no case should combination take place in any other than a multiple proportion of the equivalent or atomic number. This is found to be the case. Oxygen, for instance, combines as one, two, or three atoms; its combination presenting some multiple of its equivalent number 8, as 16, or 24: and in like manner the combining quantity of carbon is 6, or

some multiple of that number. Where this law is not found strictly to agree with analytical results, of which some examples are afforded by the sesquioxides, it may be attributed, without doubt, to some error of analysis or in the method of calculation.

Nothing can be more perfect than the manner in which nature regulates the order of combination. We have no uncertain arrangement; but, however great the number of the atoms of one element may be, over those of another, those only combine which are required, according to this great natural law, to form the compound, all the others still remaining free and uncombined. These results certainly appear to prove that the elementary particles of matter are not of the same specific gravities. Do they not also indicate that any alteration in the specific gravity of the atom would give rise to a new series of compounds, thus apparently producing a new element? Surely there is nothing irrational in the idea that the influences of heat or electricity, or of other powers of which as yet we know nothing, may be sufficient to effect such changes in the atomic constituents of this earth.

The combination of elementary atoms takes place under the influence of an unknown force which we are compelled to express by a figurative term, *affinity*. In some cases it would appear that the disposition of two bodies to unite, is determined by the electrical condition; but a closer examination of the question than it is possible to enter into in this place, clearly shows that some physical state, not electrical, influences combining power.

Chemical affinity or attraction is the peculiar disposition which one body has to unite with another. To give some instances in illustration. Water

and spirit combine most readily: they have a strong affinity for each other. Water and oil repel each other: they have no affinity; they will not enter into combination. If carbonate of potash is added to the spirit and water in sufficient quantity, the water is entirely separated, and the pure spirit will float over the hydrated potash. If potash is added to the oil and water, it combines with the oil, and, forming soap, they all unite together; but, if we now add a little acid to the mixture, the potash will quit the oil to combine with the acid, and the oil will be repelled as before and float on the liquid. This has been called single elective affinity. These elections were regarded as constant, and chemists drew up tables for the purpose of showing the order in which these decompositions occur.[203] Thus, ammonia, it was shown, would separate sulphuric acid from magnesia, lime remove it from ammonia, potash or soda from lime, and barytes from potash or soda. It was thought the inverse of this order would not take place, but recent researches have shown that the results are modified by quantity and some other conditions.

It often happens that we have a compound action of this kind in which double election is indicated. Sulphate of lime and carbonate of ammonia in solution are brought together, and there result a carbonate of lime and a sulphate of ammonia. Now, in such cases nothing more than single elective attraction most probably occurs, and the carbonic acid is seized by the lime, by the great affinity of that earth for carbonic acid, only after it has been set free from the ammonia, and then, by the force of cohesion acting with the combining powers, the insoluble salt is precipitated.[204] There is a curious fact in connection with this decomposition. If

carbonate of lime and sulphate of ammonia are mixed together dry, and exposed, in a closed vessel, to a red heat, sulphate of lime and carbonate of ammonia are formed. These opposite effects are not very easily explained. The action of heat is to set free the carbonic acid; and it can only be by supposing that considerable differences of temperature reverse the laws of affinity, that we can at all understand this phenomenon. That different effects result at high temperatures from those which prevail at low ones, recent experiments prove to us, particularly those of Boutigny, already quoted when considering decomposition by calorific action.

Under the term chemical affinity, which we regard as a power acting at insensible distances, and producing a change in bodies, we are content to allow ourselves to believe that we have explained the great operations of nature. We find that the vegetable and animal kingdoms are composed of carbon, hydrogen, oxygen, and nitrogen. The granite mountains of the earth, and its limestone hills, and all its other geological formations, are found to be metals and oxygen, and carbon and sulphur, disposed to settle in harmonious union in their proper places by chemical affinity. But what really is the power which combines atom to atom, and unites molecule to molecule? Can we refer the process to heat? The influence of caloric, although by changing the form of bodies it sometimes assists combination, is to be regarded rather as in antagonism to the power of cohesion. Can it be thought that electricity is active in producing the result? During every change of state, those phenomena which we term electrical are manifested; but we thereby only prove the general diffusion of the electric principle, and by no means show that electricity is the cause of the chemical

change. Can light determine these changes? It is evident, although light may be a disturbing power, that it cannot be the effective one; for many of these decompositions and recompositions are constantly going on within the dark and silent depths of the earth, to which a sunbeam cannot reach. That the excitation on the surface of the earth, produced by solar influence, may modify those changes, is probable. It is, however, certain that we must regard all manifestations of chemical force as dependent upon some secret principles common to all matter, diffused throughout the universe, but modified by the influences of the known imponderable elements, and by the mechanical force of aggregative attraction.

Bodies undergo remarkable changes of form, and present very different characters, by reactions, which are of several kinds. We suppose that a permanent corpuscular arrangement is maintained so long as the equilibrium of the molecular forces is undisturbed. Water, for instance, remains unchanged so long as the balance of affinity is kept up between the oxygen and hydrogen of which it is composed, or so long as the oscillations of force between these combining elements are equal; but disturb this force, or set up a new vibratory action, as by passing an electric current through the water, or by presenting another body, which has the power of reacting upon one of these corpuscular systems, and the water is decomposed, the hydrogen and oxygen gases being set free, or one alone is liberated, and the other combined with the molecules of the agent employed, and a new compound produced. This is chemistry, by which science we discover all the combinations of matter.

Having reason to conclude that atom combines with atom, according to a system most harmoniously arranged, there can be no difficulty in conceiving that molecule unites with molecule, in a manner regulated by some equally well-marked law. It was, indeed, a discovery by Wenzel, of Fribourg, that, in salts which decompose each other, the acid which saturates one base will also saturate the other base; and the subsequent observations of Richter, of Berlin, who attached proportional numbers to the acids and bases, and who remarked that the neutrality of metallic salts does not change during the precipitation of metals by each other, which led the way to the atomic theory of Dr. Dalton, to whom entirely belongs the observation, that the equivalent of a compound body is the sum of the equivalents of its constituents, and the discovery of combination in multiple proportions.

The elements of a molecule can take a new arrangement amongst themselves, without any alteration in the number of the atoms or of their weight, and thus give rise to a body of a different form and colour, although possessing the same chemical constitution. This is the case with many of the organic compounds of carbon and hydrogen.

The elements of a compound may be disassociated, and thus the dissimilar substances of which it is composed set free. A piece of chalk exposed to heat is, by the disturbance of its molecular arrangement, changed in its nature; a gaseous body, carbonic acid, is liberated, and quick-lime (oxide of calcium) is left behind. If this carbonic acid is passed through red-hot metal tubes, or brought in contact with heated potassium, it is resolved into oxygen and charcoal—the oxygen combining with the metal employed. The

oxide of calcium (lime), if subjected to the action of a powerful galvanic current, is converted into oxygen and a metal, calcium. Thus we learn that chalk is a body consisting of two compound molecules,—carbonic acid, which is formed by the combination of an atom of carbon with two atoms of oxygen,—and lime, which results from the union of an atom of calcium with one of oxygen.

The condition requisite to the production of chemical action between bodies is that they should be dissimilar. Two elementary atoms are placed within the spheres of each other's influences, and a compound molecule results. Oxygen and hydrogen form water; oxygen and carbon give rise to carbonic acid; nitrogen and hydrogen unite to form ammonia; and chlorine and hydrogen to produce hydrochloric acid. In all these cases an external force is required to bring the atoms within the range of mutual affinity: flame,—the electrical spark,—actinism,—or the interposition of a third body, is necessary in each case. There are other examples in which no such influence is required. Potassium and oxygen instantly unite: chlorine, iodine, and bromine immediately, and with much violence, combine with the metals to form chlorides, iodides, or bromides.

With compound molecules the action is in many cases equally active, and combination is readily effected, as in the cases of the acids and the oxides of some metals, which are all instances of the most common chemical attraction.

An elementary or simple molecule and molecules of a compound and different constitution are brought together, and a new compound results from an interchange of their atoms, whilst an element is liberated. These are essentially illustrations of

analytical chemistry. Sulphuretted hydrogen is mixed with chlorine; the chlorine combines with the hydrogen, and sulphur is set free. Potassium is put into water, and it combines with the oxygen of the water, whilst the hydrogen is liberated.

Two compound molecules being brought together may decompose each other, and form two new compounds by an interchange of their elements.

One element may be substituted for another under certain circumstances. Gold may be replaced by mercury; copper will take the place of silver; and iron will occasion the separation of copper from its solutions, the iron itself being dissolved to supply its place; chlorine will substitute hydrogen in the carburetted hydrogen gases; and many other examples might be adduced.

Chemical phenomena very frequently become of a complex character; and one, two, or three of these cases may be occurring at the same time in the decomposition of one compound by another. Such are the general features of chemical science. Many peculiarities and remarkable phenomena connected with chemical investigations will be named, as the examination of the elementary composition of matter is proceeded with; but, although the philosophy of chemical action is of the highest interest, it must not be allowed to detain us with its details, which are, indeed, more in accordance with a treatise on the science than one which professes to do no more than sketch out those prevailing and striking features which, whilst they elucidate the great truths of nature, are capable of being employed as suggestive examples of the tendency of scientific investigation to enlarge the boundaries of thought, and give a greater elevation to the mind, leading us from the

merely mechanical process of analysis up to the great synthetical operations, by which all that is found upon the earth for its ornament, or our necessities, is created.

Among the most remarkable phenomena within the range of physical chemistry are those of *Catalysis*, or, as it has also been called, the "*Action of presence*."[205] There are a certain number of bodies known to possess the power of resolving compounds into new forms, without undergoing any change themselves. Kirchoff discovered that the presence of an acid, at a certain temperature, converted starch into sugar and gum, no combination with the acid taking place. Thenard found that manganese, platinum, gold, and silver, and, indeed, almost any solid organic body, had the power of decomposing the binoxide of hydrogen by their presence merely, no action being detected on these bodies. Edmund Davy found that powdered platinum, moistened with alcohol, became red-hot, fired the spirit, and converted it into vinegar, without undergoing, itself, any chemical change. Döbereiner next discovered that spongy platinum fired a current of hydrogen gas directed upon it, which, by combining with the oxygen of the air, formed water. Dulong and Thenard traced the same property, differing only in degree, through iridium, osmium, palladium, gold, silver, and even glass. Further investigation has extended the number of instances; and it has even been found that a polished plate of platinum has the power of condensing hydrogen and oxygen so forcibly upon its surface, that these gases are drawn into combination and form water, with a development of heat sufficient to ignite the metal.

This power, whatever it may be, is common in both

organic and inorganic nature, and on its important purposes Berzelius has the following remarks:—

"This power gives rise to numerous applications in organic nature; thus, it is only around the eyes of the potato that diastase exists: it is by means of catalytic power that diastase, and that starch, which are insoluble, are converted into sugar and into gum, which, being soluble, form the sap that rises in the germs of the potato. This evident example of the action of catalytic power in an organic secretion, is not, probably, the only one in the animal and vegetable kingdom, and it may hereafter be discovered that it is by an action analogous to that of catalytic power, that the secretion of such different bodies is produced, all which are supplied by the same matter, the sap in plants, and the blood in animals."[206]

It is, without doubt, to this peculiar agency that we must attribute the abnormal actions produced in the blood of living animals by the addition of any gaseous miasma or putrid matter, of which we have, in all probability, a fearful example in the progress of Asiatic cholera; therefore the study of its phenomena becomes an important part of public hygiène.

Physical research has proved to us that all bodies have peculiar powers, by which they condense with varying degrees of force gases and vapours upon their surfaces; every body in nature may, indeed, be regarded as forming its own peculiar atmosphere. To this power, in all probability, does catalysis belong. Different views have, however, prevailed on this subject, and Dr. Lyon Playfair[207] argues that the catalytic force is merely a modified form of chemical affinity, exerted under peculiar conditions.

Whatever may be the power producing chemical

change, it acts in conformity with some fixed laws, and in all its transmutations, an obedience to a most harmonious system is apparent.

It is curious to observe the remarkable character of many of these natural transmutations of matter, but we must content ourselves with a few examples only. For instance:—

Sugar, oxalic acid, and citric acid are very unlike each other, yet they are composed of the same elements; the first is used as a general condiment, the second is a destructive poison, and the third a grateful and healthful acid: sugar is readily converted into oxalic acid, and in the process of ripening fruits nature herself converts citric acid into sugar. Again, starch, sugar, and gum would scarcely be regarded as alike, yet their only difference is in the mode in which carbon, hydrogen, and oxygen combine. They are composed of the same principles, in the following proportions:—

	Carbon.	**Hydrogen.**	**Oxygen.**
Starch	12	10	10
Sugar	12	11	11
Gum	12	11	11

These *isomeric* groups certainly indicate some law of affinity which science has not yet discovered. Similar and even more remarkable instances might be adduced of the same elements producing compounds very unlike each other; but the above have been selected from their well-known characters. Indeed, we may state with truth that all the varieties of the vegetable world—their woody fibre—their acid or alkaline juices—the various exudations of plants—their flowers, fruit, and seeds, and the numerous

products which, by art, they are made to yield for the uses of man, are, all of them, compounds of these three elements, differing only in the proportions in which they are combined with nitrogen, or in some peculiar change of state in one or other of the elementary principles. The chemist is now enabled by simple processes, from the refuse of manufactories to produce fruit essences which are equal in flavour to the natural production; and from benzoic acid, which is obtained in great abundance from the houses in which cows are kept, the most delicate essences are produced, which are given to the world as the distillations of a thousand flowers. By the impulse given to organic chemistry by Liebig, our knowledge of the almost infinite variety of substances, in physical character exceedingly dissimilar, which result from the combination of oxygen, hydrogen, and carbon, in varying proportions, has been largely increased. And the science is now in that state which almost causes a regret that any new organic compounds should be discovered, until some industrious mind has undertaken the task of reducing to a good general classification the immense mass of valuable matter which has been accumulated, but which, for all practical purposes, remains nearly useless and unintelligible.

These combinations, almost infinitely varied as they are, and so readily produced and multiplied as to be nearly at the will of the organic analyst, are not, any of them, accidental: they are the result of certain laws, and atom has united with atom in direct obedience to principles which have been through all time in active operation. They are unknown; the researches of science have not yet developed them, and the philosopher has not yet made his deductions.

They are to be referred to some secret fixed principles of action, to a force which has impressed upon every atom of the universe its distinguishing character. Chemistry makes us familiar with a system of order. The researches of analysts have proved that every body has a particular law of combination, to which it is bound by a mathematical precision; but it is not proportional combination alone we have to consider. If *allotrophy* is evidenced in the mineral world, it is certainly far more strikingly manifested in the vegetable and animal kingdoms.

There are some cases in which bodies appear to combine without any limitation, as spirit of wine and water, sulphuric acid and water; but these must be considered as conditions of mixture rather than of chemical combination.

The composition of bodies is fixed and invariable, and a compound substance, so long as it retains its characteristic properties, must consist of the same elements united in the same proportions. Thus, sulphuric acid is invariably composed of 16 parts of sulphur and 24 parts of oxygen. Chalk, whether formed by nature or by the chemist, yields 43·71 parts of carbonic acid, and 56·29 parts of lime. The rust which forms upon the surface of iron by the action of the atmosphere, is as invariable in its composition as if it had been formed by the most delicate adjustment of weight by the most accurate manipulator, being 28 parts of iron and 12 parts of oxygen. This law is the basis of all chemical inquiry, all analytical investigations depending upon the knowledge it affords us, that we can only produce certain undeviating compounds as the results of our decompositions. We are not in a position to offer any explanation which will account for these constant

quantities in combination. The forces of cohesion and elasticity have been advanced in explanation, on the strength of the fact that the solubility of a salt in water is regulated by cohesion, and that of a gas by its elasticity. Although it may appear that some cases of chemical combination are due to these powers,—as, for instance, when the union of oxalic acid or sulphuric acid with lime produces an insoluble salt,—we cannot thus explain the constant proportions in which the metals, sulphur, oxygen, and similar bodies, unite. It is quite certain there is a power or principle, which we have not yet reached, upon which are dependent all the phenomena which we now embrace under the term chemical affinity.

Another law teaches us that when compound bodies combine in more than one proportion, every additional union represents a multiple of the combining proportion of the first. With the difficulty which arises from the sub-multiple compounds we cannot deal:—further research may render their laws less obscure. We have seen that 8 parts of oxygen unite with 1 of hydrogen and 14 of nitrogen. It also unites with 110 of silver, 96 of platinum, 40 of potassium, 36 of chlorine, and 200 parts of mercury, giving rise to—

Water	9
Nitrous oxide	22
Oxide of silver	118
Oxide of platinum	104
Potash	48
Oxide of chlorine	44
Oxide of mercury	208

In these proportions, or in multiples of them, and in

no others, will these bodies unite with the acids or other compounds. It will, of course, be understood that any other numbers may be adopted, provided they stand in the same relation to each other.[208]

From the discovery of these harmonious arrangements was deduced the beautiful atomic theory to which allusion has been already made. Indeed, there does not appear to be any other way of explaining these phenomena than by the hypothesis that the ultimate atoms of bodies have *relatively* the weights which we arbitrarily assign to them, as their combining quantities. These views are further confirmed by the fact, that gaseous bodies unite together by volume in very simple definite proportions:—100 measures of hydrogen and 200 measures of oxygen form water; 100 measures of oxygen and 100 measures of vapour of sulphur form sulphurous acid gas. Ammoniacal gas consists of 300 volumes of hydrogen and 100 volumes of nitrogen, condensed by combination into 200 volumes; consequently, we are enabled most readily to calculate the specific gravity of ammoniacal gas. The specific gravity of nitrogen is 0·9722, that of hydrogen 0·0694. Now, three volumes of hydrogen are equal to 0·2082: this added to 0·9722 is equal to 1·1804, which is exactly the specific gravity obtained by experiment.

There is no doubt, from the generality with which this law of volumes prevails, that it would be found to extend through all substances, provided they could be rendered gaseous; in other words, there is abundant proof to convince us that throughout nature the process of combination, in the most simple ratio of volumes, is in operation to produce all the forms of matter known to us.

It has been shown, by the investigations of Dr. Dalton, in 1840, that salts, containing water of crystallization, dissolve in water without increasing the bulk of the fluid more than is due to the liquefaction of the water which these salts contain; while Joule and Playfair have shown that the anhydrous salts take up no space in solution. From this we are naturally led to conclude that the volume occupied by a salt in the solid state has a certain relation to the volume of the same salt when in solution, and has also a fixed relation to the volume occupied by any other salt. The law appears to be:—the atomic volume of any salt whatever (anhydrous or hydrated) is a multiple of 11, or of a number near 11, or a multiple of 9·8 (the atomic volume of ice), or the sum of a multiple of 11 or 9·8. Marignac, who has also paid much attention to the subject, does not think these numbers absolutely correct, but approximately so.[209] It would be a beautiful exemplification of the simplicity of Nature's operations, if it should be clearly proved that the atomic volume of solid water (ice) regulated the combining proportions by volume of all other bodies,—that it was the standard by which chemical combination and ordinary solution were determined.

In addition to the laws already indicated, there appear to be some others of which, as yet, we have a less satisfactory knowledge, and, as a remarkable case, we may adduce the phenomena of *substitution*, or that power which an elementary body, under certain conditions, possesses, of turning out one of the elements of a compound, and of taking its place.[210] Thus, the hydrogen of a compound radical, as carburetted hydrogen, may be replaced by chlorine, equivalent for equivalent, and form a chloride of carbon, which being constructed on the same type as

the original, will have the same general laws of combination.

Under the influence of these laws, all the combinations which we discover in nature take place. The metals, and oxygen, and sulphur, and phosphorus unite. The elements of the organic type, entering into the closest relations, give rise to every form of vegetable life. The acids, the gums, the resins, and the sugar which plants produce; and those yet more complicated animal substances, bone, muscle, blood, and bile; albumen, casein, milk, with those compounds which, under the influence of vital power, resolve themselves into substances which are essential to the existence, health, and beauty of the animal fabric, are all dependent on these laws. But these metamorphoses must be further considered in our examination of the more striking cases of chemical action. The changes which result from organic combination are so remarkable, and withal they show how completely the whole of the material world is in subjection to chemical force, and every variety of form the result of mysterious combination, that some particular reference to these metamorphoses is demanded.

In nearly all cases of decided chemical action, all trace of the characters of the combining bodies disappear. We say decided chemical action, because, although sulphuric acid and water combine, and salts dissolve in water, we may always recognize their presence, and therefore these and similar cases cannot be regarded as strict examples of the phenomena under consideration.

Hydrogen and oxygen, in combining, lose their gaseous forms, and are condensed into a liquid—water. Sulphuric acid is intensely sour and corrosive;

potash is highly caustic; but united they form a salt which is neither: they appear to have destroyed the distinguishing characters of each other. Combined bodies frequently occupy less space than they did previously to combination, of which numerous particular instances might be adduced. Gases in many cases undergo a remarkable condensation when chemically combined. In slaking lime, the water becomes solid in the molecules of the hydrate of lime formed, and the intense heat produced arises from the liberation of that caloric which had been employed to keep the water liquid. When a solid passes into the liquid state, cold is produced by the abstraction from surrounding objects of the heat required to effect fluidity. An alteration of temperature occurs whenever chemical change takes place, as we have already shown, with a few trivial and uncertain exceptions. The disturbance caused by the exercise of the force of affinity frequently leads to the development of several physical powers.

Changes of colour commonly arise; indeed, there does not appear to be any relation between the colour of a compound and that of its elements. Iodine is of a deep iron-grey colour; its vapour is violet; yet it forms beautifully white salts with the alkalies, a splendid red salt with mercury, and a yellow one with lead. The salts of iron vary from white and yellow to green and dark brown. Those of copper, a red metal, are of a beautiful blue and green colour, and the anhydrous sulphate is white.

Isomorphism, which appears in a very remarkable manner among the organic compounds, has, under the head of crystallization, already had our attention. There is also a class of bodies which are said to be *isomeric*; that is, to have the same composition,

although different in their physical characters. But the idea that bodies exist, which, although of a decidedly different external character, are of exactly the same chemical composition and physical condition, is not tenable; and in nearly all the examples which have been carefully examined, a difference in the aggregate number of atoms, or in the mode in which those atoms have respectively arranged themselves, or that peculiar physical difference designated by the term *allotropy*, has been detected.

Oil of turpentine and oil of lemons have the same composition, each being composed of five equivalents of carbon and four of hydrogen. These substances form, from the striking difference perceptible in their external characters, a good example of isomerism.

The laws of organic chemistry are not, however, the same as those applying to inorganic combinations. Organic chemistry is well defined by Liebig, as the chemistry of compound radicals; and under the influence of vitality, nature produces compounds which have all the properties of simple elements. [211]

When we reflect upon the conditions which prevail throughout nature, with a few of which only has science made us acquainted, we cannot fail to be struck with the various phases of being which are presented to our observation, and the harmonious system upon which they all appear to depend.

When we discover that bodies are formed of certain determinate atoms, which unite one with another, according to an arithmetical system, to form molecules, which, combining with molecules, observe a similar law, we see at once that all the

harmonies of chemical combination—the definite proportions, laws of volume, and the like—are but the necessary consequences of these simple and guiding first principles. In the pursuit of truth, investigators must discover still further arrangements, which, from their perfection, may be compared to the melodious interblending of sweet sounds, and many of the apparently indeterminate combinations will, beyond a doubt, be shown to be as definite as any others. But we cannot reflect upon the fact that these atoms and these molecules are guided in their combinations by impulses, which we can only explain by reference to human passions, as the term *elective affinity* implies, without feeling that an impenetrable mystery of a grand and startling character in its manifestations surrounds each grain of dust which is hurried along upon the wind.

We now, habitually, speak of attraction and repulsion—of the affinity and non-affinity of bodies. We are disposed, from the discovery of the attractive and repelling poles of electrified substances, to regard these powers in all cases as depending upon some electrical state, and we write learnedly upon the laws of these forces. After all, it would be more honest to admit, that we know no more of the secret impulses which regulate the combinations of matter, than did those who satisfied themselves by referring all phenomena of these kinds to sympathies and antipathies: terms which have a poetic meaning, conveying to the mind, with considerable distinctness, the fact, and giving the idea of a feeling —a passion—involving and directing inanimate matter, similar to that which stirs the human heart, and certainly calculated to convey the impression that there is working within all things a living principle, and pointing, indeed, to “the soul of the

world." The animated marble of ancient story is far less wonderful than the fact, proved by investigation, that every atom of matter is penetrated by a principle which directs its movements and orders its positions, and involved by an influence which extends, without limits, to all other atoms, and which determines their union, or otherwise.

We have gravitation, drawing all matter to a common centre, and acting from all bodies throughout the wide regions of unmeasured space upon all. We have cohesion, holding the particles of matter enchained, operating only at distances too minute for the mathematician to measure; and we have chemical attraction, different from either of these, working no less mysteriously within absolutely insensible distances, and, by the exercise of its occult power, giving determinate and fixed forms to every kind of material creation.

The spiritual beings, which the poet of untutored nature gave to the forest, to the valley, and to the mountain, to the lake, to the river, and to the ocean, working within their secret offices, and moulding for man the beautiful or the sublime, are but the weak creations of a finite mind, although they have for us a charm which all men unconsciously obey, even when they refuse to confess it. They are like the result of the labours of the statuary, who, in his high dreams of love and sublimated beauty, creates from the marble block a figure of the most exquisite moulding which mimics life. It charms us for a season; we gaze and gaze again, and its first charms vanish; it is ever and ever still the same dead heap of chiselled stone. It has not the power of presenting to our wearying eyes the change which life alone enables matter to give; and we admit the excellence

of the artist, but we cease to feel at his work. The creations of poetry are pleasing, but they never affect the mind in the way in which the poetic realities of nature do. The sylph moistening a lily is a sweet dream; but the thoughts which rise when first we learn that its broad and beautiful dark-green leaves, and its pure and delicate flower, are the results of the alchemy which changes gross particles of matter into symmetric forms,—of a power which is unceasingly at work under the guidance of light, heat, and electrical force,—are, after our incredulity has passed away—for it is too wonderful for the untutored to believe at once—of an exalting character.

The flower has grown under the impulse of principles which have traversed to it on the solar beam, and mingled with its substance. A stone is merely a stone to most men. But within the interstices of the stone, and involving it like an atmosphere, are great and mighty influences, powers which are fearful in their grander operations, and wonderful in their gentler developments. The stone and the flower hold, locked up in their recesses, the three great known forces—light, heat, and electricity: and, in all probability, others of a more exalted nature still, to which these powers are but subordinate agents. Such are the facts of science, which, indeed, are the true “sermons in stones,” and the most musical of “tongues in trees.” How weak are the creations of romance, when viewed beside the discoveries of science! One affords matter for meditation, and gives rise to thoughts of a most ennobling character; the other excites for a moment, and leaves the mind vacant or diseased. The former, like the atmosphere, furnishes a constant supply of the most healthful matter; the latter gives an

unnatural stimulus, which compels a renewal of the same kind of excitement, to maintain the continuation of its pleasurable sensations.

FOOTNOTES:

[200] All the phenomena connected with volcanic action, and the theories connected therewith, will be found in Dr. Daubeny's work, *A description of active and extinct Volcanoes, of Earthquakes, and of Thermal Springs*. 1848.

[201] Graham's *Elements of Chemistry*. New Edition.

[202] Graham's *Elements of Chemistry*; and Brande's *Manual*.

[203] Of these *tables of attraction* the following may be taken as a specimen:—

SULPHURIC ACID.
Baryta.
Strontia.
Potassa.
Soda.
Lime.
Magnesia.
Ammonia.

It thus appears that baryta separates sulphuric acid from its compounds with all inferior substances, and that ammonia is separated from the acid by all that are above it.

[204] Berthollet: *Essai de Statique Chimique*, 1803. Sir Humphry Davy, in his *Elements of Chemical Philosophy*, has given an excellent review of the views of Berthollet.

[205] *On certain combinations of a new acid, formed of Azote, Sulphur, and Oxygen*; by J. Pelouze. Translated from Annales de Chimie, vol. xvi., for Scientific Memoirs, vol. i. p. 470. *Some ideas of a new force acting in the combinations of Organic Compounds*, by Berzelius: Annales de Chimie, vol. lxi. The conclusion come to by this eminent chemist is expressed in the following translation:—"This new power, hitherto unknown, is common both in organic and inorganic nature. I do not believe that it is a power which is entirely independent of the electro-chemical affinities of the substance. I believe, on the contrary, that it is merely a new form of it; but so long as we do not see their connection and mutual dependence, it will be more convenient to describe it by a separate name. I shall, therefore, call it *catalytic power*: I shall also call *catalysis*, the decomposition of bodies by this force—in the same way as the decomposition of bodies by chemical affinity is termed analysis."

[206] Berzelius: *Annales de Chimie*, vol. lxi.

[207] *On Transformations produced by Catalytic Bodies*: by Lyon Playfair, Esq.; Phil. Mag., vol. xxxi. p. 191, 1847.—"Facts have been brought forward to show that there is at least as much probability in the view that the catalytic force is merely a modified form of chemical affinity exerted under peculiar conditions, as there is in ascribing it to an unknown power, or to the communication of an intestine motion to the atoms of a complex molecule. Numerous cases have been cited, in which the action results when the assisting or catalytic body is not in a state of change; and attempts have been made to prove, by new experiments, that the catalytic power exercises its peculiar power by

acting in the same direction as the body decomposing, or entering into union, but under conditions in which its own affinity cannot always be gratified."

[208] Consult Graham's Chemistry, *On Combining Proportions*.

[209] *Memoir on Atomic Volume and Specific Gravity*. Messrs. Lyon Playfair and Joule.—Philosophical Magazine, vol. xxvii. p. 453, or Transactions of Chemical Society of London. *Observations* on the above, by Professor de Marignac.—Bibliothèque Universelle, Feb. 1846. *On the Relation of the Volumes of bodies in the solid state, to their equivalents, or atomic weights*: by Professor Otto. *Studies on the connection between the atomic weights, crystalline form, and density of bodies*: by M. Filhol. Translated for the Cavendish Society, and published in their Chemical Reports and Memoirs.

[210] *Comptes Rendus de l'Académie des Sciences*, 1840, No. 5. A good translation of Dumas's Memoir appeared in the Philosophical Magazine, from which I extract the following familiar exposition of the laws of substitution:—"Let me make a comparison drawn from a familiar order of ideas. Let us put ourselves in the place of a man overlooking a game at chess without the slightest knowledge of the game. He would soon remark that the pieces must be used according to positive rules. In chemistry, the equivalents are our pieces, and the law of substitutions one of the rules which preside over their moves. And as in the oblique move of the pawns one pawn must be substituted for another, so in the phenomena of substitution one element must take the place of another. But this does not hinder the pawn from advancing without taking anything,

as the law of substitution does not hinder an element from acting on a body without displacing or taking the place of any other element that it may contain."—*Memoir on the Law of Substitutions, and Theory of Chemical Types.*

[211] Liebig's *Chemistry in its application to Agriculture and Physiology*: translated by Lyon Playfair, Ph. D. *Animal Chemistry, or Chemistry in its application to Physiology and Pathology*: by Justus Liebig; translated by Wm. Gregory.

CHAPTER XII.

CHEMICAL PHENOMENA.

Water—Its Constituents—Oxygen —Hydrogen—Peroxide of Hydrogen—Physical Property of Water—Ice—Sea Water—Chlorine—Muriatic Acid—Iodine—Bromine—Compounds of Hydrogen with Carbon—Combustion—Flame —Safety Lamp—Respiration—Animal Heat—The Atmosphere—Carbonic Acid—Influence of Plants on the Air —Chemical Phenomena of Vegetation—Compounds of Nitrogen—Mineral Kingdom, &c. &c.

Without attempting anything which shall approach even to the character of a sketch of chemical science, we may be allowed, in our search after exalting truths, to select such examples of the results of combination as may serve to elucidate any of the facts connected with natural phenomena. In doing this, by associating our examination with well-known natural objects or conditions, the interpretation afforded by analysis will be more evident, and the operation of the creative forces rendered more striking and familiar, particularly if at the same time we examine such physical conditions as are allied in action, and are sufficiently explanatory of important features.

A large portion of this planet is covered by the waters of the ocean, of lakes and rivers. Water forms the best means of communication between remote parts of the earth. It is in every respect of the utmost importance to the animal and vegetable kingdom; and, indeed, it is indispensable in all the great phenomena of the inorganic world. The peculiarities of saltness or freshness in water are dependent upon its solvent powers. The waters of the ocean are saline from holding dissolved various saline compounds, which are received in part from, and imparted also to, the marine plants. Perfectly pure water is without taste: even the pleasant character of freshly-drawn spring-water is due to the admixture of atmospheric air and carbonic acid. The manner in which water absorbs air is evidently due to a peculiar physical attractive force, the value of which we do not at present clearly perceive or correctly estimate. It is chemically composed of two volumes of hydrogen gas—the lightest body known, and at the same time a highly inflammable one—united with one volume of oxygen, which excites combustion, and continues that action,—producing heat and light,—with great energy. By weight, one part of hydrogen is united with eight of oxygen, or in 100 parts of water we find 88·9 oxygen, and 11·1 of hydrogen gas. That two such bodies should unite to furnish the most refreshing beverage, and indeed the only natural drink for man and animals, is one of the extraordinary facts of science. Hydrogen will not support life—we cannot breathe it and live; and oxygen would over-stimulate the organic system, and, producing a kind of combustion, give rise to fever in the animal frame; but, united, they form that drink, for a drop of which the fevered monarch would yield his diadem, and the deprivation of

which is one of the most horrid calamities that can be inflicted upon any living thing. Water appears as the antagonist principle to fire, and the ravages of the latter are quenched by the assuaging powers of the former; yet a mixture of oxygen and hydrogen gases, in the exact proportion in which they form water, explodes with the utmost violence on the contact of flame, and, when judiciously arranged, produces the most intense degree of heat known;—such is the remarkable difference between a merely mechanical mixture and a chemical combination. Beyond this, we have already noticed the remarkable fact that water deprived of air is explosive at a comparatively low temperature, less than 300°; gunpowder requiring a temperature of nearly 1000° F.

If we place in a globe, oxygen and hydrogen gases, in the exact proportions in which they combine to form water, they remain without change of state. They appear to mix intimately; and, notwithstanding the difference in the specific gravities of the two gases, the lighter one is diffused through the heavier in a curious manner, agreeably to a law which has an important bearing on the conditions of atmospheric phenomena.[212] The moment, however, that an incandescent body, or the spark from an electric machine, is brought into contact with the mixed gases, they ignite, explode violently, and combine to form water. The discovery of the composition of water was thus synthetically made by Cavendish—its constitution having been previously theoretically announced by Watt.[213]

If, instead of combining oxygen and hydrogen in the proportions in which they form water, we compel the hydrogen to combine with an additional equivalent

of oxygen, we have a compound possessing many properties strikingly different from water. This—peroxide of hydrogen, as it is called—is a colourless liquid, less volatile than water, having a metallic taste. It is decomposed at a low temperature, and, at the boiling point, the oxygen escapes from it with such violence, that something like an explosion ensues. All metals, except iron, tin, antimony, and tellurium, have a tendency to decompose this compound, and separate it into oxygen and water. Some metals are oxidized during the decomposition, but gold, silver, platinum, and a few others, still retain their metallic state. If either silver, lead, mercury, gold, platinum, manganese, or cobalt, in their highest states of oxidation, are put into a tube, containing this peroxide of hydrogen, its oxygen is liberated with the rapidity of an explosion, and so much heat is excited that the tube becomes red hot. These phenomena, to which we have already referred in noticing catalysis, are by no means satisfactorily explained, and the peculiar bleaching property possessed by the peroxide of hydrogen sufficiently distinguishes it from water. There are few combinations which show more strikingly than this the difference arising from the chemical union of an additional atom of one element. Similar instances are numerous in the range of chemical science; but scarcely any two exhibit such dissimilar properties. During the ordinary processes of combustion, it has been long known that water is formed by the combination of the hydrogen of the burning body with the oxygen of the air. The recent researches of Schönbein have shown that a peculiar body, which has been regarded as a peroxide of hydrogen, to which he has given the name of OZONE, is produced at the same time, and that it is developed in a great

many ways, particularly during electrical changes of the atmosphere. Thus we obtain evidence that this remarkable compound, which was considered as a chemical curiosity merely, is diffused very generally through nature, and produced under a great variety of circumstances. During the excitation of an electrical machine, or the passage of a galvanic current through water by the oxidation of phosphorus, and probably in many similar processes —in particular those of combustion, and we may therefore infer also of respiration—this body is formed. From observations which have been made, it would appear that, during the night, when the activity of plants is not excited by light, they act upon the atmosphere in such a way as to produce this ozone; and its presence is said to be indicated by its peculiar odour during the early hours of morning. We are not yet acquainted with this body sufficiently to speculate on its uses in nature: without doubt, they are important, perhaps second to those of water only. It is probable, as we have already had occasion to remark, that ozone may be the active agent in removing from the atmosphere those organic poisons to which many forms of pestilence are traceable; and it is a curious fact, that a low electrical intensity, and a consequent deficiency of atmospheric ozone, marks the prevalence of cholera, and an excess distinguishes the reign of influenza.[214]

Some interesting researches appear to show the probability that ozone is simply oxygen in a state of high activity. It has been found, indeed, that perfectly dry oxygen, which will not bleach vegetable colours in the dark, acquires, by exposure to sunshine, the power of destroying them. Becquerel has proved that this ozonous state may be produced in dry oxygen by passing a succession of electric

sparks through it. Fremy passed the electric sparks on the outside of a tube which contained perfectly dry oxygen, and it was found to have acquired the properties of ozone. In this case, and probably in the experiments of Becquerel, the light of the spark, rather than the electricity, appears to have been the active agent in producing this change. Schönbein himself does not appear disposed to regard ozone as being either peroxide of hydrogen, or an allotropic oxygen. He leans to his first view of its being an entirely new chemical element. The energy of this ozone is so great, that it has been found to destroy almost instantaneously the Indian-rubber union joints of the apparatus in which it is formed.[215]

Water, from the consideration of which a digression has been indulged in, to consider the curious character of one of its elements,—water is one of the most powerful chemical agents, having a most extensive range of affinities, entering directly into the composition of a great many crystallizable bodies and organic compounds. In those cases where it is not combined as water, its elements often exist in the proportions in which water is formed. Gum, starch, and sugar, only differ from each other in the proportions in which the elements of water are combined with the carbon.

In saline combinations, and also in many organic forms, we must regard the water as condensed to the solid form; that is, to exist as ice. We well know that, by the abstraction of heat, this condition is produced; but, in chemical combinations, this change must be the result of the mechanical force exerted by the power of the agency directing affinity.

In the case of water passing from a liquid to a solid state, we have a most beautiful exemplification of

the perfection of natural operations. Water conducts heat downwards but very slowly; a mass of ice will remain undissolved but a few inches under water, on the surface of which, ether, or any other inflammable body, is burning. If ice (solid water) swam beneath the surface, the summer sun would scarcely have power to thaw it; and thus our lakes and seas would be gradually converted into solid masses at our ordinary winter temperatures.

All similar bodies contract equally during the process of cooling, from the highest to the lowest points to which the experiments have been carried. It has been thought that if this applied to water, the result would be the sudden consolidation of the whole mass. A modification of the law has been supposed to take place to suit the peculiar circumstances of water. Nature never modifies a law for a particular purpose; we must, therefore, seek to explain the action of the formation of ice, as we know it, by some more rational view.

Water expands by heat, and contracts by cold; consequently, the coldest portions of this body occupy the lower portions of the fluid; but it must be remembered that these parts are warmed by the earth. Ross, however, states that at the depth of 1,000 fathoms the sea has a constant temperature of 39°. Water is said to be at its point of greatest density at 40° of Fahrenheit's thermometer; in cooling further, this fluid appears to expand, in the same way as if heated: and, consequently, water colder than this point, instead of being heavier, is lighter, and floats on the surface of the warmer fluid. It does not seem that any modification of the law is required to account for this phenomenon. Water cooled to 40° still retains its peculiar corpuscular arrangement; but

immediately it passes below that temperature, it begins to dispose itself in such a manner that visible crystals may form the moment it reaches 32°. Now, if we conceive the particles of water, at 39°, to arrange themselves in the manner necessary for the assumption of the solid form, by the particular grouping of molecules in an angular instead of a spheroidal shape, it will be clear, from what we know of the arrangement of crystals of water—ice—that they must occupy a larger space than when the particles are disposed, side by side, in minute spheres. Even the escape of air from the water in which it is dissolved is sufficient to give an apparent lightness to the colder water. This expansion still goes on increasing, from the same cause, during the formation of ice, so that the specific gravity of a mass of frozen water is less than that of water at any temperature below 40°. It must not be forgotten that ice always contains a large quantity of air, by which it is rendered buoyant.

Water, at rest, may be cooled many degrees below the freezing point without becoming solid. This is easily effected in a thin glass flask; but the moment it is agitated, it becomes a firm mass. Here we have the indication of another cause aiding in producing crystals of ice on the surface of water, under the influence of the disturbance produced by the wind, which does not extend to any depth.

As oxygen and hydrogen gases enter largely into other chemical compounds besides water, it is important to consider some of the forms of matter into the composition of which these elements enter. To examine this thoroughly, a complete essay on chemical philosophy would be necessary; we must, therefore, be content with referring to a few of the

more remarkable instances.

The waters of the ocean are salt: this arises from their holding, in solution chloride of sodium (*muriate of soda—common culinary salt*) and other saline bodies. Water being present, this becomes muriate of soda,—that is, a compound of muriatic acid and soda: muriatic acid is hydrogen, combined with a most remarkable gaseous body, called, from its yellow colour, *chlorine*; and soda, oxygen in union with the metal sodium,—therefore, when anhydrous, culinary salt is truly a chloride of sodium. Chlorine in some respects resembles oxygen; it attacks metallic bodies with great energy; and, in many cases, produces the most vivid incandescence, during the process of combination. It is a powerful bleaching agent, is destructive to animal life, and rapidly changes all organic tissues. There are two other bodies in many respects so similar to chlorine, although one is at the ordinary temperatures solid, and the other fluid, and which are also discovered in sea-water, or in the plants growing in it, that it is difficult to consider them otherwise than as different forms of the same principle. These are iodine and bromine, and they both unite with hydrogen to form acids. The part which chlorine performs in nature is a great and important one. Combined in muriate of soda, we may trace it in large quantities through the three kingdoms of nature, and the universal employment of salt as a condiment indicates the importance to the animal economy of the elements composing it. Iodine has been traced through the greater number of marine plants, existing, apparently as an essential element of their constitution; in some land plants it has also been found, particularly in the Armeria maritima, when this plant grows near the sea:[216] it has been detected in some mineral

springs, and in small quantities in the mineral kingdom[217] combined as iodide of silver, and in the aluminous slate of Latorp in Sweden.[218] Bromine is found in sea-water, although in extremely minute quantities, in a few saline springs, and in combination with silver; but we have no evidence to show that its uses are important in nature.

Hydrogen, again, unites with carbon in various proportions, producing the most dissimilar compounds. The air evolved from stagnant water, and the fire-damp of the coal mine, are both carburetted hydrogen; and the gas which we employ so advantageously for illumination, is the same, holding an additional quantity of carbon in suspension. Naphtha, and a long list of organic bodies, are composed of these two chemical elements.

These combinations lead us, naturally, to the consideration of the great chemical phenomena of combustion, which involve, indeed, the influences of all the physical powers. By the application of heat, we produce an intense action in a body said to be combustible; it burns,—a chemical action of the most energetic character is in progress, the elements which constitute the combustible body are decomposed, they unite with some other elementary principles, and new compounds are formed. A body burns—it is entirely dissipated, or it leaves a very small quantity of ashes behind unconsumed, but nothing is lost. Its volatile parts have entered into new arrangements, the form of the body is changed, but its constituents are still playing an important purpose in creation.

The ancient notion that fire was an empyreal element, and the Stahlian hypothesis of a phlogistic

principle on which all the effects of combustion depended,[219] have both given way to the philosophy of the unfortunate Lavoisier—which has, indeed, been modified in our own times—who showed that combustion is but the development of heat and light under the influence of chemical combination.

Combustion was, at one period, thought to be always due to the combination of oxygen with the body burning, but research has shown that vivid combustion may be produced where there is no oxygen. The oxidizable metals burn most energetically in chlorine, and some of them in the vapour of iodine and bromine, and many other unions take place with manifestations of incandescence. Supporters of combustion were, until lately, regarded as bodies distinct from those undergoing combustion. For example, hydrogen was regarded as a combustible body, and oxygen as a supporter of combustion. Such an arrangement is a most illogical one, since we may *burn* oxygen in an atmosphere of hydrogen, in the same manner as we burn hydrogen in one of oxygen; and so, in all the other cases, the supporter of combustion may be burnt in an atmosphere formed of the, so called, combustible. The ordinary phenomena of combustion are, however, due to the combination of oxygen with the body burning; therefore every instance of oxidization may be regarded as a condition of combustion, the difference being only one of degree.

Common iron, exposed to air and moisture, *rusts*; it combines with oxygen. Pure iron, in a state of fine division, unites with oxygen so eagerly, that it becomes incandescent, and in both cases oxide of iron is formed. This last instance is certainly a case of

combustion; but in what does it differ from the first one, except in the intensity of the action? The cases of spontaneous combustion which are continually occurring are examples of an analogous character to the above. Oxygen is absorbed, it enters more or less quickly, according to atmospheric conditions, into chemical combination; heat is evolved, and eventually,—the action continually increasing,—true combustion takes place. In this way our cotton-ships, storehouses of flax, piles of oiled-cloth, sawdust, &c., frequently ignite; and to such an influence is to be attributed the destruction of two of our ships of war, a few years since, in Devonport naval arsenal.[220]

In the economic production of heat and light, we have the combination of hydrogen and carbon with the oxygen of common air, forming water and carbonic acid. In our domestic fires we employ coal, which is essentially a compound of carbon and hydrogen containing a little oxygen and some nitrogen, with some earthy matters which must be regarded as impurities; the taper, whether of wax or tallow, is made up of the same bodies, differing only in their combining proportions, and, like coal gas, these burn as carburetted hydrogen. All these bodies are very inflammable, having a tendency to combine energetically with oxygen at a certain elevation of temperature.

We are at a loss to know how heat can cause the combination of those bodies. Sir Humphry Davy has shown that hydrogen will not burn, nor a mixture of it with oxygen explode, unless directly influenced by a body heated so as to *emit light*.[221] May we not, therefore, conclude that the chemical action exhibited in a burning body is a development of some latent force, with which we are unacquainted,

produced by the absorption of light;—that a repulsive action at first takes place, by which the hydrogen and carbon are separated from each other;—and that in the nascent state they are seized by the oxygen, and again compelled, though in the new forms of water and carbonic acid, to resume their chains of combining affinity?

Every equivalent of carbon and of hydrogen in the burning body unites with two equivalents of oxygen, in strict conformity with the laws of combination. The flame of hydrogen, if pure, gives scarcely any light, but combined with the solid particles of carbon, it increases in brightness. The most brilliant of the illuminating gases is the olefiant gas, produced by the decomposition of alcohol, and it is only hydrogen charged with carbon to the point of saturation. Flame is a cone of heated vapour, becoming incandescent at the points of contact with the air; a mere superficial film only being luminous. It is evident that all the particles of the gas are in a state of very active repulsion over the surface, since flame will not pass through wire gauze of moderate fineness. Upon this discovery is founded the inimitable safety-lamp of Davy, by means of which the explosive gases of a mine are harmlessly ignited within a cage of wire gauze. This effect has been attributed to a cooling influence of the metal; but, since the wires may be brought to a degree of heat but little below redness without igniting the fire-damp, this does not appear to be the cause. The conditions of the safety lamp may be regarded as presenting examples exactly the converse of those already stated with reference to the spheroidal state of water; and it affords additional evidence that the condition of bodies at high temperatures is subject to important physical changes.

The principle upon which the safety lamp is constructed is, that a mixture of the fire-damp and atmospheric air in certain proportions explodes upon coming in contact with a flame.

This mixture passes readily through a wire gauze, under all circumstances, and it, of course, thus approaches the flame of the lamp enclosed within such a material, and it explodes. But, notwithstanding the mechanical force with which the exploding gas is thrown back against the bars of its cage, it cannot pass them. Consequently, the element of destruction is caught and caged; and notwithstanding its fierceness and energy, it cannot impart to the explosive atmosphere without, any of its force. No combustion can be communicated through the wire gauze.

The researches which led to the safety-lamp may be regarded as among the most complete examples of correct inductive experiment in the range of English science, and the result is certainly one of the proudest achievements of physico-chemical research. By merely enveloping the flame of a lamp with a metallic gauze, the labourer in the recesses of the gloomy mine may feel himself secure from that outpouring current of inflammable gas, which has been so often the minister of death; he may walk unharmed through the explosive atmosphere, and examine the intensity of its power, as it is wasted in trifling efforts within the little cage he carries. Accidents have been attributed to the “Davy,” as the lamp is called among the colliers; but they may in most cases be traced to carelessness on the part of those whose duty it has been to examine the lamps, or to the recklessness of the miners themselves.

That curious metal, platinum, and also palladium,

possesses a property of maintaining a slow combustion, which the discoverer of the safety-lamp proposed to render available to a very important purpose. If we take a coil of platinum wire, and, having made it red-hot, plunge it into an explosive atmosphere of carburetted hydrogen and common air, it continues to glow with considerable brightness, producing, by this very peculiar influence, a combination of the gases, which is discovered by the escape of pungent acid vapours. Over the little flame of the safety-lamp, it was proposed by Davy to suspend a coil of platinum which would be thus kept constantly at a red heat. If the miner became accidentally enveloped in an atmosphere of fire-damp, although the flame of his lamp might be extinguished, the wire would continue to glow with sufficient brightness to light him from his danger, through the dark winding passages which have been worked in the bed of fossil fuel. This very beautiful arrangement has not, however, been adopted by our miners.

It is thus that the discoveries of science, although they may appear of an abstract character, constantly, sooner or later, are applied to uses by which some branch of human labour is assisted, the necessities of man's condition relieved, and the amenities of life advanced.

The respiration of animals is an instance of the same kind of chemical phenomena as we discover in ordinary combustion. In the lungs the blood becomes charged with oxygen, derived from the atmospheric air, with which it passes through the system, performing its important offices, and the blood is returned to the lungs with the carbonic acid formed by the separation of carbon from the body which is

thrown off at every expiration. It will be quite evident that this process is similar to that of ordinary combustion. In man or animals, as in the burning taper,—which is aptly enough employed by poets as the symbol of life,—we have hydrogen and carbon, with some nitrogen superadded; the hydrogen and oxygen form water under the action of the vital forces; the carbon with oxygen produces carbonic acid, and, by a curious process, the nitrogen and hydrogen also combine, to form ammonia.[222]

All the carbon which is taken into the animal economy passes, in the process of time, again into the atmosphere, in combination with oxygen, this being effected in the body, under the *catalytic* power of tissues, immediately influenced by the excitation of nervous forces, which are the direct manifestations of vital energy. The quantity of carbonic acid thus given out to the air is capable of calculation, with only a small amount of error. It appears that upwards of fifty ounces of carbonic acid must be given off from the body of a healthy man in twenty-four hours. On the lowest calculation, the population of London must add to the atmosphere daily 4,500,000 pounds of carbonic acid. It must also be remembered that in every process for artificial illumination, and in all the operations of the manufactures in which fire is used, and also in our arrangements to secure domestic comfort, immense quantities of this gas are formed. We may, indeed, fairly estimate the amount, if we ascertain the quantity of wood and coal consumed, of all the carbon which combines with oxygen while burning, and escapes into the air, either as carbonic acid or carbonic oxide. The former gas, the same as that which accumulates in deep wells and in brewers' vats, is highly destructive to life, producing very

distressing symptoms, even when mixed with atmospheric air, in but slight excess over that proportion which it commonly contains. The oppressive atmosphere of crowded rooms is in a great measure due to the increased proportion of carbonic acid given off from the lungs of those assembled, and collected in the almost stagnant air of badly ventilated apartments. It will be evident to every one, that unless some provision was made for removing this deleterious gas from the atmosphere as speedily as it formed, consequences of the most injurious character to the animal races would ensue. It is found, however, that the quantity in the atmosphere is almost constantly about one per cent. The peculiar properties of carbonic acid in part ensure its speedy removal. It is among the heaviest of gaseous bodies, and it is readily absorbed by water; consequently, floating within a short distance from the surface of the earth, a large quantity is dissolved by the waters spread over it. A considerable portion is removed by the vegetable kingdom; indeed, the whole of that produced by animals, and by the processes of combustion, eventually becomes part of the vegetable world, being absorbed with water by the roots, and separated from the air by the peculiar functions of the leaves. However, this heavy gas unites with the lighter atmospheric fluid in obedience to that law which determines the diffusion of different specific gravities through each other.

The leaves of plants may be regarded as performing similar offices to the lungs of animals. They are the breathing organs. In the animal economy a certain quantity of carbon is necessarily retained, in combination with nitrogen and other elements, to form muscle; but this is constantly undergoing change; the entire system being renewed within a

comparatively limited period. The conditions with plants are somewhat different. For instance, the carbon is fixed in a tree, and remains as woody fibre until it decays, even though the life of the plant may extend over centuries.

Animals, then, are constantly supplying carbonic acid; plants are as constantly feeding on it; thus is the balance for ever maintained between the two kingdoms. Another condition is, however, required to maintain for the uses of men and animals the necessary supply of oxygen gas. This is effected by one of those wonderful operations of nature's chemistry which must strike every reflecting mind with admiration. During the night plants absorb carbonic acid; but there is a condition of repose prevailing then in their functions, and consequently their powers of effecting the decomposition of this gas are reduced to their minimum. The plant sleeps, and vital power reposes; its repose being as necessary to the plant as to the animal. With the first gleam of the morning sun the dormant energies of the plant are awakened into full action; it decomposes this carbonic acid, secretes the carbon, to form the rings of wood which constitute so large a part of its structure, and pour out oxygen gas to the air. The plant is, therefore, an essential element in the conditions necessary for the support of animal life.

The animal produces carbonic acid in an exact proportion to the quantity of carbonaceous matter which it consumes. Fruit and herbage contain a small quantity of carbon in comparison with muscle and fat. But let us confine our attention to the human race. Man within the Tropics, where the natural temperature is high, does not require so great an amount of chemical action to go on within him for

the purpose of maintaining the requisite animal heat; consequently his Maker has surrounded him with fruits and grains which constitute his food.

As we advance to the colder regions of the earth man becomes a flesh-eater, and his carnivorous appetite increases as the external temperature diminishes. Eventually we reach the coldest zones, and the human being there devours enormous quantities of fat to supply the necessities of his condition.

It must necessarily follow, that the inhabitants of the tropics do not produce so much carbonic acid as those who dwell in colder regions. In the first place, their habits of life are different, and they are not under the necessity of maintaining animal heat by the use of artificial combustion, as are the people of colder climes. The vegetation of the regions of the tropics is much more luxuriant than that of the temperate and arctic zones. Hence an additional supply of carbonic acid is required between the torrid zones, and a less quantity is produced by its animals. These cases are all met by the great aërial movements. A current of warmed air, rich in oxygen, moves from the equator towards the poles, whilst the cooler air, charged with the excess of carbonic acid, sets in a constant stream towards the equator. By this means the most perfect equalization of the atmospheric conditions is preserved.

The carbonic acid poured out from the thousand mouths of our fiery furnaces,—produced during the laborious toil of the hard-working artizan,—and exhaled from every populous town of this our island home,—is borne away by this our aërial currents to find its place in the pines of the Pacific Islands, the spice-trees of the Eastern Archipelago, and the cinchonas of Southern America. The plants of the

valley of the Caucasus, and those which flourish amongst the Himalayas, equally with the less luxuriant vegetation of our temperate climes, are directly dependent upon man and the lower animals for their supply of food.

If all plants were removed from the earth, animals could not exist. How would it be if the animal kingdom was annihilated?—would it be possible for vegetation to continue? This question is not quite so easily answered; but, if we suppose all the carbon-producing machines—the animals—to be extinct, from whence would the plants draw their supply? It has been supposed that during the epoch of the coal formation a luxuriant vegetation must have gone on over the earth's surface, when the existence of animal life was regarded as problematical. It is supposed that the air was then charged with carbonic acid, and that the calamites, lepidodendra, and sigilaria, were employed to remove it, and fit the earth for the oxygen-breathing races. The evidence upon these points is by no means satisfactory; and although at one time quite disposed to acquiesce in a conjecture which appears to account so beautifully for the observed geological phenomena of carboniferous periods, we do not regard the necessities for such a condition of the atmosphere as clearly made out.[223] Geological research, too, has shown that the immense forests from which our coal is formed teemed with life. A frog as large as an ox existed in the swamps, and the existence of insects proves the high order of organic creation at this epoch.

In all probability the same mutual dependence which now exists between the animal and vegetable kingdoms existed from the beginning of time, and

will continue to do so under varying circumstances through the countless ages of the earth's duration.

There is yet another very important chain of circumstances which binds these two great kingdoms together. This is the chain of the animal necessities. A large number of races feed directly upon vegetables; herbs and fruits are the only things from which they gain those elements required to restore the waste of their systems.

These herbivorous animals, which must necessarily form fat and muscle from the elements of their vegetable diet, are preyed on by the carnivorous races; and from these the carbon is again restored to the vegetable world. Sweep off from the earth the food of the herbivora, they must necessarily very soon perish, and with their dissolution, the destruction of the carnivora is certainly ensured. To illustrate this on a small scale, it may be mentioned that around the coasts of Cornwall, pilchards were formerly caught in very great abundance, in the shallow water within coves, where these fish are now but rarely seen. From the investigations of the Messrs. Couch, whose very accurate observations on the Cornish fauna have placed both father and son amongst the most eminent of British naturalists,[224] it appears that the absence of these fish is to be attributed entirely to the practice of the farmers, who cut the sea-weed from the rocks for the purpose of manuring their lands. By this they destroy all the small crustacea inhabiting these immature marine forests feeding on the algæ, and as these, the principal food of the pilchards, have perished they seek for a substitute in more favourable situations. Mr. Darwin remarks, that if the immense sea-weeds of the Southern Ocean were removed by any cause,

the whole fauna of these seas would be changed.

We have seen that animals and vegetables are composed principally of four elementary principles, —oxygen, hydrogen, nitrogen, and carbon. We have examined the remarkable manner in which they pass from one condition—from one kingdom of nature—into another. The animal, perishing and dwindling by decomposition into the most simple forms of matter, mingling with the atmosphere as mere gas, gradually becomes part of the growing plant, and by like changes vegetable organism progresses onward to form a portion of the animal structure.

A plant exposed to the action of natural or artificial decomposition passes into air, leaving but a few grains of solid matter behind it. An animal, in like manner, is gradually resolved into “thin air.” Muscle, and blood, and bones, having undergone the change, are found to have escaped as gases, leaving only “a pinch of dust,” which belongs to the more stable mineral world. Our dependency on the atmosphere is therefore evident. We derive our substance from it—we are, after death, resolved again into it. We are really but fleeting shadows. Animal and vegetable forms are little more than consolidated masses of the atmosphere. The sublime creations of the most gifted bard cannot rival the beauty of this, the highest and the truest poetry of science. Man has divined such changes by the unaided powers of reason, arguing from the phenomena which science reveals in unceasing action around him. The Grecian sage’s doubts of his own identity, were only an extension of a great truth beyond the limits of our reason. Romance and superstition resolve the spiritual man into a visible form of extreme ethereality in the spectral creations, “clothed in their own horror,” by

which their reigns have been perpetuated.

When Shakespeare made his charming Ariel sing—

"Full fathom five thy father lies,
  Of his bones are coral made,
Those are pearls that were his eyes:
  Nothing of him that doth fade,
But doth suffer a sea change
Into something rich and strange,"

he painted, with considerable correctness, the chemical changes by which decomposing animal matter is replaced by a siliceous or calcareous formation.

But the gifted have the power of looking through the veil of nature, and they have revelations more wonderful than even those of the philosopher, who evokes them by perpetual toil and brain-racking struggle with the ever-changing elements around him.

The mysteries of flowers have ever been the charm of the poet's song. Imagination has invested them with a magic influence, and fancy has almost regarded them as spiritual things. In contemplating their surpassing loveliness, the mind of every observer is improved, and the sentiments which they inspire, by their mere external elegance, are great and good. But in examining the real mysteries of their conditions, their physical phenomena, the relations in which they stand to the animal world, "stealing and giving odours" in the marvellous interchange of carbonic acid and ammonia for the soul-inspiring oxygen—all speaking of the powers of some unseen, in-dwelling principle, directed by a supreme ruler—the philosopher finds subjects for deep and soul-trying

contemplation. Such studies lift the mind into the truly sublime of nature. The poet's dream is the dim reflection of a distant star: the philosopher's revelation is a strong telescopic examination of its features. One is the mere echo of the remote whisper of nature's voice in the dim twilight; the other is the swelling music of the harp of Memnon, awakened by the sun of truth, newly risen from the night of ignorance.

To return from our long, but somewhat natural digression, to a consideration of the chemical phenomena connected with the atmosphere, and its curious and important element, nitrogen, we must first examine the evidence we have of the condition of the air itself.

The mean pressure exerted upon the surface of the earth, as indicated by the barometer, is equal to a column of mercury thirty inches high; that is, the column of air from the surface of the ocean to its highest limits exactly balances that quantity of mercury. If our tube of mercury had the area of one square inch, the columns would weigh fifteen pounds, which represents a pressure of fifteen pounds upon every square inch of the earth's surface. This pressure, it must be remembered, is the compound weight of the gaseous envelope, and the elastic force of the aqueous vapour contained in it. [225] If the atmosphere were of uniform condition, its height, as inferred from the barometer, would be about five miles and a half. The density of the air, however, diminishes with the pressure upon it, so that at the height of 11,556 feet, the atmosphere is of half density; or one volume of air, as taken at the surface of the earth, is expanded into two at that height. Thus the weight is continually diminishing;

but this is regularly opposed by the decreasing temperature, which diminishes the rate of about one degree for every 352 feet of ascent, although in all probability it is less rapid at great distances from the earth.

It has been calculated from certain phenomena of refraction, that our atmosphere must extend to about forty miles from the surface of the earth. It may, in a state of extreme tenuity, extend still further; but it is probable that the intense cold produced by rarefaction sets limits to any extension much beyond this elevation.

The uses of the atmosphere are many. It is the medium for regulating the dispersion of watery vapours over the earth. If there were no atmosphere, and that, as now, the equatorial climes were hot and the poles cold, evaporation would be continually going on at the equator, and condensation in the colder regions. The sky of the tropical climes would be perpetually cloudless, whilst in the temperate and arctic zones we should have constant rain and snow. By having a gaseous atmosphere, a more uniform state of things is produced; the vapours arising from the earth become intimately mixed with the air, and are borne by it over large tracts of country, and only precipitated when they enter some stratum much colder than that which involves them. There are opposite tendencies in an atmosphere of air and one of vapour. The air circulates from the colder to the warmer parts, and the vapour from the warmer to the colder regions; and as the currents of the air, from the distribution of land and sea—the land, from its low conducting power, being more quickly heated than the sea—are very complicated, and as some force is employed in keeping the vapour suspended

in the air, water is less suddenly deposited on the earth than it would have been, had not these tendencies of the air and its hygrometric peculiarities been such as we find them.

The blue colour of the sky, which is so much more agreeable to the eye than either red or yellow, is due to a tendency of the mixed gas and vapour to reflect the blue rays rather than red or yellow. The white light which falls upon the surface of the earth, without absorption or decomposition in its passage from the sun, is partially absorbed by, and in part reflected back from, the earth. The reflected rays pass with tolerable freedom through this transparent medium, but a portion of the blue rays are interrupted and rendered visible to us. That it is reflected light, is proved by the fact of its being in a polarized state.[226] Clouds of vapour reflect to us again, not isolated rays, but the undecomposed beam, and consequently they appear white as snow to our vision.

The golden glories of sunset,—when, “like a dying dolphin,” heaven puts on the most gorgeous hues, which are continually changing,—depend entirely upon the quantity of watery vapour which is mixed with air, and its state of condensation. It has been observed, that steam at night, issuing into the atmosphere under a pressure of twenty or thirty pounds to the square inch, transmits and reflects orange-red light. This we may, therefore, conclude to be the property of such a condition of mixed vapour and air, as prevails when the rising or the setting sun is shedding over the eastern or the western horizon the glory of its coloured rays.[227]

Thus science points out to us the important uses of the air. We learn that life and combustion are

entirely dependent on it, and that it is made the means for securing greater constancy in the climates of the earth than could otherwise be obtained. The facts already dwelt upon are sufficient to convince every thinking mind that the beautiful system of order which is displayed in the composition of the atmosphere, in which the all-exciting element, oxygen, is subdued to a tranquil state by another element, nitrogen, (which, we shall have presently to show, is itself, under certain conditions, one of the most energetic agents with which we are acquainted,) indicates a supreme power, omniscient in the adaptation of things to an especial end. Oxygen and nitrogen are here *mixed* for the benefit of man; man *unites* them by the aid of powers with which he is gifted, and the consequences are of a fatal kind. The principles which the great Chemist of Nature renders mild are transformed into sources of evil by the chemist of art.

Beyond all this, the atmosphere produces effects on light which add infinitely to the beauty of the world. Were there no atmosphere, we should only see those objects upon which the sun's rays directly fell, or from which they were reflected. A ray falling through a small hole into a dark room, illuminating one object, which reflects some light upon another, is an apt illustration of the effect of light upon the earth, if it existed without its enveloping atmosphere. By the dispersive powers of this medium, sunlight is converted into daylight; and instead of unbearable, parallel rays illuminating brilliantly, and scorching up with heat those parts upon which they directly fall, leaving all other parts in the darkness of night, we enjoy the blessings of a diffusion of its rays, and experience the beauties of soft shades and slowly-deepening shadows. Without

an atmosphere, the sun of the morning would burst upon us with unbearable brilliancy, and leave us suddenly, at the close of day, at once in utter darkness. With an atmosphere we have the twilight with all its tempered loveliness,—a “time for poets made.”

In chemical character, atmospheric air is composed of twenty-one volumes of oxygen, and seventy-nine volumes of nitrogen: or one hundred grains of air consist of 23·1 grains of the former, and 76·9 grains of the latter. Whether the air is taken from the greatest depths or the most exalted heights to which man has ever reached, an invariable proportion of the gases is maintained. The air of Chimborazo, of the arid plains of Egypt, of the pestilential delta of the Niger, or even of the infected atmosphere of an hospital, all give the same proportions of these two gases as we find existing on the healthful hills of Devonshire, or in the air of the city of London. This constancy in constitution leads to the supposition that the oxygen and nitrogen are chemically combined; but many eminent philosophers have contended that they are merely mechanically mixed; and they have shown that some peculiar properties prevail amongst gaseous bodies, which very fully explain the equal admixture of two gases the specific gravities of which are different. This is particularly exemplified in the case of carbonic acid, of which gas one per cent. can be detected in all regions of the air to which the investigations of man have reached. This gas, although so heavy, is, by the law of diffusion, mixed with great uniformity throughout the mass.[228] Every exhalation from the earth, of course, passes into the air; but these are generally either so light that they are carried into the upper regions, and there perform their parts in the

meteorological phenomena, or they are otherwise very readily absorbed by water or growing plants, and thus is the atmosphere preserved in a state of purity for the uses of animals. Again, the quantity of oxygen contained in the air, and its very peculiar character, ensures the oxidation of all the volatile organic matters which are constantly passing off,—as the odoriferous principles of plants, the miasmata of swamps, and the products of animal putrefaction; these are rapidly converted into water, carbonic acid, or nitric acid, and quickly enter into new and harmless combinations. The elements of contagion we are unacquainted with; but since the attention of inquirers has been of late directed to this important and delicate subject, some light may possibly be thrown upon it before long.

Nothing, shows more strikingly the admirable adaptation of all things for their intended uses than the atmosphere. In it we find the source of life and health; and chemistry teaches us, most indisputably, that it is composed of certain proportions of oxygen and nitrogen gases; and experience informs us that it is on the oxygen that we are dependent for all that we enjoy. So beautifully is the atomic or molecular constitution ordered, that it is impossible to produce any change in the air without rendering it injurious to the vegetable and animal economy. It might be thought, from the well-known exhilirating character of oxygen gas, that, if a larger quantity existed in the atmosphere than that which we find there, the enjoyments of life would be of a more exciting kind; but the consequences of any increase would be exceedingly injurious; and, by quickening all the processes of life to an unnatural extent, the animal fabric would soon decay: excited into fever, it would be destroyed by its own fires. Chemistry has made us

acquainted with six other compounds of oxygen and nitrogen, neither of them fitted for the purposes of vitality, of which the following are the most remarkable:—

Nitrous oxide, or the, so called, *laughing gas*, which contains two volumes of nitrogen to one of oxygen, would prove more destructive than even pure oxygen, from the delirious intoxication which it produces.

Nitric oxide is composed, according to Davy, of two volumes of nitrogen and two of oxygen. It is of so irritating a nature, that the glottis contracts spasmodically when any attempt is made to breathe it; and the moment it escapes into the air it combines with more oxygen, and forms the deep red fumes of nitrous acid.

Nitrous acid and the peroxide of nitrogen each contains an additional proportion of oxygen, and they are still more destructive to all organization.

Nitric acid contains five volumes of oxygen united to two of nitrogen; and the well-known destructive properties of aqua fortis it is unnecessary to describe.

The atmosphere, and these chemically active compounds, contain the same elements, but their mode of combining is different; and what is, in the one case, poisonous to the highest degree, is, in the other, rendered salubrious, and essential to all organized beings.

Nitrogen gas may be regarded in the light of a diluent to the oxygen. In its pure state it is only characterised by its negative properties. It will not burn, or act as a supporter of combustion. Animals speedily perish if confined in it; but they die rather

through the absence of oxygen than from any poisonous property of this gas. Yet, in combination, we find nitrogen exhibiting powers of a most energetic character. In addition to the fulminating compounds and the explosive substances already named, which are among the most remarkable instances of unstable affinity with which we are acquainted, we have also the well-known pungent body, ammonia. From the analogous nature of this volatile compound, and the fixed alkalies soda and potash, it was inferred that it must, like them, be an oxide of a metallic base. Davy exposed ammonia to the action of potassium, and to the influence of the voltaic arc produced from 2,000 double plates, without at all changing its character. From its slight tendency to combination, and from its being found abundantly in the organs of animals feeding on substances that do not contain it, it is, however, probably a compound body. A phenomenon of an obscure and mysterious character is presented in the formation of the "ammoniacal amalgam," as it is called.

Mercury, being mixed with an ammoniacal salt, is exposed to powerful galvanic action; and a compound, maintaining its metallic appearance, but of considerable lightness and very porous, presents itself.[229] This preparation has been carefully examined by Davy, Berzelius, and others. It is always resolved into ammonia and mercury; and, although the latter chemist is strongly inclined to regard it as affording evidence of the compound nature of nitrogen,—and he has, indeed, proposed the name *nitricum* for its hypothetical base,—yet, to the present time, we have no satisfactory explanation of this apparent metallization of ammonia.

No attempt will be made to describe the various elementary substances which come under the class of metallic bodies, much less to enumerate their combinations. Many of the metals, as silver and copper, are found sometimes in a native state, or nearly pure; but, for the most part, they exist, in nature, in combination with oxygen or sulphur; gold furnishing a remarkable exception. They are occasionally found combined with other bodies,—as oxidized carbon, phosphorus, chlorine, &c.; but these cases are by no means so common. Those substances called metals are generally found embedded in the rocks, or deposited in fissures formed through them; but it is one of the great discoveries of modern science, that those rocks themselves are metallic oxides. With metals we generally associate the idea of great density; but potassium and sodium, the metallic bases of potash and soda, are lighter than water, and they consequently float upon that fluid. We learn, therefore, from the researches of science, that the crust of this earth is composed entirely of metals, combined with gaseous elements; and there is reason for believing that one, or perhaps two, of the gases we have already named are also of a metallic character. Strange as it may appear, there is nothing, as will be seen on attentive consideration, irrational in this idea. Many of the metals proper, under the influence of such heat as we can, by artificial means, command, are dissipated in vapour, and may be maintained in this state perfectly invisible. Indeed, the transparent space above the surface of the mercury in the tube of a barometer, known as the Torricellian vacuum, is filled with the vapour of mercury. There is, therefore, no reason why nitrogen, or even hydrogen, should not be metallic molecules kept by the force of the repulsive

powers of heat, or some other influence, at a great distance from each other. The peculiar manner in which nitrogen unites with mercury, and the property which hydrogen possesses of combining with antimony, zinc, arsenic, potassium, sodium, and possibly other metals, besides its union with sulphur and carbon—in all which cases there is no such change of character as occurs when they combine with oxygen—appear to indicate bodies which, chemically, are not very dissimilar to those metals themselves, although, physically, they have not the most remote resemblance.

"We know nothing," says Davy, "of the true elements belonging to nature; but, so far as we can reason from the relations of the properties of matter, hydrogen is the substance which approaches nearest to what the elements may be supposed to be. It has energetic powers of combination, its parts are highly repulsive as to each other, and attractive of the particles of other matter; it enters into combination in a quantity very much smaller than any other substance, and in this respect it is approached by no known body."[230]

Many of the elements are common to the three kingdoms of nature: most of those found in one condition of organization are discovered in another. The carbonates are an abundant mineral class. In the vegetable kingdom we find carbon combining with oxygen, hydrogen, and nitrogen: these elements, also, constitute the substance of animals, the proportion of nitrogen being, however, much larger. If one element, more than another, belongs especially to the animal economy, it is phosphorus, although this is not wanting in the vegetable world; and it is not uncommon in the mineral. Sulphur is

common to the three kingdoms: it is abundant in the mineral, being one of the products of volcanic action; it is united with the metals, forming sulphurets; and is found in our rocks in the state of sulphuric acid or oxidized vapour, combined with the metallic bases of lime and other earths. In the vegetable kingdom we discover sulphur in all plants of the onion kind, in the mustard, and some others; it enters into the composition of vegetable albumen, and appears always combined with albumen, fibrine, and caseine, in the animal economy.

Chlorine is found most abundantly in combination with sodium, as common salt: in this state, in particular, we may trace it from the depths of the earth, its waters, and its rocks, to the plants and animals of the surface. Iodine is most abundant in marine plants; but it has been found in the mineral world, traced to plants, and it is indicated in the flesh of some animals. Bromine is known to us as a product of certain saline waters, and a few specimens of natural bromide of silver have been examined. Fluorine, the base of the acid which, combining with lime, forms fluor-spar, is found to exist to some considerable extent in bones; it has been discovered in milk and blood; and investigations have proved its existence in the vegetable world. It must not be forgotten that the earths, lime and magnesia, enter into the composition of the more solid parts of plants and animals. Lime is one of the principal constituents of animal bone and shells, and it is found in nearly all vegetables.

Silica, or the *earth* of flints, is met with in beautiful transparent crystals, in the depths of the mine; in all rock and soils we find it. In the bark of many plants, particularly the grasses, it is discovered, forming the

hard supporting cuticle of the stalk, in wheat, the Dutch rush, the sugar-cane, the bamboo, and many other plants.

It is thus that we find the same elementary principle presenting itself in every form of matter, under the most Protean shapes. Numerous phenomena of even a more striking character than those selected, are exhibited in every department of chemistry; but within the limits of this essay it is impracticable to speak of any beyond those which directly explain natural phenomena.

The chemical elements, which actually exist in nature as simple bodies, are probably but few. Most of the gases are in all probability compounds of some ethereal ultimate principles; and with the advance of science we may fairly hope to discover the means of reducing some of them to a yet more simple state.

Curious relations, which can be traced through certain bodies, lead us to believe that they may be only modified conditions of one element. Flint and charcoal do not at first appear allied; but carbon in some of its states approaches very near to the condition of silicon, the metallic base of flint. When we remember the differences which are evident in three forms of one body—coke, graphite, and diamond—the dissimilitude between flint, a quartz crystal, and carbon, will cease to be a strong objection to the speculation.

Phosphorus, sulphur, and selenium, have many properties in common. Iodine, bromine, chlorine, and fluorine, appear to belong to the same group. Iron and nickel, and cobalt, have a close relation. Silver and lead are usually combined, and exhibit a strong relationship. Gold, platinum, and the rarer

metals, have so many properties in common, that they may form a separate group from all the others.

Indeed, a philosophical examination of the elements now supposed to constitute the material world, enables us to divide them into about six well-defined groups. Wide differences exist within these groups; but still we find a sufficient number of common properties to warrant our classing them in one family.

The dream of the alchemists, in the vain endeavour to realise which they exhausted their lives and dissipated their wealth, had its foundation in a natural truth. The transmutation of one form of matter into another may be beyond the power of man, but it is certainly continually taking place in the laboratory of nature, under the directing law of the great Creator of this beautiful earth.

The speculations of men, through all ages, have leaned towards this idea, as is shown by the theory of the four elements,—Air, Fire, Earth, and Water,—of the ancients, the three,—Salt, Sulphur, and Mercury,—of the alchemists, and the refined speculations of Newton and Boscovich on the ultimate constitution of matter. All experimental inquiry points towards a similar conclusion. It is true we have no direct evidence of any elementary atom actually undergoing a change of state; but when we regard the variations produced by electrical influence, the changes of state which arise from the power of heat, and the physical alterations produced by light, it will be difficult to come to any other conclusion than that the particles of matter known to us as ultimate are capable of change, and consequently must be far removed from positively simple bodies, since the real elementary atom,

possessing fixed properties, cannot be supposed capable of undergoing any transmutation. Allotropism could not occur in any absolutely simple body.

It will now be evident that in all chemical phenomena we have the combined exercise of the great physical forces, and evidences of some powers which are, as yet, shrouded in the mystery of our ignorance. The formation of minerals within the clefts of the rocks, the decomposition of metallic lodes, the germination of seeds, the growth of the plant, the development of its fruit and its ultimate decay, the secret processes of animal life, assimilation, digestion, and respiration, and all the changes of external form, which take place around us, are the result of the exercise of that principle which we call chemical.

By chemical action plants take from the atmosphere the elements of their growth; these they yield to animals, and from these they are again returned to the air. The viewless atmosphere is gradually formed into an organized being, the lordly tree upon whose branches the fowls of the air have their homes, and the human animal, exalted by being charged with a spiritual soul: yet the tree and the man alike are gradually resolved again into thin air. The changes of the mineral world are of an analogous character; but we cannot trace them so clearly in all their phenomena.

The planet on which we live began its course charged with a fixed quantity of physical force, and this has remained constant to the present moment, and will do so to the end of time. By influences external to this earth the balance of these forces is continually disturbed; and in the effort to restore the

equilibrium, we have the production of all the varied forms of matter, and the manifestation of each particular physical principle or power. As motion and attraction, balanced against each other, maintain the earth in her elliptical orbit, so the opposition of forces determines the existence of the amorphous rock, the light-refracting crystal, the fixed and flowering plant, and the locomotive animal.

An eternal round of chemical action is displayed in nature. Life and death are but two phases of its influences. Growth and decay are equally the result of its power.

FOOTNOTES:

[212] Dr. Priestley appears to have been the first to observe the peculiar property of the diffusion of gases. Dr. Dalton, however, first drew attention to the important bearing of this fact on natural phenomena, and he published his views on *The Miscibility of Gases* in the Manchester Memoirs, vol. v. The following extract from his memoir *On the Constitution of the Atmosphere* will exhibit its bearings:—

It may be worth while to contrast this view of the constitution of the atmosphere with the only other one, as far as I know, that has been entertained.

According to one view,	According to th

1. The volumes of each gas found at the surface of the earth are proportional to the whole weights of the respective atmospheres.

Azote	79
Oxygen	21
Aqueous vapour	1·33
Carbonic acid	1·0
	101·43

2. The altitude of each atmosphere differs from that of every other, and the proportions of each in the compound atmosphere gradually vary in the ascent.

3. When two atmospheres are mixed, they take their places according to their specific gravity, not in separate strata, but intermixedly. There is, however, a separate stratum of the specifically lighter atmosphere at the summit over the other.

[213] The discussion of this question, commenced by Arago in his *Eloge*, was continued by Lord Brougham in his *Lives of Watt and Cavendish*, and by Mr. Vernon Harcourt, in his address as President of the British Association, and more recently in his *Letter to Lord Brougham*. Watt's *Letters* on the subject have been since published under the superintendence of Mr. Muirhead.

[214] See several papers *On Ozone*, by Professor Schönbein, in the Philosophical Magazine, and in the Reports of the British Association. Consult a paper by the Author: *Athenæum*, September, 1849.

[215] Memoire *sur l'Ozone*; Bàle 1849. Poggendorff's *Annalen*, lxxvii., p. 592. Ibid, lxxviii. p. 162.

[216] *Chemical Gazette*, 1849.

[217] Iodide of silver has been found at Albarradon, near Mazapil, in Mexico. Iodide of mercury, of a fine lemon-yellow colour, has been discovered in the sandstone of Casas, Viegas, Mexico. Algers; Phillips' *Mineralogy*.

[218] GENTELE'S Reports of the Stockholm Academy.

[219] Stahl, taking up the obscure notions of Becher and Van Helmont, supposed the phenomena of combustion to be due to phlogiston. He imagined that by combination with phlogiston, a body was rendered combustible, and that its disengagement occasioned combustion, and after its evolution there remained either an acid or an earth: thus sulphur was, by this theory, supposed to be composed of phlogiston and sulphuric acid, and lead of the calx of lead and phlogiston, &c.

[220] Being called upon by the Solicitor for the Admiralty to examine into the causes of the fire which destroyed the *Imogene* and *Talavera*, in Devonport Arsenal, I discovered a bin under the roofing which covered these ships, in which there had been accumulating for a long period all the refuse of the wheelwrights' and painters' shop; and it was quite evident that spontaneous combustion had taken place in the mass of oiled oakum, sawdust, anti-attrition, and old sail-cloth, there

allowed to accumulate.

[221] *Researches on Flame*: Sir H. Davy's Collected Works.

[222] See note, *ante*, *On the Chemical Theory of Respiration*.

[223] At the request of the British Association, a committee undertook the investigation of this subject. Experiments were carried on by Dr. Daubeny, in the Botanic Gardens at Oxford, and by the Author, at his residence, Stockwell. Dr. Daubeny, in his report made at the meeting of the British Association at Birmingham, appears disposed to consider ten per cent. of carbonic acid in excess as destructive to the growth of ferns. I found, however, that, by gradually increasing the quantity, the ferns would live in an atmosphere still more highly charged with carbonic acid.

[224] See memoir *On the Pilchard*, by Mr. Couch, in the Reports of the Royal Cornwall Polytechnic Society.

[225] "This scale, in which the humidity of the air is expressed, is the simple natural scale in which air at its maximum of humidity (*i.e.*, when it is saturated with vapour) is reckoned as = 100, and air absolutely deprived of moisture as = 0; the intermediate degrees are given by the fraction 100 × actual tension of vapour ÷ tension required for the saturation of the air at its existing temperature. Thus, if the air at any temperature whatsoever contains vapour of half the tension, which it would contain if saturated, the degree is 50; if three-fourths, then 75; and so forth. Air of a higher temperature is capable of containing a greater quantity of vapour than air of less temperature; but it is the proportion of what it

does contain, to what it would contain if saturated, which constitutes the measure of its dryness or humidity. The capacity of the air to contain moisture being determined by its temperature, it was to be expected that an intimate connection and dependence would be found to exist between the annual and diurnal variations of the vapour and of the temperature."—Sabine, *On the Meteorology of Toronto*; Reports of the British Association, vol. xiii. p. 47. *The Temperature Tables*: by Prof. W. H. Dove; Reports for 1847 should be consulted.

[226] Sir David Brewster's *Optics*, and Memoirs in the Philosophical Transactions. Sir John Herschel's Treatise on *Light*, Encyclopædia Metropolitana.

[227] *On the Colour of Steam under certain circumstances*: by Professor Forbes; Philosophical Magazine, vol. xiv. p. 121, vol. xv. p. 25. In the first paper the following remarks occur:—"I cannot doubt that the colour of watery vapour under certain circumstances is the principal or only cause of the red colour observed in clouds. The very fact that that colour chiefly appears in the presence of clouds is a sufficient refutation of the only explanation of the phenomena of sunset and sunrise, having the least plausibility, given by optical writers. If the red light of the horizontal sky were simply complementary to the blue of a pure atmosphere, the sun ought to set red in the clearest weather, and then most of all; but experience shows that a lurid sunrise or sunset is *always* accompanied by clouds or diffused vapours, and in a great majority of cases occurs when the changing state of previously transparent and colourless vapour may be

inferred from the succeeding rain. In like manner, terrestrial lights seen at a distance grow red and dim when the atmosphere is filled with vapour soon to be precipitated. Analogy applied to the preceding observations would certainly conduct to a solution of such appearances; for I have remarked that the existence of vapour of high tension is by no means essential to the production of colour, though of course a proportionally greater thickness of the medium must be employed to produce a similar effect when the elasticity is small."

[228] *On the Law of Diffusion of Gases*: by Thomas Graham, M.A., F.R.S., &c.; Edinburgh Philosophical Transactions, 1832. *Sur l'Action Capillaire des Fissures, &c.*: by Döbereiner; Annales de Chimie, xxiv. 332.

[229] *Electro-chemical Researches on the Decompositions of the Earths, with observations on the Metals obtained from the Alkaline Earths, and on the Amalgam procured from Ammonia*: by Sir Humphry Davy; Philosophical Transactions, 1808, and collected works, vol. v. p. 102.

[230] *Elements of Chemical Philosophy*: by Sir H. Davy.

CHAPTER XIII.

TIME.—GEOLOGICAL PHENOMENA.

Time, an element in Nature's Operations—Geological Science—Its Facts and Inferences—Nebular Hypothesis applied—Primary Formations—Plutonic and Metamorphic Rocks—Transition Series—Palæozoic Rocks—Commencement of Organic Arrangements—Existence of Phosphoric Acid in Plutonic Rocks—Fossil Remains—Coal Formation—Sandstones—Tertiary Formations—Eocene, Miocene, and Pliocene Formations—Progressive changes now apparent—General Conclusions—Physics applied in explanation.

The influence of time, as an element, in producing certain structural arrangements, by modifying the operations of physical force, under whatever form it may be exerted, has scarcely been sufficiently attended to in the examination of cosmical phenomena. Every particle of matter is, as it were, suspended between the agencies to which we have been directing our attention. Under the influences of the physical powers, sometimes exerted in common, but often with a great preponderance in favour of one of them, every accumulated heap of mud or sand

is slowly cohering, and assuming the form of a rock possessing certain distinguishing features, as it regards lamination, cleavage, &c.

The minute particles of matter are necessarily but slightly influenced by the physical forces: their action in accordance with the laws which determine physical condition is manifested in an exceedingly modified degree. But in all the operations of nature, what is deficient in power is made up in time, and effects are produced during myriads of ages, by powers far too weak to give satisfactory results by any experiments which might be extended even over a century.

If, with the eye of a geologist, we take but a cursory glance over the Earth, we shall discover that countless ages must have passed during the progress of this planet to its present state. This is a fact written by the finger of nature, in unmistakeable characters, upon the mighty tablets of her mountains.

The superficial crust of the earth,—by which is meant only that film, compared with its diameter, which is represented by a few miles in depth—is composed of distinct mineral masses, exhibiting peculiar physical conditions and a certain order of arrangement. These rocks appear to have resulted from two dissimilar causes; in one class the action of heat is evident, and in the other we have either the slow deposition of matter suspended in water, or crystallization from solution; an aqueous origin is indicated by peculiarities of formation in all the more recent rocks.

There are few branches of science which admit of speculation to the extent to which we find it carried in geology. The consequences of this are shown in

the popular character of the science. A few observations are made over a limited area, and certain structural conditions are ascertained, and at once the mind, “fancy free,” penetrates the profound depths of the earth, and imagination, having “ample room and verge enough,” creates causes by which every effect is to be interpreted. Such students, generally ignorant of the first principles of physics, knowing little of mineralogy, and less of chemistry, to say nothing of palæontology, having none of the requisites for an observer, boldly assume premises which are untenable, and think they have explained a phenomenon,—given to the world a truth,—when they have merely promulgated an unsubstantiated speculation, which may have occasional marks of ingenuity, and but little else.

The carefully-made observations of those who, with unwearying industry, have traversed hill and valley, marked and measured the various characters, thicknesses, inclinations, and positions of rocks; who have watched the influences of heat in changing, of water in wearing, and the results of precipitation in forming, strata; who have traced the mechanical effects of earthquake strugglings and of volcanic eruptions, and, reasoning from an immense mass of accumulated facts, deduced certain general conclusions,—are, however, of a totally different character; and it is such observers as these who induced Herschel to say truly, that “geology, in the magnitude and sublimity of the objects of which it treats, undoubtedly ranks, in the scale of the sciences, next to astronomy.”[231]

The origin of this planet is involved in great obscurity, which the powers of the most gifted are unable to penetrate. It stands the work of an

Almighty and Eternal mind, the beginning of which we cannot comprehend, nor can we define the period of its termination.

It may, probably, be safe to speculate that there was a time when this globe consisted of only one homogeneous stratum. Whether this remains,—whether, in our plutonic rocks, our granites, or our porphyries, we have any indications of the primitive state of the world, or whether numerous changes took place before even our unstratified formations had birth, are questions we cannot answer. The geologist looks back into the vista of time, and reckons, by phenomena, the progress of the world's mutations. The stratified formations must have occupied thousands of ages; but before these were, during a period extending over countless thousands, the unstratified rocks may have been variously metamorphosed. It matters not whether we admit the nebular hypothesis or not,—a time must have been when all these bodies which now form the mass of this globe existed in the most simple state. We have already shown that very remarkable changes in external character and in chemical relations are induced, in the same simple element, by its having been exposed to some peculiar and different conditions; and already have we speculated on the probability that the advance of science will enable us to reduce the numerous elements we now reckon, to two or three. It is, therefore, by no means an irrational thought (which must, however, be held in the light of a pure conjecture), to suppose that at the beginning a mighty mass of matter, in the most attenuated state, was produced in space, and was gradually, under the influence of gravitation, of cohesive force, and of chemical aggregation, moulded into the form of a sphere. Ascending to the

utmost refinement of physics, we may suppose that this mass was of one uniform character, and that it became in dissimilar parts—its surfaces and towards its centre—differently constituted, under the influences of the same powers which we now find producing, out of the same body, charcoal and the diamond, and creating the multitudinous forms of organized creations. These conditions being established, and carried to an extent of which, as yet, science has afforded us no evidence, chemical intermixture may have taken place, and a new series of compounds have been formed, which, by again combining, gave rise to another and more complex class of bodies.

The foundation of the superficial crust of the earth appears to be formed of a class of rocks which have resulted from the slow cooling of an immense mass of heated matter. These rocks have been called *igneous*; but are now more generally termed *Plutonic* (such as granites, syenites, &c.) Immediately above these, we find rocks which have resulted by deposition from water. These masses, having been exposed to the action of the heat below, have been considerably changed in their character, and hence they are often called *metamorphic*; but metamorphic rocks may, however, be of any age. The rocks formerly termed the *transition* series—from their forming the connecting link between the earlier formations—are now, from the circumstance of their being fossiliferous, classed under the general term of palæozoic rocks, to distinguish them from the rocks in which no organic remains have been found. Above these are found the secondary strata, and, still more recently produced, we have a class now usually denominated the tertiary formations. “Eternal as the hills” is a poetic expression, implying a long

duration; but these must, from the nature of things, eventually pass away. The period of time necessary for the disintegration of a granite hill is vastly beyond the powers of computation, according to our conception of the ordinary bounds of finite things. But a consideration of the results of a few years,—under the influence of the atmosphere and the rains,—as shown in quantity of solid matter carried off by the rivers, and deposited at their mouths, will tend to carry conviction to every mind, that a degrading process is for ever in action on the surface of the earth. The earth itself may be eternal, but the surface is continually undergoing mutation, from various causes, many of which we must briefly consider.[232]

In regarding geological phenomena, the absence of any fossil remains has often been supposed to indicate a period previous to any organic formations. The inorganic constituents of matter are probably of prior origin to the organic combinations; the vessel was constructed, upon which the organic creation was to float in space before any vital organisms were created. The supposed evidences in favour of the assumption that there was no organic life during the formation of the oldest rocks we know, are in some respects doubtful; and we can well understand that changes may have been induced in the earlier rock formations, by heat or by other powers, quite sufficient to destroy all traces of organized forms. It was long thought that phosphoric acid was not to be detected in rocks which are regarded as of igneous origin; and since this acid is peculiarly a constituent of organic bodies, this has been adduced as a proof that the plutonic rocks must have existed previously to the appearance of vegetable or animal life upon the surface of the globe. The researches of modern chemists have, however, shown that phosphoric acid

is to be found in formations of granitic origin, in porphyry, basalt, and hornblende rocks.[233] If, therefore, we are to regard this substance as of organic origin, the rational inference is against the speculation; but there is no more necessity for supposing phosphorus to be formed in the animal economy than in the mineral kingdom, from which it will probably be found the animal obtained it.

Without attempting to enter into any account of the apparent progress of life over the earth, it appears desirable that some description should be given of the kinds of plants and animals which we know to have existed at different epochs. We shall thus learn, at least, some of the prevailing characteristics of the earth during its transitions, and be in a better condition for applying our knowledge of physical power to the explanation of the various geological phenomena.

Among the earliest races we have those remarkable forms, the trilobites, inhabiting the ancient ocean.

These crustacea bear some resemblance, although a very remote one, to the common wood-louse, and, like that animal, they had the power of rolling themselves into a ball when attacked by an enemy. The eye of the trilobite is a most remarkable organ; and in that of one species, *Phacops caudatus*, not less than two hundred and fifty lenses have been discovered. This remarkable optical instrument indicates that these creatures lived under similar conditions to those which surround the crustacea of the present day.

At the period of the trilobites of the Silurian rocks, all the animals contemporaneous with them had the organs necessary for the preservation of life in the waters.

Next in order of time to the trilobite, the most singular animals inhabiting those ancient seas, whose remains have been preserved, are the *Cephalopoda*, possessing some traces of organs which belong to vertebrated animals. There are numerous arms for locomotion and prehension, arranged in a centre round the head, which is furnished with a pair of sharp, horny mandibles, embedded in powerful muscles. These prehensile arms are provided with a double row of suckers, by which the animal seized its prey. Of these cephalopodous animals there are many varieties, but all of them appear to be furnished with powers of rapid locomotion, and those with shells had an hydraulic arrangement for sinking themselves to any depth of the seas in which, without doubt, they reigned the tyrants.

Passing by without notice the numerous fishes, which appear to have exhibited a similar order of progression to the other animals, we must proceed to the more remarkable period when the dry land first began to appear.

All the animals found in the strata we have mentioned are such as would inhabit the seas; but we gradually arrive at distinct evidence of the separation of the land from the water, and the “green tree yielding seed” presents itself to our attention; not that the strata earlier than this are entirely destitute of any remains indicating vegetable growth, but those they exhibit are such as, in all probability, may be referred to marine plants.

Those plants, however, which are found in the carboniferous series are most of them distinguished by all the characteristics of those which grow upon the land; we, therefore, in the mutilated remains of vegetation left us in our coal-formations, read the

history of our early world.

Then the reed-like calamite bowed its hollow and fragile stems over the edges of the lakes the tree-ferns grew luxuriantly in the shelter of the hills, and gave a wild beauty to the humid valleys; the lepidodendrons spread themselves in mighty forests along the plains, which they covered with their curious cones; whilst the sigillariæ extended their multitudinous branches, wreathing like serpents amongst the luxurious vegetation, and embraced, with their roots (stigmariæ), a most extensive space on every side.[234]

The seas and lakes of this period abounded with minute animals nearly allied to the coral animals, which are now so actively engaged in the formation of islands in the tropical and southern seas. During the ages which passed by without any remarkable disturbance of the surface of the earth, the many bands of mountain limestone were formed by the ceaseless activity of these minute architects. Encrinites (creatures in some respects resembling star-fish) existed in vast numbers in the oceans of this time; and the great variety of bivalve shells, and those of a spiral character, discovered in the rocks of this period, show the waters of the newer palæozoic period to have been instinct with life.

In the world then, as it does now, water acting on the dry land produced remarkable changes. We have evidence of extensive districts over which the most luxuriant vegetation must have spread for ages,—from the remains of plants in every state of decay,—which we find went to form our great coal-fields. These, by some changes in the relative levels of land and water, became covered with this fluid; and over this mass of decaying organic matter, sand and mud

were for ages being deposited. At length, rising above the surface, it becomes covered with vegetation, which is, after a period, submerged; the same deposition of sand and mud again takes place, it is once more fitted for vegetable growth, and thus, cycle after cycle, we see the dry land and the water changing places with each other. This will be evident to every one who will carefully contemplate a section of one of the coal-fields of Great Britain. We find a stratum of coal lying upon a bed of under clay, and above it an extensive stratum of shale or sandstone, probably formed by the denudation of the neighbouring hills; and in this manner we have many strata of coal, shale, clay, ironstone, and sandstone alternating with each other; the coal-formations of the South Wales coal-field having the extraordinary thickness of 1500 feet. The lowest bed of this extensive series must at one time have been exposed as the surface of the country.

Ascending in the series, we have now formations of a more recent character, in which fishes of a higher order of organization, creeping and flying saurians, crocodiles and lizards, tortoises, serpents, and frogs, are found. The lias formations (a term corrupted from *layers*), consisting of strata in which an argillaceous character prevails, stand next in series. In these we have animals preserved in a fossil state, of a distinguishingly different character from those of the inferior strata. We meet with extended beds of pentacrinites, some inches in thickness; and their remains are often so very complete that every part of the skeleton can be made out, although so complicated that it cannot consist of less than 150,000 parts. In these formations we often find the curiously beautiful remains of the ammonites, of which a great variety have been discovered. Of the

belemnites—animals furnished with the shell and the ink-bag of the cuttle-fish, with which it darkened the water to hide itself from enemies, numerous varieties have also been disentombed, with the ink-bag so well preserved, that the story of the remarkable fossil has been written with its own ink. In addition to these we find nautili; and sixty species of extinct fishes have been described by Agassiz from the lias of Lyme Regis alone.

When these rocks were in the progress of formation, there existed the ichthyosaurus, or fish-lizard, which appears, in many respects, to have resembled the crocodile of the Nile. It was a predatory creature of enormous power, and must have been the tyrant and terror of the seas which it inhabited. Its alligator-like jaws, its powerful eye, its fish-like fins, and turtle-like paddles, were all formed to facilitate its progress as a destructive minister. The plesiosaurus was, if possible, a still more extraordinary creation. To the head of a lizard was united an enormously long neck, a small and fish-like body, and the tail of a crocodile: it appears formed for existence in shallow waters, so that, when moving at the bottom, it could lift its head above the surface for air, or in search of its food. The flora of this period must have been extensive; and it resembled the vegetation which exists at present in Tropical regions.

We pass now to a new epoch, which is well distinguished by its animals from all that had preceded it. Races of reptiles still have place upon the earth, and we have now the megalosaurian remains; these animals possessing a strength and rapacity which would render them objects of terror as well as astonishment, could they be restored to the world which they once ravaged. An enormous

bat-like creature also existed at this time—the pterodactyl—which, in the language of Cuvier, was, "undoubtedly, the most extraordinary of all the beings of whose former existence a knowledge is granted to us, and that which, if seen alive, would appear most unlike anything that exists in the present world." "You see before you," says the same writer, "an animal which, in all points of bony structure, from the teeth to the extremities of the nails, presents the well-known saurian characteristics, and of which no one can doubt that its integuments and soft parts, its scaly armour and its organs of circulation and reproduction, are likewise analogous. But it was, at the same time, an animal provided with the means of flying; and, when stationary, its wings were probably folded back like those of a bird, although, perhaps, by the claws attached to its fingers, it might suspend itself from the branches of trees."[235]

From the disintegration of the older rocks have no doubt arisen those formations which are known as the oolitic series. In these strata are preserved the remains of plants and animals more resembling those which now exist upon the earth; and, for the first time,—unless the evidence of the footsteps of birds on the new red sandstone of America be accepted,—we meet with the remains of the feathered tribes.

In these formations we discover animals belonging to the class Mammalia,—the amphitherium and the phascolotherium,—which appear to have resembled, in many respects, the marsupial animals of New Holland.[236]

The wealden formations, which are the next in order of position, are a series of clays and sands, with subordinate beds of limestone, grit, and shale. These

have, in some instances, been formed in the sea; but they are usually regarded as fresh-water deposits. All the older rocks bear evident marks of marine origin, unless some of the coal-measure strata may be regarded as otherwise; but nearly all the wealden series contain the remains of land, fresh-water, and estuary animals, and of land vegetables. The creatures which we discover, preserved, to tell the history of this period, are numerous, and have marked peculiarities to distinguish them from those already described, or from any now existing on the earth. We find land saurians of a large kind, and animals of all sizes; even insects, of which a great variety are found in the wealds. The remarkable iguanodon was an animal which, even by the cautious measurement of Professor Owen, must have been at least twenty-eight feet long; and this enormous creature was suspected, by Cuvier, and has been proved by Owen, to have been an "herbivorous saurian for terrestrial life."[237] Dr. Mantell calculates that no less than seventy individuals of the iguanodon of all ages have come under his notice; and the bones of a vast number of others must have been broken up by the workmen in the few quarries of Tilgate grit; so that these creatures were by no means rare at the period of their existence.[238]

The uppermost of these secondary formations is the cretaceous or chalk group, which spreads over a large portion of south-eastern England, and is met with in all parts of Europe. This chalk, which is a carbonate of lime, appears to have been slowly precipitated from tranquil water, as, according to Sir Henry De la Beche, organic remains are beautifully preserved in it. Substances of no greater solidity than common sponges retain their forms, delicate shells remain unbroken, fish even are frequently not

flattened, and altogether we have the appearances which justify us in concluding that, since these organic exuviæ were entombed, they have been protected from pressure by the consolidation of the rock around them.[239]

Beneath the chalk exists what has been called, from its colour—derived from a silicate of the protoxide of iron,—green sand, and was, no doubt, formed by deposition from the same water in which the carbonate of lime was suspended,—the green sand falling to the bottom more readily from its greater specific gravity. "The tranquillity," observes Sir Henry De la Beche, "which seems to have prevailed during this great accumulation of siliceo-calcareous matter, whether it may have been a deposit from water, in which it was mechanically suspended, partly the work of living creatures, or in a great measure chemical, is very remarkable."[240]

In the chalk, the remains of the leaves of dicotyledonous plants and fragments of wood are found more abundantly than in the earlier strata, many of which are marked with the perforations of marine worms, indicating that they had floated for some time in the ocean. It should, however, be remembered, that these are not the first indications of vegetable life,—leaves have been found in the new red sandstone; and the flora of the coal formation must not be forgotten. The manner in which silica has deposited itself on organic bodies—such as the sponges—is curious; the whole of the organized tissue being often removed, and flint having taken its place. Flints formed by such a process as this abound in the upper chalk. The association of carbon and silicon, combined with oxygen, as we find them in the cretaceous formations, is most interesting, and

naturally gives rise to some speculation on the relation of these two elements. Both carbon and silicon, as has been already shown, exist in several allotropic conditions; and, although the statements made by Dr. Brown relative to the conversion of carbon into silicon are proved to be grounded on experimental error, it is not improbable that a very intimate relation may exist between these elements. [241] The probability is, that the sponge animal has the power of secreting silica to give strength to its form. "Many species," says Rymer Jones, speaking of recent sponges, "exhibiting the same porous structure, have none of the elasticity of the officinal sponge—a circumstance which is due to the difference observable in the composition of their skeletons or ramified frame-work. In such the living crust forms within its substance not only tenacious bands of animal matter, but great quantities of crystallized spicula, sometimes of a calcareous, at others of a siliceous, nature." Thus, a frame of siliceous matter being formed by the living animal, a deposition of the same substance is continued after death.

Sea-urchins and star-fish, and numerous fossil shells, are found in these beds, which, however, differ materially from the remains of the same animals found in the earlier formations. A vast number of new species and genera of fish are also discovered in the chalk.

Nearly all the animals and plants which existed up to this period are now extinct, although they have some imperfect representatives at the present day.

The uppermost group, which has been called the supercretaceous or tertiary formation, appears in our island to have been formed during four great eras, as

we find fresh-water deposits alternating with marine ones. The term *eocene*, which is the first or oldest deposit; *miocene*, which is the second; *pliocene*, which is the third; and the *newer pliocene*,—which is the fourth and last, have been applied to these formations, the names referring to the respective proportions of existing species found among their fossil shells.[242]

All these formations show distinct evidence of their having been deposited from still or slowly-flowing deep waters. Thus the eocene appears in the Paris basin,—formed clearly at an estuary, in which are mingled some interesting fresh-water deposits;—in the lacustrine formations in Auvergne; also at Aix; and in the north of Italy. It appears probable that, in the formations generally termed eocene, both fresh-water and marine deposits have been confounded, and several formations of widely-different eras regarded as the result of one. We have not yet been furnished with any distinct and clear evidence to show that the deposits of the Paris basin, and those of Auvergne, are of the same age. At all events, it is sufficient for our present purpose to know that they are the result of actions which are now as general as they were when the plastic clay of Paris, and its sulphate of lime, or the London clay, were slowly deposited.

As a general conclusion, we may decide that, at the eocene period, existing continents were the sites of vast lakes, rivers, and estuaries, and were inhabited by quadrupeds, which lived upon their thickly-wooded margins. Many remains, allied to those of the hippopotamus, have been found in the subsidences of this period.

Examples of the miocene or middle tertiary era are to

be found in Western France, over the whole of the great valley of Switzerland, and the valley of the Danube. In these deposits we find the bones of the rhinoceros, elephant, hippopotamus, and the dinotherium, an extinct animal, possessing many very distinguishing features.[243]

The pliocene period has been termed the age of elephants, and is most remarkable for the great mastodons and gigantic elks, with other animals not very unlike those which are contemporaneous with man.

In the superficial layers of the earth, the diluvium, alluvium, peat and vegetable soil, we have a continuation of the history of the mutations of our globe and of its inhabitants, which has been here so briefly sketched. They bring us up to the period when man appeared in the world, since whose creation it is evident no very extensive change has been produced upon the surface. We have viewed the phenomena of each great epoch, marked as they are by new creations of organized beings, and it would appear as if, through the whole series, from the primary rocks up to the modern alluvial deposits, a progressive improvement of the earth's surface had been effected, to fit it at last for the abode of the human race.

Thus have we preserved for us, in a natural manner, evidences which, if we read them aright, must convince us that the laws by which creation has ever been regulated are as constant and unvarying as the Eternal mind by which they are decreed. Our earth, we find, by the records preserved in the foundation-stones of her mountains, has existed through countless ages, and through them all exhibited the same active energies that prevail at the present

moment. By precisely similar influences to those now in operation, have rocks been formed, which, under like agencies, have been covered with vegetation, and sported over by, to us, strange varieties of animal life. Every plant that has grown upon the earliest rocks which presented their faces to the life-giving sun, has had its influence on the subsequent changes of our planet. Each trilobite, each saurian, and every one of the mammalia which exist in the fossil state, have been small laboratories in which the great work of eternal change has been carried forward, and, under the compulsion of the strong laws of creation, they have been made ministers to the great end of forming a world which might be fitting for the presence of a creature endued with a spark taken from the celestial flame of intellectual life.

For a few moments we will return to a consideration of the operations at present exhibiting their phenomena, and examine what bearing they have upon our knowledge of geological formations.

During periods of immense, but unknown, duration, the ocean and the dry land are seen to have changed their places. Enormous deposits, formed at the bottom of the sea, are lifted by some mechanical, probably volcanic, force, above the waters, and the land, like the ocean surrounding it, teems with life. This state of things lasts for ages; but the time arrives when the ocean again floods the land, and a new state of things, over a particular district, has a beginning.

It must not be imagined that the changes which we have spoken of, as if they were the result of slow decay and gradual deposit, were effected without occasional violent convulsions. Many of the strata

which were evidently deposited at the bottom of the sea, and, of course, as horizontal beds, are now found nearly vertical. We have evidence of strata of immense thickness having been subjected to forces that have twisted and contorted them in a most remarkable manner. Masses of solid rock, many thousand feet deep, are frequently bent and fractured throughout their whole extent. Mountains have been upheaved by internal force, and immense districts have suddenly sunk far below their usual level. By the expansive force due to that temperature which must be required to melt basaltic and trap rocks, the whole of the superficial crust of a country has been heaved to a great height, immense fissures have been formed by the breaking of the mass, and the melted matter has been forced through the opening, and overflowed extensive districts, or volcanoes have been formed, and wide areas have been buried under the ashes ejected from them. With the cause of these convulsions we are at present unacquainted.

We have evidence of the extent to which these forces may be exerted, in the catastrophes which have occurred within historical times, and which have happened even in our own day. Herculaneum and Pompeii, buried under the lava and ashes of Vesuvius, in an hour when the inhabitants of these cities were unprepared for such a fearful visitation,—the frightful earthquakes which have, from time to time, occurred in South America—are evidences of the existence of hidden forces which shake the firm-set earth. Similar ravaging catastrophes may have often occurred, and, involving cataclysms, swept the surface to produce the changes we detect over every part of the earth, compared with which the earthquakes and floods of history are but trivial things. Evidence has been adduced, to show that the

mountains of the Old World may have approached in height the highest of the Andes or Himalayas, and these have not been destroyed by any sudden effect, but by the slow disintegrating action of the elements. [244] All these phenomena are now in progress: the winds and the rains wear the faces of the exposed rock; their *débris*, mixed with decayed vegetable and animal matter, are washed off from the surface, and borne away by the rivers, to be deposited in the seas. Thus it is that the great delta of the Ganges is formed, and that a continual increase of matter is going on at the mouths of rivers. The Amazon, the Mississippi, and other great rivers, bear into the ocean, daily, thousands of tons of matter from the surface of the earth.[245] This is, of course, deposited at the bottom of the sea, and it must, in the process of time, alter the relative levels of the ocean and the land. Islands have been lifted by volcanic power from the bottom of the sea, and many districts in South America have been depressed by the same causes.

Changes as extensive have been, in all probability, effected by forces "equally or more powerful, but acting with less irregularity, and so distributed over time as to produce none of those interregnums of chaotic anarchy which we are apt to think (perhaps erroneously) great disfigurements of an order so beautiful and harmonious as that of nature."[246] These forces are, without doubt, even now in action.

Had it not been for these convulsive disturbances of the surface, the earth would have presented an almost uniform plain, and it would have been ill-adapted for the abode of man. The hills raised by the disturbances of nature, and the valleys worn by the storms of ages, minister especially to his wants, and

afford him the means of enjoyment which he could not possess had the surface been otherwise formed. The “iced mountain tops,” condensing the clouds which pass over them, send down healthful streams to the valleys, and supply the springs of the earth, thus securing the fertility and salubrity of the distant plains. The severities of climate are mitigated by these conditions, and both the people of the tropics and those dwelling near the poles are equally benefited by them.

Gravitation, cohesion, motion, chemical force, heat, and electricity, must, from that hypothetical time when the earth floated a cloud of nebulous vapour, in a state of gradual condensation up to the present moment, have been exercising their powers, and regulating the mutations of matter.

When the dry land was beneath the waters, and when darkness was upon the face of the deep, the same great operations as those which are now in progress in the depths of the Atlantic, or in the still waters of our inland lakes, were in full activity. At length the dry land appears; and—mystery of mysteries—it soon becomes teeming with life in all the forms of vegetable and animal beauty, under the aspect of the beams of a glorious sun.

Geology teaches us to regard our position upon the earth as one far in advance of all former creations. It bids us look back through the enormous vista of time, and see, shining still in the remotest distance, the light which exposes to our vision many of nature’s holy wonders. The elements which now make up this strangely beautiful fabric of muscle, nerves, and bone, have passed through many ordeals, ere yet it became fashioned to hold the human soul. No grain of matter has been added to the planet,

since it was weighed in a balance, and poised with other worlds. No grain of matter can be removed from it. But in virtue of those forces which seem to originate in the sun, “the soul of the great earth,” a succession of new forms has been produced, as the old things have passed away.

Under the forces we have been considering, acting as so many contending armies, matter passes from one condition to another, and what is now a living and a breathing creature, or a delicate and sweetly-scented flower, has been a portion of the amorphous mass which once lay in the darkness of the deep ocean, and it will again, in the progress of time, pass into that condition where no evidences of organization can be found,—again, perhaps, to arise clothed with more exalted powers than even man enjoys.

When man places himself in contrast with the Intelligences beyond him, he feels his weakness; and the extent of power which he can discover at work, guided by a mysterious law, is such, that he is dwarfed by its immensity. But looking on the past, surveying the progress of matter through the inorganic forms up to the higher organizations, until at length man stands revealed as the chief figure in the foreground of the picture, the monarch of a world on which such elaborate care has been bestowed, and the absolute ruler of all things around him, he rises like a giant in the conscious strength of his far-searching mind. That so great, so noble a being, should suffer himself to be degraded by the sensualities of life to a level with the creeping things, upon which he has the power to tread, is a lamentable spectacle, over which angels must weep.

The curious connection between the superstitions of races, the traditionary tales of remote tribes, and the

developments of the truths of science, are often of a very marked character, and they cannot but be regarded as instructive. In the wonders of “olden time” fiction has ever delighted; and a thousand pictures have been produced of a period when beings lived and breathed upon the earth which have no existence now.

Hydras, harpies, and sea-monsters, figure in the myths of antiquity. In the mythology of the northern races of Europe we have fiery flying dragons, and Poetry has placed these as the guardians of the “hoarded spirit” and protectors of the enchanted gold.

Through the whole of the romance period of European literature, nothing figures but serpents, “white and red,” toiling and fighting underground,—thus producing earthquakes, as in the story of Merlin and the building of Stonehenge. Flying monsters, griffins and others, which now live only in the meaningless embellishments of heraldry, appear to have been conceived by the earlier races of men as the representatives of power. Curious is it, too, to find the same class of ideas prevailing in the East. The monster dragons of the Chinese, blazoned on their standards and ornamenting their temples;—the Buddaical superstition that the world is supported on a vast elephant, which stands on the back of a tortoise, which again rests on a serpent, whose movements produce earthquakes and violent convulsions;—the rude decorations also of the temples of the Aztecs, which have been so recently restored to our knowledge by the adventurous travellers of Central America,—all give expression to the same mythological idea.

Do not these indicate a faint and shadowy knowledge

of a previous state of organic existence? The process of communion between man of the present, and the creations of a former world, we know not; it is mysterious, and for ever lost to us. But even the most ignorant and uncultivated races of mankind have figured for themselves the images of creatures which, whilst they do really bear some resemblance to things which have for ever passed away, do not, in the remotest degree, partake of any of the peculiarities of existing creations.

The ichthyosaurus, and the plesiosaurus, and the pterodactylus, are preserved in the rude images of harpies, of dragons, and of griffins; and, although the idea of an elephant standing on the back of a tortoise was often laughed at as an absurdity, Captain Cautley and Dr. Falconer at length discovered in the hills of Asia the remains of a tortoise in a fossil state of such a size that an elephant could easily have performed the feat.[247]

Of the ammonites, we have more exact evidence; they were observed by our forefathers, and called by them snake-stones. According to the legends of Catholic saints they were considered as possessing a sacred character:—

"Of these and snakes, each one
Was changed into a coil of stone
When holy Hilda prayed."

And in addition to this petrifying process, one of decapitation is said to have been effected; hence the reason why these *snake-stones* have no heads.

We also find, in the northern districts of our island, that the name of "St. Cuthbert's beads" is applied to the fossil remains of encrinites.

Thus we learn that, to a great extent, fiction is dependent upon truth for its creations; and we see that when we come to investigate any wide-spread popular superstition, although much distorted by the medium of error through which it has passed, it is frequently founded upon some fragmentary truth. There are floating in the minds of men certain ideas which are not the result of any associations drawn from things around; we reckon them amongst the mysteries of our being. May they not be the truths of a former world, of which we receive the dim outshadowing in the present, like the faint lights of a distant Pharos, seen through the mists of the wide ocean?

Man treads upon the wreck of antiquity. In times which are so long past, that the years between them cannot be numbered by the aids of our science, geology teaches us that forms of life existed perfectly fitted for the conditions of the period. These performed their offices in the great work; they passed away, and others succeeded to carry on the process of building a world for man. The past preaches to the present, and from its marvellous discourses we venture to infer something of the yet unveiled future. The forces which have worked still labour: the phenomena which they have produced will be repeated.

Ages on ages slowly pass away,
And nature marks their progress by decay.
The plant which decks the mountain with its bloom,
Finds in the earth, ere long, a damp dark tomb:
And man, earth’s monarch, howe’er great and brave
—
Toils on—to find at last a silent grave.
The chosen labours of his teeming mind

Fade by the light, and crumble 'neath the wind;
And e'en the hills, whose tops appear to shroud
Their granite peaks deep in the vapoury cloud,
Worn by tempests—wasted by the rains,
Sink slowly down to fill wide ocean's plains.
The ocean's breast new lands again display,
And life and beauty drink the light of day:
The powers which work at great creation's wheel,
Will from the wrecks of matter still reveal
New forms of wondrous beauty—which will rise
Pure as the flame of love's young sacrifice,
Beaming with all the pristine hues of youth,
Robed by the day, and crowned by holy truth.

FOOTNOTES:

[231] *Preliminary Discourse*; Sir J. F. W. Herschel. Lardner's Cabinet Cyclopædia.

[232] *Geological Researches*; by Sir Henry De la Beche, C.B. (*Degradation of Mountains*, p. 167.) *Geological Manual*, p. 184. *Principles of Geology*; by Sir Charles Lyell, 7th Edition, p. 150, 686. *On the Denudation of South Wales, and the adjacent countries of England*; by Professor Andrew Ramsay; Memoirs of the Geological Survey and Museum of Practical Geology, vol. i. p. 297.

[233] Fownes, *On the Existence of Phosphoric Acid in Rocks of Igneous Origin*; Phil. Trans. 1844, p. 53. Nesbitt, *Quarterly Journal of the Chemical Society*.

[234] *On the Vegetation of the Carboniferous Period as compared with that of the present day; On some peculiarities in the structure of Stigmaria; Remarks on the Structure and*

Affinities of some Lepidostrobi: by Dr. Hooker; Memoirs of the Geological Survey, &c., vol. ii. pp. 387, 431, 440.

[235] See Owen, Quarterly Journal of the Geological Society, No. 6, p. 96. Dr. Buckland, Geological Transactions, vol. iii. p. 220. *The Wonders of Geology*: by Dr. Mantell, vol. ii. p. 493.

[236] *Report on British Fossil Mammalia*: by Richard Owen, Esq., F.R.S.; British Association Reports, vols. xi. xii.

[237] *Notice on the Iguanodon, a newly discovered fossil reptile from the sandstone of Tilgate Forest, in Sussex*: by Gideon Mantell, Esq, F.R.S., &c.; Philosophical Transactions, vol. cxv. p. 179. *On the Structure of Teeth, &c.*; by Professor Owen.

[238] Dr. Mantell, *Wonders of Geology*. *Geology of the South-east of England.*

[239] *Geological Researches*; *Geological Manual*; by Sir Henry Thos. De la Beche, C.B., &c.

[240] Ibid.

[241] *Experimental Researches on the production of Silicon from Paracyanogen*: by Samuel Brown, M.D.; Transactions of the Royal Society of Edinburgh, vol. xv. p. 229. *Experiments on the alleged conversion of Carbon into Silicon*: by R. H. Brett, Ph.D., and J. Denham Smith, Esq.; Philosophical Magazine, vol. xix. p. 295, New Series. See also Dr. Brown's reply to the above, ibid, p. 388.

[242] *Geology, Introductory, Descriptive, and Practical*: by Prof. Ansted, vol. ii. p. 22.

[243] *The Wonders of Geology*: by Dr. Mantell, vol. i. p. 162. *Bridgewater Treatise*: by Dr. Buckland. Dr. J. J. Kemp, and Dr. A. V.

Klipstein, *On the Dinotherium*; Darmstadt, 1836. Cuvier and De Blainville have also carefully described the fossil remains of this animal.

[244] See Professor Ramsay's memoir *On Denudation*: Memoirs of the Geological Survey of Great Britain.

[245] "The distances to which river water, more or less charged with detritus, would flow over sea-water, will depend upon a variety of obvious circumstances. Captain Sabine found discoloured water, supposed to be that of the Amazons, three hundred miles distant in the ocean from the embouchure of that river. It was about 126 feet deep. Its specific gravity was = 1·0204, and the specific gravity of the sea-water = 1·0262. This appears to be the greatest distance from land at which river water has been detected on the surface of the ocean. If rivers, containing mechanically suspended detritus, flowed over sea-water in lines which, in general terms, might be called straight, the deposit of transported matter which they carried out would also be in straight lines. If, however, they be turned aside by an ocean current, as was the case with that observed by Captain Sabine, the detritus would be thrown, and cover an area corresponding in a great degree with the sweep which the river has been compelled to make out of the course, that its impulse, when discharged from its embouchure, might lead it to take: supposing the velocity with which this river-water was moving has been correctly estimated at about three miles per hour, it is not a little curious to consider that the agitation and resistance of its particles should be sufficient to keep finely comminuted solid matter mechanically suspended, so that it

would not be disposed freely to part with it, except at its junction with the sea-water over which it flows, and where, from friction, it is sufficiently retarded. So that a river, if it can preserve a given amount of velocity flowing over the sea, may deposit no very large amount of mechanically suspended detritus in its course from the embouchure, where it is ultimately stopped. Still, however, though the deposit may not be so abundant as at first sight would appear probable, the constant accumulation of matter, however inconsiderable at any given time, must produce an appreciable effect during the lapse of ages."—Sir Henry De la Beche's *Geological Researches*, p. 72.

[246] Sir J. F. W. Herschel: *Preliminary Treatise*.

[247] *Fauna Antiqua Sivalensis. Being the Fossil Zoology of the Sewalik Hills in the North of India*: by Hugh Falconer and Proby T. Cautley. 1844.

CHAPTER XIV.

PHENOMENA OF VEGETABLE LIFE.

Psychology of Flowers—Progress of Matter towards Organization—Vital Force—Spontaneous Generation—The Vegetable Cell—Simplest Development of Organization—The Crystal and the Cell—Primitive Germ—Progress of Vegetation—Influence of Light—Morphology—Germination—Production of Woody Fibre—Leaves—Chlorophylle—Decomposition of Carbonic Acid—Influence of Light, Heat, and Actinism on the Phenomena of Vegetable Life—Flowers and Fruits—Etiolation—Changes in the Sun's Rays with the Seasons—Distribution of Plants—Electrical and Combined Physical Powers

The variety of beautiful forms which cover the surface of this sphere, serve, beyond the physical purposes to which we have already alluded, to influence the mind, and give character to the inhabitants of every locality. There are men who

appear to be dead to the mild influences of flowers; but these sweet blossoms—the stars of our earth—exert a power as diffusive as their pervading odours.

The poet tells us of a man to whom

The primrose on the river's brim
A yellow primrose was to him,
And it was nothing more.

But it was something more. He, perhaps, attended not to the eloquent teaching of its pure, pale leaves: he might not have been conscious of the mysterious singing of that lowly flower: he might, perchance, have crushed it beneath his rude foot rather than quaff the draught of wisdom which it secreted in its cell; but the flower still ministered to that mere sensualist, and in its strange, tongueless manner, reproved his passions, and kept him "a wiser and a better man," than if it had pleased God to have left the world without the lovely primrose.

The psychology of flowers has found many students—than whom not one read them more deeply than that mild spirit who sang of the Sensitive Plant, and in wondrous music foreshadowed his own melancholy fate.[248] That martyr to sensibility, Keats, who longed to feel the flowers growing above him, drew the strong inspiration of his volant muse from those delicate creations which exhibit the passage of inorganic matter into life; and other poets will have their sensibilities awakened by the æsthetics of flowers, and find a mirror of truth in the crystal dew-drop which clings so lovingly to the purple violet, and draws fresh beauties from its coloured petals.

If we examine carefully all the conditions of matter

which we have made the subject of our studies, we cannot but perceive how gradual is the progress of the involved action of the physical forces, as we advance from the molecule—the mere particle of matter—up to the organic combination. At first we detect only the action of cohesion in forming the rude mass; then we have the influence of the crystallogenic powers giving a remarkable regularity to bodies; we next discover the influences of heat and electrical force in determining condition, and of chemical action as controlled by them. Yet, still we have a body without organization. Light exerts its mysterious powers, and the same elements assume an organized form; and, in addition to the recognized agencies, we dimly perceive others on which vitality evidently depends. These empyreal influences become more and more complicated to us: ascending in the scale, they rise beyond our science; and, at length, we find them guiding the power of intelligence, while instinct and reason are exhibited in immediate dependence upon them.

Let it not be imagined that this view has any tendency to materialism. The vital energy is regarded as a spiritualization, and reason as a divine emanation; but they are connected with materialities, on which they act, and by which they are themselves controlled. The organic combinations, and the physical powers by which these unions of matter are effected and retained, have a direct action over that ethereality which is life, and the powers of life again control these more material forces. The spirit, in whatever state, when connected with matter, is, like Prometheus chained to his rock, in a constant struggle to escape from its shackles, and assert the full power of its divine strength.

We have seen variety enough in the substances which make up the inorganic part of creation; but infinitely more varied are the forms of organization. In the vegetable world which is immediately around us, from the green slime of our marshes to the lustrous flowers of our gardens and the lordly trees of our forests, what an extraordinary diversity of form is apparent! From the infusoria of an hour, to the gigantic elephant roaming in his greatness in the forests of Siam—the noble lion of the caves of Senegal—the mighty condor of the Andes—and onward to man, the monarch of them all, how vast are the differences, and yet how complete are they in their respective conditions! In the creation we have examined, we have had conclusive evidence, that from the combination of *atoms* every peculiar form has been produced. In the creation we are about to examine, we shall discover that all the immense diversity of form, of colour, and condition which is spread over the world in the vegetable and animal kingdoms, results from the combination of *cells*. The atom of inorganic nature becomes a cell in organic creation. This cell must be regarded as the compound radical of the chemist, and by decomposing it, we destroy the essential element of organization.

With the mysterious process by which the atom is converted into a cell, or a compound radical, we are unacquainted; but we must regard the cell as the organic atom. It is in vain that the chemist or the physiologist attempts to examine this change of the inorganic elements to an organized state; it is one of the mysteries of creation, which is to be, in all probability, hid from our eyes, until this “mortal coil” is shaken off, and we enjoy the full powers of that intelligence which we are promised we shall enjoy in an immortal state.

Again and again has the attention of men been attracted to the *generatio æquivoca*; they have sometimes thought they have discovered a *generatio primitiva* or *spontanea*; but a more careful examination of these organisms has shown that an embryo existed—a real germination has taken place.

Count Rumford[249] stated that threads of silk and wool had the power of decomposing carbonic acid in water in the sunshine; and hence some have referred organization to a mere chemical change produced by luminous excitation; and we have heard of animal life resulting from pounded siliceous matter. All such statements must be regarded as evidences of imperfect investigation.

Dr. Carus, alluding to the experiments of Gruithuisen, Priestley, and Ingenhousz,[250] says: —"These show, more than any other experiments, that, in the purest water, under the influence of air, light, and heat, beings are formed, which, oscillating as it were between the animal and the plant, exhibit the primitive germs of both kingdoms."[251] Treviranus[252] repeated, and appeared to confirm these results; but in these experiments we have no evidence that the germ did not previously exist in the spring-water which was employed.

Some have regarded the cell as a crystal; they see the crystal forming, by the accumulation of atoms, into a fixed form, under the influence of an "inner life;" and, advancing but a step, they regard the cell as the result of an increased exercise of the physical influences.[253] We have referred crystalline form to certain magnetic conditions; and it is evident that the atomic cell is influenced by similar forces; but if we place a crystal in its natural fluid, though it increases in size, it never alters in form: whereas, if we

examine a cell in its natural position, it gives indications of motion, it produces other cells, and we have a development of organs which are in no respect the same in form as the original. From a vesicle floating invisible to the unaided human sense in its womb of fluid, is produced a plant possessing strange powers, or an animal gifted with volition. The idea, that two kinds of polarity—light on one side, and gravitation on the other—produce the two peculiar developments of roots and branches, can only be regarded as one of those fanciful analogies which prove more imagination than philosophy.[254]

The conditions are, however, most curious; they deserve very attentive study; but in examining the phenomena, the safest course is to allow the effects as they arise to interpret to us, and not admit the love of hypothesis to lead us into bewildering analogies; or uncertain phenomena to betray us to hasty inferences. It is of this evil that Bacon speaks, in his "Advancement of Learning." He says:—

"The root of this error, as of all others, is this, that men, in their contemplations of nature, are accustomed to make too timely a departure, and too remote a recess from experience and particulars, and have yielded and resigned themselves over to the fumes of their own fancies and popular argumentations."

Without venturing, therefore, to speculate on the origin of the primitive cell, or unit of organic life, which involves the problem of the metamorphosis of a rude mass—the primitive transformation of the rudimentary atoms into organic form,—we must admit that the highly organized plant or animal is but an aggregation of cells; their arrangement being dependent upon certain properties peculiar to them,

and the exercise of forces such as we have been studying,—all of which appear to act externally to the plant or animal itself.

Experiments have been brought forward, in which it appeared that, after all organization which could by any possibility have existed, had been destroyed by the action of fire, solutions of flint and metallic salts, have, under the influence of electric currents, exhibited signs of organic formations, and that, indeed, insects—a species of acari—have been developed in them. The experiments were said to have been made with care, and many precautions taken to shut out all chances of any error, but not all the precautions required in a matter of such exceeding delicacy; and we are bound not to receive the evidence afforded as the true expression of a fact without much further investigation. All experience,—setting aside the experiment named,—is against the supposition that pounded or dissolved flint could by any artificial means be awakened into life. Ova may have been conveyed into the vessels which contained the solutions under experiment; and in due time, although possibly quickened by electric excitation, the animals—the most common of insects—came into existence.[255]

The rapid growth of confervæ upon water has often been brought forward as evidence of a spontaneous generation, or the conversion of inorganic elements into organic forms; but it has been most satisfactorily proved that the germ must be present, otherwise no evidence of anything like organization will be developed. All the conditions required for the production of vegetable life appear to show, that it is quite impossible for any kind of plant, even the very lowest in the scale, to be formed in any other way

than from an embryo in which are contained the elements necessary for it, and the arrangements required for the various processes which are connected with its vitality.

The earth is now covered with vegetable life, but there must have existed a time when “darkness was upon the face of the deep,” and organization had not yet commenced tracing its lovely net-work of cells upon the bare surface of the ocean-buried rock. At length the mystery of organic creation began: into this science dares not penetrate, but it is privileged to begin its search a little beyond this point, and we are enabled to trace the progress of organic development through a chain of interesting results which are constantly recurring.

If we take some water, rising from a subterranean spring, and expose it to sunshine, we shall see, after a few days, a curious formation of bubbles, and the gradual accumulation of green matter. At first we cannot detect any marks of organization—it appears a slimy cloud of an irregular and undetermined form. It slowly aggregates, and forms a sort of mat over the surface, which at the same time assumes a darker green colour. Careful examination will now show the original corpuscles involved in a net-work formed by slender threads, which are tubes of circulation, and may be traced from small points which we must regard as the compound atom, the vegetable unit. We must not forget, here, that we have to deal with four chemical elements,—oxygen, hydrogen, carbon, and nitrogen, which compose the world of organized forms, and that the water affords us the two first as its constituents, gives us carbon in the form of carbonic acid dissolved in it, and that nitrogen is in the air surrounding it, and frequently mixed with it

also.

Under the influence of sunshine, we have now seen these elements uniting into a mysterious bond, and the result is the formation of a cellular tissue, which possesses many of the functions of the noblest specimens of vegetable growth. But let us examine the progress. The bare surface of a rock rises above the waters covered over with this green slime, a mere veil of delicate net-work, which, drying off, leaves no perceptible trace behind it; but the basis of a mighty growth is there, and under solar influence, in the process of time, other changes occur.

After a period, if we examine the rock, we shall find upon its face little coloured cups or lines with small hard discs. These, at first sight, would not be taken for plants, but on close examination they will be found to be lichens. These minute vegetables shed their seed and die, and from their own remains a more numerous crop springs into life. After a few of these changes, a sufficient depth of soil is formed, upon which mosses begin to develope themselves, and give to the stone a second time a faint tint of green, a mere film still, but indicating the presence of a beautiful class of plants, which, under the microscope, exhibit in their leaves and flowers many points of singular elegance. These mosses, like the lichens, decaying, increase the film of soil, and others of a larger growth supply their places, and run themselves the same round of growth and decay. By and by, funguses of various kinds mingle their little globes and umbrella-like forms. Season after season plants, perish and add to the soil, which is at the same time increased in depth by the disintegration of the rock over which it is laid, the cohesion of particles being broken up by the operations of

vegetable life. The minute seeds of the ferns floating on the breeze, now find a sufficient depth of earth for germination, and their beautiful fronds, eventually, wave in loveliness to the passing winds.

Vegetable forms of a higher and a higher order gradually succeed each other, each series perishing in due season, and giving to the soil additional elements for the growth of plants of their own species or those of others. Flowering herbs find a genial home on the once bare rock; and the primrose pale, the purple foxglove, or the gaudy poppy, open their flowers to the joy of light. The shrub, with its hardy roots interlaced through the soil, and binding the very stones, grows rich in its bright greenery. Eventually the tree springs from the soil, and where once the tempest beat on the bare cold rock, is now the lordly and branching monarch of the forest, with its thousand leaves, affording shelter from the storm for bird and beast.

Such are the conditions which prevail throughout nature in the progress of vegetable growth; the green matter gathering on a pond, the mildew accumulating on a shaded wall, being the commencement of a process which is to end in the development of the giant trees of the forest, and the beautifully tinted flower of nature's most chosen spot.

We must now consider closely the phenomena connected with the growth of an individual plant, which will illustrate the operation of physical influences throughout the vegetable world. The process by which the embryo, secured in the seed, is developed, is our first inquiry.

A seed is a highly carbonized body, consisting of integuments and embryo: between these, in most

seeds, lies a substance called the *albumen*, or *perisperm*. The embryo contains the elements of the future plant—the cotyledons, the plumule, and the radicle; the former developing into stalk and leaves, the latter into roots. This embryo hides the living principle, for the development of which it is necessary that the starch and gluten undergo a chemical change, and that an elevation of temperature is produced. The vital power is dormant —it sleeps—in the seed until the proper conditions are produced. It has been proved, that the powers of maintaining life in the seed are very great; excessive cold, sufficiently intense to freeze mercury, will not kill seed, and they resist a comparatively high temperature. It is probable that heat only destroys seeds by drying them too completely. The temperature at which seeds germinate is exceedingly varied,—those belonging to our own clime will germinate when the thermometer rises above 40° F., but the seeds of tropical plants demand that a temperature of from 70° to 84°, or even to 90°, be steadily applied to them. In some cases it has been found that even boiling the seeds has been advantageous to the future process of germination in the soil. But let us take the seed of some ordinary plant, and trace its progress.

An apparently dead grain is placed in the soil. If the temperature is a few degrees above the freezing point, and the soil holds a due quantity of water, the integument of the seed imbibes moisture and swells; the tissue is softened, and the first effort of vital force begins. The seed has now the power of decomposing water, the oxygen combines with some of the carbon of the seed, and is expelled as carbonic acid. Saussure's experiments prove this. The air above the soil in which a horse-bean was placed to

germinate, gave, before the experiment, nitrogen 210·26, and oxygen 56·29, and after germination, nitrogen 209·41, oxygen 44·38, and carbonic acid 11·27. This part of the process is but little removed from the merely chemical changes which we have already considered. We find the starch of the seed changed into gum and sugar, which affords nutritive food for the developing embryo. The seed now lengthens downwards by the radicle, and upwards by the cotyledons, which, as they rise above the earth, acquire a green colour. Here the first stage of vegetable life ends, the chemically exciting process is at an end, and a new stimulus is required to continue in full activity the vital powers. Carbonic acid is no longer given off.

The cotyledons, which are two opposite roundish leaves, act as the lungs; by them carbonic acid taken from the atmosphere is absorbed and carried by a circulating process, now in full activity, through the young plant. The carbonic acid, a compound of carbon and oxygen, is decomposed; it is deprived of its carbon, which is retained by the plant, and oxygen is exhaled. The plant at this period is little more than an arrangement of cellular tissue, a very slight development of vascular and fibrous tissue appearing as a cylinder lying in the centre of the sheath. At this point, however, we begin more distinctly to trace the operations of the new power; the impulses of life are strikingly evident.

The young root is now lengthening, and absorbing from the moisture in the soil, which always contains some soluble salts, a portion of its nutriment, which is impelled upwards by a force—probably capillary attraction and endosmose action combined—to the point from which the plumule springs. Capillary

force raises the fluids through the tubes in the stalk, and conveys them to the veins in the leaves, while the endosmose force diffuses them through the vegetable tissues. The plumule first ascends as a little twig, and, at the same time, by exerting a more energetic action on the carbonic acid than the cotyledons have done, the carbon retained by them being only so much as is necessary to form chlorophylle, or the green colouring matter of leaves, some wood is deposited in the centre of the radicle. From this time the process of lignification goes on through all the fabric,—the increase, and indeed the life, of the plant depending upon the development of a true leaf from the plumule.

It must not be imagined that the process consists, in the first place, of a mere oxidation of the carbon in the seed,—a slow combustion by which the spark of life is to be kindled;—the hydrogen of the water plays an important part, and, combining also with the carbon, forms necessary compounds, and by a secondary process gives rise again to water by combination with oxygen in the cells of the germinating grain. Nor must we regard the second class of phenomena as mere mechanical processes for decomposing carbonic acid, but the result of the combined influences of all the physical powers and life superadded.

This elongating little twig, the plumule, at length unfolds itself, and the branch is metamorphosed into a leaf. The leaf aërates the sap it receives, effects the decomposition of the carbonic acid, the water, and in all probability the ammonia which it derives from the air, and thus returns to the pores, which communicate with the pneumatic arrangements of the plant, the necessary secretions for the formation

of bark, wood, and the various proximate principles which it contains.

After the first formation of a leaf, others successively appear, all constructed alike, and performing similar functions. The leaf is the principal organ to the tree; and, indeed, Linnæus divined, and Goethe demonstrated, the beautiful fact, that the tree was developed from this curiously-formed organ.

"Keeping in view," says the poet-philosopher, "the observations that have been made, there will be no difficulty in discovering the leaf in the seed-vessel, notwithstanding the variable structure of that part and its peculiar combinations. Thus the pod is a leaf which is folded up and grown together at its edges, and the capsules consist of several leaves grown together, and the compound fruit is composed of several leaves united round a common centre, their sides being opened so as to form a communication between them, and their edges adhering together. This is obvious from capsules which, when ripe, split asunder, at which time each portion is a separate pod. It is also shown by different species of one genus, in which modifications exist of the principle on which their fruit is formed; for instance, the capsule of *nigella orientalis* consists of pods assembled round a centre, and partially united; in *nigella damascena* their union is complete."[256]

Professor Lindley thus explains the same view:—"Every flower, with its peduncle and bracteolæ, being the development of a flower-bud, and flower-buds being altogether analogous to leaf-buds, it follows as a corollary that every flower, with its peduncle and bracteolæ, is a metamorphosed branch.

"And, further, the flowers being abortive branches, whatever the laws are of the arrangement of

branches with respect to each other, the same will be the laws of the flowers with respect to each other.

"In consequence of a flower and its peduncle being a branch in a particular state, the rudimentary or metamorphosed leaves which constitute bracteæ, floral envelopes, and sexes, are subject to exactly the same laws of arrangement as regularly-formed leaves."[257]

The idea that the leaf is the principal organ of the plant, and that from it all the other organs are probably developed, is worthy the genius of the great German poet.

Every leaf, a mystery in itself, is an individual gifted with peculiar powers; they congregate in families, and each one ministers to the formation of the branch on

which it hangs, and to the main trunk of the tree of which it is a member. The tree represents a world, every part exhibiting a mutual dependence.

"The one red leaf, the last of its clan,
That dances as often as dance it can;
Hanging so light and hanging so high,
On the topmost twig that looks up at the sky,"

is influenced by, and influences, the lowest root which pierces the humid soil. Like whispering voices, the trembling leaves sing rejoicingly in the breeze and summer sunshine, and they tremble alike with agony when the equinoctial gale rends them from the parent stalk. The influences which pervade the whole, making up the sum of vital force, are disturbed by every movement throughout the system; a wound on a leaf is known to disturb the whole, and

an injury inflicted on the trunk interferes with the processes which are the functions of every individual leaf.[258]

The consideration of the physical circumstances necessary to germination and vegetable growth, brings us acquainted with many remarkable facts. At a temperature below the freezing point, seeds will not germinate; at the boiling point of water, a chemical change is produced in the grain, and its power of germinating is destroyed. Heat, therefore, is necessary to the development of the embryo, but its power must only be exerted within certain prescribed limits: these limits are only constant for the same class of seeds, they vary with almost every plant. This is apparent to every one, in the different periods required for germination by the seeds of dissimilar vegetables.

The seed is placed in the soil; shade is always—absolute darkness sometimes—necessary for the success of the germinating process. We have seen that the first operation of nature is purely a chemical one, but this manifestation of affinity is due to an exertion of force, which is directly dependent upon solar power. The seed is buried in the soil, when the genial showers of spring, and the increasing temperature of the earth, furnish the required conditions for this chemistry of life, and the plant eventually springs into sunshine. Thus we obtain evidence that even through some depth of soil the solar power, whatever it may be, is efficient, and that under its excitement the first spring of life, in the germ, is effected.

The cotyledons and the plumule being formed, the plant undergoes a remarkable change. The seed, like an animal, absorbed oxygen and exhaled carbonic

acid; the first leaves secrete carbon from carbonic acid inspired, and send forth, as useless to the plant, an excess of oxygen gas.

This power of decomposing carbonic acid is a vital function which belongs to the leaves and bark. It has been stated, on the authority of Liebig, that during the night the plant acts only as a mere bundle of fibres,—that it allows of the circulation of carbonic acid and its evaporation, unchanged. In his eagerness to support his chemical hypothesis of respiration, the able chemist neglected to inquire if this was absolutely correct. The healthy plant never ceases to decompose carbonic acid during one moment of its existence; but during the night, when the excitement of light is removed, and the plant reposes, its vital powers are at their minimum of action, and a much less quantity is decomposed than when a stimulating sun, by the action of its rays, is compelling the exertion of every vital function.

During this process, we have another example of natural organic chemistry. The four inorganic elements of which the vegetable kingdom is composed—oxygen, hydrogen, nitrogen, and carbon —are absorbed as air or moisture by the leaves and through the roots, and the great phenomenon of vegetable life is the conversion of these to an organic condition. Sugar and gum are constantly produced, and from these, by combination with atmospheric nitrogen, a proteine compound is formed, which is an essential element in the progress of development. [259]

Plants growing in the light are beautifully green, the intensity of colouring increasing with the brilliancy of the light. Those which are grown in the dark are etiolated, their tissues are weak and succulent, their

leaves of a pale yellow. It is, therefore, evident that the formation of this chlorophylle—as the green colouring matter of leaves is called—results from some action determined by the sun's rays.

Chlorophylle is a carbonaceous compound formed in the leaves, serving, it would appear, many purposes in the process of assimilation. In the dark the plant still requires carbon for its further development, and growing slowly, it removes it from the leaves, decomposing the chlorophylle, and supports its weak existence by preying on parts of its own structure, until at length, this being exhausted, it actually perishes of starvation.

Plants always turn towards the light: the guiding power we know not, but the evidence of some impulsive or attracting force is strong; and the purpose for which they are constituted to obey it, is proved to be the dependence of vegetable existence upon luminous power.

Light is not, however, alone sufficient to perfect the plant: another agent is required to aid in the production of flowers and fruits, and this power is proved to be heat—and heat, perhaps, in some peculiar condition. Having reached that point of development when the reproductive functions are, by another change in the chemical operations going on within the vegetable structure, to be called forth, it has been found that the heat rays become in a remarkable manner effective. It has also been observed that plants bend from the red, or calorific rays, instead of towards them, as they are found to do to every other ray of the spectrum. From this we may argue that the influence of these rays is to check the vegetation, and thus to ensure the perfection of the reproductive processes.

It has already been stated that we have the means of separating, to a considerable extent, the three principles which we discover in the sunbeam, from each other, by the use of absorbent media.

By a peculiar yellow glass we cut off the chemical principle of the sunbeam, and admit the passage of the *luminous rays* only—LIGHT.

By a cobalt blue glass we obstruct the *light*, but allow the chemical agent to pass through freely, without, indeed, any loss—ACTINISM.

By a glass coloured deep blood-red by oxide of gold we obstruct the chemical principle and much of the light, but such a medium is perfectly transparent to HEAT.

Therefore, this gives us the means of experimenting with either of these principles, and of examining the parts which they respectively play in the work of organization.

Some seeds being placed in the soil, in every respect in their natural conditions, duly supplied with moisture, and a uniform and proper temperature maintained, we place above the soil the three media above named, and allow one portion to be exposed to all the ordinary influences of the solar rays.

The result will be, that the seeds under the blue glass will germinate long before those which are exposed to the combined influences of the sunshine: a few of the seeds will struggle into day under the red glass, but the process of germination is entirely checked under the yellow glass. Here we see that the chemical radiations have quickened the chemical changes, and accelerated the process, under the red glass, through which rays having some peculiar chemical action pass; the germinating process,

though checked, is not entirely stopped. Whereas, it would appear that under the influences of light which has been deprived of chemical power, this conversion of the starch into gum and sugar, which appears to be necessary, is entirely prevented.

If the experiment is continued, it will be found that under the blue glass the plants grow rapidly, but weakly; and that instead of producing leaves and wood they consist chiefly of stalk, upon which will be seen here and there some abortive attempts to form leaves. When the process of germination has terminated, if the young plant is brought under the yellow glass, it grows most healthfully, and forms an abundance of wood, the leaves having an unusually dark green colour, from the formation of a large quantity of chlorophylle. Plants do not, however, produce flowers with readiness under this medium; but if, at the proper period, they are brought under the red glass, the flowering and fruiting processes are most effectively completed.[260]

These experiments, simple as they are, prove to us the importance of light: the *luminous principle* of the sunbeam is exciting the vital powers of the plant to decompose carbonic acid and form wood; and the calorific agent, possibly under those modifications which have already been noticed as belonging to the parathermic rays, is essential to the production of flower and fruit.

Observations, which have been extended over many years, prove that with the seasons these solar powers are, relatively to each other, subject to an interesting change. In the spring, the actinic or chemical power prevails, and during this period its agency is required for the vitalization of the germ. As the summer comes on, the actinic rays diminish, and those of

light increase. Perhaps it would be more strictly correct to say that the luminous intensity being increased, the chemical power was retarded; the former expression implies a variation in quantity, which may not be correct. We see the necessity for this, since luminous power is required for the secretion of the carbon, with which the woody fibre is formed, and also for the elaboration of the proximate principles of the plant. Autumn, the season of fruit, is characterized by an increase of the heat rays, and a diminution of the others: this change being necessary, as science now teaches us, for the due production of flower and fruit.

The calorific rays of the solar beam, to which the autumnal phenomena of vegetation appear particularly to belong, are of a peculiar character. They have been called, the Parathermic rays, and exhibit a curious compound nature. To these rays we may refer the ripening of fruit and grain, and the browning of the leaf before its fall. May not the rise of the sap in spring be traced to the excitement of either light or actinism, and its recession, in the autumn, to that power from which the plant is found to bend, and which appears to be their modified form of heat?

There can be no doubt that the varieties of climate and the peculiarities of countries, as it regards their animal and vegetable productions, are dependent on the same causes. The distribution of species has been referred by some to specific centres of creation around which the plants and animals have spread, without reference to physical conditions. Although centres of creation may be admitted, these centres themselves have been determined by the physical fitness of each centre to the conditions of the

creation, and in like manner the migration of tribes is solely due to these physical forces we have been considering. In every zone we find that vegetable organization is peculiarly fitted for the considerations by which it is surrounded. Under the equator we have the spice-bearing trees, the nutmeg, the clove, the cinnamon, and the pepper-tree; there we have also the odoriferous sandal, the ebony, the banyan, and the teak: we have frankincense, and myrrh, and other incense-bearing plants; the coffee-tree, the tea-plant, and the tamarind.

A little further north we have the apricot, the citron, the peach, and the walnut. In Spain, Sicily, and Italy, we have the orange and lemon-tree blooming rich with perfume, and the pomegranate and the myrtle growing wild upon the rocks. Beyond the Alps the vegetation again changes; instead of the cypress, the chesnut, and the cork-tree, which prevail to the south of them, we have the hardier oak, the beech, and the elm. Still further north, we have the Scotch and spruce fir and larch. On the northern shores of the Baltic, and in that line of latitude, the hazel alone appears; and beyond this the hoary alder, the sycamore, and the mountain ash. Within the Arctic circle we find the mezereum, the water-lilies, and the globe-flowers; and, when the weakness of the solar radiations becomes too great even for these, the reindeer moss still lends an aspect of gladness to the otherwise sterile soil.

The cultivation of vegetables depends on the temperature of the clime. The vine flourishes where the mean annual temperature ranges between 50° and 73°, and it is only cultivated profitably within 30° S. and 50° N. of the equator. To the same limits is confined the cultivation of maize and of olives.

Cotton is grown profitably up to latitude 46° in the Old World, but only up to 40° in the New. We have evidence derived from photographic phenomena, that the constitution of the solar rays varies with the latitude. The effects of the sun's rays in France and England in producing chemical change are infinitely more decided than, with far greater splendour of light, they are found to be in the lands under or near the equator. Indeed, the remarks made on the variations in the character of the sunbeam with the changing seasons, may apply equally to the variations in latitude.

Fungals are among the lowest forms of vegetation, but in these we have peculiarities which appear to link them with the animal kingdom. Marcet found that mushrooms absorbed oxygen, and disengaged carbonic acid. In all probability this is only a chemical phenomenon of a precisely similar character to that which we know takes place with decaying wood. In the conversion of wood into *humus*, oxygen is absorbed, and combining with the carbon, it is evolved as carbonic acid. Of course we have the peculiar condition of vitality to modify the effect, and we have, too, in this class of plants, the existence of a larger quantity of nitrogen than is found in any other vegetating substance.

These few sketches of remarkable phenomena connected with vegetation are intended to show merely the operations of the physical powers of the universe, so far as we know them, upon these particular forms of organization. During the process of germination, electricity is, according to Pouillet, evolved; and again, in ripening fruits, there appears to be some evidence of electrical currents. Vegetables are, however, in the growing state, such good

conductors of electricity, that it is not, according to the laws of this force, possible that they should accumulate it; so that the luminous phenomena stated to have been observed cannot be due to this agency. We know, however, that under every condition of change, whether induced by chemical or calorific action, electricity is set in motion; and we have reasons for believing that the excitation of light will also give rise to electrical circulation.

The question, whether plants possess sensation, whether they have any disposition of parts at all analogous to the nervous system of animals, has been often put forward, but as yet the answers have been unsatisfactory. The point is one well worthy all the attention of the vegetable physiologist; but regarding plants as the link between the animal and the mineral kingdom,—looking upon phyto-chemistry, as exhibited by them, as the means employed to produce those more complex organizations which exist in animals,—we necessarily consider plants as mere natural machines for effecting organic arrangements, and, as such, that they cannot possess any nervous sensibility. Muscular contraction may be represented in many of their marvellous arrangements; and any disturbance produced by natural or artificial means would consequently effect a change in the operations of those forces which combine to produce vegetable life. Indeed, the experiments of Carlo Matteucci, already referred to, prove that an incision across a leaf, the fracture of a branch, or the mere bruising of any part of the plant, interferes with the exercise of that power which, under the operation of luminous agency, decomposes carbonic acid, and effects the assimilation of the other elements.

To recapitulate. A plant is an organized creation; it is so in virtue of certain strange phyto-chemical operations, which are rendered active by the solar influences involved in the great phenomena of light, and by the excitation of caloric force mid electrical circulation. It is a striking exemplification of the united action of certain empyreal powers, which give rise to the combination, of inorganic principles under such forms that they become capable of obeying the mysterious impulses of life.

The poet has imaged the agency of external powers in various shapes of spiritualized beauty. From the goddess Flora, and her attendant nymphs, to the romantic enchantress who called up flowers by the light touch of her wand, we have, in all these creations, foreshadowings of the discovery of those powers which science has shown are essential to vegetable life. A power from without influences the plant; but the animal is dependent upon a higher agency which is potent within him.

The poet's dream pleases the imaginative mind; and, associating in our ideas all that is graceful and loveable in the female form, with that diviner feeling which impresses the soul with the sense of some unseen spirituality, we perceive in the goddess, the enchantress, or the sylph, pure idealizations of the physical powers. The spirit floating over these forms of beauty, and adorning them with all the richness of colour—painting the rose, and giving perfume to the violet—is, in the poet's mind, one which ascends to nearly the highest point of etherealization, and which becomes, indeed, to him a spirit of light; they ride upon the zephyrs, and they float, in all the luxury of an empyreal enjoyment, down to the earth upon a sunbeam. Such is the work of the

imagination. What is the result of the search of plodding science after truth? The sunbeam has been torn into rays, and every ray tasked to tell of its ministry.

Nature has answered to some of the interrogations; and, passing over all the earth, echoed from plant to plant, we have one universal cry proclaiming that every function of vegetable life is due to the spirits of the sun.

The mighty Adansonia of Senegal, hoary with the mosses of five thousand years,—the Pohon upas in their deadly valleys,—the climbing lianas of the Guiana forests,—the contorted serpent-cactus on the burning hills,—the oaks, which spread their branches in our tempered climes,—the glorious flowers of the inter-tropical regions, and those which gem our virent plains,—the reindeer lichen of northern lands, and the confervæ of the silent pool,—the greatest and humblest creations of the vegetable world,—all proclaim their direct dependence upon the mysterious forces which are bound together in the silver thread of Light.

These undulations, pulsations too refined for mortal ears, which quicken and guide these wonderful organisms, may be indeed regarded as sphered music for ever repeating the Divine command, "*Let there be Light*," by the creation of which, a dark and dreary chaos was moulded into a star of beauty, capable of radiating brightness to other space-wandering worlds.

FOOTNOTES:

[248] Percy Bysshe Shelley.

[249] *Experiments on the production of dephlogisticated air from water with various substances*: by Lieut.-General Sir Benjamin, Count of Rumford; Phil. Trans., vol. lxxvii. p. 84.

[250] *Experiments upon Vegetables, discovering their great power of purifying the common air in the Sunshine, and of injuring it in the Shade and at Night; to which is joined, A new method of examining the accurate degrees of Salubrity of the Atmosphere*, by John Ingenhousz, Councillor of the Court, and Body Physician to their Imperial and Royal Majesties, F.R.S., &c. London: printed for P. Elmsley, in the Strand, and H. Payne, Pall Mall, 1779.

[251] *The Kingdoms of Nature, their life and affinity*: by Dr. C. G. Carus; Scientific Memoirs, vol. i. p. 223.

[252] In *Biologie*, by G. R. Treviranus, vol. ii. p. 302, the following passage occurs:—"If we expose spring water to the sun in open or even closed transparent vessels, after a few days bubbles rise from the bottom, or from the sides of the vessel, and a green crust is formed at the same time. Upon observing this crust through a microscope, we discover a mass of green particles, generally of a round or oval form, very minute, and overlaid with a transparent mucous covering, some of them moving freely, whilst others, perfectly similar to these, remain motionless and attached to the sides of the vessel. This motion is sometimes greater than at others. The animalcules frequently lie as if torpid, but soon recover their former activity."

[253] *On the Structure of the Vegetable Cell*: by Mohl.—Scientific Memoirs, vol. iv. p. 113.

Outlines of Structural and Physical Botany: by Henfrey.

[254] Dr. Carus, in the memoir already quoted, says:—"But since, in the organization of the earth, light and air, as constituting a second integrant part, stand opposed to gravitation, and since the plant bears a relation, not only to gravitation, but to light also, when its formation is complete it will necessarily present a second anatomical system, namely, that of the spiral vessels, which have been very justly considered, of late, as the organs that perform in plants the functions of nerves."

[255] Mr. Crosse's Experiments in the Journal of the London Electrical Society, and Mr. Weekes in the Electrical Magazine, and a communication appended to *Explanations: a Sequel to the Vestiges of the Natural History of Creation*.

[256] *Die Metamorphose der Pflanzen*: Goethe, sect. 78.

[257] Lindley's *Elements of Botany*.

[258] See the very curious experiments of C. Matteucci. Traduit et extrait du "*Cimento*."—Archives des Sciences Physiques et Naturelles; *Quelques Expériences sur la Respiration des Plantes*. Nov. 1846.

[259] Consult *Rural Economy*, by J. B. Boussingault; *The Chemical and Physiological Balance of Organic Nature*, by Dumas and Boussingault; and *Agricultural Chemistry*, by Liebig.

[260] The practical value of the discovery now described, will be best understood from the following letter from Mr. Lawson, of Edinburgh:—

Edinburgh, 1, George the
Fourth's Bridge,
Sept. 8, 1853.

MY DEAR SIR,—I am favoured with yours of the 5th, relative to my practical experience in the effect of the chemical agency of coloured media on the germination of seeds and the growth of plants.

I must first explain that it is our practice to test the germinating powers of all seeds which come into our warehouses before we send them out for sale; and, of course, it is an object to discover, with as little delay as possible, the extent that the vital principle is active, as the value comes to be depreciated in the ratio it is found to be dormant. For instance, if we sow 100 seeds of any sort, and the whole germinate, the seed will be the highest current value; but if only 90 germinate, its value is 10 per cent. less; if 80, then its value falls 20 per cent.

I merely give this detail to show the practical value of this test, and the influence it exerts on the fluctuation of prices.

Our usual plan formerly was to sow the seeds to be tested

in a hot-bed or frame, and then watch the progress and note the results. It was usually from eight to fourteen days before we were in a condition to decide on the commercial value of the seed under trial.

My attention was, however, directed to your excellent work, “On the Physical Phenomena of Nature,” about five years ago, and I resolved to put your theory to a practical test. I accordingly had a case made, the sides of which were formed of glass coloured blue or indigo, which case I attached to a small gas stove for engendering heat; in the case shelves were fixed in the inside, on which were placed small pots wherein the seeds to be tested were sown.

The results were all that could be looked for: the seeds freely germinated in from two to five days only, instead of from eight to fourteen days as before.

I have not carried our experiments beyond the germination of seeds, so that I cannot afford practical information as to the effect of other rays on the after

culture of plants.

I have, however, made some trials with the yellow ray in preventing the germination of seeds, which have been successful; and I have always found the violet ray prejudicial to the growth of the plant after germination. —I remain, my dear Sir,

Very faithfully yours,

CHARLES LAWSON.

CHAPTER XV.

PHENOMENA OF ANIMAL LIFE.

Distinction between the Kingdoms of Nature—Progress of Animal Life—Sponges—Polypes—Infusoria—Animalcula—Phosphorescent Animals—Annelidans—Myriapoda—Animal Metamorphoses—Fishes—Birds—Mammalia—Nervous System—Animal Electricity—Chemical Influences—Influence of Light on Animal Life—Animal Heat—Mechanical Action—Nervous Excitement—Man and the Animal Races, &c.

"A stone grows; plants grow and live; animals grow, live, and feel." Such were the distinctions made by Linnæus, between the conditions of the three kingdoms of nature. We cannot, however, but regard them as in all respects illogical. The stone—a solid mass of unorganized particles—enlarges, if placed in suitable conditions, by the accretion of other similar particles around it; but it does not, according to any meaning in which we use the word, *grow*. Plants and animals grow; and they differ, probably, only in the phenomena of sensation. Yet, the trembling mimosa, and several other plants, appear to possess as much feeling as sponges and some of the lower classes of

animals. By this definition, however, of the celebrated Swedish naturalist, we have a popular and simple expression of a great fact.

As we have only to examine the question of the agency of the physical forces upon animal life, we must necessarily confine our attention to the more striking phenomena with which science has made us acquainted; and, having briefly traced the apparent order in which the advance of organization proceeded, we must direct our few concluding remarks to the physico-physiological influences, which we must confess to know but too imperfectly.

We learn that, during the states of progress which geology, looking into the arcana of time, has made us acquainted with, a great variety of animal forms were brought into existence. They lived their periods. The conditions of the surface of the earth, the sea, or the atmosphere, were altered; and, no longer fitted for the enjoyments of the new life, these races passed away, and others occupied their places, which, in turn, went through all the stages of growth, maturity, and decay; until at length, the earth being constituted for the abode of the highest order of animals, they were called into existence; and man, the intellectual monarch of the world, was placed supreme amongst them all. Types of nearly all those forms of life which are found in the fossil state are now in existence; and if we examine the geographical distribution of animals—the zones of elevation over the surface of the earth, and the zones of depth in the ocean,—we shall find, now existing, animal creations strikingly analogous to the primitive forms and conditions of the earth's inhabitants. From the depths of the ocean we may even now study—as that most indefatigable

naturalist, Professor Edward Forbes, has done—the varying states of organization under the circumstances of imperfect light and varying temperature.[261]

The gradual advance of animal life in the ascending strata has led to many speculations, ingenious and refined, on the progressive development of animals. That the changes of the inorganic world have impressed new conditions on the organic structures of animals, to meet the necessities of their being, must be admitted. Comparative anatomy has demonstrated that such supposed differences really existed between the creatures of secondary formations—those of the tertiary and the present periods. It has been imagined, but upon debatable foundations, that the atmosphere, during the secondary periods, was highly charged with carbonic acid; and, consequently, that though beneficial to the growth of plants, and peculiarly fitted for the conditions required by those which the fossil flora makes us acquainted with, it was not adapted to support any animals above the slow-breathing, cold-blooded fishes and reptiles. Under the action of the super-luxuriant vegetation of these periods, this carbonic acid is supposed to have been removed, an addition of oxygen furnished; and thus, consequently, the earth gradually fitted for the abode of warm-blooded and quick-breathing creatures. We do, indeed, find a very marked line between the fossil remains of the lias formations which enclose the saurians, and the wealden, in which birds make their appearance more numerously than in any previous formation.

Founded upon these facts, speculations have been put forth on the gradual development of animals

from the lowest up to the highest orders. Between the polype and man a continuous series has been imagined, every link of the chain being traced into connection with the one immediately succeeding it; and, through all the divisions, zoophytes, fishes, amphibia, reptiles, birds, and mammalia are seen, according to this hypothesis, to be derived by gradual advancement from the preceding orders. The first having given rise to amphibia,—the amphibion gives birth to the reptile,—the reptile advances to the bird,—and from this class is developed the mammal. A slight investigation will convince us that this view has no foundation. Although a certain relationship may be found between some of the members of one class, and those of the other immediately joining it, yet this is equally discovered to exist towards classes more remote from each other; and in no one instance can we detect anything like the passage of an animal of one class into an animal of another. Until this is done, we cannot but regard the forms of animal life as distinct creations, each one fitted for its state of being, springing from the command of the great First Cause.[262]

But it is time to quit these speculative questions, and proceed to the examination of the general conditions of animal life at the present time.

Lowest in the scale of animals, and scarcely distinguishable from a vegetable, we find the sponge, attached to and passing its life upon a rock, exhibiting, indeed, less signs of feeling than many of the vegetable tribes. The chemical differences between vegetables and sponges are, however, very decided; and we find in the tissues of the sponge a large quantity of nitrogen, a true animal element, which exists, but in smaller quantities, in vegetables.

These creations, standing between vegetable and animal life, possess the singular power of decomposing carbonic acid, as plants do; and the water in which they live always contains an excess of free oxygen.

The polypes are a remarkably curious class. “Fixed in large arborescent masses to the rocks of tropical seas, or in our own climate attached to shells or other submarine substances, they throw but their ramifications in a thousand beautiful and plant-like forms; or, incrusting the rocks at the bottom of the ocean with calcareous earth, separated from the water which bathes them, they silently build up reefs and shoals, justly dreaded by the navigator; and sometimes giving origin, as they rise to the surface of the sea, to islands, which the lapse of ages clothes with luxuriant verdure, and peoples with appropriate inhabitants.”[263]

Most of the polypes are fixed and stationary; but the hydra and some others have the power of changing their positions, which they do in search of the light of the sun. They do not appear to have organs of sight requiring light; but still they delight in the solar influences. The most extraordinary fact connected with the hydra is its being multiplied by division. If an incision be made in the side of a hydra, a young polype soon developes itself; and if one of these creatures be divided, it quickly restores the lost portion of its structure. The varieties of the polypes are exceedingly numerous, and many of them are in the highest degree curious, and often very beautiful. The actiniæ, like flowers, appear to grow from the rocks, unfolding their tentacula to the light; and, in the excitement due to their eagerness for prey, they exhibit a beautiful play of colours and most

interesting forms. Microscopic zoophytes of the most curious shapes are found,—all of which attest, under examination, the perfection of all created things.

Infusoria and animalcula,—animals, many of them, appearing under the microscope as little more than a transparent jelly,—must be recognized as the most simple of the forms of life. They exist in all waters in uncountable myriads; and, minute creatures as they are, it has been demonstrated that many of the great limestone hills are composed entirely of their remains.

The acalephæ, or the phosphorescent animals of the ocean, are no less curious. From creatures of the most minute size, they extend to a considerable magnitude, yet they appear to be little more than animated masses of sea-water. If any one of these sea-jellies, or jelly-fishes as they are often called (even the largest varieties of them), is cast upon the shore, it is soon, by the influence of the sun, converted into a mere fibre no thicker than a cobweb: an animal weighing seven or eight pounds is very soon reduced to as many grains. There are numerous kinds of these singular creatures, most of which are remarkable for the powerful phosphorescent light they emit. The *beroes* and the *pulmonigrade* shine with an intense white light many feet below the surface, whilst the *Cestum Veneris*, or girdle of Venus, gliding rapidly along, presents, on the edge of the wave, an undulating riband of flame of considerable length. There can be no doubt that this arises from the emission of phosphorescent matter of an unknown kind from the bodies of these animals.

The microscope has made us familiar with the mysteries of a minute creation which we should not

otherwise have comprehended. These creatures are found inhabiting the waters and the land, and they exist in the intestinal structure of plants and animals, preying upon the nutritive juices which pass through their systems. Although these beings are so exceedingly small that even the most practised observer cannot detect them with the naked eye, they are proved, by careful examination under the microscope, to be in many cases elaborately organized. Ehrenberg has discovered in them filamentary nerves and nervous masses, and even vessels appropriated to the circulation of fluids, showing that they belong really to a high condition of existence.

Passing over many links in that curious chain which appears to bind the animal kingdom into a complete whole, we come to the articulata of Cuvier—the homogangliata of Owen.

All those creatures which we have been hitherto considering are too imperfect in the construction of their simple organizations to maintain a terrestrial existence; they are, therefore, confined to a watery medium. In the articulata, we have evidences of higher attributes, and indications of instincts developed in proportion to the increased perfection of organization. Commencing with the annelidans, all of which, except the earthworms, are inhabitants of the waters, we proceed to the myriapoda, presenting a system intermediate in every respect between that of worms and insects; we then find embraced in the same order, the class insecta, which includes flies and beetles of all kinds; and, as the fourth division of articulated beings, the arachnidans or spiders; and, lastly, the marine tribe of crustaceans.

The most remarkable phenomena connected with these animals are the metamorphoses which they undergo. The female butterfly, for instance, lays eggs, which, when hatched, produce caterpillars: these live in this state for some time, feeding upon vegetables, and, after casting their skins as they increase in size, at last assume an entirely different state, and, dormant in their oblong case, they appear like dead matter. This chrysalis, or pupa, is generally preserved from injury by being embedded in the earth, from which, after a season, a beautifully perfect insect escapes, and, floating on the breeze of summer, enjoys its sunshine, and revels amidst its flowers.

No less remarkable is the metamorphosis of the caducibranchiate amphibia, passing through the true fish condition of the tadpole to the perfect air-breathing and four-footed animal, the frog.

A metamorphosis of the crustaceans, somewhat similar to that which takes place in insects, has been of late years creating much discussion amongst naturalists: but the question appears to be now settled by the careful and long-continued observations of Mr. Thompson and Mr. R. C. Couch.

A wide line of demarcation marks the separation of the invertebrata from the four great classes of vertebrate animals—fishes, reptiles, birds, and mammalia. Every part of the globe,—the ocean and the inland lake,—the wide and far-winding river, and the babbling stream,—the mountain and the valley, —the forest with its depth of shade, and the desert with its intensity of light,—the cold regions of the frost-chained north, and the fervid clime within the tropics—presents for our study innumerable animals, each fitted for the conditions to which it is destined;

and through the whole we find a gradual elevation in the scale of intelligence, until at last, separated from all by peculiar powers, we arrive at man himself.

In each of these four classes the animals are furnished with a bony skeleton, which is in the young animal little more than cartilage; but, as growth increases, lime becomes deposited, and a sufficient degree of hardness is thus produced to support the adult formation. Some anatomists have endeavoured to show that even in the mechanical structure of the bony fabrics of animals, we are enabled to trace a gradual increase in the perfection of arrangement, from the fish until the most perfect is found in man. Many of the mammalia, however, are furnished with skeletons which really surpass that of man. These belong to animals which depend for subsistence upon their muscular powers, and with whom man is, in this particular, on no equality. What is the lord of the creation, compared with the antelope for fleetness, or with the elephant and many other animals for strength?

As we ascend the scale of animal life we find a more perfectly developed nervous system; and the relative size of the brain, compared with that of the brute, is found progressively to increase, until it arrives at the utmost perfection in man. On the system of nerves depends sensation, and there can be no doubt that the more exalted the order of intelligence displayed, the more exquisitely delicate is the nervous system. Thus, in this world, refined genius must necessarily be attended with a condition of sensibility which, too frequently, to the possessor is a state of real disease.

It must be evident to every reader that but very few of the striking features of animal life have been mentioned in the rapid survey which has been taken

of the progress of animal organization. The subject is so extensive that it would be quite impossible to embrace it within any reasonable limits; and it furnishes matter so curious and so instructive, that, having once entered on it, it would have been difficult to have made any selection, and we must have devoted a volume to the æsthetics of natural science. Passing it by, therefore, with the mere outline which has been given, we must proceed to consider some of the conditions of vitality.

Bell has proved that one set of nerves is employed in conveying sensation to the brain, and another set in transferring the desires of the will to the muscles. By the separation of a main branch of one of the nerves of sensation, although all the operations of life will still proceed, the organ to which that nerve goes is dead to its particular sense. In like manner, if one of the nerves of volition is divided, the member will not obey the inclination of the brain. It is evident, therefore, although many of the great phenomena of vital force are dependent on the nervous system, and the paralysis of a member ensues upon the separation or the disease of a nerve, that the nerves are but the channels through which certain influences are carried. The *vis vitæ* or vital principle —for we are compelled by the imperfection of our knowledge to associate under this one term the ultimate causes of many of the phenomena of life—is a power which, although constantly employed, has the capability of continually renewing itself by some inexplicable connection existing between it and many external influences. We know that certain conditions are necessary to the health of animals. Diseased digestion, or any interruption in the circulation of the blood, destroys the vital force, and death ensues. The processes of digestion and of the

circulation are perfectly understood, yet we are no nearer the great secret of the living principle.

Animals are dependent on several external agents for the support of existence. The oxygen of the air is necessary for respiration. Animal heat, as will be shown presently, is in a great measure dependent upon it. The external heat is so regulated that animal existence is comfortably supported. Electricity is without doubt an essential element in the living processes; and, indeed, many physiologists have been inclined to refer vital force to the development of electricity by chemical action in the brain. This view has, however, no foundation in experiment beyond that afforded by the appearance of electric currents, when the brain is excited. This proves no more than that the operations of mind develope physical power in the matter with which it is mysteriously connected.

The phenomena of the Torpedo and Gymnotus we have already noticed,[264] and there are other creatures which certainly possess the power of secreting and discharging electricity. Galvani's experiments, and those of Aldini, appear to show—and the more delicate researches of Matteucci have satisfactorily determined—that currents of electricity are always circulating in the animal frame;—that positive electricity is constantly passing from the interior to the exterior of a muscle. Matteucci, by arranging a series of muscles, has formed an electric pile of some energy.[265] These currents have been detected in man, in pigeons, fowls, eels, and frogs.

In the human body it is evident a large quantity of electricity exists in a state of equilibrium. Du Bois Raymond has shown that we may by mere muscular motion give rise to electric currents which can be

measured by the galvanometer. This, however, may be said of every substance. It is perhaps more easily disturbed in the human system; indeed, the manifestation of sparks from the hair and other parts of the body by friction is not uncommon. Every chemical action, it has been already shown, gives rise to electrical manifestations; and the animal body is a laboratory, beautifully fitted with apparatus, in which nearly every chemical process is going on. It has been proved that acid and alkaline principles are constantly acting upon each other through the tissues of the animal frame; and we have the curious phenomena of endosmose and exosmose in constant effort, and catalysis or *surface force*, operating in a mysterious manner.[266]

With the refined physiological questions connected with the phenomena of sensation we cannot deal, nor will any argument be adduced for or against the hypothesis which would refer these phenomena to some extraordinary development of electric force in the brain. The entire subject appears to stand beyond the true limits of science, and every attempt to pass it is invariably found to lead to a confused mysticism, in which the real and the ideal are strangely confounded. Science stops short of the phenomena of vital action.

We cannot, however, but refer to the idea entertained by many that the brain is an electric battery, and the nerves a system of conductors. On this view Sir John Herschel remarks:—"If the brain be an electric pile constantly in action, it may be conceived to discharge itself at regular intervals, when the tension of the electricity reaches a certain point, along the nerves which communicate with the heart, and thus excite the pulsation of that organ."

Priestley, however, appears to have been the first to promulgate this idea.

Light is an essential element in producing the grand phenomenon of life, though its action is ill understood. Where there is light, there is life, and any deprivation of this principle is rapidly followed by disease of the animal frame, and the destruction of the mental faculties. We have proof of this in the squalor of those whose necessities compel them to labour in places to which the blessings of sunshine never penetrate, as in our coal-mines, where men having everything necessary for health, except light, exhibit a singularly unhealthy appearance. The state of fatuity and wretchedness to which those individuals have been reduced who have been subjected for years to incarceration in dark dungeons, may be referred to the same deprivation. Again, in the peculiar aspect of those people who inhabit different regions of the earth under varying influences of light, we see evidence of the powerful effects of solar action. Other forces, as yet undiscovered, may, in all probability do, exert decided influences on the animal economy; but, although we recognize many effects which we cannot refer to any known causes, we are perfectly unable to imagine the sources from which they spring.

It will be interesting now to examine the phenomena of animal heat, the consideration of which naturally leads us to consider the digestive system, the circulatory processes, and the effects of nervous excitation.

The theory, which attributes animal heat to the combination of the carbon of the food taken into the stomach with the oxygen of the air inspired through the lungs, has become a very favourite one. It must,

however, be remembered that it is by no means new. The doctrines of Brown, known as the Brunonian system, and set forth in his *Elementa Medicinæ*, are founded upon similar hasty generalizations. Although, without doubt, true in a certain degree, it is not so to the extent to which its advocates would have us believe. That the carbonaceous matter received into the stomach, after having undergone the process of digestion, enters into combination with the oxygen breathed through the lungs or absorbed by the skin, and is given off from the body in the form of carbonic acid, and that, during the combination, heat is produced, by a process similar to that of ordinary combustion, is an established fact; but the idea of referring animal heat entirely to this chemical source, when there are other well-known causes producing calorific effects, is an example of the errors into which an ingenious mind may be led, when eagerly seeking to establish a favourite hypothesis.

Animal and vegetable diet, which is composed largely of carbon and hydrogen, passes into the digestive system, and becomes converted into the various matters required for the support of the animal structure. The blood is the principal fluid employed in distributing over the system the necessary elements of health and vigour, and for restoring the waste of the body. This fluid, in passing through the lungs, undergoes a very remarkable change, and not merely assumes a different colour, but really acquires new properties, from its exposure to the air with which the cells of these organs are filled. By a true chemical process, the oxygen is separated from the air, that oxygen is made to combine with the carbon and hydrogen, and carbonic acid and water are formed. These are

liberated and thrown off from the body either through the lungs or by the skin. In the processes of life, as far as we are enabled to trace them, we see actions going on which are referred to certain causes which we *appear* to explain. Thus, the combination of the oxygen of the air with the carbon of the blood is truly designated a case of chemical affinity; and we find that in endeavouring to imitate the processes of nature in the laboratory, we are, to a certain extent, successful. We can combine carbon and oxygen to produce carbonic acid; and we know that the result of that combination is the development of certain definite quantities of heat. Let us examine the conditions of this chemical phenomenon, and we shall find that in the natural and artificial processes,—for we must be allowed to make that distinction,—there are analogous circumstances. If we place a piece of pure carbon, a lump of charcoal or a diamond, in a vessel of air, or even of pure oxygen gas, no change will take place in either of these elements, and, however long they may be kept together, they will still be found as carbon or diamond, and oxygen gas. If we apply heat to the carbon until it becomes incandescent, it immediately begins to combine with the oxygen gas,—it burns;—after a little time all the carbon has disappeared, and we shall find, if the experiment has been properly made, that a gas is left behind which is distinguished by properties in every respect the reverse of those of oxygen, supporting neither life nor combustion, whereas oxygen gives increased vigour to both. We have now, indeed, carbonic acid gas formed by the union of the two principles.

A dead mass of animal matter may be placed in oxygen gas, and, unless some peculiar conditions are in some way brought about, no change will take

place; but, if it were possible to apply the *spark of life* to it, as we light up the spark in the other case, or if, as that is beyond the power of man, we substitute a living creature, a combination between the carbon of the animal and the gas will immediately begin, and carbonic acid will be formed by the waste of animal matter, as in the other case it is by the destruction of the carbon; and, if there is not a fresh supply given, the animal must die, from the exhaustion of its fabric. Now, in both these cases, it is clear that, although this chemical union is a proximate cause of heat, there must be existing some power superior to it, as the ultimate cause thereof.

The slow combustion (*eremacausis*) of vegetable matter, decomposing under the influence of moisture and the air, does not present similar conditions to those of the human body, although it has been insisted upon to be in every respect analogous. That the results resemble each other is true, but we must carefully distinguish between effects and causes; and the results of chemical decomposition in inert matter differ from those in the living organism. The vegetable matter has lost the principle of organic life, and, that gone, the tendency of all things being to be resolved into their most simple forms, a disunion of the elements commences: oxygen, hydrogen, and carbon pass off either in the gaseous state or as water, whilst some carbon is liberated in a very finely-divided condition, and enters slowly into combination with oxygen supplied by the water or the air. Hydrogenous compounds are at the same time formed, and, under all these circumstances, as in all other chemical phenomena, an alteration of temperature results. Heat results from the chemical changes, and eventually true combustion begins.

The animal tissue may act in the same way as platina has already been shown to act in producing combination between gases; but of this we have no proof. We know that electricity is capable of producing the required conditions, and we also learn, from the beautiful researches of Faraday, that the quantity of electricity developed during decomposition is exactly equal to that required to effect the combination of the same elements. Thus it is quite clear that, during the combination of the carbon of the blood with the oxygen of the air, a large amount of electricity must become latent in the compound. The source of this we know not: it may be derived from some secret spring within the living structure, or it may be gathered from the matter surrounding it. There is much in nervous excitation which appears like electrical phenomena, and attempts have been frequently made to refer sensation to the agency of electricity. But these are the dreams of the ingenious, for which there is but little waking reality.

Every mechanical movement of the body occasions the development of heat; every exertion of the muscles produces sensible warmth; and, indeed, it can be shown by experiment that every expansion of muscular fibre is attended with the escape of caloric, and its contraction with the absorption of it. There are few operations of the mind which do not excite the latent caloric of the body, and frequently we find it manifested in a very remarkable manner by a suddenly-awakened feeling. The poet, in the pleasure of creation, glows with the ardour of his mind, and the blush of the innocent is but the exhibition of the phenomenon under some nervous excitation, produced by a spirit-disturbing thought. Thus we see that the processes of digestion and respiration are

not the only sources of animal heat, but that many others exist to which much of the natural temperature of the body must be referred.

So much that is mysterious belongs to the phenomena of life, that superstition has had a wide scope for the exercise of its influence; and through all ages a powerful party of mankind have imagined that the spirit of human curiosity must be checked before it advances to remove the veil from any physiological causes. Hence it is that even at the present day so much that stands between what, in our ignorance, we call the real and the supernatural, remains uninvestigated. Even those men whose minds are sceptical upon any development of the truths of great natural phenomena,—who, at all events, will have proof before they admit the evidence, are ready to give credit to the grossest absurdities which may be palmed upon them by ingenious charlatans, where the subject is man and his relations to the spiritual world.

Man, and the races of animals by which he is surrounded, present a very striking group, consider them in whatever light we please. The gradual improvement of organic form, and the consequent increase of sensibility, and eventually the development of reason, are the grandest feature of animated creation.

The conditions as to number even of the various classes are not the least remarkable phenomena of life. In the lowest orders of animals, creatures of imperfect organization,—consequently those to whom the conditions of pain must be nearly unknown,—increase by countless myriads. Of the infusoria and other beings, entire mountains have been formed, although microscopes of the highest

powers are required to detect an individual. Higher in the scale, even among insects, the same remarkable conditions of increase are observed. Some silkworms lay from 1,000 to 2,000 eggs; the wasp deposits 3,000; the ant from 4,000 to 5,000. The queen bee lays between 5,000 and 6,000 eggs according to Burmeister; but Kirby and Spence state that in one season the number may amount to 40,000 or 50,000. But, above all, the white ant (*Termes fatalis*) produces 86,400 eggs each day, which, continuing for a lunar month, gives the astonishing number of 2,419,200, a number far exceeding that produced by any known animal.

These may appear like the statements in which a fictionist might indulge, but they are the sober truths discovered by the most pains-taking and cautious observers. And it is necessary that such conditions should prevail. These insects, and all the lower tribes of the animal kingdom, furnish food for the more elevated races. Thousands are born in an hour, and millions upon millions perish in a day. For the support of organic life, like matter is required; and we find that the creatures who are destined to become the prey of others are so constituted that they pass from life with a perfect unconsciousness of suffering. As the animal creation advances in size and strength, their increase becomes limited; and thus they are prevented from maintaining by numbers that dominion over the world which they would be enabled from their powers to do, were their bands more numerous than we now find them.

The comparative strength, too, of the insect tribes has ever been a subject of wonder and of admiration to the naturalist. The strength of these minute creatures is enormous; their muscular power, in

relation to their size, far exceeds that of any other animal. The grasshopper will spring two hundred times the length of its own body. The dragonfly, by its strength of wing, will sustain itself in the air for a long summer day with unabated speed. The house-fly makes six hundred strokes with its wings, which will carry it five feet, every second. The stag-beetle, were it the size of the elephant, would be able to tear up the largest mountains.

Such are the wonders of the natural world; from the zoophyte, growing like a flowering plant[267] upon an axis filled with living pith—a small remove from the conditions of vegetable life, upwards through the myriads of breathing things—to man, we see the dependence of all upon these physical powers which we have been considering.

To trace the effects of those great causes through all their mysterious phases is the work of inductive science; and the truths discovered tend to fit us for the enjoyment of the eternal state of high intelligence to which every human soul aspires.

That which the ignorant man calls the supernatural, the philosopher classes amongst natural phenomena. The ideal of the credulous man becomes the real to him who will bend his mind to the task of inquiry. Therefore to attempt to advance our knowledge of the unknown, to add to the stores of truth, is an employment worthy the high destiny of the human race. Remembering that the revelations of natural science cannot in any way injure the revelation of eternal truth, but, on the contrary, aid to establish in the minds of the doubting a firm conviction of its Divine origin and of man’s high position, we need never fear that we are proceeding too far with any inquiry, so long as we are cautious to examine the

conditions of our own minds, that they be not made the dupe of the senses.

In the fairies of the hills and valleys, in the gnomes of the caverns, in the spirits of the elements, we have the attempts of the mind, when the world was young, to give form to the dim outshadowings of something which was then felt to be hidden behind external nature.

In the Oread, the Dryad, and the Nereid, we have, in like manner, an embodiment of powers which the poet-philosopher saw in his visions presiding over the mountain, the forest, and the ocean. Content with these, invested as they were with poetic beauty, man for ages held them most religiously sacred; but the progress of natural science has destroyed this class of creations. “Great Pan is dead,” but the mountains are not voiceless; they speak in a more convincing tone; and, instead of the ear catching the dying echo of an obscure truth, it is gladdened with the full, clear note of nature in the sweetest voice proclaiming secrets which were unknown to the dreams of superstition.

FOOTNOTES:

[261] *Reports of the Fauna of the Ægean*: by Professor Forbes.—Reports of the British Association. *On the Physical Conditions affecting the Distribution of Life in the Sea and the Atmosphere, &c.*: by Dr. Williams. Swansea.

[262] *The Vestiges of the Natural History of Creation.*

[263] *General Outline of the Animal Kingdom*: by Professor Thomas Rymer Jones, F.Z.S.

[264] In addition to the memoirs already referred to, Note p. 211, see Carlisle, *On the battery of the Torpedo, governed by a voluntary muscle*.—Phil. Trans., vol. xcv. p. 11. Todd, *Experiments on the Torpedo of the Cape of Good Hope*.—Ibid., vol. cvi. p. 120. Todd, *Experiments on the Torpedo Electricus at La Rochelle*.—Ibid., vol. cvii. p. 32.

[265] For a concise account of these experiments see *Elements of Natural Philosophy*: by Golding Bird, A.M., M.D., &c. 3rd Edition, chap, xx p. 336. In this work all the most recent researches are given, and the authorities referred to; see also Matteucci's interesting papers already quoted.

[266] *On the laws according to which the mixing of fluids, and their penetration into permeable substances, occurs, with special reference to the processes in the Human and Animal Organism*, by Julius Vogel, of Giessen: translated for the Cavendish Society. Liebig, *On the Motion of the Juices in the Animal Body*.

[267] *A General Outline of the Animal Kingdom*: by Thomas Rymer Jones, p. 54, et seq.

CHAPTER XVI.

GENERAL CONCLUSIONS.

The Changes produced on Physical Phenomena by the Movement of the Solar System considered —Exertion of the Physical Forces through the Celestial Spaces—The Balance of Powers—Varieties of Matter—Extension of Matter—Theory of Nonentity—A Material Creation an indisputable fact —Advantages of the Study of Science—Conclusion.

We have examined terrestrial phenomena under many of the harmonious conditions which, with our limited intelligence, we can reach by the aid of science. From the first exhibition of force, in the cohesion of two atoms, onward to the full development of organic form in the highest order of animals, we have observed strange influences. We have seen the solitary molecule invested with peculiar properties, and regulated by mighty forces; we have learned that the modes of motion given to this beautiful sphere produce curious changes in the operation of these powers; and we may with safety infer that every atom constituting this globe is held in wonderful suspension against every atom of every star, in the celestial spaces, even to that bright orb in the centre of the Pleiades, around which the entire system of created worlds is supposed to roll.

As we move around our own sun—in the limited

period of 365 days, and round our own axis in 24 hours—we experience transitions from heat to cold, dependent upon our position in regard to that luminary and the laws which regulate the reception and retention of certain physical forces. May we not therefore conclude, without being charged with making any violent deduction, that in the great revolution of our system around the centre of space, we are undergoing gradual changes which are essential to the great scheme of creation, though at present incomprehensible to us?

In our consideration of the influence of time on the structure of the earth as we find it, we discovered that, in ages long past, the vegetation of the tropics existed upon these northern parts of the globe; and geological research has also proved that over the same lands the cold of an arctic winter must have long prevailed—the immense glaciers of that period having left the marks of their movements upon the face of the existing rocks.[268] We know that during 3,000 years no change of temperature has taken place in the European climate. The children of Israel found the date and the vine flourishing in Canaan; and they exist there still. Arago has shown that a trifling alteration of temperature would have destroyed one or the other of these fruit-bearing trees, since the vine will not ripen where the mean temperature of the year is higher than 84°, or the date flourish where it sinks below that degree.

How immense, then, the duration of time since these changes must have taken place! The 432,000 years of Oriental mythology is a period scarcely commensurable with these effects; yet, to the creature of three-score years, that period appears an eternity. The thirty-three millions of geographical

miles which our solar system traverses annually, if multiplied by three thousand years, during which we know no change has taken place, give us 99,000,000,000 as the distance passed over in that period. How wide, then, must have been the journey of the system in space to produce the alteration in the physical powers, by which these changes have been effected!

We have an example, and a striking one, of the variations which may be produced in all the physical conditions of a world, in those disturbances of Uranus which led to the discovery of Neptune. For thirty years or more certain perturbations were observed in this distant planet, the discovery of Sir William Herschel, and calculation pointed to some still more remote mass of matter as the cause, which has been verified by its actual discovery. But now Uranus is at rest;—quietly that star progresses in its appointed orbit,—Neptune can no longer, for the present, cause it to move with greater or less rapidity —they are too remote to produce any sensible influence upon each other. Consequently, for thirty years, it is evident, phenomena must have occurred on the surface of Uranus, which can be no longer repeated until these two planets again arrive at the same positions in their respective paths which they have occupied since 1812. These considerations assist us in our attempts to comprehend infinite time and space; but the human mind fails to advance far in the great sublimity.

Through every inch of space we have evidence of the exercise of such forces as we have been considering. Gravitation chains world to world, and holds them all suspended from the mystic centre. Cohesion binds every mass of matter into a sphere, while motion

exerts a constant power, which tends to alter the form of the mass. The earth's form—a flattened spheroid—the rings of Saturn and of Neptune are the consequences of motion in antagonism to cohesion. Heat, radiating from one planet to another, does its work in all, giving variety to matter. Light seeks out every world—each trembling star tells of the mystery of its presence. Where light and heat are, chemical action, as an associated power, must be present; and electricity must do its wondrous duties amongst them all. Modified by peculiar properties of matter, they may not manifest themselves in phenomena like those of our terrestrial nature; but the evidence of light is a sufficient proof of the presence of its kindred elements; and it is difficult to imagine all these powers in action without producing some form of organization. In the rounded pebble which we gather from the sea-shore, in the medusa floating bright with all the beauty of prismatic colour in the sun-lit sea,—in the animal, mighty in his strength, roaming the labyrinthine forests, or, great in intelligence, looking from this to the mysteries of other worlds,—in all created things around us, we see direct evidence of a beautiful adjustment of the balance of forces, and the harmonious arrangement of properties.

One atom is removed from a mass and its character is changed; one force being rendered more active than another, and the body, under its influence, ceases to be the same in condition. The regulation which disposes the arrangements of matter on this earth, must exist through the celestial spaces, and every planet bears the same relation to every other glittering mass in heaven's o'erarching canopy, as one atom bears to another in the pebble, the medusa, the lion, or the man. An indissoluble bond unites

them all, and the grain of sand which lies buried in the depth of one of our primary formations, holds, chained to it by these all-pervading forces, the uncounted worlds which, like luminous sand, are sprinkled by the hand of the Creator through the universe. Thus we advance to a conception of the oneness of creation.

The vigorous mind of that immortal bard who sang "of man's first disobedience," never, in the highest rapture, the holiest trance of poetic conception, dreamed of any natural truths so sublime as those which science has revealed to us.

The dependence of all the systems of worlds upon each other, every dust composing each individual globe being "weighed in a balance," the adjustment of the powers by which every physical condition is ordered, the disposition of matter in the mass of the earth, and the close relation of the kingdoms of nature,—are all revelations of natural truths, exalting the mind to the divine conception of the universe.

There is a remarkable antagonism displayed in the operation of many of these forces. Gravitation and cohesion act in opposition to the repellent influences of caloric. Light and heat are often associated in a very remarkable manner; but they are certainly in their radiant states in antagonism to chemical action, whether produced by the direct agency of actinic force, or through the intermediate excitement of the electrical current.[269] And in relation to chemical force, as manifested in organic combinations, we have the all-powerful operation of LIFE preventing any exercise of its decomposing power.[270] As world is balanced against world in the universe, so in the human fabric, in the vegetable structure, in the crystallized gem, or in the rude rock, force is

weighed against force, and the balance hangs in tranquillity. Let but a slight disturbance occasion a vibration of the beam, and electricity shakes the stoutest heart with terror, at the might of its devastating power.[271] Heat melts the hardest rocks, and the earth trembles with volcanic strugglings; and actinic agency, being freed from its chains, speedily spreads decay over the beautiful, and renders the lovely repulsive.

We know matter in an infinite variety of forms, from the most ponderous metal to the lightest gas; and we have it within our power to render the most solid bodies invisible in the condition of vapour. Is it not easy, then, to understand that matter may exist equally attenuated in relation to hydrogen, as that gas itself is, when compared with the metal platinum? A doubt has been raised against this view, from the difficulty of accounting for the passage of the physical elements through solid masses of matter. If we, however, remember that the known gases have the power of transpiration through matter in a remarkable degree,[272] and that the passage of water through a sieve may be prevented by heat, it will be at once apparent that the permeation of any radiant body through fixed solid matter is entirely a question of conditions.

We can form no idea of the size of the ultimate atom; we cannot comprehend the degree of etherealization to which matter may be extended. Our atmosphere, we have seen, is only another condition of the same elements which compose all the organized forms of matter upon the earth, and, at the height reached by man, it is in a state of extreme attenuation. What must be its condition at the distance of forty miles from the earth? According to known laws, certain

phenomena of refraction have led us to set these bounds to the matter constituting our globe: but it may exist in such a state of tenuity, that no philosophical instrument constructed by human hands could measure its refracting power; and who shall declare with certainty that matter itself may not be as far extended as we suppose its influences to be?

“Hast thou perceived the breadth of the earth? declare if thou knowest it all.

“Knowest thou the ordinances of heaven? Canst thou set the dominion thereof in the earth?”

A cheerless philosophy, derived from the transcendentalism of the German schools, by an unhappy metaphysical subtlety, and grafted upon what professes to be a positive philosophy, but which is not so, is spreading amongst us, and would teach us to regard all things as the mere exhibition of properties, a manifestation of powers; it believes not in a material creation. The grandeur of the earth, and the beautiful forms adorning it, are not entities. Yonder exquisite specimen of the skill of man, in which mind appears to shine through the marble,—that distant mountain which divides the clouds as they are driven by the winds across it,—those trees, amid whose branches the birds make most melodious music,—this flower, so redolent of perfume, so bright in colour, and so symmetric in form,—and that lovely being who, a model of beauty and grace, walks the earth an impersonation of love and charity blended, making, indeed, “a sunshine in a shady place,” are not realities. Certain forces combine to produce effects, all of which unite to deceive poor man into the belief that he is a material being, and the inhabitant of a material world. There may be ingenuity in the philosophy of this school; its

metaphysics may be of a high order; but it evidently advances from the real to the ideal with such rapidity, that every argument is based on an assumption without a proof; every assumption being merely a type of the philosophy itself,—a baseless fabric, a transcendental vision.

A material creation surrounds us. This earth, all that it contains, and the immense hosts of stellar worlds, are absolute entities, surrounded with, and interpenetrated by, certain exhibitions of creative intelligence, which perform, according to fixed laws, the mighty labours upon which depend the infinite and eternal mutations of matter. The origin of a grain of dust is hidden from our finite comprehensions; but its existence should be a source of hope, that those minds which are allowed the privilege of tracing out its marvellous properties,—of examining the empyreal principles upon which its condition, as a grain of dust, depends,—and even of reducing these giant elements to do our human bidding,—may, after a period of probation, be admitted to the enjoyment of that infinite power to which the great secrets of creation will be unveiled.

Every motion which the accurate search of the experimentalist has traced, every principle or power which the physicist has discovered, every combination which the chemist has detected, every form which the naturalist has recorded, involves reflections of an exalting character, which constitute the elements of the highest poetry. The philosophy of physical science is a grand epic, the record of natural science a great didactic poem.

To study science for its useful applications merely, is to limit its advantages to purely sensual ends. To pursue science for the sake of the truths it may

reveal, is an endeavour to advance the elements of human happiness through the intelligence of the race. To avail ourselves of facts for the improvement of art and manufactures, is the duty of every nation moving in the advance of civilization. But to draw from the great truths of science intelligible inferences and masterly deductions, and from these to advance to new and beautiful abstractions, is a mental exercise which tends to the refinement and elevation of every human feeling.

The mind thus exercised during the mid-day of life, will find in the twilight of age a divine serenity; and, charmed by the music of nature, which, like a vesper hymn poured forth from pious souls, proclaims in devotion's purest strain the departure of day, he will sink into the repose of that mysterious night which awaits us all, tranquil in the happy consciousness that the sun of truth will rise in unclouded brilliancy, and place him in the enjoyment of that intellectual light, which has ever been among the holiest aspirations of the human race.

The task of wielding the wand of science,—of standing a scientific evocator within the charmed circle of its powers, is one which leads the mind through nature up to nature's God.

Experiment and observation instruct us in the discovery of a fact;—that fact connects itself with natural phenomena,—the ultimate cause of which we learn from Divine revelation, and receive in full belief,—but the proximate causes are reserved as trials of man's intelligence; and every natural truth, discovered by induction, enables the contemplative mind to deduce those perfect laws which are exemplifications of the fresh-springing and all enduring POETRY OF SCIENCE.

FOOTNOTES:

[268] "As to the polishing and grooving of hard rocks, it has lately been ascertained that glaciers give rise to these effects when pushing forward sand, pebbles, and rocky fragments, and causing them to grate along the bottom. Nor can there be any doubt that icebergs, when they run aground on the floor of the ocean, imprint similar marks upon it."—*Principles of Geology, or the modern changes of the Earth and its Inhabitants considered as illustrative of Geology*: by Charles Lyell, M.A., F.R.S. *Travels through the Alps of Savoy, and other parts of the Pennine Chain, with Observations on the Phenomena of Glaciers*: by James D. Forbes, F.R.S.

[269] This may be readily proved by the following simple but instructive experiment:—Take two pairs of watch-glasses; into one pair put a solution of nitrate of silver, into the other a weak solution of iodide of potassium; connect the silver solution of each pair with the potash one by a film of cotton, and carry a platina wire from one glass into the other. Place one series in sunshine, and the other in a dark place. After a few hours it will be found that the little galvanic arrangement in the dark will exhibit, around the platina wire, a very pretty crystallization of metallic silver, but no such change is observable in the other exposed to light. If a yellow glass is interposed between the glass and the sunshine, the action proceeds as when in the dark. This experiment is naturally suggestive of many others, and it involves some most important considerations.

[270] In cases of violent death it is often found the gastric juice has, in a few hours, dissolved

portions of the stomach.—Dr. Budd's Lecture before the College of Physicians.

[271] Faraday's *Experimental Researches*, vol. i.; from which a quotation has already been made, showing the enormous quantity of electricity which is latent in matter.

[272] *On the Motion of Gases*: by Professor Graham, F.R.S.—Phil. Trans., vol. cxxxvi. p. 573.

INDEX.

Absorption of heat by air, water, and earth, 74.
—— of light, 125.
Acalephæ, or phosphorescent animals, 387.
Actinism, 166.
—— producing chemical change, 174.
—— and light antagonistic, 177.
——, influence of, on plants, 372.
Action of presence—*Catalysis*, 280.
"Active principles" of Newton, 11.
Adams on planet Neptune, 32.
Adiathermic bodies, 95.
Aërial currents dependent on heat, 80.
—— chemical, 274.
Affinity, 292.
Age of the world, 404.
Aggregation, attraction of, 48.
——, crystalline, 58.
Agonic lines, 244.
Air, absorption of heat by, 74.
—— density of the, 319.
Alchemy, Nature's, 293.
Aldini on animal electricity, 393.
Allotropic conditions of atoms, 43.
Allotropism, 330.
Allotropy, 291.
Alum, opacity to heat rays, 65.
Alpinus' theory of matter, 47.

Ammonites of the lias, 341.
Ammoniacal amalgam, 325.
Ampère's theory of magnetism, 239.
Analogy, dangers of reasoning by, 152.
Ancients' knowledge of magnetism, 235.
Animals, phosphorescence of, 154.
—— respiration of, 310.
—— articulated, 388.
Animal magnetism, 267.
—— electricity, 211, 392.
—— life, progress of, 338.
——, phenomena of, 383.
Arago on the surface of the sun, 123.
—— on copying the Egyptian temples, 177.
—— on magnetic variation, 246.
Arbor Dianæ—silver tree, 261.
Aristotle on motion, 10.
Atmosphere, uses of the, 319.
Atmospheric refraction, 322.
Atomic theory, 278.
—— volumes, 287.
Atoms, allotropic state of, 43.
Atom, the organic, 360.
——, ultimate size of, 408.
——, the, and its powers, 3.
Attraction, chemical, 275.
Aurora of the sun, 186.

Back's account of Aurora, 249.
Balance of forces, 14.
Bartholin on Iceland spar, 140.
Beccaria, Father, on phosphorescence, 160.

Becquerel's experiments on electricity, 227.
—— on ozone, 300.
Bell on the nerves, 391.
Belemnites, 341.
Berkeley, Bishop, on motion, 10.
Berzelius on allotropy, 44.
—— on catalysis, 281.
Biela's comet, 26.
Biot on polarization, 145.
Bolognian stone, 161.
Bouguer on the absorption of light by the atmosphere, 126.
Boutigny on heat, 107.
Boletus igniarius, 102.
Boyle on motion, 9.
Brain and nerves, 391.
Brahminical philosophy, 245.
Brewster, Sir D., refers magnetism to the sun, 263.
—— on magnetism, 247.
Brown's doctrines of life, 395.
Butterfly, metamorphosis of, 389.

Cagniard de la Tour state, 106.
Calorific transparency, 65.
—— influence on plants, 376.
Calotype, the, 174.
Canton's phosphorus, 161.
Carbon, allotropic state of, 43.
Carboniferous plants, fossil, 339.
Carbonic acid, solid, 111.
—— quantity in atmosphere, 311.

Cassini on magnetic variation, 246.
Catalysis, 280.
Cell, organic, 361.
Cellini, Benvenuto, on the carbuncle, 159.
Central sun, doctrine of a, 27.
Changes, physical, 290.
Chemical phenomena developing heat, 42.
—— decomposition producing heat, 97.
—— combination by heat, 98.
—— affinity suspended by heat, 109.
—— radiations, 166.
—— power of solar rays in the Tropics, 177.
—— agency of luminous rays, 178.
—— action influenced by magnetism, 252.
—— forces, 270.
—— elements, 272.
—— proportions, 285.
—— metamorphoses, 289.
—— phenomena, 295.
—— composition of atmosphere, 322.
—— rays, action of, on germination, 375.
Chemistry, Electro, 206.
—— of Nature, 270.
—— Animal, 396.
Chinese knowledge of magnet, 236.
Chlorophylle, formation of, 373.
Chloride of sulphur, transparency of, to heat, 65.
Chlorine and hydrogen combine by light, 171.
Chlorine in the ocean, 303.
Cholera and electricity, 215.

Choroid coat, the, 149.
Chromatic lines on the earth, 133.
Clay converted into slate by electricity, 227.
Climate of the earth, 350.
Clock, Electrical, 233.
Coal formation, theory of, 314.
Cohesive force opposed to gravitation, 33.
Cohesion and gravitation, 49.
—— distinguished from crystallization, 51.
Cold, extreme, 110.
Colour of bodies, 132.
—— changes of, in chemical combinations, 290.
—— blue, of sky, 320.
—— of steam, 321.
Colours, Newton's theory of, 135.
Coloured heat rays, 85.
Combining equivalents, 273.
—— forces, 292.
Combination, laws of, 286.
—— of forces, 330.
Combustion, 305.
Comets, 26.
Condensation of gases, 290.
Conduction of heat, 69.
Conducting power of bodies for heat, 89.
Condition, change of chemical, 271.
Conversion of motion, 16.
Convection of heat, 69.
Cotyledons, use of the, 368.
Coulomb on repulsion of atoms, 47.

Creation, oneness of, 406.
Cretaceous formations, 344.
Crosse on electricity, 227.
Crustaceans, metamorphosis of, 389.
Crust of the earth, 333.
Crystals, pseudomorphous, 54.
——, size of, 56.
Crystallogenic forces, 50.
Crystalline bodies, magnetic influence of, 260.
Cudworth's "Plastic Nature," 10.
Current, electric, speed of, 231.
——, electricity, magnetic, 239.
Crystallization, 50.
Cultivation, limits of, 379.
Currents of electricity around the earth, 224.
Cyanite, a true magnet, 48.

Daguerre's discovery, 170.
Daguerreotype, the, 172.
Dalton on Aurora Borealis, 248.
—— on liquefaction, 287.
Dalton's atomic theory, 278.
Daniel on incandescence, 100.
Dark lines of spectrum, 125.
Darwin on sea-weeds of the Southern Ocean, 316.
Davy, Sir H., on the elements, 328.
—— on flame, 307.
—— discovers the alkaline metals, 325.
Decomposition, electro-chemical, 208.
De la Tour, Cagniard's experiments, 105.
Delaroche on heat, 93.

Density of the earth, 31.
Development, animal, 384.
Dew, formation of, 81.
Diamond, allotropic carbon, 43.
——, phosphorescence of, 160.
Diamagnetism, 253.
Diamagnetic nature of gases, 259.
Diathermic bodies, 94.
Diffusion of gases, 323.
Digestion a cause of heat, 105.
Dip of magnetic needle, 247.
Dimorphism in crystals, 55.
Directive power of a magnet on crystals, 261.
Distribution of elements, 328.
Divisibility of matter, 38.
Döbereiner's lamp, 281.
Dispersion of light, 129.
Draper on incandescence, 100.
Dumas on atoms, 39.
Dust, a grain of, 2.

Earth, physical, the, 1.
—— density of, 31.
—— the revolution of the, 77.
——, geological formation of, 333.
Earth's, motion, 11.
—— temperature dependent on the sun, 63.
Effects produced by loss of heat, 69.
Eggs, number of, laid by insects, 399.
Elective affinity, 292.
Electricity, 193.
Electricity and light influencing crystallization,

57.
——, kinds of, 195.
—— contained in water, 203.
—— developed by chemical action, 204.
——, velocity of, 231.
—— of plants, 380.
Electric condition of matter, 5.
—— telegraph, the, 231.
—— affinity, 275.
Electrical phosphorescence, 160.
—— action influenced by actinism, 183.
—— radiations, 190.
—— clock, 233.
Electro-chemistry, 206.
Electro culture, 223.
Electrotype, the, 229.
Electro-chemical decomposition, 208.
Electro-magnetism, 240.
Electrum, 193.
Elements, chemical, 37, 272.
——, atmospheric, 325.
——, interchanges of, 319.
Englefield on heat rays, 67.
Eocene formations, 346.
Equinoxes, precession of the, 244.
——, the vernal and autumnal, 77.
Epicurus' hooked atoms, 48.
Epipolic phenomena, 129.
Eremacausis, 105.
Ether, hypothesis of an, 120.
Examples of crystallization, 59.

Expansion of bodies by heat, 96.
Eye, mechanism of, 149.

Faraday on Magnetism of Crystals, 59.
—— on solidification of gases, 112.
—— on magnetization of light, 147.
—— on the gymnotus, 211.
—— on diamagnetism, 254.
Ferro-magnetic bodies, 255.
Fish Lizard, the, 341.
Fixed stars, light of, 122.
Flint glass, permeability to heat, 65.
Flora, fossil, 345.
Flowers, influences of, 317.
Fluid, magnetic theory of, 252.
Fluorescence of light, 130.
Forbes, Prof. Jas., on vibrations of heated metals, 97.
Forbes, Prof. Edward, on zones of life in the ocean, 127.
Forbes on colour of steam, 321.
Force producing motion, 9.
—— a cause of motion, 17.
——, molecular, 40.
—— of crystallization, 61.
Forces, active, in matter, 3.
——, balance of, 14.
—— in antagonism, 407.
Form, change of, 2.
—— of surface, influence of, on climate, 351.
——, variety of vegetable, 359.
Foster describes Northern Lights, 249.

Fox, R. W., on temperature of Cornish mines, 91.
Franklin on atoms, 47.
Franklin's kite experiment, 214.
Freezing mixtures, 110.
Freezing, remarkable phenomena of, 112.
—— of water, 302.
Friction, 17.
Frictional electricity, 199.
Fraunhofer's dark lines, 125.
Franklin's experiment on heat, 75.
Fusion influenced by pressure, 107.

Galvanism, 201.
Galvani's experiment, 201.
Gases, condensation of, 111, 290.
——, magnetism of, 259.
Gaseous constitution, 317.
Gauss's theory of magnetism, 243.
Generation, spontaneous, 363.
Geological phenomena, 332.
Germ, Treviranus on the, 361.
Germination of seeds, 367.
Glass, coloured, transparency to heat, 65.
Goethe's theory of colour, 139.
Goethe on phosphorescence, 157.
—— on the leaf, 369.
Graham's law of diffusion, 323.
Gravitation, 21.
Growth explained, 52.
——, progress of, 364.
—— defined, 383.

Grove decomposes water by heat, 98.
Gulf stream, the, 81.
Gulielmini on crystallisation, 50.
Gun cotton, 103.
Gymnotus electricus, 211.
Gyroscope, the, 14.

Hansteen and Arago on Northern Lights, 248.
Hansteen on magnetism, 244.
Heat, solar and terrestrial, 62.
——, conductors of, 90.
——, rays absorbed by atmosphere, 63, 73.
—— and light, their relations, 64.
——, radiation of, 82.
—— rays, coloured, 85.
—— lessens chemical affinity, 88.
——, latent, 101.
——, decomposition by, 109, 276.
——, scientific knowledge of, 114.
—— developed by combustion of wood equivalent to heat absorbed in growth, 116.
——, influence of, on magnetism, 241.
——, action of, on water, 302.
——, influence of on plants, 371.
—— essential to life, 395.
Heliography of M. Niepce, 170.
Herbivorous animals, 315.
Herschel on the nebulæ, 24.
Herschel, Sir W., on heat rays, 67.
Hobbes on the properties of matter, 8.
Hopkins on the temperature of fusion, 107.

Huyghens on double refraction, 140.
Hydra, the, 387.
Hydrogen, peroxide of, 298.
—— and oxygen, 289, 297.
Hydro-carbons, 297.
Hydro-carbon compounds, 308.
Hypnotism, Mr. Braid on, 269.

Ice, 301.
Ichthyosaurus, the, 341.
Igneous rocks, 335.
Ignition by chemical action, 102.
Iguanodon, the, 343.
Incandescence, temperature of, 69–100.
Influences of matter on heat, 79.
Infusoria and animalculæ, 387.
Interference of light, 138.
Intensity, magnetic, 247.
Invisible light, Moser on, 188.
Iodide of silver found natural, 304.
Iodine, 304.
Iridescent paper, 137.
Iron, magnetic, 235.
——, soft, rendered magnetic, 241.
——, rusting, 306.
Isomeric compounds, 291.
Isomorphism, 290.
Isothermic lines, 92.
Isodynamic lines, 247.

Jones, Rymer, on sponges, 345.
Joule on anhydrous salts, 287.

—— on heat and motion, 18.

Kircher's Magnetism, 264.
Kupffar on magnetic storms, 249.

Lamination of clay by electricity, 226.
Land and sea, alternations of, 340.
Laplace's theory of the universe, 23.
Latent heat, 101.
Lavoisier's theory of combustion, 305.
Law of gravitation, 30.
Lawson, letter from Mr., on germination of seeds, 375.
Leaf, the functions of the, 369.
Leaves of plants, action on air of, 311.
Le Verrier on planet Neptune, 32.
Leyden jar, the, 198.
Lias formations, 341.
Liebig and organic chemistry, 284.
Life and light, 52.
——, influence of light on, 153.
—— dependent on light, 164.
——, vegetable, 362.
——, mysteries of, 398.
Light, 118.
—— essential to life, 39.
—— of fixed stars, 122.
——, transparency to, 124.
——, transmission of, through different media, 128.
——, absorption of, 125.
——, interference of, 138.

——, polarized condition of, 141.
——, magnetization of, 146.
——, artificial, 162.
——, influence of, on plants, 373.
—— and heat, correlation of, 64.
Lightning conductors, 215.
Lindley on the leaf, 370.
Lubbock, Sir J., on shooting stars, 22.
Lodes, mineral, electricity of, 225.
Luminous and actinic rays distinguished, 176.

Machine electricity, 209.
Magellanic clouds, 25.
Magnetic curves, 236.
—— iron ore, 237.
—— polarity, 237.
—— points of convergence, 244.
—— poles of the earth, 245.
—— intensity, 247
—— storms, 249.
—— lines of no variation, 243.
Magnetism, 235.
—— induced, 238.
—— influenced by heat, 242.
——, universality of, 253.
—— of gases, 259.
—— induced by solar rays 263.
—— and electricity, correlation of, 239.
—— and crystallisation, 57.
Magneto-electrical decomposition, 230.
Magnetisation of light, 146.
Malus on polarisation, 139.

Mammalia, fossil, 343.
Man, temperature of, 105.
Manganesiate of potash, 171.
Mantell, Dr., on the iguanodon, 343.
Mariotte on seat of vision, 149.
Matter, its general conditions, 1.
——, forms of, 21.
——, transmutation of, 37.
——, divisibility of, 38.
——, solid, absorption of heat by, 75.
——, influence of, on light, 162.
——, polarity of, 265.
—— and its properties, 409.
——, entity of, 410.
——, varied condition of, 36.
Mayer's hypothesis of three colours, 138.
Mechanical force and heat, 103.
Mechanism of the eye, 149.
Media, influence of, on light, 128.
Medusæ, phosphorescence of, 159.
Melloni on coloured heat rays, 85.
—— on new nomenclature for heat, 95.
Mesmer and electricity, 222.
Metamorphic rocks, 336.
Metamorphoses of animals, 389.
Mexico, Gulf of, warmth of the, 81.
Mica, black, transparency to heat, 66.
Miller, Dr., on dark lines of the spectrum, 126.
Mineral veins, electricity of, 225.
Mines, Cornish, temperature of, 91.
Miocene formations, 346.

Mirrors, magic, 191.
Mitscherlich on expansion of crystals by heat, 257.
Molecular forces, 35, 40.
——, compound action of, 279.
Molecules, Dumas on, 39.
—— combination, 277.
Morichini and Carpi on magnetism of violet rays of light, 263.
Moser on invisible light, 189.
Motion, 7.
—— a property of matter, 8.
——, principles of, 10.
—— of the earth, 12.
—— round an axis shows the earth's motion, 18.
——, influence of, on form, 32.
Mountain ranges probably determined by magnetic force, 262.
Multiplication of life, 399.
Musical notes produced by heat, 97.
Muscular contraction by electricity, 202.
Musschenbroek of Leyden, 198.
Mythology, ancient, probable origin of, 353.

Natural polarization, 145.
Nebulous state of matter, 23.
Neptune, discovery of, 32.
Newton on gravitating force, 49.
Newton on motion, 9.
Newton's hypothesis of matter, 4.
—— theory of heat, 115.

—— theory of light, 120.
—— theory of colours, 135.
Niepce on the chemical radiations, 168.
Nitrogen, magnetic neutrality of, 259.
——, combinations of, 324.
——, supposed metallic nature of, 325.
Nocturnal radiation, 83.
Northern lights, the, 268.

Obsidian transparency to heat, 66.
Ocean, waters of, 303.
Oersted discovers electro-magnetism, 238.
Orders of animals, 386.
Organic creation, influence, 185.
—— compounds, 283.
—— compounds, influence of light on them, 181.
—— chemistry, 331.
—— cell, 360.
—— remains, 337.
Organized forms, varieties of, 35.
—— bodies, heat of, 104.
Organization, progress of, 385.
Oxides, metallic, 326.
Oxidizable metals, 305.
Oxygen gas magnetic, 259.
—— and nitrogen, uses of, 321.
—— and carbon in animals, 396.
Ozone, 299.
—— and electricity, 217.

Palladium maintaining slow combustion, 309.

Parathermic rays, 74.
—— rays, influence in nature, 377.
Particles, Dumas on, 39.
Peach on phosphorescence of the sea, 159.
Pearsall on phosphorescence, 160.
Pendulum, oscillation of, indicates the earth's motion, 13.
Perkins on repulsion of heat, 108.
Permeation of heat, 96.
Perturbations of Uranus, 31.
Pestilential diseases, 216.
Phenomena of vision, 148.
——, natural, of electricity, 194.
——, recent geological, 349.
Phosphorescence of animals, 154.
—— of plants, 156.
Phosphorescent spectrum, 184.
Phosphoric acid detected in the oldest rocks, 337.
Photosphere of the sun, 123.
Photography, 170.
——, its importance, 180.
Physiological influences of electricity, 219.
Physical forces, action of, 4, 45.
—— forces, modes of motion, 7.
—— properties of polarized light, 142.
Physiological influences of magnetism, 268.
Pilchard, on the, by Couch, 315.
Plants, distribution of, dependent on light, 133.
——, phosphorescence of, 156.
——, respiration of, 312.

—— and animals, dependence of, 313.
——, growth of, 368.
—— bend to the light, 373.
——, distribution of, 378.
—— of the Tropics, 381.
Plane polarization, 141.
“Plastic nature” of Cudworth, 10.
Plateau’s experiment on bodies relieved from gravitation, 33.
Platinum maintaining slow combustion, 309.
Plato on motion, 10.
—— on light, 119.
Plesiosaurus, the, 341.
Pliocene formations, 346.
Plücker on crystallo-magnetic force, 57.
—— on diamagnetic bodies, 256.
Plumule, use of, 369.
Plutonic rocks, 334.
Polarization, circular and elliptical, 143.
Polarization of light, 139.
Polar condition of matter, 265.
Polypes and infusoria, 387.
Porosity of matter, 41.
Porta, Baptista—camera obscura, 149.
Powers, active, in nature, 405.
Prevost, theory of, on heat, 96.
Primary origin of our planet, 334.
Principles of motion, 10.
Prismatic refraction, 121.
—— rays, heat of, 67.
—— analysis of sunbeam, 134.

Principle of gravitation, 29.
——, elementary, 38.
Properties, essential, of matter, 5.
Pseudomorphism, 54.
Psychology of flowers, 357.
Pterodactyl, the, 342.
Pythagorean doctrine of motion, 10.

Quinine, solution, influence of, on light, 129.

Radiant heat, 69.
Radiation and absorption of heat, 77.
——, nocturnal, 83.
Raia torpedo, 211.
Raymond, Du Bois, on animal electricity, 221.
Refrangibility, rays of high, 130.
—— of solar forces, 168.
Refraction, prismatic, 121.
Races, dependence of, 315.
Repulsion of heat, 108.
Respiration of animals, 310.
—— plants, 312.
Rest, absolute and relative, 15.
Respiration a cause of heat, 105.
Retina, the, 149.
Revelations of nature, 401.
Revolution of magnetic poles, 246.
Robinson on decomposition by heat, 98.
Rock formations, 335.
Rocks, conducting power of, 224.
Rosse's, Lord, telescopes, 25.
Rumford, Count, experiments on heat, 18.

—— on chemical properties of light, 99.
Rings, Newton's, 137.

Safety lamp of Davy, 309.
Salt rock, transparency to heat, 65.
Saturn's ring explained, 34.
Savart on vibrating plates, 257.
Seasons, influence of heat on the, 70.
Sea, phosphorescence of, 158.
Schönbein on ozone, 299.
Schwabe on solar spots, 243.
Seebeck on thermo-electricity, 211, 248.
Selenite and alabaster, 60.
Sénarmont on conducting power of crystals for heat, 257.
Shooting stars, 21.
Silicon, allotropic state of, 43.
Silica, substitution of, 345.
Simple bodies, chemical, 329.
Sky of tropical climes, 319.
Slow combustion in animals, 397.
Smee on electricity and vitality, 219.
Solar system, motion of, 11.
—— disc, light from, 185.
—— influence on magnetism, 263.
Solidification of gases by Faraday, 112.
Solstices, summer and winter, 77.
Solar spots connected with magnetism, 243.
Solar phosphori, 161.
Somerville, Mrs., magnetises needles by light, 263.
Sound and light, analogy of, 151.

Spectra produced by polarization of light, 144.
Spectrum, dark lines of, 125.
Spheroidal condition of fluids, 107.
Spontaneous ignition, 307.
Stahl on phlogiston, 305.
Stars, shooting, theories of, 21.
Steel ornaments incandescent, 137.
Stereoscope, the, 151.
Stokes, Prof., on fluorescence, 130.
Stratified formations, 334.
Strength of animals, 400.
Structure, influence of, on magnetism, 256.
——, relation of, to physical phenomena, 257.
Struvé on motion of solar system, 12.
Substitution, chemical, 279.
——, law of, 288.
Substances, all, electric, 197.
Subterranean temperature, 91.
Sulphuric acid, permeability to heat, 65.
Surfaces, action of, 282.
Sulzar on galvanism, 201.
Sulphuretted hydrogen, solid, 111.
Sun, the central, 28.
——, the source of light, 121.
——, physical state of the, 123.
——, a magnetic centre, 265.

Tadpole, metamorphosis of, 389.
Talbot’s sensitive photographic process, 178.
Telegraph, electric, 231.
Temperature of incandescence, 68.
Temperature, subterranean, 91.

Terrestrial currents of electricity, 224.
—— magnetism, 255.
Thales of Miletus discovers electricity, 193.
Theories of light, 86, 118.
Thermography, 188.
Thermometric examination of the temperature of flowers, 76.
Thermo-electricity, 209.
Theory of motion producing force, 15.
Thilorier on solid carbonic acid, 111.
Time, influence of, 332.
Tissues, catalytic power of, 310.
Tourmaline, action of, on light, 142.
Trade winds, 81.
Transition series of rocks, 336.
Transparency, calorific, 67.
——, luminous, 124.
Transmutation of matter, 37.
Transmission of light, 128.
Transcalescent bodies, 94.
Trevelyan, Mr., on vibration of heated metals, 97.
Tyndale proves the influence of structure on magnetism, 258.
Type, elements of the organic, 289.

Undulations producing colour, 131.
Undulatory theory of heat, 115.
—— theory of light, 121.
Uranus, discovery of, 31.
Uranium glass, influence of, on light, 129.

Vapour, elastic force of, 318.
Variation, magnetic, 244.
Vegetables conductors of electricity, 379.
Vegetable life, phenomena of, 357.
Vegetation of carboniferous epoch, 339.
Velocity of electricity, 231.
Vertebrate animals, 390.
Vision, phenomena of, 148.
Vis vitæ, vital principle, 391.
Vision single with a pair of eyes, 150.
Vitality superior to physical force, 53.
Vision, seat of, 149.
Volume, doctrine of, 287.
Volcanic action referred to chemical action, 271.
Volatilization of matter, 27.
Voltaic electricity, 201.

Water, absorption of heat by, 74.
—— frozen free of air, 112.
—— free of air, peculiar state of, 113.
——, electricity in a drop of, 204.
——, composition of, 296.
Wargentin's notice of aurora, 248.
Wave movement of heat and light, 68.
Wealden formations, 343.
Wedgwood on incandescence, 100.
Wells, Dr., on dew, 84.
Wiedemann on electrical vibrations, 257.
Wenzel's proportional numbers, 277.
Winds dependent on heat, 80.
Wollaston notices dark lines in spectrum, 125.

World, its age, 404.

Young on molecular forces, 49.

Zodiacal light, 25.
Zoophytes, microscopic, 387.

THE END.

Wilson and Ogilvy, 57, Skinner Street, Snowhill,
London.

BOHN'S BOOKS.

BOHN'S STANDARD LIBRARY.

Post 8vo., Elegantly Printed, and bound in Cloth, at 3s. 6d. per Vol.

1. THE MISCELLANEOUS WORKS AND REMAINS OF THE REV. ROBERT HALL, with Memoir by DR. GREGORY, and Essay by JOHN FOSTER. *Portrait.*

2 & 3. ROSCOE'S LIFE AND PONTIFICATE OF LEO X. Edited by his Son, with the Copyright Notes, Documents, &c. In 2 Vols. *Portraits.*

4. SCHLEGEL'S LECTURES ON THE PHILOSOPHY OF HISTORY. Translated from the German, with a Memoir by J. B. ROBERTSON, Esq. *Portrait.*

5 & 6. SISMONDI'S HISTORY OF THE LITERATURE OF THE SOUTH OF EUROPE. Translated by ROSCOE. In 2 Vols. *Portraits.*

7. ROSCOE'S LIFE OF LORENZO DE MEDICI, with the Copyright Notes, &c.

8. SCHLEGEL'S LECTURES ON DRAMATIC LITERATURE. *Portrait.*

9 & 11. BECKMANN'S HISTORY OF INVENTIONS, DISCOVERIES, AND ORIGINS. Fourth Edition, revised and enlarged. In 2 Vols. *Portraits.*

10. SCHILLER'S HISTORY OF THE THIRTY YEARS' WAR AND REVOLT OF THE NETHERLANDS. Translated by A. J. W. MORRISON. *Portrait.*

12. SCHILLER'S WORKS. Vol. II. [Conclusion of "The Revolt of the Netherlands;" "Wallenstein's Camp;" "The Piccolomini;" "The Death of Wallenstein;" and "Wilhelm Tell."] *With Portrait of Wallenstein.*

13. MEMOIRS OF THE LIFE OF COLONEL HUTCHINSON. By his Widow: with an "Account of the Siege of Lathom House." *Portrait.*

14. MEMOIRS OF BENVENUTO CELLINI, by HIMSELF. By ROSCOE. *Portrait.*

15, 18, & 22. COXE'S HISTORY OF THE HOUSE OF AUSTRIA, from the foundation of the Monarchy, 1218–1792. Complete in 3 vols. *Portraits.*

16, 19, & 23. LANZI'S HISTORY OF PAINTING. By ROSCOE. In 3 Vols. *Portraits.*

17. OCKLEY'S HISTORY OF THE SARACENS. Revised and Completed. *Portrait.*

20. SCHILLER'S WORKS. Vol. III. ["Don Carlos," "Mary Stuart," "Maid of Orleans," and "Bride of Messina."] *Frontispiece.*

21, 26, & 33. LAMARTINE'S HISTORY OF THE GIRONDISTS; or, Memoirs of the French Revolution, from *unpublished sources*. In 3 Vols. *Portraits.*

24. MACHIAVELLI'S HISTORY OF FLORENCE, PRINCE, &c. *Portrait.*

25. SCHLEGEL'S LECTURES ON THE PHILOSOPHY OF LIFE AND THE PHILOSOPHY OF LANGUAGE. Translated by A. J. W. MORRISON.

27, 32, & 36. RANKE'S HISTORY OF THE POPES. Translated by E. FOSTER. In 3 Vols. *Portraits.* (The only complete English translation.)

28, 30, & 34. COXE'S MEMOIRS OF THE DUKE OF MARLBOROUGH. In 3 Vols. *Portraits.*

*** ATLAS, of 26 fine large Maps and Plans of Marlborough's Campaigns, (being all those published in the original edition at £12 12s.) 4to. 10s. 6d.

29. SHERIDAN'S DRAMATIC WORKS AND LIFE. *Portrait.*

31. GOETHE'S WORKS. Vol. I. [His Autobiography. 13 Books.] *Portrait.*

35. WHEATLEY ON THE COMMON PRAYER. *Frontispiece.*

37. MILTON'S PROSE WORKS. Vol. I. *Portrait.*

38, 41, & 45. MENZEL'S HISTORY OF GERMANY. Complete in 3 Vols. *Portrait.*

39. MILTON'S PROSE WORKS. Vol. II. *Frontispiece.*

40. MILTON'S PROSE WORKS. Vol. III. *Portrait of Laud.*

42. SCHLEGEL'S ÆSTHETIC AND MISCELLANEOUS WORKS.

43. GOETHE'S WORKS. Vol. II. [Remainder of his Autobiography, and Travels.]

44. SCHILLER'S WORKS. Vol. IV. ["The Robbers," "Fiesko," "Love and Intrigue," and "The Ghost-Seer."] Translated by HENRY G. BOHN.

46. SCHLEGEL'S LECTURES ON MODERN HISTORY.

47. LAMARTINE'S HISTORY OF THE FRENCH

REVOLUTION OF 1848.

48 & 50. JUNIUS'S LETTERS, with Notes, Additions, Essay, Index, &c. 2 Vols.

49, 55, 60, 65, 71. VASARI'S LIVES OF THE MOST CELEBRATED PAINTERS, SCULPTORS, AND ARCHITECTS. Translated by MRS. FOSTER, with Notes. Complete in 5 Vols., with Index.

51. TAYLOR'S (JEREMY) HOLY LIVING AND DYING. *Portrait.*

52. GOETHE'S WORKS. Vol. III. ["Faust," "Iphigenia," "Torquato Tasso," and "Egmont."] Translated by Miss SWANWICK. With "Goetz von Berlichingen," translated by SIR WALTER SCOTT.

53, 56, 58, 61, 66, 67, & 75. NEANDER'S CHURCH HISTORY. Carefully revised by the REV. A. J. W. MORRISON.

54. NEANDER'S LIFE OF CHRIST.

57, 64. NEANDER'S PLANTING OF CHRISTIANITY, & ANTIGNOSTIKUS, 2 Vols.

59. GREGORY'S (DR.) LETTERS ON THE CHRISTIAN RELIGION.

62 & 63. JAMES' (G. P. R.) LOUIS XIV. Complete in 2 Vols. *Portraits.*

68 & 70. SIR JOSHUA REYNOLDS' LITERARY WORKS, with Memoir, 2 Vols. *Port.*

69. ANDREW FULLER'S PRINCIPAL WORKS. *Portrait.*

72. BUTLER'S ANALOGY OF RELIGION, AND SERMONS, with Notes, &c. *Port.*

73. MISS BREMER'S WORKS. Translated by MARY HOWITT. New Edition, revised. Vol. I. ["The Neighbours," and other Tales.] Post 8vo. *Portrait.* 3*s.* 6*d.*

74. NEANDER'S MEMORIALS OF CHRISTIAN LIFE IN THE EARLY AND MIDDLE AGES (including his "Light in Dark Places"). Post 8vo. 3*s.* 6*d.*

Uniform with the STANDARD LIBRARY, *price 3s. 6d.*,

BOHN'S EXTRA VOLUMES.

1. GRAMMONT'S MEMOIRS OF THE COURT OF CHARLES II. *Portrait.*

2 & 3. RABELAIS' WORKS. Complete in 2 Vols. *Portrait.*

4. COUNT HAMILTON'S FAIRY TALES. *Portrait.*

Uniform with the STANDARD LIBRARY, *price 5s.* (*excepting "Cosmos," which is only 3s. 6d., and Mantell's "Petrifactions," which is 6s.*),

BOHN'S SCIENTIFIC LIBRARY.

1. STAUNTON'S CHESS PLAYER'S HAND-BOOK, *with Diagrams*.

2. LECTURES ON PAINTING, by THE ROYAL ACADEMICIANS.

3, 4, 8, & 15. HUMBOLDT'S COSMOS; or, Sketch of a Physical Description of the Universe. Translated, with Notes, by E. C. OTTE. In 4 Vols., *with fine Portrait*. This Translation (though published at so low a price) is more complete than any other. The Notes are placed beneath the text. Humboldt's analytical summaries, and the passages hitherto suppressed, are included; and comprehensive Indices subjoined. 3*s.* 6*d.* per Volume.

5. STAUNTON'S CHESS PLAYER'S COMPANION, comprising a New Treatise on Odds, a Collection of Match Games, Original Problems, &c.

6. HAND-BOOK OF GAMES, by VARIOUS AMATEURS and PROFESSORS.

7. HUMBOLDT'S VIEWS OF NATURE, *with coloured view of Chimborazo, &c.*

9. RICHARDSON'S GEOLOGY, AND PALÆONTOLOGY, Revised by Dr. WRIGHT, *with upwards of 400 Illustrations on Wood*.

10. STOCKHARDT'S PRINCIPLES OF CHEMISTRY. Exemplified in Simple Experiments, *with upwards of 270 Illustrations*.

11. DR. G. A. MANTELL'S PETRIFACTIONS AND THEIR TEACHINGS; A Hand-Book to the Fossils in the British Museum. *Beautiful Wood Engravings.* 6*s.*

12. AGASSIZ AND GOULD'S COMPARATIVE PHYSIOLOGY. New and Enlarged Edition, *with nearly 400 fine Illustrations*.

13 & 19. HUMBOLDT'S PERSONAL NARRATIVE OF HIS TRAVELS IN AMERICA. Vols. I. & II. (to be completed in 3 Volumes.)

14. PYE SMITH'S GEOLOGY AND SCRIPTURE. Fifth Edition, with Memoir.

16. **OERSTED'S SOUL IN NATURE, &C.** *Portrait.*

17. STAUNTON'S CHESS TOURNAMENT, *with Diagrams*.

18 & 19. BRIDGEWATER TREATISES. KIRBY on the History, Habits, and Instincts of Animals; Edited by T. RYMER JONES. In 2 Vols. *Many Illustrations.*

UNIFORM WITH THE STANDARD LIBRARY,

BARBAULD'S (MRS.) SELECTIONS FROM THE SPECTATOR, TATLER, GUARDIAN, AND FREEHOLDER. In 2 Vols. 3*s.* 6*d.* per Volume.

BRITISH POETS, from MILTON to KIRKE WHITE, Cabinet Edition, comprising, in a very small but remarkably clear type, as much matter as the sixty volumes of Johnson's Poets. Complete in 4 Vols., *with Frontispieces*. 14*s.*

CARY'S TRANSLATION OF DANTE. Extra cloth. 7*s.* 6*d.*

CATTERMOLE'S EVENINGS AT HADDON HALL. 24 exquisite Engravings on Steel, from Designs by himself; the Letter-Press by the BARONESS DE CALABRELLA. Post 8vo. 7*s.* 6*d.*

CLASSIC TALES; comprising The Vicar of Wakefield, Elizabeth, Paul and Virginia, Gulliver's Travels, Sterne's Sentimental Journey, Sorrows of Werter, Theodosius and Constantia, Castle of Otranto, and Rasselas. 12mo. *7 Portraits.* 3*s.* 6*d.*

DEMOSTHENES. Translated by LELAND. *Portrait.* 3*s.*

CHILLINGWORTH'S RELIGION OF PROTESTANTS. 3*s.* 6*d.*

HORACE'S ODES AND EPODES, translated literally and rythmically, by the REV. W. SEWELL. 3*s.* 6*d.*

IRVING'S (WASHINGTON) WORKS. Complete in 10 Vols., £1 15*s.*, or 3*s.* 6*d.* per Vol.

JOYCE'S SCIENTIFIC DIALOGUES. Greatly Improved Edition, with Questions, &c., by PINNOCK. (Upwards of 600 pages). *Woodcuts.* 5*s.*

JOYCE'S INTRODUCTION TO THE ARTS AND SCIENCES. 5*s.*

LAMARTINE'S THREE MONTHS IN POWER. Sewed, 2*s.*

LAMARTINE'S POETICAL MEDITATIONS AND RELIGIOUS HARMONIES, with Biographical Sketch. *Portrait.* Cloth, 3*s.* 6*d.*

LAWRENCE'S LECTURES ON COMPARATIVE ANATOMY, PHYSIOLOGY, ZOOLOGY, AND THE

NATURAL HISTORY OF MAN. *Front. and Plates.* 5*s.*

LILLY'S INTRODUCTION TO ASTROLOGY. A New and Improved Edition, by ZADKIEL, with his Grammar of Astrology, and Tables of Nativities. 5*s.*

LOUDON'S (MRS.) ENTERTAINING NATURALIST, a Popular Description, Tales, and Anecdotes of more than Five Hundred Animals, with Indexes of Scientific and Popular Names. *With upwards of 500 beautiful Woodcuts, by* BEWICK, HARVEY, WHIMPER, &c. Revised and enlarged. 7*s.* 6*d.*

LOWTH'S LECTURES ON THE SACRED POETRY OF THE HEBREWS. 3*s.* 6*d.*

MAXWELL'S VICTORIES OF THE BRITISH ARMIES. New Edition, *with highly finished Steel Portraits*, extra gilt cloth. 7*s.* 6*d.*

MICHELET'S HISTORY OF THE FRENCH REVOLUTION. 4*s.*

MILLER'S PHILOSOPHY OF HISTORY. Third Revised and Improved Edition, 4 Volumes, at 3*s.* 6*d.* per Volume.

MILNER'S HISTORY OF THE CHURCH OF CHRIST. 4 vols. 14*s.*

MITFORD'S (MISS) OUR VILLAGE. 2 Vols., New Edition, *with Woodcuts and beautiful Frontispieces on Steel*, gilt cloth. Each Vol. 5*s.*

PARKES' ELEMENTARY CHEMISTRY. New Edition, revised, 5*s.*

ROBINSON CRUSOE, including his further Adventures, with Life of Defoe, &c. *Upwards of 60 fine Woodcuts*, from designs by HARVEY and WHIMPER. 4*s.* 6*d.*

SCHILLER'S PHILOSOPHICAL & ÆSTHETIC LETTERS AND ESSAYS. 3*s.* 6*d.*

SHAKSPEARE'S PLAYS AND POEMS, with Life, by CHALMERS. In 1 Vol. 3*s.* 6*d.*

STANDARD LIBRARY CYCLOPÆDIA OF POLITICAL, CONSTITUTIONAL, STATISTICAL, AND FORENSIC KNOWLEDGE. 4 Vols. 3*s.* 6*d.* each.

This work contains as much as eight ordinary octavos. It was first published in another shape by Mr. Charles Knight, under the title of Political Dictionary, at £1 16*s.* The Compiler, MR. GEORGE LONG, is one of the most competent Scholars of the day.

Also, uniform with the STANDARD LIBRARY, *price* 5*s.*,

BOHN'S ECCLESIASTICAL LIBRARY.

1. EUSEBIUS' ECCLESIASTICAL HISTORY, Translated from the Greek, with Notes.

BOHN'S SHILLING SERIES.

*Those marked *, being Double Volumes, are* 1*s.* 6*d.*

1. EMERSON'S REPRESENTATIVE MEN.
2. IRVING'S LIFE OF MAHOMET.*
3. THE GENUINE AUTOBIOGRAPHY OF BENJAMIN FRANKLIN.
4. WILLIS'S PEOPLE I HAVE MET.*
5. IRVING'S SUCCESSORS OF MAHOMET.*
6.—— LIFE OF GOLDSMITH.*
7.—— SKETCH-BOOK.*
8.—— TALES OF A TRAVELLER.*
9.—— TOUR ON THE PRAIRIES.
10 & 11.—— CONQUESTS OF GRANADA AND SPAIN. 2 Vols.*
12 & 13.—— LIFE OF COLUMBUS. 2 Vols.*
14.—— COMPANIONS OF COLUMBUS.*
15 & 16. TAYLOR'S EL DORADO; or, Pictures of the Gold Region. 2 Vols.*
17. IRVING'S ADVENTURES OF CAPTAIN BONNEVILLE.*
18.—— KNICKERBOCKER.*
19.—— TALES OF THE ALHAMBRA.*
20.—— CONQUEST OF FLORIDA.*
21.—— ABBOTSFORD AND NEWSTEAD.
22.—— SALMAGUNDI.*
23.—— BRACEBRIDGE HALL.*
24.—— ASTORIA (*with fine Portrait of the Author*). 2 Vols. in 1. 2*s.*
25. LAMARTINE'S GENEVIEVE; or, The History of a Servant Girl. Translated by A. R. SCOBLE.*
26. MAYO'S BERBER; or, The Mountaineer of the Atlas. A Tale of Morocco.
27. WILLIS'S LIFE HERE AND THERE; or, Sketches of Society and Adventure.*
28. GUIZOT'S LIFE OF MONK, with Appendix and *Portrait.**
29. THE CAPE AND THE KAFFIRS: A Diary of Five

Years' Residence, with Advice to Emigrants. By H. WARD. *Plate and Map of the Seat of War.* 2*s.*

30. WILLIS'S HURRY-GRAPHS; or, Sketches of Scenery, Celebrities, and Society, taken from Life.*

31. HAWTHORNE'S HOUSE OF THE SEVEN GABLES. A Romance.

32. LONDON AND ITS ENVIRONS; with Historical and Descriptive Sketch of the Great Exhibition. By CYRUS REDDING. *Numerous Illustrations.* 2*s.*

33. LAMARTINE'S STONEMASON OF SAINT POINT.*

34. GUIZOT'S MONK'S CONTEMPORARIES. A Series of Biographic Studies on the English Revolution. *Portrait of Edward Lord Clarendon.*

35. HAWTHORNE'S TWICE-TOLD TALES.

36.—————— Second Series.

37.—— SNOW IMAGE, and other Tales.

38.—— SCARLET LETTER.

39. EMERSON'S ORATIONS AND LECTURES.

Also, uniform with the STANDARD LIBRARY, 5*s.* (*except Thucydides, Æschylus, Virgil, Horace, and Cicero's Offices, which are* 3*s.* 6*d. each*),

BOHN'S CLASSICAL LIBRARY.

A SERIES OF LITERAL PROSE TRANSLATIONS OF THE GREEK AND LATIN CLASSICS, WITH NOTES.

1. HERODOTUS. By the REV. HENRY CARY, M.A. *Index, and Frontispiece.*

2 & 3. THUCYDIDES. By the REV. H. DALE. In 2 Vols. (3*s.* 6*d.* each).

4. PLATO. Vol. I. By CARY. [The Apology of Socrates, Crito, Phædo, Gorgias, Protagotas, Phædrus, Theætetus, Euthyphron, Lysis.]

5. LIVY'S HISTORY OF ROME. Vol I., Books 1 to 8.

6. PLATO. Vol. II. By DAVIS. [The Republic, Timæus, and Critias.]

7. LIVY'S HISTORY OF ROME. Vol. II., Books 9 to 26.

8. SOPHOCLES. The Oxford Translation, revised.

9. ÆSCHYLUS. By an OXONIAN. (Price 3*s.* 6*d.*)

10. ARISTOTLE'S RHETORIC AND POETIC. With Examination Questions.

11. LIVY'S HISTORY OF ROME. Vol. III., Books 27 to

36.

12 & 14. EURIPIDES. From the Text of Dindorf. In 2 Vols.

13. VIRGIL. By DAVIDSON. New Edition, Revised. (Price 3*s.* 6*d.*)

15. HORACE. By SMART. New Edition, Revised. (Price 3*s.* 6*d.*)

16. ARISTOTLE'S ETHICS. By PROF. R. W. BROWNE, of King's College.

17. CICERO'S OFFICES. [Old Age, Friendship, Scipio's Dream, Paradoxes, &c.]

18. PLATO. Vol. III. By G. BURGES, M.A. [Euthydemus, Symposium, Sophistes, Politicus, Laches, Parmenides, Cratylus, and Meno.]

19. LIVY'S HISTORY OF ROME. Vol. IV. (which completes the work).

20. CÆSAR AND HIRTIUS. With Index.

21. HOMER'S ILIAD. *Frontispiece.*

22. HOMER'S ODYSSEY, HYMNS, EPIGRAMS, AND BATTLE OF THE FROGS AND MICE.

23. PLATO. Vol. IV. By G. BURGES, M.A. [Philebus, Charmides, Laches, The Two Alcibiades, and Ten other Dialogues.]

24, 25, & 32. OVID. By H. T. RILEY, B.A. Complete in 3 Vols. *Frontispieces.*

26. LUCRETIUS. By the REV. J. S. WATSON. With the Metrical Version of J. M. GOOD.

27, 30, 31, & 34. CICERO'S ORATIONS. By C. D. YONGE. Complete in 4 Vols (Vol. 4 contains also the Rhetorical Pieces.)

28. PINDAR. By DAWSON W. TURNER. With the Metrical Version of MOORE. *Front.*

29. PLATO. Vol. V. By G. BURGES, M.A. [The Laws.]

33. THE COMEDIES OF PLAUTUS. By H. T. RILEY, B.A. In 2 Vols. Vol. I.

35. JUVENAL, PERSIUS, &c. By the REV. L. EVANS, M.A. With the Metrical Version of GIFFORD. *Frontispiece.*

Also, uniform with the STANDARD LIBRARY, *at* 5*s. per volume*,

BOHN'S ILLUSTRATED LIBRARY.

1 to 8. LODGE'S PORTRAITS OF ILLUSTRIOUS

PERSONAGES OF GREAT BRITAIN. 8 Vols. post 8vo. *240 Portraits.*

9. CRUIKSHANK'S THREE COURSES AND DESSERT, *with 50 Illustrations*.

10. PICKERING'S RACES OF MAN, *with numerous Portraits* (*or Coloured* 7*s.* 6*d.*)

11. KITTO'S SCRIPTURE LANDS, AND BIBLICAL ATLAS, *with 24 Maps*, (*or Coloured*, 7*s.* 6*d.*)

12. WHITE'S NATURAL HISTORY OF SELBORNE, with Notes by SIR WM. JARDINE and others, edited, with large additions, by ED. JESSE, Esq. *With 40 highly-finished Wood Engravings* (*Coloured*, 7*s.* 6*d.*)

13. DIDRON'S CHRISTIAN ICONOGRAPHY, *with 150 beautiful Engravings*. In 2 Vols. Vol. I.

14. REDDING ON WINES. New and Revised Edition, *with 20 beautiful Woodcuts*.

15 & 16. ALLEN'S BATTLES OF THE BRITISH NAVY. New Edition. Enlarged by the Author. *Numerous fine Portraits* on Steel. 2 Vols.

17 & 18. ROME IN THE NINETEENTH CENTURY. Fifth Edition, in 2 Vols., *with 34 fine Steel Engravings*, and Index.

Also, uniform with the STANDARD LIBRARY, *price* 5*s.*,

BOHN'S ANTIQUARIAN LIBRARY.

1. BEDE'S ECCLESIASTICAL HISTORY, & THE ANGLO-SAXON CHRONICLE.

2. MALLET'S NORTHERN ANTIQUITIES. By BISHOP PERCY. With Abstract of the Eyrbiggia Saga, by SIR WALTER SCOTT. Edited by J. A. BLACKWELL.

3. WILLIAM OF MALMESBURY'S CHRONICLE OF THE KINGS OF ENGLAND.

4. SIX OLD ENGLISH CHRONICLES: viz., Asser's Life of Alfred; the Chronicles of Ethelwerd, Gildas, Nennius, Geoffry of Monmouth, and Richard of Cirencester.

5. ELLIS'S EARLY ENGLISH METRICAL ROMANCES. Revised by J. ORCHARD HALLIWELL. Complete in one vol., *with Illuminated Frontispiece*.

6. CHRONICLES OF THE CRUSADERS: Richard of Devizes, Geoffrey de Vinsauf, Lord de Joinville. Complete in 1 volume, *with Frontispiece*.

7. EARLY TRAVELS IN PALESTINE. Willibald, Sæwulf, Benjamin of Tudela, Mandeville, La Brocquiere, and Maundrell. In one volume. *With Map.*

8, 10, & 12. BRAND'S POPULAR ANTIQUITIES OF GREAT BRITAIN. By SIR HENRY ELLIS. In 3 Vols.

9 & 11. ROGER OF WENDOVER'S FLOWERS OF HISTORY (formerly ascribed to Matthew Paris.) In 2 Vols.

13. KEIGHTLEY'S FAIRY MYTHOLOGY. Enlarged. *Frontispiece* by CRUIKSHANK.

14, 15, & 16. SIR THOMAS BROWNE'S WORKS. Edited by SIMON WILKIN. *Portrait.* In 3 Vols. With Index.

BOHN'S MINIATURE LIBRARY.

Foolscap 12mo. elegantly bound in morocco cloth.

BARBAULD AND AIKIN'S EVENINGS AT HOME. *Frontisps.* 3*s.*

BOURRIENNE'S MEMOIRS OF NAPOLEON, *fine Portrait and Frontisp.* 3*s.* 6*d.*

BUNYAN'S PILGRIM'S PROGRESS. With a Life and Notes by SCOTT, containing all in Southey's Edition. *25 fine Woodcuts, by* HARVEY, *Frontisp.* &c. 3*s.* 6*d.*

—— CHEEVER'S LECTURES ON, *Frontisp.* 2*s.* 6*d.*

BYRON'S POETICAL WORKS, in 1 thick Volume, including several suppressed Poems not included in other editions. *Beautiful Frontispiece.* 3*s.* 6*d.*

—— DON JUAN, complete. *Frontispieces.* 2*s.* 6*d.*

COLERIDGE'S SELECT POETICAL WORKS. 2*s.*

COWPER'S POETICAL WORKS, with Life by SOUTHEY, including all the copyright Poems (700 pages). *Beautiful Frontispieces after* HARVEY, *by* GOODALL. 3*s.* 6*d.*

ENCYCLOPÆDIA OF MANNERS AND ETIQUETTE, comprising an improved edition of Chesterfield's Advice to his Son on Men and Manners. 2*s.*

HEBER'S (BP.) & MRS. HEMANS' POETICAL WORKS. 3 Vols. in 1. *Frontisp.* 3*s.*

HERRICK'S POETICAL WORKS, complete. *Frontispiece.* 3*s.*

JOE MILLER'S JEST BOOK. *Frontispiece.* 3*s.*

LONGFELLOW'S POETICAL WORKS, viz.—Voices of

the Night—Evangeline—Seaside and Fireside—Spanish Students—Translations. *Portrait and Frontisp.* 3*s.* 6*d.*

—— **PROSE WORKS**, viz.—Outre-Mer—Hyperion—Kavanagh. 3*s.* 6*d.*

MILTON'S POETICAL WORKS, with Life and Notes by DR. STEBBING; and Dr. Channing's Essay on Milton. *Frontispiece.* 3*s.* 6*d.*

OSSIAN'S POEMS, with Dissertations by MACPHERSON and Dr. Blair. *Frontisp.* 3*s.*

POPE'S HOMER'S ILIAD. Essay on Homer. Notes and Essays. *Frontispiece.* 3*s.*

—— **ODYSSEY**, (uniform). *Frontispiece.* 3*s.*

SCOTT'S POETICAL WORKS, and Life, in one volume. *Port. and Frontisp.* 3*s.* 6*d.*

STURM'S REFLECTIONS ON THE WORKS OF GOD. *Frontisp.* 2*s.*

THOMPSON'S SEASONS. With his Castle of Indolence, *4 beautiful Woodcuts*. 2*s.*

VATHEK, AND THE AMBER WITCH. 2 vols. in 1. 3*s.*

TRANSCRIBER'S NOTE.

Archaic, obsolete, unusual and inconsistent spellings have been maintained as in the original book. Obvious errors have been fixed as detailed below. Changes are indicated below and in the text with a mouse-over like this.

Some entries in the index were out of alphabetical order in the original book. They have been moved without noting them in the details below.

The totals in the various tables are not equal to the sum of the column above them. I assume this is due to round off error, or details in the original data which are not represented here. No attempt has been made to correct these totals.

In the original book, half of the publisher's catalogue (Bohn's Books) was in the beginnig of the book. It was moved to immediately precede the other half of the catalogue at the end of the book.

Preface, Contents, Introduction, Index, Bohn's Books and Transcriber's Note have been added to the table of contents. Only the chapters of the book were in the table of contents in the original book. The title "Bohn's Books" was inserted into the beginning of the publisher's book catalogue.

In the table below, the first line shows the text in this ebook, the second line shows the text in the original book.

Page vii.:	conditions of Matter—Diamagnetism, &c. 235
Originally:	conditions of Matter—Dia-Magnetism, &c. 235

Page viii.:	Time, an element in Nature's Operations—Geological
Originally:	Time, an element in Nature's Operations = = Geological
Page viii.:	Progress of Matter towards Organization
Originally:	Progress of Matter rowards Organization
Page xii.:	of external nature, evoked beautiful spiritualizations
Originally:	of external nature, evoked beautiful spirtualizations
Footnote 1:	Boscovich regarded the constitution of matter differently
Originally:	Boscovitch regarded the constitution of matter differently
Footnote 1:	full explanation of the theory of Boscovich.)
Originally:	full explanation of the theory of Boscovitch.)
Page 8:	The views of metaphysicians regarding motion involve
Originally:	The views of metaphyscians regarding motion involve
Page 14:	tremulous gyration upon the deck of a vast aërial ship

Originally:	tremulous gyration upon the deck of a vast aerial ship
Page 27:	agent of organisation and all manifestations of beauty?
Originally:	agent of organisation and all manifestatious of beauty?
Footnote 18:	fixes, est déterminée par ce qui précède entre certaines
Originally:	fixes, est determinée par ce qui précède entre certaines
Footnote 18:	est le groupe central de l'ensemble du système
Originally:	est le groupe central l'ensemble du système
Footnote 24:	into a single mass at the bottom of the flask under
Originally:	into a single mass at the bottom of the flask unde
Page 42:	with which the particles combined, from interstices,
Originally:	with which the particles combined, from insterstices,
Page 45:	bromine, &c., are the results of different *allotropic*
Originally:	bromime, &c., are the results of different *allotropic*

Page 46:	which,—from the imperfections of science,—resisting
Originally:	which,—from the imperfectious of science,—resisting
Page 46:	The experiments of Faraday and of Plücker prove
Originally:	The experiments of Faraday and of Plucker prove
Footnote 25:	Young's *Natural Philosophy*; ed. by Rev. P. Kelland.
Originally:	Young's *Natural Philosophy*; ed. by Rev. P. Lelland.
Footnote 35:	Hence the origin of compound and visible bodies; hence
Originally:	Hence the origin of compouud and visible bodies; hence
Page 50:	her operations, but the very processes themselves.
Originally:	her operations, but the very processes themselvss.
Paqe 59:	combination appears to the eye in no respect different
Originally:	combinatiou appears to the eye in no respect different
Page 61:	Those fissures formed by the first system of crystalline

Originally:	Those fissures formed by the first sytsem of crystalline
Page 68:	luminous power are sufficiently striking to convince us
Originally:	luminous power are sufficienlty striking to convince us
Page 109:	of temperature is experienced.[79] Professor Plücker, of
Originally:	of temperature is experienced.[79] Professor Plucker, of
Footnote 55:	this motion. He was followed by Musschenbroek, and then
Originally:	this motion. He was followed by Muschenbroek, and then
Footnote 61:	*regarding the internal temperature of the Earth*: by
Originally:	*regarding the internal temperature of tha Earth*: by
Footnote 78:	*en vertu de l'état sphéroïdal dans un creuset*
Originally:	*en vertu de l'état sphérodïal dans un creuset*
Page 121:	Fraunhofer, Herschel, Brewster, and others, but proceed
Originally:	Frauenhofer, Herschel, Brewster, and others, but proceed

Page 123: between charcoal points at the poles of a powerful voltaic

Originally: between charcoal points a the poles of a powerful voltaic

Page 129: of quinine, and the fluor spar, we obtain the same results

Originally: of quinine, and the flour spar, we obtain the same results

Page 140: the first instance, by Erasmus Bartholin, in Iceland-spar,

Originally: the first instance, by Erasmus Bartolin, in Iceland-spar,

Page 145: from what has been already stated, that some

Originally: from what has beeen already stated, that some

Page 153: to prove that light is absolutely necessary to

Originally: to prove that light is absolutely neccessary to

Page 159: of light behind them.[113] By microscopic examination

Originally: of light behind them.[113] By miscroscopic examination

Page 159: Benvenuto Cellini gave a curious account of a carbuncle

Originally:	Benvenuto Cellini give a curious account of a carbuncle
Page 160:	near a fire. From this it may be inferred that the
Originally:	near a a fire. From this it may be infered that the
Footnote 88:	Brande's *Manual of Chemistry*; or, indeed, any work
Originally:	Brande's *Mannal of Chemistry*; or, indeed, any work
Footnote 94:	Schouw, *Grundzüge der Pflanzengeographie*. Also his
Originally:	Schouw, *Grundüzge der Pflanzengeographie*. Also his
Footnote 95:	Fraunhofer's measure of illuminating power is as
Originally:	Frauenhofer's measure of illuminating power is as
Footnote 99:	*Sur une Propriété de la Lumière Réfléchie*: Mémoires
Originally:	*Sur une Propriété de la Lumière Réfléchie*: Memoires
Page 176:	the strongest sunlight which has passed through
Originally:	the strongest sun-light which has passed through

Page 179: productions of the photographer as on those of the

Originally: productions of the photograper as on those of the

Page 180: preserve the lineaments of those who have benefited

Originally: preserve the lineaments of those who have benefitted

Page 185: line, over which no action takes place, is preserved at

Originally: line, over which no action takes plates, is preserved at

Page 185: presented to us by a circular body: calorific action seems

Originally: present to us by a circular body: calorific action seems

Page 188: piece of wood is used instead of a metal, there will, by

Originally: piece of wood is used instead of a medal, there will, by

Footnote 126: *dans la végétation*: by Senebier; Genève et Paris, 1788

Originally: *dans la végetation*: by Senebier; Genève et Paris, 1788

Page 198: Leyden phial,—so called from its inventor, Musschenbroek,

Originally:	Leyden phial,—so called from its inventor, Muschenbrock,
Page 219:	may be made a measurer of nervous irritability.[154] There
Originally:	may be made a measurer of nervous iritability.[154] There
Footnote 141:	*Traité Expérimental de l'Électricité et du Magnétisme*:
Originally:	*Traité Expérimental de l'Electricité et du Magnétisme*:
Footnote 146:	*Traité Expérimental de l'Électricité et du Magnétisme*.
Originally:	*Traité Expérimental de l'Electricité et du Magnétisme*
Footnote 160:	where the cobalt was discovered between two portions of
Originally:	where the cobalt was discovered betweed two portions of
Page 235:	Storms—Magnetic conditions of Matter —Diamagnetism,
Originally:	Storms—Magnetic conditions of Matter —Dia-Magnetism,
Page 236:	Magnêtum, quia sit patriis in finibus ortus.
Originally:	Magnêtum, buia sit patriis in finibus ortus.

Page 251:	conditions of change in this our earth: an element to
Originally:	conditions of change in this our earth: an elemeut to
Page 257:	Wiedemann, by employing a fine point through which
Originally:	Wiedmann, by employing a fine point through which
Page 258:	than in any other. M. Wiedemann comes to the conclusion
Originally:	than in any other. M. Wiedmann comes to the conclusion
Page 260:	salt, the protosulphate, ordinarily crystallizes so that
Originally:	salt, the proto-sulphate, ordinarily crystallizes so that
Footnote 176:	Humboldt: *Exposé des Variations Magnétiques*.
Originally:	Humboldt: *Exposé des Variations Magnetiques*.
Footnote 188:	*Electro-Magnetic Influence*, by Professor Zantedeschi.
Originally:	*Electro-Magnetic Influence*, by Professor Zandeteschi.
Footnote 190:	detailed account of the experiments of Faraday, Plücker,

Originally: detailed account of the experiments of Faraday, Plucker,

Page 276: light determine these changes? It is evident, although

Originally: light determine these change? It is evident, although

Page 281: chemical change. Döbereiner next discovered that

Originally: chemical change. Dœbereiner next discovered that

Page 282: a fearful example in the progress of Asiatic

Originally: a fearful example in the progress of Asatic

Page 300: as being either peroxide of hydrogen, or an allotropic

Originally: as being either per-oxide of hydrogen, or an allotropic

Page 304: the gas which we employ so advantageously for illumination

Originally: the gas which we emply so advantageously for illumination

Page 306: increasing,—true combustion takes place. In this way

Originally: increasing,—true combustion takes plaee. In this way

Page 306:	sawdust, &c., frequently ignite; and to such an
Originally:	saw-dust, &c., frequently ignite; and to such an
Page 316:	Mr. Darwin remarks, that if the immense sea-weeds of
Originally:	Mr. Darwin remarks, that if the immense seaweeds of
Page 317:	When Shakespeare made his charming Ariel sing—
Originally:	When Shakspeare made his charming Ariel sing—
Footnote 212:	(Redundant line removed before item 2 in table.)
Originally:	According to one view, | According to the other view,
Page 334:	speculation, which may have occasional marks of ingenuity,
Originally:	speculation, whieh may have occasional marks of ingenuity,
Page 337:	origin, the rational inference is against the speculation;
Originally:	orgin, the rational inference is against the speculation;
Page 370:	capsule of *nigella orientalis* consists of pods assembled

Originally: capsule of *nigilla orientalis* consists of pods assembled

Page 370: a centre, and partially united; in *nigella damascena*

Originally: a centre, and partially united; in *nigilla damascena*

Page 399: whose minds are sceptical upon any development of the

Originally: whose mind are sceptical upon any development of the

Page 406: evidence of a beautiful adjustment of the balance of

Originally: evidence of a beautifnl adjustment of the balance of

Page 408: Let but a slight disturbance occasion a vibration

Originally: Let but a slight disturbance occcasion a vibration

Page 409: A cheerless philosophy, derived from the transcendentalism

Originally: A cheerless philosophy, derived from the transendentalism

Page 410: which are allowed the privilege of tracing out its

Originally: which are alowed the privilege of tracing out its

Page 413: Aëreal currents dependent on heat, 80.

Originally: Æreal currents dependent on heat, 80.

Page 413: Animal electricity, 211, 392.
Originally: Magnetic electricity, 211, 392.

Page 413: Bartholin on Iceland spar, 140.
Originally: Bartolin on Iceland spar, 140.

Page 414: Cagniard de la Tour state, 106.
Originally: Caignard de la Tour state, 106.

Page 415: Döbereiner's lamp, 281.
Originally: Doebereiner's lamp, 281.

Page 415: Eye, mechanism of, 149.
Originally: Eye, mechanism of, 491.

Page 416: —— on diamagnetism, 254.
Originally: —— on dia-magnetism, 254.

Page 418: Musschenbroek of Leyden, 198.
Originally: Muschenbrock of Leyden, 198.

Page 421: Wiedemann on electrical vibrations, 257.
Originally: Wiedman on electrical vibrations, 257.

Bohn's Books: **LOUDON'S (MRS.) ENTERTAINING NATURALIST**,
Originally: **LOUDON'S (MRS.) ENTERTAING NATURALIST**,

Bohn's Books:	Indexes of Scientific and Popular Names. _With_
Originally:	Indexes of Scientific and and Popular Names. _With_
Bohn's Books:	**18. PLATO.** Vol. III. By G. BURGES, M.A. [Euthydemus,
Originally:	**8. PLATO.** Vol. III. By G. BURGES, M.A. [Euthydemus,
Bohn's Books:	**24, 25, & 32. OVID.** By H. T. RILEY, B.A. Complete in 3
Originally:	**24, 25, & 32. OVID.** By H. T. RILEY, B.A. Complete in 3
Bohn's Books:	**35. JUVENAL, PERSIUS, &c.** By the REV. L. EVANS, M.A.
Originally:	**34. JUVENAL, PERSIUS, &c.** By the REV. L. EVANS, M.A.

*** END OF THE PROJECT GUTENBERG EBOOK THE POETRY OF SCIENCE; OR, STUDIES OF THE PHYSICAL PHENOMENA OF NATURE ***

Updated editions will replace the previous one—the old editions will be renamed.

Creating the works from print editions not protected by U.S. copyright law means that no one owns a United States copyright in these works, so the Foundation (and you!) can copy and distribute it in the United States without permission and without paying copyright royalties. Special rules, set forth in the General Terms of Use part of this license, apply to copying and distributing Project Gutenberg™ electronic works to protect the PROJECT GUTENBERG™ concept and trademark. Project Gutenberg is a registered trademark, and may not be used if you charge for an eBook, except by following the terms of the trademark license, including paying royalties for use of the Project Gutenberg trademark. If you do not charge anything for copies of this eBook, complying with the trademark license is very easy. You may use this eBook for nearly any purpose such as creation of derivative works, reports, performances and research. Project Gutenberg eBooks may be modified and printed and given away—you may do practically ANYTHING in the United States with eBooks not protected by U.S. copyright law. Redistribution is subject to the trademark license, especially commercial

redistribution.

START: FULL LICENSE

THE FULL PROJECT GUTENBERG™ LICENSE

PLEASE READ THIS BEFORE YOU DISTRIBUTE OR USE THIS WORK

To protect the Project Gutenberg™ mission of promoting the free distribution of electronic works, by using or distributing this work (or any other work associated in any way with the phrase “Project Gutenberg”), you agree to comply with all the terms of the Full Project Gutenberg License available with this file or online at www.gutenberg.org/license.

Section 1. General Terms of Use and Redistributing Project Gutenberg electronic works

1.A. By reading or using any part of this Project Gutenberg electronic work, you indicate that you have read, understand, agree to and accept all the terms of this license and intellectual property (trademark/copyright) agreement. If you do not agree to abide by all the terms of this agreement, you must cease using and return or destroy all copies of Project Gutenberg electronic works in your possession. If you paid a fee for obtaining a copy of or access to a Project Gutenberg electronic work and you do not agree to be bound by the terms of this agreement, you may obtain a refund from the person or entity to whom you paid the fee as set

forth in paragraph 1.E.8.

1.B. “Project Gutenberg” is a registered trademark. It may only be used on or associated in any way with an electronic work by people who agree to be bound by the terms of this agreement. There are a few things that you can do with most Project Gutenberg electronic works even without complying with the full terms of this agreement. See paragraph 1.C below. There are a lot of things you can do with Project Gutenberg electronic works if you follow the terms of this agreement and help preserve free future access to Project Gutenberg electronic works. See paragraph 1.E below.

1.C. The Project Gutenberg Literary Archive Foundation (“the Foundation” or PGLAF), owns a compilation copyright in the collection of Project Gutenberg electronic works. Nearly all the individual works in the collection are in the public domain in the United States. If an individual work is unprotected by copyright law in the United States and you are located in the United States, we do not claim a right to prevent you from copying, distributing, performing, displaying or creating derivative works based on the work as long as all references to Project Gutenberg are removed. Of course, we hope that you will support the Project Gutenberg mission of promoting free access to electronic works by freely sharing Project Gutenberg works in compliance with the terms of this agreement for keeping the Project Gutenberg name associated with the work. You can easily comply with the terms of this agreement by keeping this work in the same format with its attached full Project

Gutenberg License when you share it without charge with others.

1.D. The copyright laws of the place where you are located also govern what you can do with this work. Copyright laws in most countries are in a constant state of change. If you are outside the United States, check the laws of your country in addition to the terms of this agreement before downloading, copying, displaying, performing, distributing or creating derivative works based on this work or any other Project Gutenberg work. The Foundation makes no representations concerning the copyright status of any work in any country other than the United States.

1.E. Unless you have removed all references to Project Gutenberg:

1.E.1. The following sentence, with active links to, or other immediate access to, the full Project Gutenberg License must appear prominently whenever any copy of a Project Gutenberg work (any work on which the phrase “Project Gutenberg” appears, or with which the phrase “Project Gutenberg” is associated) is accessed, displayed, performed, viewed, copied or distributed:

> This eBook is for the use of anyone anywhere in the United States and most other parts of the world at no cost and with almost no restrictions whatsoever. You may copy it, give it away or re-use it under

the terms of the Project Gutenberg™ License included with this eBook or online at www.gutenberg.org. If you are not located in the United States, you will have to check the laws of the country where you are located before using this eBook.

1.E.2. If an individual Project Gutenberg electronic work is derived from texts not protected by U.S. copyright law (does not contain a notice indicating that it is posted with permission of the copyright holder), the work can be copied and distributed to anyone in the United States without paying any fees or charges. If you are redistributing or providing access to a work with the phrase “Project Gutenberg” associated with or appearing on the work, you must comply either with the requirements of paragraphs 1.E.1 through 1.E.7 or obtain permission for the use of the work and the Project Gutenberg trademark as set forth in paragraphs 1.E.8 or 1.E.9.

1.E.3. If an individual Project Gutenberg electronic work is posted with the permission of the copyright holder, your use and distribution must comply with both paragraphs 1.E.1 through 1.E.7 and any additional terms imposed by the copyright holder. Additional terms will be linked to the Project Gutenberg License for all works posted with the permission of the copyright holder found at the beginning of this work.

1.E.4. Do not unlink or detach or remove the full

Project Gutenberg License terms from this work, or any files containing a part of this work or any other work associated with Project Gutenberg.

1.E.5. Do not copy, display, perform, distribute or redistribute this electronic work, or any part of this electronic work, without prominently displaying the sentence set forth in paragraph 1.E.1 with active links or immediate access to the full terms of the Project Gutenberg License.

1.E.6. You may convert to and distribute this work in any binary, compressed, marked up, nonproprietary or proprietary form, including any word processing or hypertext form. However, if you provide access to or distribute copies of a Project Gutenberg work in a format other than “Plain Vanilla ASCII” or other format used in the official version posted on the official Project Gutenberg website (www.gutenberg.org), you must, at no additional cost, fee or expense to the user, provide a copy, a means of exporting a copy, or a means of obtaining a copy upon request, of the work in its original “Plain Vanilla ASCII” or other form. Any alternate format must include the full Project Gutenberg License as specified in paragraph 1.E.1.

1.E.7. Do not charge a fee for access to, viewing, displaying, performing, copying or distributing any Project Gutenberg works unless you comply with paragraph 1.E.8 or 1.E.9.

1.E.8. You may charge a reasonable fee for copies of or providing access to or distributing Project Gutenberg electronic works provided

that:

- You pay a royalty fee of 20% of the gross profits you derive from the use of Project Gutenberg works calculated using the method you already use to calculate your applicable taxes. The fee is owed to the owner of the Project Gutenberg trademark, but he has agreed to donate royalties under this paragraph to the Project Gutenberg Literary Archive Foundation. Royalty payments must be paid within 60 days following each date on which you prepare (or are legally required to prepare) your periodic tax returns. Royalty payments should be clearly marked as such and sent to the Project Gutenberg Literary Archive Foundation at the address specified in Section 4, “Information about donations to the Project Gutenberg Literary Archive Foundation.”

- You provide a full refund of any money paid by a user who notifies you in writing (or by e-mail) within 30 days of receipt that s/he does not agree to the terms of the full Project Gutenberg™ License. You must require such a user to return or destroy all copies of the works possessed in a physical medium and discontinue all use of and all access to other copies of Project Gutenberg™ works.

- You provide, in accordance with paragraph 1.F.3, a full refund of any money paid for a work or a replacement copy, if a defect in the electronic work is discovered and reported to you within 90 days of receipt of the work.

• You comply with all other terms of this agreement for free distribution of Project Gutenberg™ works.

1.E.9. If you wish to charge a fee or distribute a Project Gutenberg™ electronic work or group of works on different terms than are set forth in this agreement, you must obtain permission in writing from the Project Gutenberg Literary Archive Foundation, the manager of the Project Gutenberg™ trademark. Contact the Foundation as set forth in Section 3 below.

1.F.

1.F.1. Project Gutenberg volunteers and employees expend considerable effort to identify, do copyright research on, transcribe and proofread works not protected by U.S. copyright law in creating the Project Gutenberg™ collection. Despite these efforts, Project Gutenberg™ electronic works, and the medium on which they may be stored, may contain “Defects,” such as, but not limited to, incomplete, inaccurate or corrupt data, transcription errors, a copyright or other intellectual property infringement, a defective or damaged disk or other medium, a computer virus, or computer codes that damage or cannot be read by your equipment.

1.F.2. LIMITED WARRANTY, DISCLAIMER OF DAMAGES - Except for the “Right of Replacement or Refund” described in paragraph 1.F.3, the Project Gutenberg Literary Archive Foundation, the owner of the Project Gutenberg™ trademark, and any other party

distributing a Project Gutenberg™ electronic work under this agreement, disclaim all liability to you for damages, costs and expenses, including legal fees. YOU AGREE THAT YOU HAVE NO REMEDIES FOR NEGLIGENCE, STRICT LIABILITY, BREACH OF WARRANTY OR BREACH OF CONTRACT EXCEPT THOSE PROVIDED IN PARAGRAPH 1.F.3. YOU AGREE THAT THE FOUNDATION, THE TRADEMARK OWNER, AND ANY DISTRIBUTOR UNDER THIS AGREEMENT WILL NOT BE LIABLE TO YOU FOR ACTUAL, DIRECT, INDIRECT, CONSEQUENTIAL, PUNITIVE OR INCIDENTAL DAMAGES EVEN IF YOU GIVE NOTICE OF THE POSSIBILITY OF SUCH DAMAGE.

1.F.3. LIMITED RIGHT OF REPLACEMENT OR REFUND - If you discover a defect in this electronic work within 90 days of receiving it, you can receive a refund of the money (if any) you paid for it by sending a written explanation to the person you received the work from. If you received the work on a physical medium, you must return the medium with your written explanation. The person or entity that provided you with the defective work may elect to provide a replacement copy in lieu of a refund. If you received the work electronically, the person or entity providing it to you may choose to give you a second opportunity to receive the work electronically in lieu of a refund. If the second copy is also defective, you may demand a refund in writing without further opportunities to fix the problem.

1.F.4. Except for the limited right of replacement or refund set forth in paragraph 1.F.3, this work

is provided to you ‘AS-IS’, WITH NO OTHER WARRANTIES OF ANY KIND, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO WARRANTIES OF MERCHANTABILITY OR FITNESS FOR ANY PURPOSE.

1.F.5. Some states do not allow disclaimers of certain implied warranties or the exclusion or limitation of certain types of damages. If any disclaimer or limitation set forth in this agreement violates the law of the state applicable to this agreement, the agreement shall be interpreted to make the maximum disclaimer or limitation permitted by the applicable state law. The invalidity or unenforceability of any provision of this agreement shall not void the remaining provisions.

1.F.6. INDEMNITY - You agree to indemnify and hold the Foundation, the trademark owner, any agent or employee of the Foundation, anyone providing copies of Project Gutenberg™ electronic works in accordance with this agreement, and any volunteers associated with the production, promotion and distribution of Project Gutenberg™ electronic works, harmless from all liability, costs and expenses, including legal fees, that arise directly or indirectly from any of the following which you do or cause to occur: (a) distribution of this or any Project Gutenberg work, (b) alteration, modification, or additions or deletions to any Project Gutenberg work, and (c) any Defect you cause.

Section 2. Information about the Mission

of Project Gutenberg

Project Gutenberg is synonymous with the free distribution of electronic works in formats readable by the widest variety of computers including obsolete, old, middle-aged and new computers. It exists because of the efforts of hundreds of volunteers and donations from people in all walks of life.

Volunteers and financial support to provide volunteers with the assistance they need are critical to reaching Project Gutenberg's goals and ensuring that the Project Gutenberg collection will remain freely available for generations to come. In 2001, the Project Gutenberg Literary Archive Foundation was created to provide a secure and permanent future for Project Gutenberg and future generations. To learn more about the Project Gutenberg Literary Archive Foundation and how your efforts and donations can help, see Sections 3 and 4 and the Foundation information page at www.gutenberg.org.

Section 3. Information about the Project Gutenberg Literary Archive Foundation

The Project Gutenberg Literary Archive Foundation is a non-profit 501(c)(3) educational corporation organized under the laws of the state of Mississippi and granted tax exempt status by the Internal Revenue Service. The Foundation's EIN or federal tax identification number is 64-6221541. Contributions to the Project Gutenberg Literary Archive Foundation

are tax deductible to the full extent permitted by U.S. federal laws and your state's laws.

The Foundation's business office is located at 41 Watchung Plaza #516, Montclair NJ 07042, USA, +1 (862) 621-9288. Email contact links and up to date contact information can be found at the Foundation's website and official page at www.gutenberg.org/contact

Section 4. Information about Donations to the Project Gutenberg Literary Archive Foundation

Project Gutenberg™ depends upon and cannot survive without widespread public support and donations to carry out its mission of increasing the number of public domain and licensed works that can be freely distributed in machine-readable form accessible by the widest array of equipment including outdated equipment. Many small donations ($1 to $5,000) are particularly important to maintaining tax exempt status with the IRS.

The Foundation is committed to complying with the laws regulating charities and charitable donations in all 50 states of the United States. Compliance requirements are not uniform and it takes a considerable effort, much paperwork and many fees to meet and keep up with these requirements. We do not solicit donations in locations where we have not received written confirmation of compliance. To SEND DONATIONS or determine the status of compliance for any particular state visit

www.gutenberg.org/donate.

While we cannot and do not solicit contributions from states where we have not met the solicitation requirements, we know of no prohibition against accepting unsolicited donations from donors in such states who approach us with offers to donate.

International donations are gratefully accepted, but we cannot make any statements concerning tax treatment of donations received from outside the United States. U.S. laws alone swamp our small staff.

Please check the Project Gutenberg web pages for current donation methods and addresses. Donations are accepted in a number of other ways including checks, online payments and credit card donations. To donate, please visit: www.gutenberg.org/donate.

Section 5. General Information About Project Gutenberg electronic works

Professor Michael S. Hart was the originator of the Project Gutenberg concept of a library of electronic works that could be freely shared with anyone. For forty years, he produced and distributed Project Gutenberg eBooks with only a loose network of volunteer support.

Project Gutenberg eBooks are often created from several printed editions, all of which are confirmed as not protected by copyright in the U.S. unless a copyright notice is included. Thus, we do not necessarily keep eBooks in

compliance with any particular paper edition.

Most people start at our website which has the main PG search facility: www.gutenberg.org.

This website includes information about Project Gutenberg, including how to make donations to the Project Gutenberg Literary Archive Foundation, how to help produce our new eBooks, and how to subscribe to our email newsletter to hear about new eBooks.